



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>







THE NEW YORK PUBLIC LIBRARY

ASTOR LENOX TILDEN FOUNDATION

500 FIFTH AVENUE, NEW YORK, N. Y.

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

ANNUAL REPORT
OF THE
CHIEF OF ENGINEERS,
UNITED STATES ARMY,
TO THE
SECRETARY OF WAR,
FOR
THE YEAR 1884.

IN FOUR PARTS.

PART IV.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.

1884.

14305-



CONTENTS.

[Alphabetical Index will be found at the end of each Part.]

PART I.

EXTRACT FROM REPORT OF THE SECRETARY OF WAR.....	xxi
OFFICERS OF THE CORPS OF ENGINEERS	3

SEA-COAST AND LAKE FRONTIER DEFENSES.

General discussion	4
--------------------------	---

ESTIMATES OF APPROPRIATIONS FOR 1885-6.....	9
---	---

NORTHERN FRONTIER.—Ft. Wayne, Mich., 10; Ft. Porter, N. Y., Ft. Niagara, N. Y., 11; Ft. Ontario, N. Y., 12; Ft. Montgomery, N. Y., 13. THE PENOBSCOT, ME.—Ft. Knox, 13. THE KENNEBEC, ME.—Ft. Popham, 14; PORTLAND, ME.—Ft. Gorges, Ft. Preble, Ft. Scammel, 14; battery on Portland Head, batteries on Cow Id., batteries on Great Hog Id., 15. PORTSMOUTH, N. H., AND NAVY-YARD AT KITTERY, ME.—Ft. McClary, Ft. Constitution, battery on Gerrish's Id., battery on Jerry's Point, 16. MARBLEHEAD HARBOR, MASS.—Ft. Sewall, 17. BOSTON AND NAVY-YARD AT CHARLESTOWN, MASS.—Ft. Warren, battery at Long Id. Head, 17; Ft. Winthrop, Ft. Independence, 18. PLYMOUTH HARBOR, MASS.—Ft. Andrew, Ft. Staudish, 19. NEW BEDFORD, MASS.—Fort at Clark's Point, 19. NARRAGANSETT BAY, R. I.—Ft. Adams, 20; defenses of Dutch Id., 21. NEW LONDON HARBOR AND NAVY-YARD, CONN.—Ft. Trumbull, 21; Ft. Griswold, 22. NEW HAVEN, CONN.—Ft. Hale, 22. NEW YORK AND NAVY-YARD AT BROOKLYN.—Ft. Schuyler, 22; fort at Willets Point, 23; defenses of Governor's Id., 24; sea-wall on Governor's Id., Ft. Wood, Ft. Hamilton and additional batteries, 25; mortar battery Ft. Hamilton, Ft. Lafayette, Ft. Wadsworth, 26; fort on site of Ft. Tompkins, 27; Glacis Gun Battery (n. of site of Ft. Tompkins), Glacis Mortar Battery (s. of site of fort on Ft. Tompkins), Battery Hudson, 28; South Mortar Battery, North Cliff Battery, 29; South Cliff Battery, Two-gun Battery near site of fort on Ft. Tompkins, fort at Sandy Hook, 30. PHILADELPHIA AND LEAGUE ISLAND NAVY-YARD.—Ft. Mifflin, 31; mortar battery at Ft. Mifflin, site for defenses at Red Bank, 32; Ft. Delaware, battery at Finn's Point, 33; mortar battery at Finn's Point, fort opposite Ft. Delaware, mortar battery opposite Ft. Delaware, 34. BALTIMORE, MD.—Ft. McHenry, 35; Ft. Carroll, 36. WASHINGTON, D. C.—Ft. Foote, 36; Ft. Washington, obstructions of the Potomac, 37. HAMPTON ROADS AND GOSPORT NAVY-YARD, VA.—Ft. Monroe, 37; artesian well at Ft. Monroe, Ft. Wool, 39. BEAUFORT HARBOR, N. C.—Ft. Macon, 40. WILMINGTON, N. C.—Ft. Caswell, 41. CHARLESTON, S. C.—Ft. Moultrie, 41; Ft. Sumter, Ft. Johnson, 42; Castle Pinckney, 43. SAVANNAH, GA.—Ft. Oglethorpe, Ft. Pulaski, 43; new fort on Tybee Id., 44. CUMBERLAND SOUND.—Ft. Clinch, 44. SAINT AUGUSTINE, FLA.—Ft. Marion, 45. KEY WEST, FLA.—Ft. Taylor and batteries, 45. HARBOR OF DRY TORTUGAS, FLA.—Ft. Jefferson, 46. PENSACOLA HARBOR AND NAVY-YARD, FLA.—Ft. Pickens, 46; Ft. Barrancas and redoubt, Ft. McRee, 47. MOBILE, ALA.—Ft. Morgan, Ft. Gaines, 48. MISSISSIPPI SOUND.—Fort on Ship Id., 48. NEW ORLEANS, LA.—Ft. Pike, Ft. Macomb, Tower Dupré, 49; Battery Bienvenue, tower at Proctorsville, Ft. Jackson, 50; Ft. St. Philip, Ft. Livingston, 51. GALVESTON, TEXAS.—Batteries at the entrance to the harbor of Galveston, 52. SAN DIEGO HARBOR, CALIFORNIA.—Fort at San Diego, 52. SAN FRANCISCO, NAVY-YARD AT MARE ISLAND AND ARSENAL AT BENICIA, CAL.—Ft. Winfield Scott, 52; fort at Lime Point, 53; fort on Alcatraz Id., Ft. Mason, batteries on Angel Id., 54. DEFENSES OF THE COLUMBIA, OREG., AND WASH.—Ft. Stevens, Ft. Canby, 55.





ANNUAL REPORT
OF THE
CHIEF OF ENGINEERS,
UNITED STATES ARMY,
TO THE
SECRETARY OF WAR,
FOR
THE YEAR 1884.

IN FOUR PARTS.

PART IV.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.

1884. w



14305-



CONTENTS.

[Alphabetical Index will be found at the end of each Part.]

PART I.

EXTRACT FROM REPORT OF THE SECRETARY OF WAR.....	xxi
OFFICERS OF THE CORPS OF ENGINEERS	3

SEA-COAST AND LAKE FRONTIER DEFENSES.

General discussion	4
--------------------------	---

ESTIMATES OF APPROPRIATIONS FOR 1885-6.....	9
---	---

NORTHERN FRONTIER.—Ft. Wayne, Mich., 10; Ft. Porter, N. Y., Ft. Niagara, N. Y., 11; Ft. Ontario, N. Y., 12; Ft. Montgomery, N. Y., 13. THE PENOBSCOT, ME.—Ft. Knox, 13. THE KENNEBEC, ME.—Ft. Popham, 14; PORTLAND, ME.—Ft. Gorges, Ft. Preble, Ft. Scammel, 14; battery on Portland Head, batteries on Cow Id., batteries on Great Hog Id., 15. PORTSMOUTH, N. H., AND NAVY-YARD AT KITTERY, ME.—Ft. McClary, Ft. Constitution, battery on Gerrish's Id., battery on Jerry's Point, 16. MARBLEHEAD HARBOR, MASS.—Ft. Sewall, 17. BOSTON AND NAVY-YARD AT CHARLESTOWN, MASS.—Ft. Warren, battery at Long Id. Head, 17; Ft. Winthrop, Ft. Independence, 18. PLYMOUTH HARBOR, MASS.—Ft. Andrew, Ft. Staudish, 19. NEW BEDFORD, MASS.—Fort at Clark's Point, 19. NARRAGANSETT BAY, R. I.—Ft. Adams, 20; defenses of Dutch Id., 21. NEW LONDON HARBOR AND NAVY-YARD, CONN.—Ft. Trumbull, 21; Ft. Griswold, 22. NEW HAVEN, CONN.—Ft. Hale, 22. NEW YORK AND NAVY-YARD AT BROOKLYN.—Ft. Schuyler, 22; fort at Willets Point, 23; defenses of Governor's Id., 24; sea-wall on Governor's Id., Ft. Wood, Ft. Hamilton and additional batteries, 25; mortar battery Ft. Hamilton, Ft. Lafayette, Ft. Wadsworth, 26; fort on site of Ft. Tompkins, 27; Glacis Gun Battery (n. of site of Ft. Tompkins), Glacis Mortar Battery (s. of site of fort on Ft. Tompkins), Battery Hudson, 28; South Mortar Battery, North Cliff Battery, 29; South Cliff Battery, Two-gun Battery near site of fort on Ft. Tompkins, fort at Sandy Hook, 30. PHILADELPHIA AND LEAGUE ISLAND NAVY-YARD.—Ft. Mifflin, 31; mortar battery at Ft. Mifflin, site for defenses at Red Bank, 32; Ft. Delaware, battery at Finn's Point, 33; mortar battery at Finn's Point, fort opposite Ft. Delaware, mortar battery opposite Ft. Delaware, 34. BALTIMORE, MD.—Ft. McHenry, 35; Ft. Carroll, 36. WASHINGTON, D. C.—Ft. Foote, 36; Ft. Washington, obstructions of the Potomac, 37. HAMPTON ROADS AND GOSPORT NAVY-YARD, VA.—Ft. Monroe, 37; artesian well at Ft. Monroe, Ft. Wool, 39. BEAUFORT HARBOR, N. C.—Ft. Macon, 40. WILMINGTON, N. C.—Ft. Caswell, 41. CHARLESTON, S. C.—Ft. Moultrie, 41; Ft. Sumter, Ft. Johnson, 42; Castle Pinckney, 43. SAVANNAH, GA.—Ft. Oglethorpe, Ft. Pulaski, 43; new fort on Tybee Id., 44. CUMBERLAND SOUND.—Ft. Clinch, 44. SAINT AUGUSTINE, FLA.—Ft. Marion, 45. KEY WEST, FLA.—Ft. Taylor and batteries, 45. HARBOR OF DRY TORTUGAS, FLA.—Ft. Jefferson, 46. PENSACOLA HARBOR AND NAVY-YARD, FLA.—Ft. Pickens, 46; Ft. Barrancas and redoubt, Ft. McRee, 47. MOBILE, ALA.—Ft. Morgan, Ft. Gaines, 48. MISSISSIPPI SOUND.—Fort on Ship Id., 48. NEW ORLEANS, LA.—Ft. Pike, Ft. Macomb, Tower Dupré, 49; Battery Bienvenue, tower at Proctorsville, Ft. Jackson, 50; Ft. St. Philip, Ft. Livingston, 51. GALVESTON, TEXAS.—Batteries at the entrance to the harbor of Galveston, 52. SAN DIEGO HARBOR, CALIFORNIA.—Fort at San Diego, 52. SAN FRANCISCO, NAVY-YARD AT MAKE ISLAND AND ARSENAL AT BENICIA, CAL.—Ft. Winfield Scott, 52; fort at Lime Point, 53; fort on Alcatraz Id., Ft. Mason, batteries on Angel Id., 54. DEFENSES OF THE COLUMBIA, OREG., AND WASH.—Ft. Stevens, Ft. Canby, 55.

THE BOARD OF ENGINEERS.

Officers constituting Board; *Coast defenses*, 55; RECAPITULATION, 57; ESTIMATES, New York, Philadelphia, Boston, 58; Baltimore, 59; *Torpedo defenses*, 59; SUMMARY OF OPERATIONS, 61; estimates for heavy guns and emplacements, 62; estimates for gun emplacements, excluding armor, guns, and machinery, 63.

BOARD OF ENGINEERS FOR THE PACIFIC COAST.

Officers constituting the board.....
 BATTALION OF ENGINEERS AND ENGINEER SCHOOL OF APPLICATION.....
 ENGINEER POST AND DEPOT OF WILLETS POINT, NEW YORK HARBOR.....

RIVER AND HARBOR IMPROVEMENTS.

GENERAL STATEMENT

ATLANTIC COAST.

IN CHARGE OF COL. C. E. BLUNT, CORPS OF ENGINEERS—

Lubec Channel, Me., 67; Moos-a-bec Bar, Me., 68; Belfast Harbor, Me., Rockland Harbor, Me., 69; Cathance River, Me., Royal River, Me., Portland Harbor, Me., 70; Kennebunk River, Me., Portsmouth Harbor, N. H., 71; Cocheco River, N. H., Lamprey River, N. H., 72; examinations and surveys, 73.

IN CHARGE OF MAJ. CHARLES W. RAYMOND, CORPS OF ENGINEERS—

Newburyport Harbor, Mass., 73; Merrimac River, Mass., 74; Scituate Harbor, Mass., Boston Harbor, Mass., 75; Plymouth Harbor, Mass., 76; Provincetown Harbor, Mass., Lynn Harbor, Mass., 77; Malden River, Mass., removal of sunken vessel obstructing navigation, 78; examinations and surveys, 78.

IN CHARGE OF LIEUT. COL. GEORGE H. ELLIOT, CORPS OF ENGINEERS—

Hyannis Harbor, Mass., Nantucket Harbor, Mass., 79; Wood's Holl, Mass., 80; Wareham Harbor, Mass., 82; Taunton River, Mass., 83; Pawtucket River, R. I., 84; Providence River and Narragansett Bay, R. I., 85; Newport Harbor, R. I., 87; Block Island Harbor, 88; Little Narragansett Bay, R. I. and Conn., 89; Stonington Harbor, Conn., 90; examinations and surveys, 91.

IN CHARGE OF LIEUT. COL. WALTER MCFARLAND, CORPS OF ENGINEERS—

Thames River, Conn., New London Harbor, Conn., 92; Connecticut River, Mass. and Conn., 93; Clinton Harbor, Conn., New Haven Harbor, Conn., 94; Breakwater at New Haven, Conn., Milford Harbor, Conn., 95; Housatonic River, Conn., 96; Bridgeport Harbor, Conn., Southport Harbor, Conn., Norwalk Harbor, Conn., 97; Mamaroneck Harbor, N. Y., Port Jefferson Harbor, N. Y., 98; Greenport Harbor, N. Y., 99; examinations and surveys, 99.

IN CHARGE OF BRIG. GEN. JOHN NEWTON, CHIEF OF ENGINEERS, BVT. MAJOR GEN., U. S. A.—

Removing obstructions in East River and Hell Gate, New York, 100.

IN CHARGE OF CAPT. JAMES MERCUR, CORPS OF ENGINEERS—

Hudson River, N. Y., 101; Rondout Harbor, N. Y., Buttermilk Channel, N. Y., 102; Harlem River, N. Y., Gowanus Bay, N. Y., 103; Echo Harbor, New Rochelle, N. Y., 104; harbor at New Rochelle, N. Y., Port Chester Harbor, N. Y., 105; examinations and surveys, 105.

IN CHARGE OF MAJ. GEORGE L. GILLESPIE, CORPS OF ENGINEERS, BVT. LIEUT. COL., U. S. A.—

Flushing Bay, N. Y., 106; Newtown Creek, N. Y., East Chester Creek, N. Y., 107; Canarsie Bay, N. Y., 108; Sheepshead Bay, N. Y., 109; Sumpawanus Inlet, N. Y., Chesapeake Creek, N. J., 110; Passaic River above Newark, N. J., 111; Passaic River from Pennsylvania Railroad Bridge to its mouth, N. J., 112; Channel between Staten Island and New Jersey, 113; Shrewsbury River, N. J., 114; Rahway River, N. J., Elizabeth River, N. J., 115; Woodbridge Creek, N. J., Manasquan River, N. J., 116; Raritan Bay, N. J., 117; Raritan River, N. J., 118; Mattawan Creek, N. J., 119; Keyport Harbor, N. J., South River, N. J., 120; removal of sunken vessels obstructing or endangering navigation, 121; examinations and surveys, 122.

IN CHARGE OF MAJ. W. H. HEUER, CORPS OF ENGINEERS—

Delaware River, between Trenton, N. J., and Bridesburg, Pa., 122; Delaware River, below Bridesburg, Pa., 123; Delaware River, at Schooner Ledge, Delaware River, near Cherry Island Flats, 126; Frankford Creek, Pa., Schuylkill River, Pa., 127; Ice Harbor at Marcus Hook, Pa., Ice Harbor at Chester, Pa., Ice Harbor at New Castle, Del., 128; Ice Harbor at Reedy Island, Del., 129; Wilmington Harbor, Del., Broadkill River, Del., 130; Mispillion Creek, Del., Duck Creek, Del., 131; Cohansey Creek, N. J., Salem River, N. J., 132; Rancocas River, N. J., Saint Jones River, Del., 133; Maurice River, N. J., Mantua Creek, N. J., 134; Woodbury Creek, N. J., Raccoon River, N. J., Indian River, Del., 135; north branch of Susquehanna River, Pa., 136; construction of iron pier in Delaware Bay, near Lewes, Del., Delaware Breakwater Harbor, Del., removal of wrecks from Delaware Bay and River, 137; removing sunken vessels obstructing or endangering navigation; Port Warden's Lines, Philadelphia, Pa., 138; examinations and surveys, 138.

IN CHARGE OF LIEUT. COL. WILLIAM P. CRAIGHILL, CORPS OF ENGINEERS—

Susquehanna River, near Havre de Grace, Md., 139; Elk River, Md., 140; Corica Creek, Md., Chester River, at Kent Island Narrows, Md., Chester River, Md., from Spry's Landing to Crumpton, 141; improving channel to Baltimore, Md., 142; Harbor of Annapolis, Md., 143; Choptank River, between Denton and Greensborough, Md., harbor of Cambridge, Md., 144; Upper Thoroughfare, between Deil's Island and the mainland, Broad Creek, Del., from the mouth to Laurel, Wicomico River, Md., 145; James River, Va., 146; Appomattox River, Va., 147; Shenandoah River, W. Va., 148; New River, from the mouth of Wilson, in Grayson County, Va., to mouth of Greenbrier River, W. Va., Great Kanawha River, W. Va., 149; Elk River, W. Va., Cape Fear River, N. C., 150; removing sunken vessels obstructing or endangering navigation, 151; examinations and surveys, 151.

IN CHARGE OF MAJ. PETER C. HAINS, CORPS OF ENGINEERS, BVT. LIEUT. COL., U. S. A.—

Harbors at Washington and Georgetown, D. C., 151; Potomac River in the vicinity of Washington, D. C., 152.

IN CHARGE OF MR. S. T. ABERT, U. S. CIVIL ENGINEER—

Channel at Mount Vernon, Va., 154; Neabsco Creek, Va., Breton Bay, Leonardtown, Md., Nomini Creek, Va., 155; harbor at entrance of Saint Jerome's Creek, Md., Rappahannock River, Va., 156; Totusky River, Va., 157; Urbana Creek, Va., Mattaponi River, Va., Pamunkey River, Va., 158; York River, Va., Chickahominy River, Va., 159; Staunton River, Va., 160; Dan River, between Madison, N. C., and Danville, Va., Roanoke River, N. C., 161; French Broad River, N. C., 162; examinations and surveys, 163.

IN CHARGE OF CAPT. F. A. HINMAN, CORPS OF ENGINEERS—

Harbor at Norfolk, Va., 163; improving approach to Norfolk Harbor and the United States navy-yard, between Lambert's Point and Fort Norfolk, 164; Archer's Hope River, Va., Blackwater River, Va., Nottaway River, Va., 165; North Landing River, Va. and N. C., Meherrin River, N. C., 166; Currituck Sound, Coanjok Bay, North River Bar, N. C., Scuppernon River, N. C., 167; Edenton Bay, N. C., Pamlico and Tar rivers, N. C., 168; Neuse River,

IN CHARGE OF CAPT. F. A. HINMAN, CORPS OF ENGINEERS—Continued.

N. C., Beaufort Harbor, N. C., 169; line of inland navigation from New Bern to Beaufort Harbor, N. C., via Clubfoot, Harlowe, and Newport rivers, Trent River, N. C., 171; Contentnea Creek, N. C., Cape Fear River, from Wilmington to Fayetteville, N. C., 172; Lillington River, N. C., Yadkin River, N. C., 173; New River, N. C., Great Pee Dee River, S. C., 174; Waccamaw River S. C., Santee River, S. C., 175; Wateree River, S. C., 176; Georgetown Harbor, S. C., 177; examinations and surveys, 177.

IN CHARGE OF COL. Q. A. GILLMORE, CORPS OF ENGINEERS, BVT. MAJ. GEN. U. S. A.—

Charleston Harbor, S. C., 178; Wappoo Cut, S. C., Edisto River, S. C., 180; Salkiehatchie River, S. C., 181; Ashley River, S. C., 182; Savannah Harbor and River, Ga., 183; Savannah River, Ga., 184; Savannah River above Augusta, Ga., 185; Saint Augustine Creek (Thunderbolt River), Ga., formerly Marsh, Ga., 186; Altamaha River, Ga., 187; Brunswick Harbor, Ga., 188; entrance to Cumberland Sound, Ga. and Fla., 189; inside passage between Fernandina and Saint John's River, Fla., Saint John's River, Fla., 190; Volusia Bar, Fla., 192; Upper Saint John's River, Fla., 193; examinations and surveys, 194.

GULF OF MEXICO.**IN CHARGE OF MAJ. A. N. DAMRELL, CORPS OF ENGINEERS—**

Mobile Harbor, Ala., 194; Pensacola Harbor, Fla., Key West Harbor, Fla., 195; Chattahoochee River, Ga. and Ala., Flint River, Ga., 196; Appalachicola River, Fla., Appalachicola Bay, Fla., 197; Tampa Bay, Fla., Suwanee River, Fla., Choctawhatchee River, Ala. and Fla., 198; Cahaba River, Ala., 199; Tallapoosa River, Ala., Old Town Creek, Miss., 200; La Grange Bayou, Fla., Withlacoochee River, Fla., Caloosahatchee River, Fla., Peas Creek, Fla., 201; Escambia and Conecuh rivers, Fla. and Ala., 202; Alabama River, Ala., Warrior and Tombigbee rivers, Ala. and Miss., 203; Tombigbee River above Columbus, Miss., Noxubee River, Miss., 204; Pascagoula River, Miss., Manatee River, Fla., 205; roadstead leading into Back Bay of Biloxi, Miss., removing sunken vessels obstructing or endangering navigation, 206; examinations and surveys, 206.

IN CHARGE OF CAPT. THOMAS TURTLE, CORPS OF ENGINEERS—

Inspection of the improvement at the South Pass of the Mississippi River, 206; Sabine Pass and Blue Buck Bar, Tex., 207; Sabine River, La. and Tex., Neches River, Tex., 208.

IN CHARGE OF MAJ. AMOS STICKNEY, CORPS OF ENGINEERS—

Pearl River from Jackson to Carthage, Miss., Pearl River below Jackson, Miss., 209; Amite River, La., Tangipahoa River, La., 210; Tchefuncte River, La., Tickfaw River, La., 211; Bayou Teche, La., connecting Bayou Teche with Grand Lake at Charenton, La., 212; Bayou Black, La., Bayou Courtableau, La., 213; Bayou Terrebonne, La., Bayou La Fourche, La., 214; Calcasieu River, La., Calcasieu Pass, La., 215; examinations and surveys, 216.

IN CHARGE OF MAJ. S. M. MANSFIELD, CORPS OF ENGINEERS, BVT. LIEUT. COL., U. S. A.—

Entrance to Galveston Harbor, Tex., 216; ship-channel in Galveston Bay, Tex., Trinity River, Tex., 217; Buffalo Bayou, Tex., channel over the bar at mouth of Brazos River, Tex., 218; Pass Cavallo Inlet to Matagorda Bay, Tex., Aransas Pass and Bay up to Rockport and Corpus Christi, Tex., 219; harbor at Brazos Santiago, Tex., protection of river bank at Fort Brown, Tex., 220.

WESTERN RIVERS.**IN CHARGE OF MAJ. A. M. MILLER, CORPS OF ENGINEERS—**

Red River, La., Ouachita River, Ark. and La., 221; Bayou Bartholomew, La. and Ark., Boeuf River, La., 222; Tensas River, La., Cypress Bayou, Tex. and La., Yazoo River, Miss., 223; Big Sunflower River, Miss., Tchula Lake, Miss., Tallahatchee River, Miss., 224; Coldwater River, Miss., Yallabusha River, Miss., Big Hatchee River, Tenn., 225; South Forked Deer River, Tenn., water-gauges on the Mississippi River and its principal tributaries, 226; examinations and surveys, 226.

IN CHARGE OF MAJ. MILTON B. ADAMS, CORPS OF ENGINEERS—

Removing snags, &c., from Arkansas River, Ark., 227; White and Saint Francis rivers, Ark., 228; Arkansas River at Pine Bluff and Fort Smith, Ark., Arkansas River between Fort Smith, Ark., and Wichita, Kans., 229; White River between Jacksonport and Buffalo Shoals, Ark., White River above Buffalo Shoals, Ark., 230; L'Anguille River, Ark., Black River, Ark. and Mo., Saline River, Ark., 231; examinations and surveys, 232.

IN CHARGE OF MAJ. O. H. ERNST, CORPS OF ENGINEERS—

Mississippi River, between the Illinois and Ohio rivers, 232; harbor and Mississippi River at Alton, Mississippi River opposite the city of Saint Louis, Mo., 234; Mississippi River at or near Cape Girardeau, Mo., and Minton Point, Ill., Osage River, Kans. and Mo., 235.

IN CHARGE OF MAJ. CHARLES R. SUTER, CORPS OF ENGINEERS—

Removing snags and wrecks from the Mississippi and Missouri rivers, 236; Missouri River from its mouth to Sioux City, Iowa, &c., survey of Missouri River from its mouth to Fort Benton, Mont.; Gasconade River, Mo., 237.

IN CHARGE OF CAPT. JAMES B. QUINN, CORPS OF ENGINEERS—

Missouri River from Sioux City to Fort Benton, Mont., 237; Yellowstone River, Mont., and Dak., 238.

IN CHARGE OF MAJ. ALEXANDER MACKENZIE, CORPS OF ENGINEERS—

Upper Mississippi River, operations of spag-boat, &c., 238; Mississippi River from Saint Paul to the Des Moines Rapids, Mississippi River from Des Moines Rapids to mouth of Illinois River, 239; harbors of refuge on Lake Pepin, removal of bar in Mississippi River opposite Dubuque, Iowa, ice harbor at Dubuque, Iowa, 240; Rock Island Rapids, Mississippi River, harbor at Rock Island, Ill., harbor at Muscatine, Iowa, 241; Des Moines Rapids, Mississippi River, operating and care of Des Moines Rapids Canal, 242; dry dock at the Des Moines Rapids Canal, Mississippi River at Quincy, Ill., Quincy Bay, Ill., 243; examinations and surveys, 244.

TEST OF THE ADAMS FLUME..... 244

IN CHARGE OF MAJ. CHARLES J. ALLEN, CORPS OF ENGINEERS—

Preservation of Falls of Saint Anthony, Minn., 244; Mississippi River above the Falls of Saint Anthony, Minn., construction of lock and dam on Mississippi River at Meeker's Island, Minn., 245; Chippewa River, Wis., Chippewa River at Yellow Banks, Wis., 246; Saint Croix River below Taylor's Falls, Minn. and Wis., Minnesota River, Minn., 247; Red River of the North, Minn. and Dak., lock and dam at Goose Rapids on Red River of the North, Minn. and Dak., 248; reservoirs upon the headwaters of the Mississippi River and its tributaries, 249; surveys for reservoirs at the sources of the Mississippi, Saint Croix, Chippewa, and Wisconsin rivers, 250; examinations and surveys, 250.

IN CHARGE OF MAJ. WILLIAM R. KING, CORPS OF ENGINEERS—

Tennessee River, 250; Cumberland River, 252; Hiwassee River, French Broad River, Tenn., 254; Clinch River, Tenn., Duck River, Tenn., Obey's River, Tenn., 255; Caney Fork River, Tenn., Coosa River, Ga. and Ala., 256; Oostenaula and Coosawattee rivers, Ga., Ocmulgee River, Ga., 257; Oconee River, Ga., 258; Red River, Tenn., Little Tennessee River, Tenn., South Fork Cumberland River, Ky., 259; examinations and surveys, 260.

IN CHARGE OF LIEUT. COL. WILLIAM E. MERRILL, CORPS OF ENGINEERS, BVT. COL., U. S. A.—

Ohio River, 260; operating and care of Louisville and Portland Canal, 261; falls of the Ohio River at Louisville, Ky., Monongahela River, W. Va. and Pa., Allegheny River, Pa., 262; ice harbor at mouth of Muskingum River, Ohio, harbor of refuge near Cincinnati, Ohio, 263; examinations and surveys, 263.

IN CHARGE OF CAPT. JAMES C. POST, CORPS OF ENGINEERS—

Kentucky River, Ky., Tradewater River, Ky., 264; Big Sandy River, W. Va. and Ky., 265; Guyandotte River, W. Va. and Ky., Little Kanawha River, W. Va., 266; examination, 267.

IN CHARGE OF MAJ. JARED A. SMITH, CORPS OF ENGINEERS—

Wabash River, Ind. and Ill., 267; White River, Ind., 268; examination, 269.

BRIDGING NAVIGABLE WATERS OF THE UNITED STATES.

Bridge across Thames River, near New London, Conn., bridge across the Ohio River, at the city of Wheeling, W. Va., bridge across the Ohio River, near Beaver, Pa., 268; bridge across the Arkansas River, at Little Rock, Ark., bridge across the Arkansas River, at Van Buren, Ark., bridge across the Saint Croix River, in the States of Wisconsin and Minnesota, 270; pile and ponton bridge across the Mississippi River, at Dubuque, Iowa, bridges across the Great Kanawha River, W. V., 271.

LAKE HARBORS AND RIVERS.

IN CHARGE OF MAJ. CHARLES J. ALLEN, CORPS OF ENGINEERS—

Harbor at Duluth, Minn., 271; dredging Superior Bay, Wis., 272; harbor at Grand Marais, Minn., 273.

IN CHARGE OF LIEUT. COL. J. W. BARLOW, CORPS OF ENGINEERS—

Ontonagon Harbor, Mich., 273; Eagle Harbor, Mich., Marquette Harbor, Mich., 274; harbor of refuge at Grand Marais, Mich., 275; Manistique Harbor, Mich., harbor at mouth of Cedar River, Mich., 276; Menomonee Harbor, Mich. and Wis., Oconto Harbor, Wis., 277; Pensaukee Harbor, Wis., Green Bay Harbor, Wis., 278; harbor of refuge at entrance of Sturgeon Bay Canal, Wis., 279; Ahnapee Harbor, Wis., Keweenaw Harbor, Wis., 280; Two Rivers Harbor, Wis., 281; Manitowish Harbor, Wis., Sheboygan Harbor, Wis., 282; Port Washington Harbor, Wis., 283; removal of sunken vessels obstructing or endangering navigation, 284.

IN CHARGE OF CAPT. W. L. MARSHALL, CORPS OF ENGINEERS—

Harbor of refuge, Milwaukee Bay, Wis., 284; Milwaukee Harbor, Wis., Racine Harbor, Wis., 285; Kenosha Harbor, Wis., Waukegan Harbor, Ill., 286; Fox and Wisconsin rivers, 287; examination, 289.

IN CHARGE OF MAJ. W. H. H. BENTLEY, CORPS OF ENGINEERS—

Chicago Harbor, Ill., 289; Calumet Harbor, Ill., Calumet River, Ill., Illinois River, Ill., 290; examinations and surveys, 291.

IN CHARGE OF MAJ. JARED A. SMITH, CORPS OF ENGINEERS—

Harbor at Michigan City, Ind., 292; harbor at New Buffalo, Mich., 293.

IN CHARGE OF CAPT. D. W. LOCKWOOD, CORPS OF ENGINEERS—

Charlevoix Harbor, Mich., 293; Frankfort Harbor, Mich., harbor of refuge at Portage Lake, Mich., 294; Manistee Harbor, Mich., Ludington Harbor, Mich., 295; Pentwater Harbor, Mich., White River Harbor, Mich., 296; Muskegon Harbor, Mich., Grand Haven Harbor, Mich., 297; Grand River, Mich., Black Lake Harbor, Mich., 298; Saginaw Harbor, Mich., South Haven Harbor, Mich., 299; Saint Joseph Harbor, Mich., removal of wrecked schooner from Charlevoix Harbor, Mich., 300; examinations and surveys, 301.

IN CHARGE OF LIEUT. COL. O. M. FOK, CORPS OF ENGINEERS, BVT. BRIG. GEN., U. S. A.—

Hay Lake Channel, Saint Mary's River, Mich., 301; Saint Mary's Falls Canal and River, Mich., operating and care of Saint Mary's Falls Canal, Mich., dry dock at Saint Mary's Falls Canal, Mich., 302; harbor at Cheboygan, Mich., harbor at Thunder Bay, Mich., 303; harbor at Au Sable, Mich., Saginaw River, Mich., 304; harbor of refuge, Sand Beach, Lake Huron, Mich., 305; ice-harbor of refuge, Belle River, Mich., repairs of Saint Clair Flats Canal, Mich., operating and care of Saint Clair Flats Ship-Canal, Mich., 306; Clinton River, Mich., Detroit River, Mich., 307; examinations and surveys, 308.

IN CHARGE OF MAJ. L. COOPER OVERMAN, CORPS OF ENGINEERS—

Monroe Harbor, Mich., 308; Toledo Harbor, Ohio, 309; Port Clinton Harbor, Ohio, 310; Sandusky City Harbor, Ohio, 311; Sandusky River, Ohio, 312; Huron Harbor, Ohio, Vermillion Harbor, Ohio, 313; Mouth of Black River, Ohio, 314; Rocky River, Ohio, Cleveland Harbor, Ohio, 315; Fairport Harbor, Ohio, 317; examination, 318.

IN CHARGE OF CAPT. EDWARD MAGUIRE, CORPS OF ENGINEERS—

Ashtabula Harbor, Ohio, 318; Conneaut Harbor, Ohio, Erie Harbor, Pa., 319; Dunkirk Harbor, N. Y., 320; Buffalo Harbor, N. Y., Niagara River, N. Y., 321.

IN CHARGE OF LIEUT. COL. HENRY M. ROBERT, CORPS OF ENGINEERS—

Wilson Harbor, N. Y., Olcott Harbor, N. Y., Oak Orchard Harbor, N. Y., 322; Charlotte Harbor, N. Y., 323; Pultneyville Harbor, N. Y., Great Sodus Harbor, N. Y., 324; Little Sodus Harbor, N. Y., Oswego Harbor, N. Y., 325; Sackett's Harbor, N. Y., 326; Ogdensburg Harbor, N. Y., Grass River, N. Y., Plattsburg Harbor, N. Y., 327; Swanton Harbor, Vt., Burlington Harbor, Vt., 328; Otter Creek, Vt., Ticonderoga River, N. Y., 329; examinations and surveys, 330.

PACIFIC COAST.

IN CHARGE OF LIEUT. COL. GEORGE H. MENDELL, CORPS OF ENGINEERS—

Oakland Harbor, Cal., 330; Wilmington Harbor, Cal., Sacramento and Feather rivers, Cal., 331; San Joaquin River, Cal., Petaluma Creek, Cal., 332; Humboldt Bay and Harbor, Cal., removal of sunken vessels obstructing or endangering navigation, 333; examinations and surveys, 334.

IN CHARGE OF COL. C. SEAFORTH STEWART, CORPS OF ENGINEERS—

Harbor at San Diego, Cal., 334.

IN CHARGE OF CAPT. CHARLES F. POWELL, CORPS OF ENGINEERS—

Lower Willamette and Columbia rivers, Oreg. and Wash., 334; Mouth of Columbia River, Oreg., 335; Upper Willamette River, Oreg., 336; Upper Columbia and Snake rivers, Oreg. and Wash., 336; Columbia River at the Cascades, Oreg., 337; entrance to Coos Bay, Oreg., entrance to Yaquina Bay, Oreg., 338; mouth of Coquille River, Oreg., Cowlitz River, Wash., 339; Skagit, Stie-laquamish, Nootsack, Snohomish, and Snoqualmie rivers, Wash., Chehalis River, Wash., 340; Lower Clearwater River, Idaho, gauging waters of Columbia River and principal tributaries, 341; examinations, 342.

EXAMINATIONS, SURVEYS, AND CONTINGENCIES OF RIVERS AND HARBORS.

Estimate for 1885-'86..... 342

WASHINGTON AQUEDUCT, ETC.

IN CHARGE OF MAJ. G. J. LYDECKER, CORPS OF ENGINEERS—

Washington Aqueduct, 342; increasing water supply to city of Washington, 343; erection of fishways at Great Falls of the Potomac, 344.

PUBLIC BUILDINGS, GROUNDS, ETC., DISTRICT OF COLUMBIA.

IN CHARGE OF COL. A. F. ROCKWELL, UNITED STATES ARMY 344

MISSISSIPPI RIVER COMMISSION..... 344

PRINTING AND DISTRIBUTION OF CHARTS OF THE NORTHERN AND NORTHWESTERN LAKES..... 345

MILITARY AND GEOGRAPHICAL MAPS..... 345

GEOGRAPHICAL SURVEYS WEST OF THE 100TH MERIDIAN.

IN CHARGE OF CAPT. GEORGE M. WHEELER, CORPS OF ENGINEERS 34

RECONNAISSANCES AND EXPLORATIONS.

Officers on duty at headquarters of the Army, of divisions, and departments 347; reports made, 348-9; estimate for surveys and reconnaissances and publications of maps, 349.

OFFICE OF THE CHIEF OF ENGINEERS.

Officers of the Corps of Engineers in charge of Divisions 349, 35

STATEMENT OF RANK AND DUTIES OF OFFICERS OF THE CORP
OF ENGINEERS DURING THE FISCAL YEAR 35LAWS AFFECTING THE CORPS OF ENGINEERS, 48TH CONGRESS
1ST SESSION, 1883-'84 37

APPENDIX No. 1.

REPORT OF CAPT. W. H. BIXBY, CORPS OF ENGINEERS.

Preparation of report upon investigations in Europe in 1881-'82 42

APPENDIXES Nos. 1 AND 2.

REPORT OF LIEUT. COL. H. L. ABBOT, CORPS OF ENGINEERS, BVT
BRIG. GEN., U. S. A.No. 1. BATTALION OF ENGINEERS AND ENGINEER SCHOOL OF APPLICA
TION 42

No. 2. ENGINEER DEPOT AND POST AT WILLETS POINT 45

RIVERS AND HARBORS, ETC.

APPENDIX A.

REPORT OF COL. CHARLES E. BLUNT, CORPS OF ENGINEERS

IMPROVEMENTS.—Lubec Channel, Me., 460; Moose-a-bec Bar at Jonesport, Me., 462; Belfast Harbor, Me., 463; Rockland Harbor, Me., 464; Cathance River, Me., 465; Royal River, Me., 466; Portland Harbor, Me., 467; Kennebunk River, Me., 468; Portsmouth Harbor, N. H., 469; Cocheco River, N. H., 471; Lamprey River, N. H., 472.

EXAMINATIONS AND SURVEYS.—Androscoggin River, below Brunswick, Me., 473; for extension and completion of the breakwater near the Third Bridge in Portsmouth Harbor, N. H., connecting Goat Island and New Castle, 474; Penobscot River and Bangor Harbor, Me., 475; breakwater at the mouth of Saco River, Me., 482; at and near mouth of the Great Bay, so called, with a view to increasing the depth of the flow of water, and improvement of the navigation of the Piscataqua River and its tributaries, 485.

APPENDIX B.

REPORT OF MAJ. CHARLES W. RAYMOND, CORPS OF ENGINEERS.

IMPROVEMENTS.—Newburyport Harbor, Mass., 493; Merrimac River, Mass., 500; Scituate Harbor, Mass., 502; Boston Harbor, Mass., 503; Plymouth Harbor, Mass., 514; Provincetown Harbor, Mass., 518; Lynn Harbor, Mass., 520; Malden River, Mass., 551; removal of sunken vessels or craft endangering or obstructing navigation, 552.

EXAMINATIONS AND SURVEYS.—The Headland in the town of Hull, at the entrance to Boston Harbor, Mass., 552; Ipswich River and Harbor, Mass., 557; Sandy Bay, Rockport, Mass., with a view to construction of a breakwater for a harbor of refuge, 565; Boston Harbor, Mass., and Fort Point Channel, and the channel leading to the wharves of the New York and New England Railroad, 588.

APPENDIX C.

REPORT OF LIEUT. COL. GEORGE H. ELLIOT, CORPS OF ENGINEERS.

IMPROVEMENTS.—Hyannis Harbor, Mass., 591; Nantucket Harbor, Mass., 593; Wood's Holl and Harbor of Refuge at Wood's Holl, Mass., 597; Wareham Harbor, Mass., 600; Taunton River, Mass., 604; Pawtucket River, R. I., 608; Providence River and Narragansett Bay, R. I., 617; Newport Harbor, R. I., 623; Block Island Harbor, R. I., 626; Little Narragansett Bay, R. I. and Conn., 629; Stonington Harbor, Conn., 630.

EXAMINATION.—Pawtuxet Harbor, R. I., 633.

APPENDIX D.

REPORT OF LIEUT. COL. WALTER MCFARLAND, CORPS OF ENGINEERS.

IMPROVEMENTS.—Thames River, Conn., 636; New London Harbor, Conn., 638; Connecticut River, Mass. and Conn., 639; Clinton Harbor, Conn., 643; New Haven Harbor, Conn., 645; breakwater at New Haven, Conn., 647; Milford Harbor, Conn., 648; Housatonic River, Conn., 650; Bridgeport Harbor, Conn., 651; Southport Harbor, Conn., 653; Norwalk Harbor, Conn., 654; Mamaroneck Harbor, N. Y., 655; Port Jefferson Harbor, N. Y., 656; Greenport Harbor, N. Y., 657.

EXAMINATIONS AND SURVEYS.—Connecticut River, from Bellows Falls, Vt., to Pittsburgh, N. H., 659; Bissell's Cove, R. I., 663; Stony Brook Harbor, N. Y., 664; Black Rock Harbor, Conn., 665; Stamford Harbor, Conn., 670; Westport Harbor, Conn., 673; Branford Harbor, Conn., 678; channel-way from Riverhead, on Peconic River, to Great Peconic Bay, Long Island, N. Y., 681; Duck Island Harbor, Conn., for a breakwater, 684; Madison Harbor, Conn., 685; Southold Harbor, Long Island, N. Y., 686.

APPENDIX E.

REPORT OF BRIG. GEN. JOHN NEWTON, CHIEF OF ENGINEERS, BVT. MAJ. GEN., U. S. A.

IMPROVEMENT.—Removing obstructions in East River and Hell Gate, N. Y., 689.

APPENDIX F.

REPORT OF CAPT. JAMES MERCUR, CORPS OF ENGINEERS.

IMPROVEMENTS.—Hudson River, N. Y., 695; Rondout Harbor, N. Y., 700; Buttermilk Channel, N. Y., 701; Harlem River, N. Y., 704; Gowanus Bay, N. Y., 706; Echo Harbor, New Rochelle, N. Y., 708; harbor at New Rochelle, N. Y., 709; Port Chester Harbor, N. Y., 712.

EXAMINATIONS AND SURVEYS.—Gowanus Creek, at Brooklyn, N. Y., 713; Minisceongo Creek, N. Y., 714; Saugerties Harbor, on Hudson River, N. Y., 715; Peekskill Harbor, on Hudson River, N. Y., 718.

APPENDIX G.

REPORT OF MAJ. GEORGE L. GILLESPIE, CORPS OF ENGINEERS, BVT. LIEUT. COL., U. S. A.

IMPROVEMENTS.—Flushing Bay, N. Y., 724; Newtown Creek, N. Y., 726; East Chester Creek, N. Y., 728; Canarsie Bay, N. Y., 731; Sheepshead Bay, N. Y., 732; Sumpawanus Inlet, N. Y., 734; Cheesquakes Creek, N. J., 735; Passaic River, above Newark, N. J., 737; Passaic River, from Pennsylvania Railroad bridge to its mouth, N. J., 740; channel between Staten Island and New Jersey, 742; Shrewsbury River, N. J., 745; Rahway River, N. J., 747; Elizabeth River, N. J., 748; Woodbridge Creek, N. J., 749; Manasquan River, N. J., 751; Raritan Bay, N. J., 752; Raritan River, N. J., 754; Mattawan Creek, N. J., 756; Keyport Harbor, N. J., 758; South River, N. J., 760; removal of sunken vessels obstructing or endangering navigation, 762.

EXAMINATIONS AND SURVEYS.—From Deal to Seabright, on the New Jersey coast, for a breakwater to protect the shore and harbor at Long Branch, 763; channel from Pearsall's Dock to Flat Creek, in Hempstead Bay, N. Y., 764; Newtown Creek, from its mouth to Metropolitan avenue, in Brooklyn, N. Y., 765; Shoal Harbor and Compton's Creek, N. J., 770; North River, in front of Jersey City and Hoboken, to determine what is necessary to permanently deepen the channel on the New Jersey side, 774; Passaic River, between Passaic and Paterson, N. J., 780.

APPENDIX H.

REPORT OF MAJ. W. H. HEUER, CORPS OF ENGINEERS.

IMPROVEMENTS.—Delaware River, between Trenton, N. J., and Bridesburg, Pa., 792; Delaware River, below Bridesburg, Pa., 794; Delaware River, at Schooner Ledge, 808; Delaware River, near Cherry Island Flats, 809; Frankford Creek, Pa., 810; Schnylkill River, Pa., 811; ice Harbor at Marcus Hook, Pa., 814; ice Harbor at Chester, Pa., 816; ice Harbor at New Castle, Del., 816; ice Harbor at Reedy Island, Del., 817; Wilmington Harbor, Del., 826; Broadkill River, Del., 828; Mispillion Creek, Del., 829; Duck Creek, Del., 830; Cohansey Creek, N. J., 831; Salem River, N. J., 832; Rancocas River, N. J., 833; Saint Jones River, Del., 835; Maurice River, N. J., 836; Mantua Creek, N. J., 837; Woodbury Creek, N. J., 838; Raccoon River, N. J., 839; Indian River, Del., 840; north branch of Susquehanna River, Pa., 842; construction of iron pier in Delaware Bay, near Lewes, Del., 843; Delaware Breakwater Harbor, Del., 845; removal of wrecks from Delaware Bay and River, 847; removing sunken vessels or craft obstructing or endangering navigation, 850; Port Warden's Lines, Philadelphia, Pa., 851.

EXAMINATIONS AND SURVEYS.—Pensauken Creek, N. J., 852; Leipsic River, Del., from the Delaware River to the town of Leipsic, 854; Delaware River, between Trenton, N. J., and Port Jervis, N. Y., 855; Delaware River in front of Philadelphia, with a view to its improvement by removal of Windmill or Smith's Island, or the bar above the same, 858; north branch of the Susquehanna River, from Pittston to Athens, Pa., 869; Brandywine River, from its mouth to the Market Street Bridge in the city of Wilmington, Del., 879.

PART II.

APPENDIX I.

REPORT OF LIEUT. COL. WILLIAM P. CRAIGHILL, CORPS OF ENGINEERS.

IMPROVEMENTS.—Susquehanna River, near Havre de Grace, Md., 888; Elk River, Md., 889; Corsica Creek, Md., 891; Chester River, at Kent Island Narrows, Md., 893; Chester River, Md., from Spry's Landing to Crumpton, 893; channel to Baltimore, Md., 894; harbor of Annapolis, Md., 900; Choptank River, between Denton and Greensborough, Md., 901; harbor of Cambridge, Md., 902; Upper Thoroughfare, between Deil's Island and the mainland, 903; Broad Creek, Del., from the mouth to Laurel, 903; Wicomico River, Md., 903; James River, Va., 904; Appomattox River, Va., 913; Shenandoah River, W. Va., 927; New River, from the mouth of Wilson, in Grayson County, Va., to mouth of Greenbrier River, W. Va., 928; Great Kanawha River, W. Va., 928; Elk River, W. Va., 936; Cape Fear River, N. C., 937; removing sunken vessels obstructing or endangering navigation, 948.

EXAMINATIONS AND SURVEYS.—Pocomoke River, Md., with a view to a cut-off in the bend just below Snow Hill, 949; Manokin River, Md., from its mouth to Princess Anne, 951; Pungoteague Creek, from Bogg's wharf to the warehouse, Accomac County, Va., 952; Cherrystone Creek, Va., 953; Wetipquin Creek, Md., 956; Isle of Wight and Upper Synepuxent bays, Md., and Indian River, Del., with the intervening land, with a view to connect their waters, 957; Wicomico River, Md., from its mouth to Salisbury, 959; Hunting Creek, Monty, Va., 961; Dividing Creek, Talbot County, Md., 962.

APPENDIX J.

REPORT OF MAJ. PETER C. HAINS, CORPS OF ENGINEERS, BVT.
LIEUT. COL., U. S. A.

IMPROVEMENTS.—Harbors at Washington and Georgetown, D. C., 965; Potomac River in the vicinity of Washington, D. C., 970.

APPENDIX K.

REPORT OF MR. S. T. ABERT, UNITED STATES CIVIL ENGINEER.

IMPROVEMENTS.—Channel at Mount Vernon, Va., 980; Neabsco Creek, Va., 980; Breton Bay, Leonardtown, Md., 981; Nomini Creek, Va., 982; harbor at entrance of Saint Jerome's Creek, Md., 984; Rappahannock River, Va., 985; Totasky River, Va., 988; Urbana Creek, Va., 990; Mattaponi River, Va., 991; Pamunkey River, Va., 992; York River, Va., 994; Chickahominy River, Va., 996; Staunton River, Va., 998, 999; Dan River, between Madison, N. C., and Danville, Va., 1000; Roanoke River, N. C., 1001; French Broad River, N. C., 1002.

EXAMINATIONS AND SURVEYS.—Hull's Creek, Northumberland County, Va., 1004; Piscataway Creek, Prince George's County, Md., 1005; Chicamuxen Creek, Charles County, Md., 1005, Piscataway Creek, Essex County, Va., 1006; Port Tobacco Creek, Charles County, Md., 1008; Quantico Creek, Va., 1010; Piankatank River, Va., 1013; Great Wicomico River, from Cedar Point to Indian Point, Northumberland County, Va., 1016; Roanoke River, N. C., 1020.

APPENDIX L.

REPORT OF CAPT. F. A. HINMAN, CORPS OF ENGINEERS.

IMPROVEMENTS.—Harbor at Norfolk, Va., 1028; approach to Norfolk Harbor and the United States navy-yard, between Lambert's Point and Fort Norfolk, 1030; Archer's Hope River, Va., 1031; Blackwater River, Va., 1031; Notaway River, Va., 1031; North Landing River, Va. and N. C., 1032; Meherrin River, N. C., 1034; Currituck Sound, Coanok Bay, and North River Bar, N. C., 1034; Scuppernon River, N. C., 1035; Edenton Bay, N. C., 1035; Pamlico and Tar rivers, N. C., 1036; Nause River, N. C., 1037; Beaufort Harbor, N. C., 1039; line of inland navigation from New Berne to Beaufort Harbor, N. C., via Clubfoot, Harlowe, and Newport rivers, 1040; Trent River, N. C., 1041; Contentnea Creek, N. C., 1042; Cape Fear River, from Wilmington to Fayetteville, N. C., 1042; Lillington River, N. C., 1044; Yadkin River, N. C., 1045; New River, N. C., 1046; Great Pee Dee River, S. C., 1047; Waccamaw River, S. C., 1048; Santee River, S. C., 1049; Wateree River, S. C., 1051; Georgetown Harbor, S. C., 1052.

EXAMINATIONS AND SURVEYS.—Milford Haven, Va., 1053; the Sound between Beaufort and New River, and of White Oak River to Smith's Mill's, N. C., 1055; Waccamaw River, between Conwayborough, S. C., and Waccamaw Lake, N. C., 1056; Broad River, from Rutherfordton, N. C., to South Carolina line, 1058; Alligator River, N. C., 1059; Black River, N. C., 1061; the Sound between Morehead City, in Carteret County, N. C., 1062; Town Creek, Beaufort County, N. C., 1063; Bay River, N. C., 1064; Cape Fear River, above Fayetteville, N. C., 1064; Clubfoot, Harlowe, and Newport rivers, N. C., on line of inland navigation to Beaufort Harbor, N. C., 1065; Edenton Bay, N. C., 1071.

APPENDIX M.

REPORT OF COL. Q. A. GILLMORE, CORPS OF ENGINEERS, BVT. MAJ.
GEN., U. S. A.

IMPROVEMENTS.—Charleston Harbor, S. C., 1078; Wappoo Cut, S. C., 1089; Edisto River, S. C., 1092; Salkiechatchie River, S. C., 1094; Ashley River, S. C., 1097; Savannah Harbor and River, Ga., 1098; Savannah River, Ga., 1107; Savannah River above Augusta, Ga., 1110; Saint Augustine Creek (Thunderbolt River), Ga., 1111; Romerly Marsh, Ga., 1111; Altamaha River, Ga., 1114; Brunswick Harbor, Ga., 1118; entrance to Cumberland Sound, Ga. and Fla., 1121; inside passage between Fernandina and Saint John's River, Fla., 1125; Saint John's River, Fla., 1126; Volusia Bar, Fla., 1134; Upper Saint John's River, Fla., 1137.

EXAMINATIONS AND SURVEYS.—The channel of Saint John's River at its entrance into and exit out of Lake Monroe, and between Lake George and Lake Monroe, for straightening and improving the navigation of said river between the said lakes, 1135; to open a passage between the north end of Indian River and Mosquito Lagoon, Fla., 1143.

APPENDIX N.

REPORT OF MAJ. A. N. DAMRELL, CORPS OF ENGINEERS.

IMPROVEMENTS.—Mobile Harbor, Ala., 1152; Pensacola Harbor, Fla., 1161; Key West Harbor, Fla., 1166; Chattahoochee River, Ga. and Ala., 1167; Flint River, Ga., 1170; Appalachicola River, Fla., 1174; Appalachicola Bay, Fla., 1175; Tampa Bay, Fla., 1178; Suwanee River, Fla., 1179; Choctawhatchee River, Ala. and Fla., 1180; Cahaba River, Ala., 1186; Tallapoosa River, Ala., 1189; Old Town Creek, Miss., 1191; La Grange Bayou, Fla., 1192; Withlacoochee River, Fla., 1194; Caloosahatchee River, Fla., 1195; Peas Creek, Fla., 1196; Escambia and Conecuh rivers, Fla. and Ala., 1197; Alabama River, Ala., 1200; Black Warrior and Tombigbee rivers, Ala. and Miss., 1204; Tombigbee River above Columbus, Miss., 1210; Noxubee River, Miss., 1211; Pascagoula River, Miss., 1214; Manatee River, Fla., 1215; roadstead leading into Back Bay of Biloxi, Miss., 1217; removing sunken vessels obstructing or endangering navigation, 1217.

EXAMINATIONS AND SURVEYS.—Harbor at Cedar Keys, Fla., especially the northwest channel, 1218; channel inside the shoals along the coast of Florida, from Cedar Keys to Clear Water Harbor and Tampa, Fla., 1220; Saint Mark's River, Fla., 1222; harbor at Cedar Keys, Fla., 1223; shoal between Dauphin Island and Cedar Point, Ala., 1227.

APPENDIX O.

REPORT OF CAPT. THOMAS TURTLE, CORPS OF ENGINEERS.

INSPECTION.—Improvement at the South Pass of the Mississippi River, 1235.

APPENDIX P.

REPORT OF CAPT. THOMAS TURTLE, CORPS OF ENGINEERS.

IMPROVEMENTS.—Sabine Pass and Blue Buck Bar, Tex., 1249; Sabine River, La. and Tex., 1255; Neches River, Tex., 1256.

APPENDIX Q.

REPORT OF MAJ. AMOS STICKNEY, CORPS OF ENGINEERS.

IMPROVEMENTS.—Pearl River from Jackson to Carthage, Miss., 1259; Pearl River below Jackson, Miss., 1262; Amite River, La., 1263; Tangipahoa River, La., 1266; Tchefuncte River, La., 1268; Tickfaw River, La., 1271; Bayou Teche, La., 1272; connecting Bayou Teche with Grand Lake at Charenton, La., 1275; Bayou Black, La., 1276; Bayou Courtableau, La., 1277; Bayou Terrebonne, La., 1279; Bayou La Fourche, La., 1280; Calcasien River, La., 1281; Calcasien Pass, La., 1282.

EXAMINATIONS AND SURVEYS.—Bogue Falia, La., 1283; Atchafalaya River between Berwick's Bay and the Gulf of Mexico, 1285; water-route to connect Calcasien River with Sabine Pass, 1285; Pearl River, Miss., above Carthage, 1286; Natalbany River, La., 1289; Bayou La Fourche, La., 1291.

APPENDIX R.

REPORT OF MAJ. S. M. MANSFIELD, CORPS OF ENGINEERS, BVT.
LIEUT. COL., U. S. A.

REMARKS.—Entrance to Galveston Harbor, Tex., 1295; ship-channel in Galveston Bay, Tex., 1303; Trinity River, Tex., 1304; Buffalo Bayou, Tex., mouth of Brazos River, Tex., 1309; Pass Cavallo Inlet to Matagorda Bay; Aransas Pass and Bay, up to Rockport and Corpus Christi, Tex., harbor at Brazos Santiago, Tex., 1316; protection of river bank at Fort Brown, Tex., 1320.

APPENDIX S.

REPORT OF MAJ. A. M. MILLER, CORPS OF ENGINEERS.

REMARKS.—Red River, La., 1322; Ouachita River, Ark. and La., 1329; Bartholomew, La. and Ark., 1330; Boeuf River, La., 1331; Tensas River, La., 1331; Cypress Bayou, Tex. and La., 1332; Yazoo River, Miss., 1333; Big River, 1344; Tchula Lake, Miss., 1335; Tallahatchee River, Miss., Coldwater River, Miss., 1336; Yallabusha River, Miss., 1337; Big Hat River, Tenn., 1337; South Forked Deer River, Tenn., 1338; water-ganges of the Mississippi River and its principal tributaries, 1341.

EXAMINATIONS AND SURVEYS.—Yallabusha River, above Grenada, Miss., 1342; Osage River, Miss., 1344; Sulphur River, Tex., from its mouth to Sulphur Station, 1345; Bayou Roundaway and Bayou Vidal, La., 1347; Ouachita River, from Camden to Arkadelphia, Ark., 1351; Yazoo Pass, with a view of connection with the Mississippi River, 1355; Roebuck Lake, a tributary of the Yazoo River, Miss., 1357; Steele's Bayou, Miss., from its mouth to Swan in Washington County, 1360; Black River, from its mouth to Trinity, shortening its channel by a cut-off, 1363; Loggy Bayou, Lake Biste and the Dorcheat, La., 1363; Cane River, La., 1366; Petit Anse Bayou, La., 1369; mouth of Lake Palmyra, where it enters the Mississippi River, 1370; D'Arbonne River, La., 1372; the harbors of Monroe and Trenton, La., 1373; Ouachita River, from its mouth to Camden, Ark., 1386.

APPENDIX T.

REPORT OF MAJ. MILTON B. ADAMS, CORPS OF ENGINEERS.

REMARKS.—Removing snags, wrecks, &c., from Arkansas River, Ark., White and Saint Francis rivers, Ark., 1392; Arkansas River at Pine Bluff, Ark., 1393; Arkansas River between Fort Smith, Ark., and Wichita, Ark., 1399; White River between Jacksonport and Buffalo Shoals, Ark., 1401; Arkansas River above Buffalo Shoals, Ark., 1402; L'Anguille River, Ark., 1403; Arkansas River, Ark. and Mo., 1403; Saline River, Ark., 1404.

EXAMINATIONS AND SURVEYS.—Arkansas River, from Wichita, Kans., to Fort Smith, Indian Territory, 1405; Little River and Saline Creek, Ark., 1406; Big River, Ark., from its mouth up, 1408; White River, Ark., at the Memphis and Little Rock Railroad Bridge, near Duval's Bluff, with a view of removing obstructions from the channel, 1409.

APPENDIX U.

REPORT OF MAJ. O. H. ERNST, CORPS OF ENGINEERS.

REMARKS.—Mississippi River, between the Illinois and Ohio rivers, 1411; Mississippi River at Alton, Ill., 1527; Mississippi River opposite City of Saint Louis, Mo., 1527; Mississippi River at or near Cape Girardeau, Mo., 1529; Osage River, Kans. and Mo., 1529.

PART III.

APPENDIX V.

REPORT OF MAJ. CHARLES R. SUTER, CORPS OF ENGINEERS.

IMPROVEMENTS.—Removing snags and wrecks from the Mississippi and Missouri rivers, 1531; Missouri River from its mouth to Sioux City, Iowa, 1532; survey of Missouri River from its mouth to Fort Benton, Mont., 1533; Gasconade River, Mo., 1540.

APPENDIX W.

REPORT OF CAPT. JAMES B. QUINN, CORPS OF ENGINEERS.

IMPROVEMENTS.—Missouri River from Sioux City, Iowa, to Fort Benton, 1541; Yellowstone River, Mont. and Dak., 1543.

APPENDIX X.

REPORT OF MAJ. ALEXANDER MACKENZIE, CORPS OF ENGINEERS.

IMPROVEMENTS.—Upper Mississippi River, operations of snag-boat, &c., 1544; Mississippi River from Saint Paul to the Des Moines Rapids, 1550; Mississippi River from Des Moines Rapids to mouth of Illinois River, 1560; harbors refuge on Lake Pepin, 1570; removal of bar in Mississippi River opposite Dubuque, Iowa, 1571; ice-harbor at Dubuque, Iowa, 1571; Rock Island Rapids, Mississippi River, 1572; harbor at Rock Island, Ill., 1575; harbor at Muscatine, Iowa, 1575; Des Moines Rapids, Mississippi River, 1576; operating at Des Moines Rapids Canal, 1580; dry-dock at the Des Moines Rapids Canal, 1586; Mississippi River at Quincy, Ill., 1588; Quincy Bay, 1590.

EXAMINATIONS AND SURVEYS.—Iowa River from Wapello to its mouth, 1591; Pecatonica River from Argyle to Wayne, La Fayette County, Wis., 1593.

APPENDIX Y.

REPORT OF MAJ. CHARLES J. ALLEN, CORPS OF ENGINEERS.

IMPROVEMENTS.—Preservation of Falls of Saint Anthony, Minn., 1596; Mississippi River above the Falls of Saint Anthony, Minn., 1597; construction of lock and dam on Mississippi River at Mecker's Island, Minn., 1599; Chippewa River, Wis., 1600; Chippewa River at Yellow Banks, Wis., 1603; Saint Croix River below Taylor's Falls, Minn. and Wis., 1606; Minnesota River, Minn., 1609; Red River of the North, Minn. and Dak., 1610; construction of lock and dam at Goose Rapids on Red River of the North, Minn. and Dak., 1612; reservoir upon the headwaters of the Mississippi River and its tributaries, 1614; surveys for reservoirs at the sources of the Mississippi, Saint Croix, Chippewa and Wisconsin rivers, 1631.

EXAMINATIONS AND SURVEYS.—The source of Minnesota River, near the foot of Big Stone Lake, with a view of its being added to the reservoir system of the Mississippi and its tributaries, 1632; the lakes near the headwaters of Cannon River, in Rice and Le Sueur counties, Minn., with a view to adding the same to the reservoir system of the Mississippi and its tributaries, 1634; Minnesota River, near the village of Belle Plaine, with a view to preventing the washing away of the banks of said river opposite said village, 1637.

APPENDIX Z.

REPORT OF MAJ. WILLIAM R. KING, CORPS OF ENGINEERS.

IMPROVEMENTS.—Tennessee River, 1639; Cumberland River, 1644; Hiwassee River, 1649; French Broad River, Tenn., 1650; Clinch River, Tenn., 1651; Duck River, Tenn., 1651; Obey's River, Tenn., 1652; Caney Fork River, Tenn., 1653; Coosa River, Ga. and Ala., 1654; Oostenaule and Coosawattee rivers, Ga., 1656; Ocmulgee River, Ga., 1656; Oconee River, Ga., 1658; Red River, Tenn., 1659; Little Tennessee River, Tenn., 1659; South Fork Cumberland River, Ky., 1660.

EXAMINATIONS AND SURVEYS.—Cumberland River and its principal tributaries above Pineville, Ky., 1661; cost of placing locks and dams on the Cumberland River, from Nashville, Tenn., to the Cincinnati Southern Railroad, in Ky., 1662.

APPENDIX A A.

REPORT OF LIEUT. COL. WILLIAM E. MERRILL, CORPS OF ENGINEERS, BVT. COL., U. S. A.

IMPROVEMENTS.—Ohio River, 1678; operating and care of Louisville and Portland Canal, 1692; falls of the Ohio River at Louisville, Ky., 1699; Monongahela River, W. Va. and Pa., 1699; Allegheny River, Pa., 1702; ice-harbor at mouth of Muskingum River, Ohio, 1703; harbor of refuge near Cincinnati, Ohio, 1703.

EXAMINATIONS AND SURVEYS.—Tionesta Creek, Pa., 1704; ice-harbor at Middleport, Meigs County, Ohio, 1707; Ohio River at Rochester and Freedom, Pa., for ice-breakers, 1710; channel through Grand and Little Chains in the Ohio River, 1715; Youghiogheny River, from McKeesport to Connellsville, Pa., 1716; Tygart's Valley and Buckhannon rivers, W. Va., 1718.

APPENDIX B B.

REPORT OF CAPT. JAMES C. POST, CORPS OF ENGINEERS.

IMPROVEMENTS.—Kentucky River, Ky., 1723; Tradewater River, Ky., 1747; Big Sandy River, W. Va. and Ky., 1749; Guyandotte River, W. Va., 1753; Little Kanawha River, W. Va., 1754.

EXAMINATION.—Louisa Fork of the Big Sandy River to Grundy Court House, Va., 1755.

APPENDIX C C.

REPORT OF MAJ. JARED A. SMITH, CORPS OF ENGINEERS.

IMPROVEMENTS.—Wabash River, Ind. and Ill., 1757; White River, Ind., 1765.

EXAMINATION.—Stone formation in Kankakee River at Momence, Ill., 1766.

APPENDIX D D.

BRIDGING NAVIGABLE WATERS OF THE UNITED STATES.

Bridge across Thames River, near New London, Conn., 1769; bridge across the Ohio River, at the city of Wheeling, W. Va., 1772; bridge across the Ohio River, near Beaver, Pa., 1778; bridge across the Arkansas River, at Little Rock, Ark., 1788; bridge across the Arkansas River, at Van Buren, Ark., 1792; bridges across the Great Kanawha River, W. Va., 1796.

APPENDIX E E.

REPORT OF MAJ. CHARLES J. ALLEN, CORPS OF ENGINEERS.

IMPROVEMENTS.—Harbor at Duluth, Minn., 1809; dredging Superior Bay, Wis., 1818; harbor at Grand Marais, Minn., 1822.

APPENDIX F F.

REPORT OF LIEUT. COL. J. W. BARLOW, CORPS OF ENGINEERS.

IMPROVEMENTS.—Ontonagon Harbor, Mich., 1825; Eagle Harbor, Mich., 1828; Marquette Harbor, Mich., 1829; harbor of refuge at Grand Marais, Mich., 1831; Manistique Harbor, Mich., 1832; harbor at mouth of Cedar River, Mich., 1833; Menomonee Harbor, Mich. and Wis., 1835; Oconto Harbor, Wis., 1840; Pensaukee Harbor, Wis., 1842; Green Bay Harbor, Wis., 1844; harbor of refuge at entrance of Sturgeon Bay Canal, Wis., 1846; Ahnapee Harbor, Wis., 1847; Kewaunee Harbor, Wis., 1849; Two Rivers Harbor, Wis., 1851; Manitowoc Harbor, Wis., 1853; Sheboygan Harbor, Wis., 1855; Port Washington Harbor, Wis., 1858; removal of sunken vessels or craft obstructing or endangering navigation, 1860.

APPENDIX G G.

REPORT OF CAPT. W. L. MARSHALL, CORPS OF ENGINEERS.

IMPROVEMENTS.—Harbor of refuge, Milwaukee Bay, Wis., 1863; Milwaukee Harbor, Wis., 1866; Racine Harbor, Wis., 1867; Kenosha Harbor, Wis., 1869; Waukegan Harbor, Ill., 1871; Fox and Wisconsin rivers, 1872.

EXAMINATION.—Wisconsin River from Portage to Merrill, 1939.

APPENDIX H H.

REPORT OF MAJ. W. H. H. BENYAURD, CORPS OF ENGINEERS.

IMPROVEMENTS.—Chicago Harbor, Ill., 1943; Calumet Harbor, Ill., 1946; Calumet River, 1947; Illinois River, 1947.

EXAMINATIONS AND SURVEYS.—For Hennepin Canal, and for the enlargement of the Illinois and Michigan Canal, 1950; Calumet River, Ill. and Ind., 1951; Sangamon River from its mouth to Petersburg, 1952; Illinois and Des Plaines rivers, between La Salle and Joliet, 1957.

APPENDIX I I.

REPORT OF MAJ. JARED A. SMITH, CORPS OF ENGINEERS.

IMPROVEMENTS.—Harbor at Michigan City, Ind., 1965; harbor at New Buffalo, Mich., 1969.

APPENDIX J J.

REPORT OF CAPT. D. W. LOCKWOOD, CORPS OF ENGINEERS.

IMPROVEMENTS.—Charlevoix Harbor, Mich., 1971; Frankfort Harbor, Mich., 1973; harbor of refuge at Portage Lake, Mich., 1974; Manistee Harbor, Mich., 1976; Ludington Harbor, Mich., 1977; Pentwater Harbor, Mich., 1978; White River Harbor, Mich., 1981; Muskegon Harbor, Mich., 1983; Grand Haven Harbor, Mich., 1984; Grand River, Mich., 1986; Black Lake Harbor, Mich., 1987; Saugatuck Harbor, Mich., 1989; South Haven Harbor, Mich., 1991; Saint Joseph Harbor, Mich., 1993; removing wrecked schooner from Charlevoix Harbor, Mich., 1995.

EXAMINATIONS AND SURVEYS.—Harbor at Cross Village, Mich., 1995; for harbor of refuge at Ludington, Mich., 1999.

APPENDIX K K.

REPORT OF LIEUT. COL. O. M. POE, CORPS OF ENGINEERS, BVT. BRIG. GEN., U. S. A.

IMPROVEMENTS.—Hay Lake Channel, Saint Mary's River, Mich., 2004; Saint Mary's Falls Canal and River, Mich., 2011; operating and care of Saint Mary's Falls Canal, Mich., 2016; dry dock at Saint Mary's Falls Canal, Mich., 2030; harbor at Cheboygan, Mich., 2035; harbor at Thunder Bay, Mich., 2036; harbor at Au Sable, Mich., 2040; Saginaw River, Mich., 2041; harbor of refuge at Sand Beach, Lake Huron, Mich., 2046; ice-harbor of refuge at Belle River, Mich., 2070; repairs of Saint Clair Flats Canal, Mich., 2071; operating and care of Saint Clair Flats Ship-Canal, Mich., 2072; Clinton River, Mich., 2074; Detroit River, Mich., 2074.

EXAMINATIONS AND SURVEYS.—Harbor at Caseville, Mich., 2077; Sebawaing Harbor, Mich., 2079.

APPENDIX L L.

REPORT OF MAJ. L. COOPER OVERMAN, CORPS OF ENGINEERS.

IMPROVEMENTS.—Monroe Harbor, Mich., 2081; Toledo Harbor, Ohio, 2083; Port Clinton Harbor, Ohio, 2086; Sandusky City Harbor, Ohio, 2088; Sandusky River, Ohio, 2091; Huron Harbor, Ohio, 2092; Vermillion Harbor, Ohio, 2093; harbor at mouth of Black River, Ohio, 2094; mouth of Rocky River, Ohio, 2097; Cleveland Harbor, Ohio, 2097; Fairport Harbor, Ohio, 2108.

EXAMINATION.—The channel known as the old river bed, leading from Cuyahoga River to the harbor of refuge at Cleveland, Ohio, 2110.

APPENDIX M M.

REPORT OF CAPT. EDWARD MAGUIRE, CORPS OF ENGINEERS.

IMPROVEMENTS.—Ashtabula Harbor, Ohio, 2113; Conneaut Harbor, Ohio, 2118; Erie Harbor, Pa., 2120; Dunkirk Harbor, N. Y., 2124; Buffalo Harbor, N. Y., 2126; Niagara River, N. Y., 2131.

APPENDIX N N.

REPORT OF LIEUT. COL. HENRY M. ROBERT, CORPS OF ENGINEERS.

IMPROVEMENTS.—Wilson Harbor, N. Y., 2133; Olcott Harbor, N. Y., 2135; Oak Orchard Harbor, N. Y., 2136; Charlotte Harbor, N. Y., 2137; Pultneyville Harbor, N. Y., 2138; Great Sodus Harbor, N. Y., 2140; Little Sodus Harbor, N. Y., 2142; Oswego Harbor, N. Y., 2143; Sackett's Harbor, N. Y., 2151; Ogdensburg Harbor, N. Y., 2153; Grass River, N. Y., 2154; Plattsburg Harbor, N. Y., 2155; Swanton Harbor, Vt., 2156; Burlington Harbor, Vt., 2157; Otter Creek, Vt., 2158; Ticonderoga River, N. Y., 2160.

EXAMINATIONS AND SURVEYS.—Harbor at Port Marshall, Lake Champlain, N. Y., 2161; Boquet River, N. Y., 2162; Champlain River, N. Y., from the lake up to Champlain Town, 2165; harbor of Port Henry, Lake Champlain, N. Y., 2168; plan and estimate for a breakwater at Rouse's Point, on Lake Champlain, N. Y., 2172.

APPENDIX O O.

REPORT OF LIEUT. COL. GEORGE H. MENDELL, CORPS OF ENGINEERS, BVT. COL., U. S. A.

IMPROVEMENTS.—Oakland Harbor, Cal., 2177; Wilmington Harbor, Cal., 2186; Sacramento and Feather rivers, Cal., 2191; San Joaquin River, Cal., 2195; Petaluma Creek, Cal., 2198; Humboldt Harbor and Bay, Cal., 2199; removal of sunken vessels obstructing or endangering navigation, 2201.

EXAMINATIONS AND SURVEYS.—Redwood Slough, San Mateo County, Cal., 2204; Alameda Creek, Alameda County, Cal., 2207; Santa Monica Bay, Cal., 2209; Clear Lake, Lake County, Cal., 2210.

APPENDIX P P.

REPORT OF COL. C. SEAFORTH STEWART, CORPS OF ENGINEERS.

IMPROVEMENT.—Harbor at San Diego, Cal., 2213.

APPENDIX Q Q.

REPORT OF CAPT. CHARLES F. POWELL, CORPS OF ENGINEERS.

IMPROVEMENTS.—Lower Willamette and Columbia rivers, Oreg. and Wash., 2215; mouth of Columbia River, Oreg., 2222; Upper Willamette River, Oreg., 2226; Upper Columbia and Snake rivers, Oreg. and Wash., 2229; Columbia River at the Cascades, Oreg., 2246; entrance to Coos Bay, Oreg., 2260; entrance to Yaquina Bay, Oreg., 2265; mouth of Coquille River, Oreg., 2270; Cowlitz River, Wash., 2272; Skagit, Stielaquamish, Nootsack, Snohomish, and Snoqualmie rivers, Wash., 2274; Chehalis River, Wash., 2276; Lower Clearwater River, Idaho, 2279; gauging waters of Columbia River and principal tributaries, 2290.

EXAMINATIONS.—Lewis, Humptuleps, and Dwamish rivers, Wash., 2293.

APPENDIX R R.

REPORT OF MAJ. G. J. LYDECKER, CORPS OF ENGINEERS.

IMPROVEMENTS.—Washington Aqueduct, 2299; increasing the water supply of the city of Washington, D. C., and erection of fish-ways at the Great Falls of the Potomac River, 2301.

APPENDIX S S.

REPORT OF COL. A. F. ROCKWELL, UNITED STATES ARMY.

IMPROVEMENT and care of public buildings and grounds in and around Washington, D. C., 2339.

APPENDIX U U.

REPORT OF LIEUT. COL. O. M. POE, CORPS OF ENGINEERS, BVT. BRIG. GEN., U. S. A.

Issue of Published Charts of the Northern and Northwestern Lakes 2373

EXPLORATIONS AND SURVEYS.

APPENDIX V V.

REPORT OF CAPT. GEORGE M. WHEELER, CORPS OF ENGINEERS.

Geographical and Topographical Surveys of the Territory of the United States West of the One Hundredth Meridian, in the States and Territories of California, Colorado, Kansas, Nebraska, Nevada, Oregon, Texas, Arizona, Idaho, Montana, New Mexico, Utah, Washington, and Wyoming 2375

APPENDIX W W.

REPORT OF MAJ. THOMAS H. HANDBURY, CORPS OF ENGINEERS.

Explorations and Surveys in the Division of the Missouri 2379

APPENDIX X X.

REPORT OF LIEUT. DAN C. KINGMAN, CORPS OF ENGINEERS.

Explorations and Surveys in the Department of the Platte 2381

APPENDIX Y Y.

REPORT OF LIEUT. O. M. CARTER, CORPS OF ENGINEERS.

Explorations and Surveys in the Department of the Missouri 2383

APPENDIX Z Z.

REPORT OF CAPT. H. S. TABER, CORPS OF ENGINEERS.

Explorations and Surveys in the Department of Dakota 2387

APPENDIX A A A.

REPORT OF MAJ. W. R. LIVERMORE, CORPS OF ENGINEERS.

Explorations and Surveys in the Department of Texas 2391

APPENDIX B B B.

REPORT OF MAJ. WILLIAM A. JONES, CORPS OF ENGINEERS.

Explorations and Surveys in the Department of California 2397

APPENDIX C C C.

REPORT OF LIEUT. THEODORE A. BINGHAM, CORPS OF ENGINEERS.

Explorations and Surveys in the Department of Arizona..... 2399

APPENDIX D D D.

REPORT OF LIEUT. GEORGE W. GOETHALS, CORPS OF ENGINEERS.

Explorations and Surveys in the Department of the Columbia..... 2403

PART IV.

APPENDIX T T.

REPORT OF THE MISSISSIPPI RIVER COMMISSION.

C. B. COMSTOCK, Lieut. Col. of Engineers, Bvt. Brig. Gen., U. S. A., *President*.
 Q. A. GILLMORE, Colonel of Engineers, Bvt. Maj. Gen., U. S. A.,
 CHARLES R. SUTER, Major of Engineers, U. S. A.,
 Mr. HENRY MITCHELL, Coast and Geodetic Survey,
 Mr. B. M. HARROD, Civil Engineer,
 Mr. S. W. FERGUSON, Civil Engineer,
 Mr. ROBERT S. TAYLOR,
Commissioners.

Message of the President, 2407; letter of the Secretary of War, 2408; report of Commission, 2408; list of appendices accompanying the report, 2439; list of plates accompanying the report, 2440.

A P P E N D I X E S

TO THE

REPORT OF THE CHIEF OF ENGINEERS,

UNITED STATES ARMY.

(CONTINUED.)

APPENDIX T T.

MISSISSIPPI RIVER COMMISSION.

To the Senate and House of Representatives:

I transmit herewith to the House of Representatives a communication from the Secretary of War submitting the annual report of the Mississippi River Commission.

I take this occasion to invite the early attention of Congress to the continuation of the work on the Mississippi River, which is being carried on under the plans of the Commission. My sense of the importance of the improvement of this river, not only to the people of the Northwest, but especially to the inhabitants of the Lower Mississippi Valley, has already been expressed in a special communication to the last Congress. The harvests of grain and cotton produced in the region bordering upon the Mississippi are so vast as to be of national importance, and the project now being executed for their cheap transportation should be sufficiently provided for.

The Commission report that the results due to the still uncompleted works have been remarkable, and give the highest encouragement for expecting the ultimate success of the improvement.

The act of August 2, 1882, appropriated \$4,123,000 for the work on that part of the river below Cairo. The estimates of the Commission already transmitted to Congress call for \$3,000,000 for the continuation of the work below Cairo; and it appears from their report that all of the last appropriation available for active operations has been exhausted, and that there is urgently needed an immediate appropriation of \$1,000,000 to continue the work without loss of time, in view of the approach of the flood season with its attendant dangers. I therefore recommend to Congress the early passage of a separate bill on this subject.

CHESTER A. ARTHUR.

EXECUTIVE MANSION, *January 8, 1884.*

LETTER OF THE SECRETARY OF WAR.

WAR DEPARTMENT,
Washington City, January 7, 1884

SIR: I have the honor to submit herewith, for transmission to Congress, the annual report of the Mississippi River Commission for year 1883.

Very respectfully, your obedient servant,

ROBERT T. LINCOLN,
Secretary of War

The PRESIDENT.

REPORT.

THE MISSISSIPPI RIVER COMMISSION,
PRESIDENT'S OFFICE,
New York, December 21, 1882[3

SIR: The Mississippi River Commission have the honor to submit the following report, embracing the subjects and subdivisions specified below, to wit:

1. Progress of surveys and examinations since December 1, 1882
2. Construction.
3. Remarks on the subjects of levees and outlets.
4. Legislation.
5. Financial statements and estimates of funds for the fiscal year ending June 30, 1883, for "Surveys and expenses of the Commission" for "Improving the Mississippi River."

PROGRESS OF SURVEYS AND EXAMINATIONS.

The surveys and examinations, undertaken in pursuance of the requirements of the third section of the organic act, have been continued.

From December 1, 1882, to December 1, 1883, the following progress is reported:

Gauges.—Daily readings have been continued at the stations maintained by the Commission, and two new gauges, at Gray's Point, La., and Columbus, Ky., have been established. This service has been greatly improved during the past year, and its value, both as an aid to navigation and as a source of hydraulic data, greatly enhanced. A small steamer has been purchased and equipped for the duty of maintaining these gauges in correct position, and insuring accuracy of record and display. This boat is constantly passing up and down the river in the performance of this as her principal duty. She visits each gauge at least once a month. The daily readings are conspicuously displayed on bulletin boards, and are now a prominent feature of the records kept by pilots for their mutual information. The bulletins are frequently read at night by means of the electric light.

Field work.—No field work has been done during the year. The adjustment and reduction of previous work has been completed.

Triangulation.—The line has been continued northward along the river from Clinton, Iowa, to Savannah, Ill., 22 miles, and thence to Lake Michigan at Chicago, 145 miles. The reduction of the part from Clinton to Savannah and also of the remainder of the line from Grafton to Rock Island has been completed.

The record of the tide gauge on the Gulf of Mexico has been continued. Owing to the considerable discrepancies in the means of determination, it has been thought inadvisable to terminate the series,

that the mean Gulf level, upon which all elevations are finally to depend, remains undetermined.

Final topography and hydrography, on the same scale as mentioned in last report, has been completed from 10 miles above Vicksburg to Donaldsonville, a distance of 297 miles; from Island No. 1 to Donaldson's Point, 60 miles; from Caruthersville to Plum Point, 58 miles; from Randolph Point to Memphis, 15 miles; and from Commerce Cut-off to Trotter's Landing, 33 miles, making a grand total of 463 miles of river surveyed during the year.

In connection with this branch of work, occasion was taken to repeat, in the fall of 1882, the cross-sections near the principal crevasses of the preceding flood, for comparison with measurements of the same sections made previous to the flood.

Detail charts (scale of $\frac{1}{10000}$) from Arkansas City to Greenville, and from Lake Providence to Waterproof, comprising 160 miles of river, have been plotted and drawn in the office. In addition, the remaining sheets to Donaldsonville are partially completed. The preparation of the preliminary chart (one inch to a mile) has been continued, five sheets, extending to Rodney, Miss., having been drawn, and five sheets, extending to the foot of Island 97, published.

Trans-alluvial levels.—The system of lines undertaken, as noted in the Report of the Commission for 1881, p. 3, to obtain information as to the heights of the alluvial bottom lands and their reservoir capacity, was completed during the past year.

Other work in the same direction, consisting of 160 miles of levels in the country between Lower Red River and the Atchafalaya, has been completed.

Observations.—The series of measurements at Paducah, Columbus, Helena, Hays' Landing, and Red River Landing, which closed in December, 1882, have been reduced. The measurements of escape through crevasses and otherwise were repeated for the flood of 1883, which was, at Cairo, the highest on record. This work was not continued below Vicksburg, since at that point the flood was several feet below that of 1882, and was no longer of unusual magnitude.

High-water marks and slope.—The collection of reliable high-water marks of 1883, and previous years, has been continued. The profile of the water surface was determined for the low water of October, 1883, from Saint Louis to New Orleans.

A financial statement and an itemized statement of the expenditure of the appropriation in act of August 2, 1882, appear below.

The following papers relating to the work of surveys and examinations are submitted as appendices to this report:

Appendix A.—Annual report of the secretary of the Commission upon the field work of surveys and examinations.

Appendix B.—Report upon, and final results of, secondary triangulation from Cairo to Keokuk.

Appendix C.—Report upon, and results of, precise leveling from Carrollton to Biloxi, and from Cairo to Fulton.

Appendix D.—Reports upon field work of topography and hydrography.

Appendix E.—Report upon the work of trans-alluvial leveling, with profiles of the lines.

Appendix F.—Reports upon and results, of observations of river discharge at various points.

Appendix G.—Report upon changes of the Mississippi River, as shown by comparison of the earliest and latest authentic surveys.

CONSTRUCTION.

At the date of the last annual report of the Commission, Dec 1, 1882, work had been fairly inaugurated on the Plum Point and Providence Reaches, and also in the vicinity of Memphis and Vicksburg, and throughout December and January the work was pushed with vigor. Unfortunately the extremely cold weather interfered seriously with the stone supply from the Ohio and Upper Mississippi, the running ice at times entirely cutting off access to the quarries. As a consequence of this there was a large accumulation of mattress work, both for revetment and for pile-dike foot mats, which was afloat in place, but sunk for lack of stone. In this condition of affairs, early in February the river began to rise rapidly, bringing down great quantities of drift while the heavy running ice on the Mississippi and Ohio still prevented the procuring of an adequate supply of stone. Efforts were made to use sacks of sand instead, but without much success, and at both Plum Point and Lake Providence a considerable amount of mattress work was lost. At the former place the uncompleted pile dikes also sustained considerable damage from the accumulation of drift and the strong current, due to the rapid rising of the river. This rise continued until it finally culminated in a flood nearly as great as that of 1882, and throughout the month of July a very high stage of water prevailed continuously until about the end of July. During this period work was continued, though under very great disadvantages, and was of necessity mainly confined to repairs on the dikes, which required constant watching and repairs during the long-continued high water.

After the subsidence of the flood the construction of mattress bank revetment was resumed, but the season proved unusually stormy and labor was scarce and inefficient. Nothing of consequence was accomplished until the advent of the cool weather in the fall, since which time work has progressed favorably and rapidly. Every endeavor has been made to place the work in as safe a condition as possible, but it is greatly to be feared that this can only be partially accomplished. As the funds now available, the balance of last year's appropriation only admit of carrying on active operations till about the middle of December, after which time all work must cease until Congress makes a further appropriation for its prosecution. The Commission feel that they cannot too strongly urge upon Congress the necessities of the case and the need of early relief, as the flood season with all its attendant danger is close at hand, and the Commission before that time will have exhausted all its available funds, only reserving such amounts as are absolutely needed for the care and preservation of the extensive and costly plant belonging to the works. An appropriation of \$1,000 made immediately could be advantageously used.

The past year, with its many vicissitudes, has been fruitful in valuable experience, experience which was much needed, in view of the magnitude and of the untried difficulties of the work.

This experience has shown that the principles upon which the Commission have based their work are perfectly sound, and in this respect no modification seems necessary, though with regard to details of construction some changes have been called for.

The contraction works, consisting essentially of dikes of piling, retaining curtains or screens of brush, proved generally too weak for the work imposed upon them. The great depth of water in which they must be maintained, the enormous accumulations of floating drift, the long duration of the high-water period, are the main points in w

our experience differs from any previously noted with similar structures at other localities. This has necessitated much more substantial work than was at first deemed necessary, with a proportionate increase of cost. It should, however, be noted with regard to these works, upon which the main damage experienced has been concentrated, that they are not necessarily permanent in their nature, and are only intended to effect certain definite results, viz, the silting up of certain portions of the river-bed. When this object has been accomplished their work is, as a rule, ended, and their maintenance will no longer be required. Meanwhile, from their position and the style of their construction, more or less damage at each recurring flood is inevitable and must be expected; but such damage should be made good as soon as possible, and the general continuity of the dikes preserved, in order to obtain promptly the desired results.

The revetment work undertaken, wherever completed, has proved entirely successful, and but slight modification in the general style and in details of construction has been found necessary. As the officers and men gain skill and confidence in this work, better results, both as regards rapidity of execution and economy in cost, may be expected.

Next to the scarcity of labor, the greatest difficulty met with has been the insuring of an ample and timely supply of the materials used in construction, especially brush and stone. Already the local supply of brush on the works is about exhausted, and it has to be sought either up or down the river at points 60 or 70 miles distant from the works. The bulk of the stone needed has to be brought from above Cairo, as the few local sources of supply are entirely inadequate to the demands of the work. This has created a demand for transportation which has taxed the resources of the Commission to the very utmost, and a considerable increase in the number of barges and tow-boats at their disposal must be made as soon as funds for the purpose are available. In other respects the plant on hand seems adequate for the work and generally efficient; though it is proper to state here that the plant provided for commencing work on the New Madrid Reach, and part of that procured for the Memphis Reach, has been absorbed by the works at Plum Point and Lake Providence.

With regard to the results due to the still far from completed works it would seem premature to speak; nevertheless these results have been so remarkable that they cannot be overlooked. During the months of September and October the river below Cairo was extremely low and navigation was carried on with great difficulty. Between Cairo and the Plum Point Reach there was but $5\frac{1}{2}$ feet and 6 feet of water at several points; between that reach and Memphis and as far down as Commerce Cut-off, 40 miles below Memphis, 6 feet was found. From this point to the head of the Lake Providence Reach there was but 7 feet available, and between the Lake Providence Reach and Vicksburg but 9 feet. Below Vicksburg there were not less than $10\frac{1}{2}$ feet.

During all previous low-water seasons, when similar depths have been reported, Plum Point and Lake Providence Reaches have been fully as shoal as any points on the river, and as a rule shoaler than anything in their immediate vicinity; yet during the present season there was not less than 12 feet depth through these two reaches, and at Lake Providence, during the lowest water, over 15 feet was reported. Thus these two long stretches of habitually difficult navigation showed this year a depth twice as great as the bars above and below them, and this result can only be attributed to the works executed by the Commission. That such truly remarkable effects should have been produced by the

vey have been completed, but no project for work has as yet been prepared. With the expectation of beginning work on this reach the Commission authorized the procuring of the following plant, viz: 20 pile-drivers, 40 barges, 1 machine shop, 6 quarter-boats, 4 200-foot mattress boats, 6 100-foot mattress boats, 6 screen boats, and 40 skiffs. Of this list, the pile-drivers, barges, and machine shop have been built and assigned to other works.

On December 19, 1882, it was decided to suspend such portion of the allotment as was not needed to pay for plant which could be utilized elsewhere, and on March 16, 1883, \$300,000 of the allotment was transferred to Plum Point, and the balance, \$187,500, to Lake Providence.

This action of the Commission was rendered necessary by the failure of the river and harbor bill, as it was deemed far more important to push the works already begun at Plum Point and Lake Providence as far as possible than to attempt, with inadequate means, to initiate the improvement of another reach. Nevertheless, in the interest of navigation, this improvement should be undertaken at as early a date as practicable, as the bars on the reach were, during the recent low water, the shoalest and most troublesome on the river.

PLUM POINT REACH.

The work so far decided on for this reach comprises a system of longitudinal and cross dikes designed to close the chutes behind Elmot Bar and Island No. 30, a similar system for closing the chutes behind Osceola and Bullerton Tow-heads, and a third system designed to contract the water-way between Bullerton Tow-head and Yankee Bar, together with bank revetment on the left bank from Ashport to Gold Dust, on the right bank from Fletcher's to Elmot's, and from Petty's to Craighead Point, and along the outside of Osceola and Bullerton Tow-heads. Of this work at the date of the last report there had been constructed 2,700 feet of revetment near Ashport, and the head of Bullerton Tow-head had also been protected. The longitudinal dike of the Elmot or Gold Dust system had been built in part, as also a dike across the middle chute through Osceola Bar. The dike across the head of Osceola Chute was completed, and the one connecting Osceola and Bullerton Tow-heads was partly built. Subsequently five cross-dikes were commenced in Elmot Chute, and partly completed. Mattresses were constructed along the outside of Bullerton and Osceola Tow-heads, and wide foot-mats along the outside of the various dikes. Nearly all this mattress work was afloat when the river began rising in February, 1883, owing to the failure in the stone supply before alluded to. Attempts were made to sink the mattresses with bags of sand, but without success. The river rose very rapidly, and brought down immense quantities of drift, which accumulated under and against the floating mattresses, and finally tore them from their fastenings. In this manner a large amount of the mattress work which had been constructed was lost, and all attempts to renew it during the high water proved ineffectual. In similar manner the drift accumulated against the pile dikes. The foot-mats were either carried away or doubled up and destroyed, and the pressure of the masses of drift, aided no doubt by scour around the piles, overturned a large portion of the dikes which had been constructed. These breaks in the dikes relieved considerably the pressure against the remaining portions, and the greatest damage was confined to the first few weeks of the flood. Subsequently these dikes were in great part reconstructed in a much more substantial manner. Four cross-dikes

were ordered in Osceola Chute, of which three have been constructed and two in Bullerton Chute, the first of which only has been in construction, as the chute has been the channel during the low-season. It is hoped that all these cross-dikes can be finished before the close of active operations.

The third system of dikes below Plum Point has been begun. Cross-dikes Nos. 1 and 2, with part of the main dike, have been built.

In all, there is now standing on this reach 37,815 feet of pile dikes.

The revetment of the outside of Bullerton Tow-head has been completed during the present season, as also that of the head of the Osceola Tow-head. The revetment of the outside of this tow-head cannot be renewed for want of funds. The revetment of Ashport has been extended for the same reason. It has remained intact during the year. In spite of the damage which they sustained, the dikes did good service, and a general and extensive fill was noticed behind them. Had they been held intact their effect would undoubtedly have been greater.

The crossing from Plum Point to Bullerton was moved down a considerable distance, but the failure of the Bullerton Dikes enabled the river at low water to cut through into that chute and main channel there. It is, however, hoped and expected that the next water will break down the bar outside and establish a channel to the left of the tow-head, where it is desired to locate it.

The effect of the partial concentration of the water on those portions of the reach under improvement was very marked during the late water season. The depth of water was not less than 12 feet, compared with the amount found on the unimproved portions of the river above and below.

For details of work in this district see report of Capt. J. G. D. K. of the Corps of Engineers, Appendix J.

SECOND DISTRICT.

(Foot of Island No. 40 to mouth of White River, 180 miles in length. On charge, Maj. A. M. Miller, Corps of Engineers, U. S. A.)

2

HEADQUARTERS, MEMPHIS, TENN.

In this district are included the Memphis and Helena Reaches, the first extending from the foot of Island No. 40, 220 miles from Cairo, to Scanlan's Landing, a distance of 27 miles, and the second extending from Commerce Cut-off, 270 miles from Cairo, to Friar's Point, a distance of 55 miles.

The first reach includes Memphis Harbor.

MEMPHIS HARBOR.

This work, which has been in progress several years under the supervision of the War Department, United States Army, was carried on last year under the supervision of the Commission and by special allotment from the general appropriation.

The protection of the caving bank by mattress revetment from the freight elevator to Wolf River was completed in February, 1888. In all, since our last report, 5 mattresses covering 300 linear feet of bank have been constructed and sunk, and the upper bank has been protected and covered with stone throughout the whole distance, with the filling of two gaps, aggregating 450 feet. This revetment passed the

the great flood of 1883 without any damage and is reported in perfect order.

MEMPHIS REACH.

A low-water survey of this reach has been completed, but no project for its improvement has as yet been prepared.

It had been the intention of the Commission to begin work on this reach, and a considerable amount of plant was ordered for the purpose; but owing to the failure of the appropriation, work was confined during the year to the construction of a mattress revetment in Hopefield Bend, where the right bank was rapidly caving and threatening the harbor of Memphis. This work was begun in December, 1882, and carried on till February, 1883, when it was stopped by the rapidly rising river, 1,127 feet of mattress revetment having been to that time constructed and sunk. Work could not be resumed till August, 1883, and is still in progress. To date 14,485 feet of bank have been protected, the under-water mattress being 140 feet wide. That portion which was first put in has stood perfectly well, although the water was five feet deep on top of the bank during the flood of 1883. It will be necessary to carry this revetment down to Hopefield Point, and also to revet about $\frac{1}{2}$ mile of the left bank below the mouth of Frame Chute.

HELENA REACH.

A low-water survey of this reach has been made, but no project for its improvement has as yet been prepared.

For details of work in this district see report of Maj. A. M. Miller, United States Engineers, Appendix K.

THIRD DISTRICT.

(Mouth of White River to Warrenton, Miss., 220 miles in length. Officer in charge, Capt. W. L. Marshall, Corps of Engineers, U. S. A.)

HEADQUARTERS, VICKSBURG, MISS.

In this district are included the Choctaw Reach, extending from Cork's Point, Arkansas, 422 miles below Cairo, to Arkansas City, a distance of 31 miles; the Lake Providence Reach, extending from Carolina Landing, Mississippi, 530 miles below Cairo, to the foot of Island No. 95, a distance of 35 miles; and also the improvement of Vicksburg Harbor.

CHOCTAW REACH.

A low-water survey of this reach has been made, but no project for its improvement has as yet been prepared.

LAKE PROVIDENCE REACH.

At date of last report work on this reach was going on actively, and considerable progress had been made on the pile dikes closing the chutes behind Skipwith's and Duncansby Tow-heads, Island No. 93, Baleshed Bar, and Stack Island; and revetment was in progress along the face of Island No. 93. During the past season this work has been continued, the revetment of Louisiana Bend has been begun, as also the dikes closing Hopewell or Elton Chute.

In Louisiana Bend the work of revetting the bank has been com-

menced and to date about half a mile has been completed. The work offering peculiar difficulties, the water being over 100 feet deep at low water, while at high stages work is impossible, owing to the depth of water and the extremely rapid current. This very important work was much delayed by the difficulty in procuring labor and soon be stopped for lack of funds. The work completed will be in a very precarious condition during the next high water, as the caving during the last two years has aggregated 1,500 feet in width. The straightening of this shore line is absolutely essential on account of its influence on the direction of the river below. The caving which took place last year caused considerable damage to the Duncansby system of dikes and will be described farther on.

The Duncansby system of dikes is intended to exclude the river from the left-hand chute in front of Duncansby and Skipwith's Landing. The first series built comprised five cross-dikes, and a longitudinal dike extending to the lower tow-head in front of Skipwith's Landing. The longitudinal was a high dike; the cross-dikes were only carried to the 17-foot stage. The channel, when the work began, led into Skipwith's Chute, passing between the two tow-heads. This channel has been completely silted up, and the greater portion of the entire chute is dry at low water, but the caving in Louisiana Bend, above Meyer's Point, during the last high water, threw the channel across the river, striking high up on the Mississippi shore, and the works at the head of the chute were severely attacked, and suffered considerable damage. As it was deemed desirable to hold this line as long as possible, in order to allow time for the chute to fill up and for the new channel to develop itself to the right of the tow-heads, three additional cross-dikes were built in the chute, and a screened dike above the head of the upper tow-head. Later on the head of the tow-head was revetted and the water went entirely over it and cut a channel through behind the revetment. A heavy dike was also begun on range No. 36, and the upper dikes of the system are being strengthened, so as, if possible, to keep the river out of the left-hand chute during the coming high water.

The Meyersville, or Island No. 93 system, includes a main dike and three cross-dikes on Cottonwood Bar, which are not yet built, and a dike across the head of Island No. 93, built last year to the 17-foot stage, and a high cross-dike, to 30-foot stage, built across the chute at Meyer Landing. These dikes have proved quite effective and the chute goes dry at low water.

Previous to the rise in February, 1883, 1½ miles of low-water revetment had been constructed on the outside of Island No. 93, and the upper bank protection had been completed for 1,700 feet at the upper end of this, the last 225 feet had not been properly ballasted for lacustrine stone and was carried away. All the revetment below this point was also lost for lack of protection of the upper bank. This work had therefore to be renewed this season and is now in progress.

At the foot of Island No. 93 begins the Baleshed system of dike which comprises a longitudinal dike extending from the Mississippi shore at Homochitto Landing to the head of Stack Island. Behind this longitudinal are twelve cross-dikes. Part of the longitudinal and four of the cross-dikes were built last year, but only to the 17-foot stage. Subsequent to February, 1883, and during the high water, work was carried on and the cross-dikes were raised and strengthened, and eight others were built. All the new dikes extend to above the 25-foot stage, they are built with from 3 to 5 rows of piles and are wattled to a height of 6 feet above the present bar surface. Six of the cross-dikes are complete

the shore to the longitudinal, the six others have not yet been carried across the deep water. All the cross-dikes have foot mats, and the longitudinal has outside of it a 100-foot mat and a grillage mat and wattling wherever cross channels have been developed. The effect of these dikes has been very marked, a great fill having been secured behind them, with a corresponding deepening in the channel outside. In this system 28,000 feet of dike have been built during the year.

Much trouble was experienced at Stack Island where the river had established itself in the left-hand chute. This chute was over 80 feet deep at low water, and the Elton or Hopewell Chute on the other side of the river was over 30 feet deep. The new channel, as projected, crossed directly over Hopewell Bar. An open pile dike was built above the head of Stack Island to check the flow into that chute, and six short spurs from the right bank were thrown across the Elton or Hopewell Chute. When these works were completed the river broke through on the line desired, removing immense masses of sand and establishing itself in the position desired. These works must, however, doubtless be extended in order to keep it there.

The general result of the works has been a very marked increase of depth at low water. During the past season there was not less than 12 feet, and at the lowest water where the channel had cut out there was over 15 feet.

The systems of construction described last year have not been materially altered except in the direction of giving greater strength to the dikes, which, as now made, are much stronger, having from 3 to 5 rows of piles, and being all provided with foot mats. In 3-row dikes the middle row is wattled, in 5-row dykes the wattling is on the 2d and 4th rows. Wattling has replaced the curtains or inclined mats used last year, being found cheaper and more efficient.

In revetment work the hurdle mattresses described in our last report are still used, the only modification being the introduction alongside the poles of jointed iron rods of $\frac{3}{4}$ or $\frac{5}{8}$ inch iron for the purpose of increasing the longitudinal strength.

VICKSBURG HARBOR.

Prior to August, 1882, work at this locality had been for several years in progress under the Engineer Department, United States Army. Since that time it has been carried on under the supervision of the Commission, and has received an allotment from the general appropriation. Previous to this past season, work had been confined to the revetment of Delta Point, opposite Vicksburg, and the continuation of this work was in progress at the date of our last report. At that time 1,100 feet of the new work had been completed. Subsequently the work was continued with but slight modifications till February 10, when the allotment was exhausted. In all, 4,000 linear feet of substantial revetment was constructed, leaving about 500 feet to be built this winter. The cost of this revetment, which it is believed will be rarely, if ever, exceeded, was \$13.37 per linear foot. It passed through the last flood without any damage, and seems to be in every respect satisfactory. The plan of improvement proposed for the harbor proper of Vicksburg contemplated the excavation of a basin in front of the town, connected by a canal with the deep water in the river. For this season it was proposed to excavate a basin 300 feet wide and 1,700 feet long in front of the elevator, and to connect it with deep water in the lake by a canal 150 feet wide, the west entrance to the lake being also kept open. All dredging was to be to the

zero of the Vicksburg gauge. The contract for this dredging was at 12.1 cents per cubic yard and, after many delays, work was finally begun on April 5, and continued till September 18, when the Commission decided to stop it. During this time, 350,035 cubic yards of mud were removed. The basin for a width of 160 feet was dredged to the zero of the gauge and for a further width of 160 feet to the reference + 5 feet. The canal was excavated for a width of 80 feet to the zero plane, and an attempt was made to dredge the west entrance to the lake, which, since the project had been approved, had filled up to the extent of 17 feet. The material was hard sand and the dredging was so difficult that it was ordered to be abandoned on August 22. As the river fell, the side of the dredged basin slid in and the bottom was pushed up by the weight of the soft mud lying beyond the dredged area. This upheaval amounted to about 8 feet in depth, and the basin was re-excavated for a width of 80 feet to the zero plane. Meanwhile, the continued fall of the river surface gave a considerable head to the water impounded in the lake and it finally cut through the sand-bar at the west entrance, so that now boats drawing 5 feet are able to enter at a 12-foot stage, whereas before, at the 20-foot stage, all boats were excluded.

This effect, while very fortunate for the town, is in nowise permanent, as this cut will certainly fill up at the next high water, and will not cut out again so readily. A survey was made at low water, which showed that since May, or while the river was declining, a fill had taken place over the area covered by the proposed canal and basin amounting to from 5 to 20 feet in depth. Prior to May the fill had only been about one foot. On the line of the proposed canal alone the removal of 1,255,486 cubic yards more than originally estimated has already become necessary. It is needless to say that the Commission, in approving this plan, had not anticipated such a state of affairs as this. Repeated surveys, extending over the whole period since the formation of the lake, had shown that the fill, gradually diminishing in its yearly increment, had finally practically ceased as far as the inner harbor was concerned, and only on this condition could the plan have been recommended. When confronted by such an enormous fill, taking place, moreover, on the falling stage of the river, and requiring in consequence to be removed during the low-water stage, it became obviously necessary to call a halt until the matter could be further investigated. Such an annual fill as this will require \$200,000 for its removal, and as it must be done during the low-water period, it would require a large fleet of dredges to accomplish it. Some changes have recently taken place at Young's Point, and above Delta, which have tended to throw the river nearer Vicksburg. The eddy current up the east arm of the lake was observed to be greatly increased after June 1, and undoubtedly caused a great deposit. It is quite possible that this increased flow was due to the changes alluded to. If this, however, be the case, these changes may progress still further, and the annual fill may become even greater. In any case it would be extremely unwise to attempt any further prosecution of the plan for the present. The diversion of the Yazoo into the lake has been proposed with a view to keeping it open; but this is estimated to cost \$1,600,000, and the excavation of the canal \$766,000. The removal of the annual deposit will cost \$200,000, or say \$2,600,000 for the whole project, with no certainty as to the results. The annual commerce of Vicksburg is 10½ millions of dollars.

The following projects have been proposed:

1st. To abandon the lake and establish the town landing at Kleaton, holding Delta Point securely by extending the revetment. The latter must be done in any case.

2d. To dredge the west entrance annually, and to keep the basin clear. This would be temporary, and would cost at least \$30,000 per annum after the first year.

3d. To divert the Yazoo into the west arm of the lake, dredging out the basin and connecting canal. This would cost \$1,850,000, with annual dredging to an uncertain amount.

4th. To divert the Yazoo into the east arm of the lake and along the city front, dredging out the basin and canal to the river. This would cost \$2,600,000 and would require annual dredging in the canal.

The first project involves the abandonment of the old harbor of Vicksburg, and is, naturally, extremely distasteful to the citizens of that place; the last two projects are expensive and by no means certain; while the second can at best be but temporary in its effects.

In the opinion of the Commission, further study of the whole subject is required before any final recommendation can be made; nevertheless, with a view to affording relief to the harbor during such time as will necessarily be required for this study, the Commission recommends that during the coming season an attempt be made to carry out the second project above described, should the conditions be found to be favorable.

For details of work in third district see report of Capt. W. L. Marshall, United States Engineers, Appendix L.

FOURTH DISTRICT.

(Warrenton, Miss., to Head of Passes, 484 miles in length. Officer in charge, Maj. Amos Stickney, Corps of Engineers, U. S. A.)

HEADQUARTERS NEW ORLEANS, LA.

This district embraces the improvement of Natchez Harbor, the rectification of Red and Atchafalaya rivers, a lock at Bayou Plaquemine, and the improvement of New Orleans Harbor.

NATCHEZ HARBOR.

A survey with a view to improvement was ordered at this place, but owing to the sickly season it has been found impossible as yet to make it. The caving of the bank in Giles' Bend has not been very great, but that in Marengo Bend has been more severe. The work required is bank revetment, and can be estimated on this winter.

RED AND ATCHAFALAYA RIVERS.

During the past low water, it again became necessary to send dredge boats to Old River to attempt to keep open navigation into the Red River. Although they reached the scene of operations while there was still a through channel depth of not less than 5 feet, the effort failed utterly, and, for a period of three or four weeks, navigation was entirely suspended. In fact, for a part of this time, the water-way entirely disappeared.

The experience of this year leaves no doubt of the absolute uncertainty of any such method of preserving navigation, during low water, into Red River. While in many years it may succeed, it is utterly inefficient in the face of the unfavorable conditions that may recur any season. The dredging fleet cannot operate until the water has fallen to a certain stage. After this stage is reached, it is entirely probable that the fall may continue so rapidly as to develop the bars much faster than

the dredges can remove them. The difficulty of maintaining a channel upwards of four miles long, of navigable depth and width, in a secondary river, falling several inches a day, with a current unable to scour from its own debility, and the unctuous and adhesive quality of the bed material, would seem to be sufficient. But it is much increased in unfavorable years by the falling of the water more rapidly than the banks can dry out and solidify, or than the overflow ponds a short distance back can drain. On such occasions the semi-fluid banks slough down in immense masses, at times entirely choking the water-way.

These difficulties may recur any year, and render uncertain any attempt to keep open Red River navigation by such methods, during low water.

Still, as no better temporary method is known, and as this method has succeeded in a majority of the years in which it has been tried, and as the commercial benefits of maintaining water communication with the large producing region during the months when it is most needed for shipments are very great, exceeding the cost of dredging operations, it is recommended that, until permanent improvement of this navigation is accomplished, sufficient appropriation (as provided for in the accompanying estimates) be made to renew the work of dredging at this point when it may again become necessary.

Surveys and examinations at this locality have been prosecuted under almost equal difficulties. Immediately on the subsidence of the last flood parties were put into the field to secure information necessary for the preparation of a plan for the permanent improvement of the junction of these three rivers; but, owing to the natural difficulties of the ground and the unhealthfulness of this region, their labors are still incomplete.

Fuller details and discussions of these topics will be found in the report of Maj. A. Stickney, United States Engineers, district officer, submitted as Appendix M.

The following brief description of the existing regimen, and of the conditions which must be harmonized in any permanent plan of improvement, as observed during the past two floods, is submitted. The sectional area of Lower Old River has contracted considerably, while the enlargement of the Atchafalaya has continued. These changes are clearly the effect of the floods.

The fill in Old River is the result of the absence of current during the equilibrium held between that portion of the flood coming down the Mississippi and the overflow through the Tensas Basin, re-enforced by Red River. The scour in the Atchafalaya, considered in connection with the fill in Old River, proves that the volume causing it is not drawn directly from the Mississippi, but rather from the overflow in the Tensas Basin. The shape of the sand reefs left by the flood current substantiates this. A dam across Lower Old River, therefore, would not change the existing tendencies of the floods. The equilibrium of the accumulated mass of flood water in this region is first disturbed by a decline in the Mississippi, which starts the current in that direction. But so immense is this volume of overflow that the fall is checked by the water when near a bank full stage. In 1882 it lingered fifty-one days between the 42 and 41 foot marks on the gauge at Red River Landing. When once within the banks, the decline is more rapid. The fall of the Atchafalaya is still slower than that of the Mississippi, as in addition to its share of the Tensas it has to collect and carry off its own overflow which spreads from the Mississippi to the Têche.

The flow through Old River towards the Atchafalaya usually sets in

after mid-stage on the decline is reached, and becomes more fixed as the water continues to fall. These observations are general, and a local rise in either the Mississippi or Red River may disturb or reverse the movement. A flow through the Old River to the Mississippi is, under present conditions, advantageous to the navigation of the former stream, as it has greater velocity and less sediment than a current in the opposite direction.

The exclusion of the overflow from the Tensas Basin, by the completion of its levee system to Blackhawk, would prevent the equilibrium between the Mississippi and overflow waters in and about Old River and the head of the Atchafalaya, which is noticed in floods, and would tend to increase, both in duration and amount, the flow from the Mississippi down the Atchafalaya by way of Lower Old River. This change would probably not only prevent the further filling of Lower Old River, but would enlarge it, and ultimately accelerate the enlargement of the Atchafalaya. The prevention of the escape of flood waters, complete or partial, down the Atchafalaya would have, as an immediate effect, the greater or less increase of flood height in Old River, and steeper slope from its mouth down the Mississippi. This would precede the ultimate adjustments of the bed to the increased volume. This subject is further discussed under the head of levees and outlets.

The Commission is as mindful of the importance of this part of their work as of its difficulties. Upon the completion of surveys and examinations now in progress, full report and recommendations will be made.

LOCK AT BAYOU PLAQUEMINE.

The surveys for this work are not yet completed, having been delayed by the unhealthiness of the past season.

NEW ORLEANS HARBOR.

The project for laying 10,000 feet of mattress revetment 400 feet wide in Carrollton Bend was approved September 18, 1882. Work was begun October 9, 1883, but has made little progress to date, owing to trouble in securing a supply of brush.

In the third district the plan of scouring out the mud from under the wharves by the use of a tug has been tried with success.

On the right bank from Westwego to Algiers there has been serious caving, involving much loss to property of considerable present and much greater prospective value. Fully 40,000 feet of bank will require protection.

An interesting series of discharge observations were obtained at Carrollton between January 27 and September 7, 1883. The discharge was measured 148 times, and the observations extended from a 2-foot to a 15½-foot stage.

For details of work in this district see report of Maj. Amos Stickney, United States Engineers, Appendix M.

PLANT AND GENERAL SERVICE.

There was in use on the work during the past season the following plant, in part owned by the Government and in part chartered:

Owned by the Government.—One hundred and eighty-nine barges, thirty-nine quarter-boats, four screen-boats, three machine-shop boats, five steam tow-boats, one pumping-boat, twenty five mattress boats, four hydraulic graders, one steam-tug, and sixty-two pile-drivers.

Chartered.—Six steamers and six barges.

The general service of supply and towage, as well as the construction of plant, was throughout the year in charge of Capt. C. B. Sears, Coi of Engineers, United States Army, the executive officer of the Commission in the department of construction, to whose report reference c be made for details. (See Appendix H.)

Estimates.

At a meeting held June 26, 1883, an estimate was made for the c tinuance of work then in progress, and this estimate was duly forward to Congress through the honorable the Secretary of War. At that ti the Commission did not deem it best to make any recommendation estimate in reference to new works of improvement, the works then progress being in a comparatively incomplete state, and their results yet undeveloped. Since that time the progress of the works and t favorable results produced by them have been such as to warrant t belief that work can be undertaken in one or more additional places, it shall be the will of Congress to carry it on simultaneously in mc places than those at which it is now in progress.

In this case the Commission would recommend that the improveme of New Madrid Reach be first undertaken; and secondly, that of Me phis Reach.

Estimates for this work are submitted herewith, and the estimate p viously sent in is repeated.

LEVEES AND OUTLETS.

Work, under the allotment made by the Commission, from the appi priation of August 2, 1882, has been continued during the year on the levees which were not finished before the flood of 1883. It is expect that all will be completed before the expiration of this year. Mo detailed notice of this work will be found in the reports of the distri officers.

The Commission now recommends the continuation of levee wo during the next season on the fronts of the Tensas and Yazoo Basins.

Surveys and examinations, to ascertain the condition, cost, and effe of levees, have been continued during the past year. The limit topography of the surveys extends back from the river, to include tl site and height of all existing levees.

Besides this, special examinations of two distinct characters hav been undertaken and carried far enough to yield important inform tion.

1st. To ascertain the effect of outlets, particularly in the form of cr vasses, resurveys have been made in the neighborhood of several of t great breaks of 1882, to compare with the general survey which wa extended over the river in the years 1880 and 1881. The result of th work is graphically shown and accompanied by descriptive text i Appendix D.

In every observed case large loss of section occurred as follows :

Place.	Contraction.	Contraction
	<i>Square feet.</i>	<i>Percentage</i>
Malono's	2, 200	.0
Riverton	11, 000	..
Bolivar	8, 400	.1
Mound Place	23, 800	.3

The above figures are the means of numerous lines run at each place. It is worthy of notice that the later of these comparative surveys were taken at lower stages of water than the earlier, and therefore, through the bars, other things being equal, a more deeply excavated bed might be expected in the later surveys. But, as the contrary is the case, it may be inferred that the observed net results are decreased rather than exaggerated by the relative conditions prevailing at the time of survey. Similar observations have been made during the year at Bonnet Carré crevasse, with this difference: the foregoing comparisons were between channels before and after the breaking of the crevasses, while the following is between a channel during the flow of a crevasse and after its closure. The results harmonize. Through this part of the river (35 miles above New Orleans) such depths prevail at all stages that great changes may occur without affecting navigation; but valuable opportunity for observation on crevasse effects was afforded, at a point where conflicting statements had been made with equal vehemence. Careful surveys were therefore made while the crevasse remained open, and repeated over the same lines, in the fall of 1883, after the crevasse was closed and the flood of that year had passed. The final results of this work are not yet prepared, but the change observed is scour throughout the reach below the crevasse, amounting to approximately 12 per cent. of the low-water area.

In the last report of the Commission (Appendix F, p. 116) will be found the results of gauging observations on the Mississippi, at and above Saint Louis, in the years 1880 and 1881. Similar observations were undertaken in the fall of 1881, at Paducah, on the Ohio, and at Columbus, Helena, Hay's Landing, and Red River Landing, on the Mississippi below Cairo, and continued into the fall of 1882. The value of this series was much enhanced by the fortunate occurrence in this year of the greatest recorded flood. Accompanying this report, as Appendix F, will be found the tabulation and plotting of their results. They have not been long enough available to have received complete investigation. Certain facts, however, are quite apparent in both series. It is observable that the rate of velocity and discharge, during a rise, increases more rapidly while the river is still within its banks than during the higher stages when the banks are submerged, or escape occurs through outlets. At several of the stations the increase of velocity is entirely arrested at about a bank-full stage, and, before that elevation is reached, absolutely greater velocities, and even discharges, were found than at higher stages, when much of the volume was lost over the banks. This phenomenon probably continues while the swamps are filling, and the draft from the river is across the banks. After they are filled to or near the height of the river, this indirect motion, and its loss of power, ceases, or becomes a very gentle one, generally parallel with the river, forming what may be termed a "water bank." It is fairly inferable from this, that if the conditions under which a certain curve, representing the increment of velocity and discharge, while the river is still within its banks, was developed, were continued, the form of the curve, throughout its upward extension, would be maintained, and that the additional height required for levees to restrain maximum floods would be less than that computed alone from a consideration of the increase of volume.

An illustration of the accuracy of this inference, as well as of the way in which flood heights are immediately augmented within the river bed, under existing physical conditions by crevasse outlets, is found in the comparative conduct of the high waters of 1882 and 1883, along the front

of the Yazoo Basin. Although the volume discharged by the flood of 1882 was unquestionably greater than that of the subsequent year, owing to its duration, yet, from Cairo to Helena the waves attained heights nearly equal to each other, and, in both cases, above those of previous records. The same conditions, as regards outlets, or the gaps in Saint Francis levees, prevailed during the two years. At Helena, in both floods, the maximum heights were reached on the return of overflow from the Saint Francis Basin. But the first of the two floods under consideration wrought great havoc on the levees at the head and along the upper part of the front of the Yazoo Basin. Of 1,500 cubic feet per second gauged at Helena at the top of the flood, one-third or 500,000 cubic feet, were estimated by the assistants of the Commission charged with that duty, as escaping from the river through these breaches.

Notwithstanding this depletion, which left in the river bed a volume not exceeding that which the Helena and Hay's Landing gauging stations indicate can be discharged at these stations at a stage, respectively, 6 and 5 feet lower than the maximum readings of the year, or, approximately at a bank-full stage, the greatest flood heights were reached along the entire front of the basin.

The most destructive work of this phenomenal flood was, however, near the lower end. The water leaving the river through the crevasses at the head, and along the front, sought the lower levels near the mouth of the basin. The Yazoo River and other branches of the natural drainage system were inadequate to afford it exit. It accumulated in the basin to a height of several feet above the level in the river, until, on topping the levees, an equalization of height was established between the river and basin, above the mark that would have been reached had the flood passing through a proper channel.

In 1883, the flood wave reached Helena with approximately the same height as in the previous year, but overflow into the Yazoo Basin was prevented by the holding of the levees which had broken the year before. In passing along the Yazoo bottom, the wave did not vary materially, in height, from that of 1882, until the lower end was reached. Here, owing to the exclusion of overflow from the head of the basin, and little return flow to the river, beyond the natural drainage, occurred, and the height of 1882 at Vicksburg, the nearest gauge, was not reached by about five feet.

While these two floods attained, approximately, the same heights along the part of the river under discussion, the difference in velocity was very marked. Gaugings in 1882, when the overflow into the Yazoo Basin was enormous, established the sluggish movement of the water during high stages. This was also the personal observation of the classes engaged on the river; engineers, steamboatmen, and planters. In 1883, when the flood wave was excluded from the Yazoo bottom, great velocity along its front was universally noticed by the same servers.

The conclusions to which these facts contribute evidence may be thus stated. The loss of volume through high-water outlets causes both diminution of velocity and a deflection of the thread of movement of the stream towards the outlet, accompanied by loss of the power necessary to transport the material with which it is loaded. The excess of load is dropped in the bed, decreasing the section below the outlet. When these conditions recur frequently, and are extended over long parts of the river, as the front of any one of the great basins, where volume alternately reduced and augmented, the injury inflicted on the river as a channel or as a drain is cumulative, leading to general deterioration.

If the change from low water to flood, with its enormous range in the measure and direction of the river's forces, is unfavorable to the development of a navigable and permanent channel, or an effective discharge section from the different conditions, in the same place, at different times, it certainly increases these difficulties to allow the introduction of different conditions, at the same time, in different places.

The relief from excessive flood heights which might have been anticipated from the decrease of discharge below the outlet is not realized, owing to the immediate diminution of velocity, and of *vis viva*, and the consequent contraction of sectional area. Besides, the flood-water which escapes through the outlets is returned to the river at a point lower down under conditions which give it a power of increasing the flood's height to an elevation which would not have been reached by the same volume passing down the legitimate channel.

The facts observed during the past year, of which the more important have been here recapitulated, have corroborated the views of the Commission heretofore expressed in reference to the utility of levees as a means of channel improvement. This statement is made, as heretofore, with the limitation that for purposes of channel improvement merely, the limit of economy is reached with the confinement of the ordinary flood, and does not extend to the restraint of the abnormal or extraordinary flood. The result of this qualification is that the building of levees to the height necessary to protect the alluvial basin from overflow is not necessary as part of a logical plan of river improvement. The work of determining approximately what will be the necessary height of such system of levees has been in the hands of a committee since a time prior to the last report, who will report upon it as soon as the extensive investigations necessary to reach satisfactory conclusions upon the subject can be finished.

In the mean time it is proposed to complete the closure of gaps in the existing levees along the Yazoo and Tensas fronts begun a year ago, as the most economical and the shortest method of shutting off the escape of water into those great reservoirs and securing so far the benefit of the entire volume of the river's ordinary discharge in the improvement of the channel. Beyond that the Commission is not prepared at this time to make any specific recommendation for construction of levees as a means of channel improvement, and reserves the subject for further consideration.

The act creating the Commission makes it the duty of the Commission to consider the subject of the prevention of destructive floods, and, as bearing upon that matter, there is submitted for information the following summary of the probable extent and cost of such system of levees as would be necessary for that purpose.

It may be stated, further, that there are serious practical difficulties in the way of constructing a system of levees no higher than would be necessary for the confinement of ordinary floods, and at the same time protecting them against disastrous injury from the great floods which occur at irregular intervals. The practicability and probable cost of such protection is one of the subjects in the hands of the committee before referred to. It is obvious that for the secure protection of the valley from overflow there is necessary a system of levees high and strong enough to withstand the greatest flood. No other means of protection is practicable or even possible. These facts suggest obviously the idea of co-operation between the General Government and the communities interested in the prevention of overflow in the maintenance of a levee system which shall serve at the same time the purpose of

le of cubic yards of earthwork required for levees on Mississippi River, &c.—Cont'd.

Location.	Length.	Grade.	Contents.	Remarks.
	Miles.		Cubic yards.	
Louisiana line to opposite Warrenton.	100	3,426,080	This is the estimate of the assistant engineer in charge of the line for raising the levees 3 feet for their entire length. As the grade of the line is very uneven, this quantity of earthwork, applied to the lowest places, would raise the grade of the line more than 3 feet. It is believed to be sufficient for a safe grade. (See Appendix —.)
opposite Warrenton to Red River.	150	5,140,000	No survey has been made of this line, but the same provision is made in the estimate as in that from the Louisiana line to opposite Warrenton, viz, a uniform addition of 3 feet over the entire line, on an assumed height of 6.06 feet.
Red River to forts below New Orleans.	279	2 feet above high water, 1882.	6,652,000	This line is now complete in length, but of insufficient grade. The necessity for higher grade is explained in the following text. The assumed mean height is 7 feet, to be raised to 9 feet. In the execution of the work much the greater part of the addition would, of course, be made to the upper part of the line.
born Lake to Friar's Point.	70do	1,276,000	This estimate is based on surveys and computations made for the purpose (see Appendix —). An addition of half a foot is made to the original, making the grade of this estimate 2 feet above high water, 1882.
Friar's Point to Sunflower.	34do	620,000	There exist but two breaks in this line, but the estimate is prorated per mile from the foregoing line.
Sunflower to mouth of Yazoo River.	220	3 feet above high water, 1882.	3,925,000	This estimate is based on the report of the United States assistant engineer and engineer of Mississippi levee district (see Appendix —). The same remark applied to estimate from Louisiana line to Warrenton is true here.
aton Rouge to forts below New Orleans.	200	2 feet above high water, 1882.	4,838,000	The remarks applied to line from Red River to Forts is repeated here. The conditions are precisely the same.
			45,775,080	
Cost at 25 cents per cubic yard.	\$11,443,770	

The Commission is not prepared to state that these are the exact estimates that are likely to be adopted, but it is not believed that grades less than these, on the average, will be required for the purposes contemplated in the organic act, unless a change of regimen occurs from some remote cause, such as the extensive clearing of the precipitous slopes of some of the tributary basins.

From the experience of the General Government, as well as of the riparian States, that such embankments as the above can be constructed for an average price not exceeding 25 cents per cubic yard, giving a result of \$11,443,770.

In conclusion of this subject, the Commission considers it necessary to call the attention of Congress to peculiar conditions existing below the mouth of the Mississippi River. This section of the river is in a state of much greater station than is found in any other part of its course below the junction with the Missouri. At a short distance below Red River it becomes narrower and deeper. It has been leveed throughout for a great many years. No flood complications arise here, as above, from the return of high water which has escaped from the river at points higher up. The river finally reaches the sea through the numerous delta bayous on either

side. Its bed, enlarged by levees, is fairly adapted to the service which has hitherto been imposed upon it.

During the floods of 1874, 1882, and 1883 this part of the river filled to its utmost capacity. The levees were a wash for many miles, and the waves of passing steamers rolled over them. disastrous breaks occurred.

The gaugings at Carrollton in 1883 showed that the river point was only discharging, at a maximum, about 1,100,000 cu per second, while those at Red River Landing in the previous showed that double this volume, or about 2,200,000 feet, found down the valleys of the Mississippi and Red rivers.

While it is not anticipated that the completion of the levee Texas front to within 20 miles of Red River, and the conf within the river of that part of the flood which has been allowed above will cause greater flood heights at the mouth of Red it seems certain that it will have the effect of increasing and constant the outlet of the Mississippi through Old River de Atchafalaya.

Measures that may become necessary to prevent this, by diminishing the discharge of the Atchafalaya, or by directing more of the Red flow down the Mississippi, will throw into the latter stream a in excess of any known discharge. While this increased volume undoubtedly make room for itself by ultimate enlargement of it could only do so by the work of scour, the resistance to which be indicated and measured by increased slope, or greater elevation surface throughout that part of the river while undergoing enlargement.

Such additional service should not be imposed upon a region which have been adopted the measures necessary, under existing conditions for protection from inundation, without due preparation for the increase height which will be given the floods.

LEGISLATION.

The Commission repeats with emphasis the recommendation in three preceding reports, that provision be made by law for the appropriation, by suitable proceedings, of land and material necessary work of Mississippi River improvement undertaken by the Government. Within the past year some serious inconvenience has been suffered by exorbitant demands made by land-owners for brush and piles. materials are, in most cases, worth little or nothing to the owners are unsalable to any buyer except the Government at any price and the prices some owners ask for them they would make a large of cost. It is not believed that there would be frequent occasion sort to condemnation of private property, if such proceedings were authorized, as in most cases the existence of the power would be a great preventive of extortion; although cases may arise in which possession and exercise of the power would be highly important.

It is highly desirable, also, that Congress shall prescribe by law extent to which material found on islands and bars in the river may be used without payment of damages. It is believed that the subject of control and improvement of rivers navigable for inter-state commerce, which is vested in the United States carries with it the right to the work of improvement, without the consent of any individual owner, all such material as may be found within the limits of the river, and constituting part of it. Upon this point differences of opinion are liable to arise between the engineers in charge and riparian parties.

ers, to avoid which there should be such express provision of law as will define the respective rights of the Government and the private owner as clearly as possible.

It is recommended also that provision be made by law for retaining control by the Government over areas of lands built up from deposits induced by the works of improvement placed in the river bed. These amount in some instances to hundreds of acres, and in some localities riparian owners may be disposed to claim possession of them to the detriment of the improvement. It is expected that in most such cases it will be found desirable to encourage the growth of trees upon the newly made banks, and occupy them in that way for many years, and perhaps permanently.

It is regarded as important, also, that a law shall be enacted for the punishment of any person who shall make a cut-off at any neck or bend in the Mississippi River. The history of the river indicates a tendency to recurring cycles of change. A cut-off is followed by a sudden increase of velocity in its vicinity, and by rapid caving above and below. These are likely to cause other cut-offs, one after another, and there then results a widely-extended and long-continued disturbance of the regime of the river. During the continuance of such a period, works of improvement in the channel would be attended with the greatest difficulty. No great cut-off has occurred since that at Vicksburg in 1876, and the present conditions of the river in that respect are regarded as favorable. But the conditions are also existing for the introduction of a cycle of change by the making of a single cut-off, the injurious consequences of which it is impossible to estimate. Such events have happened in the past through the lawless acts of individuals, and against them, stringent penalties should be provided.

FINANCIAL STATEMENT.

<i>Appropriation for surveys and expenses of the Mississippi River Commission, act of March 3, 1883.</i>	
Balance on hand December 16, 1882.....	\$91,780 88
Appropriated by act approved March 3, 1883.....	150,000 00
Total	<u>241,780 88</u>
Expended from December 16, 1882, to November 30, 1883, including estimated liabilities	174,700 00
Balance which it is estimated will be required during remainder of fiscal year ending June 30, 1884	67,080 88
	<u>241,780 88</u>

The estimate of funds for fiscal year 1885, which was transmitted to the honorable the Secretary of War on June 25, 1883, is here repeated.

ESTIMATE OF FUNDS FOR SALARIES AND EXPENSES OF THE COMMISSION FOR NEXT FISCAL YEAR.

Continue the "surveys of the Mississippi River between the Head of the Gulf, near its mouth, and its headwaters, now in progress"; to make additional surveys and examinations of said river and its tributaries"; to such additional examinations and investigations, topographical, geographical, and hydrometrical, as are necessary for maturing a plan for the permanent improvement of the entire river; for salaries and expenses of the Commission in traveling, mileage, and inspection, for expenses, computing, draughting, &c., and for publication of maps and results	\$200,000 00
---	--------------

2430 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

The estimate of funds for works of improvement for the fiscal 1883, which was transmitted to the honorable the Secretary of War June 26, 1882, is here repeated.

ESTIMATE OF FUNDS FOR WORKS OF IMPROVEMENT FOR FISCAL YEAR ENDING 30, 1885.

For works of improvement on the Mississippi River below Cairo, including works in progress in the Lake Providence, Plum Point, and Memphis Reaches; the completion of the closing of existing crevasses and outlets on the Tensas and Yazoo fronts; the rectification of the bed and Atchafalaya Rivers, and the harbors of Memphis, Vicksburg, Natchez, and New Orleans \$3,000

In addition to the above, and as explained in the foregoing the Commission presents the following:

Supplemental estimate for the New Madrid and Memphis Reaches for fiscal year June 30, 1885.

For work on the New Madrid Reach \$1,000
For work on the Memphis Reach 675

FINANCIAL STATEMENTS.

Appropriation for improving Mississippi River, act of August 2, 1882.

Balance November 1, 1882	\$2,388,
Amount expended to November 1, 1883, including outstanding liabilities (estimated) to January 1, 1884, for steamboats, pile-drivers, and other floating plant; for materials, tools, supplies, and labor, continuing and beginning work at Plum Point and Lake Providence, Memphis, and New Madrid; for subsisting and quartering the labor employed, and for payments on contracts for construction and repair of levees	2,167,
Balance available and unpledged January 1, 1884, and which will be required for care of property and maintenance of organization during the remainder of the fiscal year	900,
	<hr/> 2,388,

Appropriation for New Orleans Harbor.

Balance on hand July 1, 1882	\$147,
Expended from July 1, 1882, to November 1, 1883	38,
Balance available November 1, 1883	109,
	<hr/> 147,

Appropriation for improving mouth of Red River.

Balance on hand July 1, 1882	\$90,
Expended from July 1, 1882, to November 1, 1883	51,
Balance available November 1, 1883	38,
	<hr/> 90,

Appropriation for Natchez Harbor.

Balance on hand July 1, 1882	\$8,
Expended from July 1, 1882, to November 1, 1883	2,
Balance available November 1, 1883	5,
	<hr/> 8,

Résumé.

Total amounts of funds in Treasury and in hands of disbursing officers,
November 1, 1883:

Appropriation for improving Mississippi River	\$844,717 13
Appropriation for New Orleans Harbor	109,378 91
Appropriation for mouth of Red River	38,841 74
Appropriation for Natchez Harbor	5,331 42
Total.....	998,269 20
Estimated liabilities to January 1, 1884, including retained percentages and balances due on contracts for levee work and outstanding liabilities for material and labor on works of construction.....	798,000 00
Balance available, as above	200,269 20

CHAS. R. SUTER,
Major of Engineers, U. S. A.
HENRY MITCHELL,
Coast and Geodetic Survey.
B. M. HARROD.
ROBERT S. TAYLOR.
S. W. FERGUSON.

I concur in the foregoing report, except so much of it as relates to levees and outlets, on which subject I will submit my views separately.

C. B. COMSTOCK,
Lieutenant-Colonel of Engineers, and Brevet Brigadier-General,
President Mississippi River Commission.

I concur in the foregoing report of the Commission, with the single qualification that the value of levees as a factor in the problem of channel improvement in preventing the wide dispersion of flood waters, is not affirmed in the report in sufficiently positive terms, and with that clearness and prominence to which, in my judgment, it is entitled.

Q. A. GILLMORE,
Colonel of Engineers, Brevet Major-General, U. S. A.

As I am unable to concur in the part of the report relating to levees, I submit the following remarks:

The Commission state—

The act creating the Commission makes it the duty of the Commission to consider the subject of the prevention of destructive floods, and, as bearing upon that matter, there is submitted for information the following summary of the probable extent and cost of such a system.

The Commission submits an estimate for levees, to prevent destructive floods, from Commerce, Mo., to the forts below New Orleans, and proposes heights for them of two or three feet above the high water of 1882. The cost of the proposed system is estimated at \$11,443,770, and, for the reasons stated hereafter, is, in my judgment, too small for any adequate system of levees intended to prevent destructive floods and (except at intervals of 15 or 20 years) to secure the property of the inhabitants behind them from danger of destruction.

Before a system of levees can be planned the question must be decided whether it shall be attempted to confine the greatest floods, or only those somewhat less than the greatest. When it is remembered that

the cost of these levees will necessarily be great; that, as they are high, breaks through them will involve large costs in repairs; that the object is to make possible the safe existence behind them of a large productive population in the alluvial bottoms they protect; that the expectation of such a population can justify the large expense involved; that breaks in the levees, when the bottoms are filled with plantations, would involve enormous loss of property; that the height of floods in rivers is now believed to increase as the country drain is cleared up; in view of all these considerations it seems the plan to face at once a great flood, and to provide for its confinement between levees.

It may be said that with interest at 3 per cent. it would be better to allow great floods once in ten or fifteen years to overtop and to damage the levees than to incur a greater expense to avoid an event which occurs only at such intervals of time. But, as has already been said, the only economical justification of the expense involved in an extensive system of levees is the belief that in time the whole region protected from overflow shall become populated and highly productive. At that time approaches the damage done to levees by floods which overflow over them would be insignificant in proportion to the incalculable greater damage done to the population behind them.

Moreover, great floods are not rare.

At Cairo, between 1862 and 1883, inclusive, four floods have reached or exceeded a reading on the gauge of 50.8 feet; the highest reading being 52.4 feet, in 1883. A flood of 51.5 feet may then be expected for once in ten years.

At Memphis, between 1858 and 1883, inclusive, the gauge readings equaled or exceeded 34.0 feet six times; the highest reading being 34.5 feet, in 1882. A flood of 34.5 feet may be expected once in ten years.

At Helena, between 1867 and 1883, inclusive, floods have four times equaled or exceeded a gauge-reading of 45.8 feet; the maximum being 47.2 feet, in 1882. A flood of 46.5 feet may be expected once in ten years.

At the mouth of White River, between 1862 and 1883, inclusive, floods have five times given a gauge-reading of 46.6 feet or more; the highest being 48.5 feet, in 1882. A flood of 47.5 feet may be expected once in ten years.

At Vicksburg, between 1858 and 1883, inclusive, floods have five times given gauge-readings of 48.8 feet or more; the highest being 48.8 feet, in 1862. In 1882 the flood only reached 48.8 feet, the maximum since 1867, and may have had its height diminished by the Vicksburg cut-off of 1876. A flood of 49.0 feet may be expected once in ten years.

At Natchez, between 1858 and 1883, floods reached a gauge-reading of 47.9 feet or more five times; the maximum being 50.3 feet, in 1882. A flood of 48.0 feet may be expected once in ten years.

At Red River Landing, between 1867 and 1883, the gauge has in four years had a flood reading of 46.3 feet or more, the maximum being 47.0 feet, in 1882. A flood of 47.0 feet may be expected once in ten years.

At Carrollton, floods have reached a gauge-reading of 15.4 feet or more, five times between 1859 and 1883, the highest being 15.9 feet, in 1862. A flood of 15.6 feet may be expected once in ten years.

These statements refer to the river as it has been since 1858.

In the preceding statements of floods that may be expected once in ten years, the heights are adopted from an examination of the heights of the floods mentioned.

The following table recapitulates the preceding information, and

the lowest readings on the gauges, with their years, and the high-water readings in 1882:

Distance from Cairo.	Stations.	Highest high water.		Lowest low water.	Year.	Gauge-readings for flood to be expected once in ten years.	Gauge-readings for flood of 1882.
		Feet.		Feet.		Feet.	Feet.
0	Cairo.....	52.4	1883	-1.0	1871	51.5	51.8
24	Memphis.....	35.1	1882	-1.0	1872	34.5	35.3
34	Helena.....	47.3	1882	0.0	1872	46.5	47.3
36	White River.....	48.5	1882	0.0	1872	47.5	48.5
37	Vicksburg.....	51.1	1883	-1.3	1872	49.0	48.8
70	Hatchers.....	50.3	1882	0.0	1872	49.0	47.9
76	Red River Landing.....	48.6	1882	0.0	1872	47.0	48.8
83	Carrollton.....	25.6	1882	-1.6	1872	25.6	25.0

If the figures in the last two columns of this table be compared, it will be seen that in five cases the flood of 1882 was higher than the flood that may be expected once in ten years, and in three cases lower, and that in the average of all it was 0.4 foot higher. Considering the smallness of this excess above the floods to be expected once in ten years, the fact that at four places out of eight the flood of 1882 was not the maximum flood observed in the last 20 or 25 years, and the probability that the height of floods will increase in the future, it seems proper that in the plan for any general system of levees, if the principle of keeping out all floods, whatever their height, should be surrendered (a step of doubtful advisability), the plan should at least provide for holding a flood like that of 1882.

In what follows, that flood will be the one considered.

Adopting the flood of 1882 as the one to be confined, the next question is what height of levees is necessary.

From the investigations of the Commission, the flow of the flood of 1882 at its maximum down the Mississippi Valley, whether in the river proper or in the bottom lands, is now at least approximately known. With a complete system of levees on the river banks, the whole of that flow would be confined between them.

The following table gives the approximate results of the observations of the Commission (many of them not yet published) which were made at the floods of 1882 and 1883:

Stations.	Maximum discharge observed in flood of 1882 in river proper.	Amount which was flowing down valley outside of river.	Total flow past.
	Cubic feet.	Cubic feet.	Cubic feet.
Columbus.....	1,000,000	200,000	1,800,000
Helena (estimated from observations of 1880) ..	1,200,000	600,000	1,800,000
Helena.....	1,540,000	360,000	1,900,000
Bay's Landing.....	1,060,000	840,000	2,000,000
Red River Landing.....	1,600,000	600,000	2,200,000

Observations determining the relations between gauge-readings and corresponding discharges were made at several stations. If those gauge-readings be platted as ordinates and the corresponding discharges as abscissas, the resulting broken line which deviates somewhat from a

height here is called a discharge curve. This discharge curve for the Mississippi river is usually tolerably regular until the river gets above its banks, when it may become irregular and complicated from the escape of water over the banks and from variations in the slope of the main river, due to floods in tributaries or to return of water from the swamps into which it had previously escaped.

But if the river were leveed throughout its length, it seems probable from the investigations of the Commission yet to go, that at places affected by tributary flow the discharge curve for the confined river at all stages would be a continuation of that of the unconfined river at stages less than, or equal to, that at which escape over banks begins. If this should be verified by a complete study of the subject, not made by the Commission, the method of determining the gauge reading at a place where discharge observations have been made which would pass a given discharge with the river thoroughly leveed, would be to prolong graphically the observed discharge curve, continuing it in the form it had before overflow began up till it corresponds to the desired discharge. The gauge reading corresponding to that discharge would be the corresponding height of the confined water surface.

These discharge curves at Columbus, Helena, Hay's Landing, and Red River Landing are given in the Commission's report for 1883. Any one can examine the result of prolonging them and form an idea of the new gauge heights, although different persons would differ somewhat in estimating their prolongations. From the discharge measurements and the observations of flood escape over river banks in the flood of 1882 and 1883, by Mr. Johnson and Mr. Stewart, it is known that in the flood of 1882 the maximum flow across the latitude of Columbus, Miss., was approximately 1,800,000 cubic feet per second, which at Red River Landing increased to about 2,200,000 cubic feet.

With a thorough system of levees these quantities would have been confined between the levees, and the question now is, how much would the levees have raised the river surface above the height it actually attained in 1882?

At Columbus, Ky., overflow begins at about 95 feet on the gauge. Prolongation of the discharge curve in the way previously stated gives for a discharge of 1,800,000 cubic feet a stage about 3 feet above the flood of 1882.

A discharge curve for Fulton, Tenn., is given in the Commission's report for 1881. A prolongation of that curve gives for 1,800,000 cubic feet a gauge reading of about 72 feet, or 10 feet above the flood of 1882.

The maximum discharge across the latitude of Helena, Ark., for the flood of 1882 may be taken as 1,900,000 cubic feet. Prolonging the Helena discharge-curve to this amount, the gauge reading is about 10 feet above high water of 1882.

At Hay's Landing, just below Lake Providence, the maximum discharge across its latitude in the flood of 1882 may be taken as 2,000,000 cubic feet. The discharge curve prolonged to this amount gives a gauge reading 10 feet above the flood of 1882.

At Red River Landing the question of flood height with high levees will depend on the amount of water that is allowed to escape down the Atchafalaya. The maximum observed discharge at Red River Landing in 1882 was 1,600,000 cubic feet. The estimated flow across the latitude of Red River Landing was 2,200,000, so that if 200,000 or 300,000 cubic feet were allowed to go down the Atchafalaya, the flow below Red River Landing would be 1,900,000 or 2,000,000 cubic feet, so that the ra-

of all the levees below Red River Landing would be necessary to hold this increase of 300,000 or 400,000 cubic feet per second.

Where there was a flow of from 500,000 to 900,000 cubic feet per second down the valley, outside of the river, in the flood of 1882, as was the case for long distances above and below Fulton and Lake Providence, there will be for long distances levees needed whose heights above the flood of 1882 will approach the heights of those needed at Lake Providence (or Hay's Landing) and Fulton.

A good system of levees should rise 3 feet above the expected heights of the confined water. No provision has been made for this in these remarks, because at several points the flood of 1882 was the highest of which we have accurate records, and in this paper it has not been proposed to confine the highest floods, although that is essential in a thorough and effective levee system.

Nor has the possible lowering of the river slope, which might occur some time after the building of the levees, been taken into account. The first effect of building levees would be to raise the flood surface. I know of no facts of experience which give data for determining either the amount of such ultimate lowering or the time required for it.

As stated by the Commission, a thorough study of the subject of levees has not yet been made; until then, accurate estimates are impossible, and the heights above the flood of 1882, of 3 feet at Columbus, 10 feet at Fulton, 4 feet at Helena, and 10 feet at Lake Providence, given above, are only approximations. Such as they are, they make it impossible for me to concur in the estimate of \$11,443,770 as the cost of a general system of levees from Commerce, Mo., to the Forts, adequate to preserve that country from destructive floods.

C. B. COMSTOCK,

*Lieutenant-Colonel of Engineers, and Brevet Brigadier-General,
President Mississippi River Commission.*

NEW YORK, December 22, 1883.

The Hon. ROBT. T. LINCOLN,
Secretary of War.

(Through the Chief of Engineers.)

REPORT OF THE CHIEF OF ENGINEERS T. E. KENT.

MISSISSIPPI RIVER COMMISSION.

Item.	Salaries.	Travel.	Supplies.	Subsist- ence.	Fuel.	Repairs.	Transpor- tation.	Mileage.	Miscellan- eous.	Totals.
Salaries of Chief of Division and District Engineers, and other officers and employees.	\$8,333 33									\$8,333 33
Salaries of Assistant Engineers, and other employees.	10,661 93									10,661 93
Salaries of Foremen, and other employees.	5,903 90									5,903 90
Salaries of Laborers, and other employees.	4,452 80									4,452 80
Salaries of Clerks, and other employees.	4,233 98									4,233 98
Salaries of Messengers, and other employees.	17,240 43									17,240 43
Salaries of Watchmen, and other employees.	277 50									277 50
Salaries of Janitors, and other employees.	229 00									229 00
Salaries of Engineers, and other employees.	3,401 77									3,401 77
Salaries of Foremen, and other employees.	6,483 41									6,483 41
Salaries of Laborers, and other employees.	1,544 10									1,544 10
Salaries of Clerks, and other employees.	4,455 02									4,455 02
Salaries of Messengers, and other employees.	18,431 32									18,431 32
Salaries of Watchmen, and other employees.	61 00									61 00
Salaries of Janitors, and other employees.	3,410 75									3,410 75
Salaries of Engineers, and other employees.	70,403 00									70,403 00
Salaries of Foremen, and other employees.	18,012 95									18,012 95
Salaries of Laborers, and other employees.	488 88									488 88
Totals	49,025 60	10,892 95	4,244 04	11,542 00	3,070 14	3,000 40	11,808 02	4,784 40	18,491 70	
Item.	Services maintenance engineers.	Rent.	Fuel.	Prof. work and material.	Furniture.	Drawings material and supplies.	Transportation.	Subsistence.	Miscellaneous.	Totals.
Office	\$100 00	\$1,800 00	\$847 07	\$10 00	\$74 40	\$100 41	\$870 40	\$400 10	\$400 10	\$1,000 00

* Line of travel run by contract at \$10 per mile.

SUMMARY.

Balance from appropriation March 3, 1881	982,005 73
Appropriated by act August 2, 1882.....	150,000 00
Cash deposited, sale of fuel to officers, and overpayment vouchers.....	185 50
Total	<u>148,194 23</u>
Expenditures for fiscal year ending June 30, 1883.....	178,852 00
Balance.....	<u>9,841 53</u>

SMITH S. LEACH,

First Lieutenant of Engineers, Secretary and Disbursing Officer Mississippi River Commission

2438 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY

TABLE OF TOTAL EXPENDITURES, CONSTRUCTION DEPARTMENT, MISSISSIPPI
COMMISSION, FROM THE BEGINNING OF CONSTRUCTION UP TO NOVEMBER 1

[Covering appropriations of March 3, 1881, and August 2, 1882.]

New Madrid Reach	1,400
Plum Point Reach	1,400
Memphis Reach and Harbor.....	1,400
Lake Providence Reach	1,400
Vicksburg Harbor	1,400
Delta Point, La.....	1,400
Survey of Helena Reach	1,400
Survey of Saint Francis front, first district	1,400
Survey of Saint Francis front, second district	1,400
Survey of unleveed fronts, third district	1,400
Survey of unleveed fronts, fourth district	1,400
Survey of Cubitt's Gap.....	1,400
Choctaw Bend survey.....	1,400
Observations at Carrollton, La	1,400
Closing Bonnet Carré Crevasse	1,400

LEVEES.

Second District.

Yazoo front	71
-------------------	----

Third District.

Tensas front	20
Yazoo front	31

Fourth District.

Atchafalaya front	10
Tensas front	25

Total.....	4,27
------------	------

TABLE OF TOTAL EXPENDITURES FROM SPECIAL APPROPRIATIONS.

Natchez and Vidalia (June 30, 1882, to November 30, 1883)	9
Mouth of Red River (to November 1, 1883)	5
New Orleans Harbor (July 1, 1882, to November 1, 1883)	3

Total	9
-------------	---

Total from all appropriations	4,37
-------------------------------------	------

Respectfully submitted.

CLINTON B. SEARS,
Captain Engineers, U. S. A.
Secretary Construction Committee, Mississippi River Com

LIST OF APPENDICES ACCOMPANYING THE FOREGOING REPORT.

	Page.
NDIX A.—Annual report of the Secretary	2441
NDIX B.—Report upon, and results of, secondary triangulation from Cairo to Keokuk	2443
NDIX C.—Reports upon, and results of, precise leveling from Cairo to Fulton	2454
1. Report on field work, Cairo to Grafton	2454
2. Report on field work, Grafton to Chicago	2456
3. Report on reduction	2463
NDIX C 1.—Report on cumulative errors in precise leveling	2547
NDIX D.—Reports on field work, of topography	2568
1. Arkansas City to Greenville, and Natchez to Bayou Sara ..	2568
2. Lake Providence to Warrenton, and Bayou Sara to Donaldsonville	2573
3. Warrenton to Natchez	2576
4. Resurveys in front of crevasses	2577
NDIX E.—Report on work of trans-alluvial levels	2590
NDIX F.—Reports upon, and results of, river gaugings at various points on the Mississippi and Ohio Rivers	2584
1. At Clayton, Iowa, and Paducah, Ky	2584
2. At Columbus, Ky	2600
3. At Helena, Ark	2617
4. At Hay's Landing, Miss	2627
5. At Red River Landing, La	2636
6. At Winona, Minn	2660
7. At Hannibal, Mo	2661
8. At Grafton, Ill	2664
9. Probable discharges at various points in 1881-'82	2668
NDIX G.—Report on changes of the Mississippi River from 1810 to 1883 ..	2687
NDIX H.—Report of Capt. C. B. Sears upon the operations of the general service during the past year	2692
NDIX I.—Report of Capt. J. G. D. Knight upon operations in the first district	2755
NDIX I 1.—Report upon operations at Plum Point	2764
NDIX I 2.—Report upon operations at Gold Dust dikes	2764
NDIX I 3.—Report upon operations at Osceola upper and lower dikes ..	2772
NDIX I 4.—Report upon operations at Bullerton Tow-head	2776
NDIX I 5.—Report upon operations at Osceola, Bullerton, and Plum Point dikes	2779
NDIX I 6.—Report upon hydraulic grading operations	2780
NDIX I 7.—Report upon surveys, Plum Point Reach	2785
NDIX K.—Report of Maj. A. M. Miller upon operations in the second district	2791
NDIX K 1.—Report upon operations at Hopefield Bend	2796
NDIX K 2.—Report upon operations in Memphis Harbor	2797
NDIX K 3.—Report upon a survey of Memphis Reach	2803
NDIX K 4.—Report upon a survey of the Helena Reach	2807
NDIX K 5.—Estimate for building and repairs of levees	2812
NDIX L.—Report of Capt. W. L. Marshall upon operations in the third district	2814
NDIX L 1.—Report upon operations on the Lake Providence Reach	2828
NDIX L 2.—Report upon operations at Pilcher's Point	2842
NDIX L 3.—Report upon operations in Vicksburg Harbor	2844
NDIX L 4.—Report upon levee work on the Tensas front	2856
NDIX L 5.—Report upon levee work on the Yazoo front	2858
NDIX L 6.—Report on a survey of Choctaw Reach	2867
NDIX M.—Report of Maj. Amos Stickney upon operation in the fourth district	2868
NDIX N.—Geological report upon borings in the Mississippi Valley, between Cairo and Vicksburg	2885

LIST OF PLATES ACCOMPANYING THE FOREGOING REPORT.

Description.	Designation.	
	Appendix.	Plates.
Sketch of triangulation.....	B	I
Level discrepancies.....	C	II
Progress sketch, topography.....	D	I
Sketch of sections sounded before and after the principal crevasses of the flood of 1883.....	D	II III IV V VI VII
Profiles of above.....	D	
Transalluvial levels.....		
Profile of line No. 1.....	E	I
Profile of line No. 2.....		II
Profile of line No. 4.....		III
Profile of line No. 5.....		IV
Profile of line No. 6.....		V
Profile of line No. 7.....		VI
Profile of line No. 8.....		VII
Profile of line No. 9.....		VIII
Discharge observations at Paducah, Ky.....	F	I
Discharge observations at Columbus, Ky.....		II
Discharge observations at Helena, Ark.....		III
Discharge observations at Hays' Landing, Miss.....		IV
Discharge observations at Red River Landing, La.....		V
Sketches of changes in river, 1810-1883.....		
Grand Gulf to Natchez.....	G	I
Natchez to Red River.....		II
Red River to Morganza.....		III
Morganza to Baton Rouge.....		IV
Baton Rouge to Claiborne Island.....		V
Comparison of sections of 1851 and 1883.....	G	VI VII VIII IX
Profiles high-water widths, 1851 and 1883.....	G	X
Survey of Plum Point Reach made in October, 1883.....	J	I
Progress sketch; Osceola, Bullerton, and Plum Point Dikes.....	J	II
Progress sketch; Gold Dust Dikes.....	J	III
Progress sketch, Osceola Upper and Middle Dikes.....	J	IV
Progress sketch, works at Bullerton Tow-head.....	J	V
Sections of dikes.....	J	VI
Sections of mattress and method of sinking.....	J	VII
Oscillations of the Mississippi River at Plum Point.....	J	VIII
Comparison of cross sections, Plum Point Reach.....	J	IX
Hopfield Bend and Memphis Harbor.....	K	I
Sketch of Bordeaux Chute.....	K	II
Construction works, Lake Providence Reach.....	L	I
Comparative sections of construction works.....	L	II
Dikes, Lake Providence Reach.....	L	III IV V VI VII
Chart of Lake Providence Reach.....	L	VIII
Sketch of mattress head.....	L	IX
Details of mattress head.....	L	X
Sketch of revetment.....	L	XI
Vicksburg Harbor in October, 1883.....	L	XII
Vicksburg Harbor, sections of canal.....	L	XIII
New Orleans Harbor, November, 1883.....	M	I
Diagram of discharge measurements.....	M	II
Comparison of profiles in Nine-Mile Bend.....	M	III
Total sheets.....		

* In 2 sheets.

APPENDICES.

APPENDIX A.

ANNUAL REPORT OF THE SECRETARY OF THE COMMISSION UPON THE FIELD WORK OF SURVEYS AND EXAMINATIONS.

OFFICE OF MISSISSIPPI RIVER COMMISSION,
2828 WASHINGTON AVENUE,
Saint Louis, November 13, 1883.

GENERAL: I have the honor to submit the following report of surveys and examinations during the fiscal year ending June 30, 1883:

Outfit.—During the year the fleet was increased to accommodate three topographical parties by the addition of two new boats, named the Illinois and Kentucky, counterparts, respectively, of the Mississippi and Louisiana.

The old boats have been thoroughly repaired, and the Pioneer enlarged. One of the iron launches was lost in a storm at Helena, about the end of October. After several days' search by a snag-boat, it was conceded to be impossible to recover it, and the attempt was abandoned.

The tug Mignon and survey boat Missouri were inspected by Captain Marshall on February 10, and his recommendations that the Missouri and the hull of the Mignon be abandoned, the machinery of the latter being taken out, having been approved by the Chief of Engineers, have been carried into effect.

Instruments.—The old instruments were thoroughly repaired, as noted in last report. The following have been purchased during the year: 4 transits, 3 Wye levels, 4 sextants, 3 prismatic compasses, 2 pedometers, 2 hand levels.

There have been transferred to this appropriation from that for the survey of Northern and Northwestern Lakes: 1 chronometer, 1 iron standard bar, 1 standard meter.

Organization and methods.—The only change to be noted is in the programme for precise leveling, in which the instructions have been so modified as to require that each observer shall duplicate his own work in opposite direction, so as to form a loop beginning and ending on the same bench. In this connection attention is invited to a report by Assistant L. L. Wheeler on cumulative errors, submitted herewith.

Progress and cost.—Precise levels were carried from Carrollton to the tide gauge at Biloxi, 87 miles; from Keokuk to Fulton, 171 miles; and from Fulton to Savannah, 21 miles. The last section is a part of the continuation of the line to Chicago, which has since been completed.

The cost of the work in the other sections was as follows:

Carrollton to Biloxi:

Total field cost.....	\$2,778 36
-----------------------	------------

Cost per mile of duplicated work.....	31 93
---------------------------------------	-------

Keokuk to Fulton:

Total field cost	3,252 05
------------------------	----------

Cost per mile of duplicated work.....	19 08
---------------------------------------	-------

Cost per mile of river	19 02
------------------------------	-------

Average cost per mile of duplicated work for the two sections	23 46
---	-------

The work on the Carrollton-Biloxi section was undertaken during the windy season on the Gulf coast, and, to meet this contingency, observing tents were provided. This was their first use in our work, and they were found of such great advantage that they have been employed on subsequent work, and have enabled much windy weather to be utilized.

This section was along a line of railroad, and a hand-car was kindly loaned by the company for transportation. It was found to so materially contribute to the progress of the party, that on subsequent work, lying along a railway line, a hand-car was purchased and added to the outfit of the party.

The tabulated results of the final computation for the above lines, and also for the line from Grafton to Keokuk, noted in the last annual report, are herewith submit-

2442 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

and other field reports by Assistants J. R. Johnson and J. A. Paige, and reports by Assistant L. L. Wheeler.

Topography and hydrography was carried from Arkansas City to Greenville, and from Lake Providence to Indianopolisville. 327 miles; a total of 329 miles. parties were engaged in this work, and their performance may be summarized as follows:

First party, Assistant J. A. Ockerson, Arkansas City to Greenville, and Bayou Boeuf to Indianopolisville:

Number of miles of river	
Number of square miles of topography	
Number of square miles of hydrography	
Total area surveyed in square miles	
Total field cost	
Cost per mile of river	
Cost per square mile of survey	

Second party, Assistant L. L. Wheeler, Warrenton to Natchez:

Number of miles of river	
Number of square miles of topography	
Number of square miles of hydrography	
Total area surveyed in square miles	
Total field cost	\$12.
Cost per mile of river	
Cost per square mile of survey	

In connection with the work of this party the sections of the previous survey Mainw's to Audubon, from Kiterion to head of Ozark Island, from Bolivar to C. Smith, and from Mound Place to Arkansas City, were resounded.

The sections sound are at and below the principal crevasses of the flood of 1883. This work comprised 21 square miles of hydrography, costing \$5.65 per square mile.

Third party, Assistant C. M. Winchell, Lake Providence to Warrenton, and Bayou Boeuf to Indianopolisville:

Number of miles of river	
Number of square miles of topography	
Number of square miles of hydrography	
Total area surveyed, square miles	
Total field cost	\$23.
Cost per mile of river	
Cost per square mile of survey	

For the three parties:

Total area surveyed, square miles	
Cost per square mile	

Field reports on the above work by assistants Ockerson, Winchell, Wheeler, and H. B., are submitted herewith.

Triangulation levels were completed on the following lines:

No. 5. Up Cypress Creek.

No. 6. Grand Lake to Bayou Macon Hills.

No. 7. Lake Providence to Yazoo City.

No. 8. Saint Joseph, west to high land.

No. 9. Fort Adams to Avoyelles Prairie, and thence across Bayou Boeuf to River.

The total distance of 164 miles was accomplished in a season of 174 days.

The total field cost was \$5,312.50, giving a cost per mile of \$32.43.

A report, by Assistant E. B. Davis, of the entire work is submitted herewith.

Observations to determine the escape of water from the river were made from to Vicksburg at the top of the flood of 1883. Below Vicksburg the flood was sufficient magnitude to warrant the continuance of the observations.

Determination of high-water marks have been continued, and the low-water line was extended from Commerce to Natchez.

The observation parties mentioned in last report as having begun work at Paducah, Helena, Hays' Landing, and Red River Landing, continued the measurement of sections and discharges during a year, at the expiration of which they disbanded. The results have been partially reduced, checked, and tabulated in office, and are herewith submitted, together with reports of the chiefs of the parties at Paducah, Columbus, Hays' Landing, and Red River Landing.

To ascertain the effect of the closure of Bonnet Carré crevasse, a hydrographic survey of 6 miles in front of it was made in November, 1882. This survey is now, November, 1883, being repeated.

A resurvey of the Atchafalaya was made in December, 1882, and January, 1883, to determine by comparison with a previous survey, the amount of enlargement of that stream.

I am glad of another opportunity of bringing to the attention of the committee the zealous and efficient services rendered by the assistant engineers and other employes of the Commission.

The permanent force was somewhat increased during the year by the retention of the principal officers of the third topographical party. The grade of work has been higher than we have heretofore attained. This has been accompanied by a marked reduction of cost, due to the increase of rate. These gratifying results are largely due to the policy heretofore pursued, of so arranging the work in field and office as to admit of its being done by a comparatively small force, kept continuously employed.

The slight disadvantages which this system presents are repaid a hundred fold by the personal interest in, and enthusiasm for, the work shown by a very large majority of those engaged upon it; without which the results sets forth in this report would have been impossible.

A feature of the office work of the past year has been the successful substitution of printing from types for hand-lettering on our detail sheets. The cost is very much reduced, and the appearance of the charts improved. In this connection the services of Mr. J. A. Ockerson are deserving of especial mention.

For details of expenditures, the committee is respectfully referred to the itemized statement of expenditures submitted to the Commission.

Very respectfully, your obedient servant,

SMITH S. LEACH,
First Lieutenant of Engineers, Secretary.

To General C. B. COMSTOCK,
*President Mississippi River Commission, and
Chairman Committee on Surveys and Examinations.*

APPENDIX B.

FINAL REPORT UPON A SECONDARY TRIANGULATION OF THE MISSISSIPPI RIVER BETWEEN CAIRO, ILL., AND KEOKUK, IOWA., EXECUTED UNDER THE ORDERS OF THE MISSISSIPPI RIVER COMMISSION, 1880-'81.

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., December 1, 1883.

GENERAL: I have the honor to submit herewith a memorandum compiled from the records of this office, relative to the secondary triangulation from Cairo to Keokuk, accompanied by the results in tabular form, and a sketch of the system, the whole intended to form a final report upon this portion of the work.

Very respectfully, your obedient servant,

SMITH S. LEACH,
First Lieutenant of Engineers, Secretary.

General C. B. COMSTOCK,
*President Mississippi River Commission and
Chairman of Committee on Surveys and Examinations.*

I.—The system is composed of 146 principal stations and 4 auxiliary stations, to connect the triangulation with the Chester and Cape Lacroix bases. Most of the stations are situated on the bluffs on either side of the valley. They are connected by 97 single triangles, 20 quadrilaterals, 3 pentagons, and 1 hexagon.

II.—The work depends on the following known lines:

1. A secondary base at Cairo, measured by a party of the United States Lake Survey. The length and azimuth of this base and the geodetic co-ordinates of its extremities were furnished by the office of that survey. Its length is 1,646.78 meters. (For description of this base, see Report of Chief of Engineers for 1877, Part II, page 1196.)

2. A secondary base at Chester. The length and azimuth of this base were determined by Assistant G. Y. Wisner in 1880. Its length is 3,255.07 meters.

3. The line Dryer-Insane Asylum, at Saint Louis. This line was furnished by the office of the Coast and Geodetic Survey. It depends for length and azimuth upon the American Bottom base, opposite Saint Louis, and for geodetic co-ordinates of its extremities, on the Saint Louis astronomical post. It is in the fifth triangle from the base. Its length is 13,331.3 meters.

4. A secondary base near Grafton, measured by Assistant Wisner in 1881. The

azimuth of a line near this base was determined, but not with sufficient accuracy to be used, except as a check. The length of the base is 2,031.61 meters.

5. A secondary base at Louisiana. The length and azimuth of this base were determined by Assistant Wisner in 1881. The base was connected with the Louisiana astronomical post. For description of this post, see Report of Chief of Engineers 1879, page 1918. The base is 2,705.10 meters in length.

6. A secondary base at Keokuk, measured by Assistant Wisner in 1881. The azimuth of base was determined by Assistant John Eisenmann in same year. Its length is 1,297.38 meters.

A base was also measured, with steel tape, at Cape Lacroix, but was used only as a check.

III.—The following instruments were used:

Repsold universal instrument No. 1. Diameter of horizontal limb 10 inches.* Limb graduated to 4 minutes, reads by two microscopes to 2 seconds. Angles measured in order around the station, positive and negative, direct and reversed. Eight sets were taken uniformly distributed over the limb, giving 16 pointings at each station.

Troughton & Simms No. 1. Diameter of horizontal limb, 10 inches. Limb graduated to 5 minutes, reading by two microscopes to one second. Programme same as for Repsold.

Troughton & Simms No. 2 (of the Mississippi River Commission). Same as Troughton & Simms No. 1. Programme same as for Repsold.

Troughton & Simms No. 2 (of the Lake Survey). Diameter of horizontal limb, 10 inches. Limb graduated to 5 minutes reading, by two microscopes to one second. Programme same as for Repsold.

None of the instruments closed the horizon. The limit of closure of triangles was 1 second. The instruments were mounted on tripods of rough timber, which were self-standing. The observer stood on a platform disconnected from the instrument support.

The stations were marked by stones 3 feet in length, dressed to 6 by 6 inches at each end, the balance rough. A small hole was drilled in the top. They were planted vertically, the top projecting but a few inches above ground.

The targets used in the triangulation from Cairo to Grafton were octagonal plates covered with alternate zones of black and white cloth. A nail in the bottom was placed in the hole in the top of the marking stone, and the target was then plumbed. When the station was occupied the target was removed and reset before leaving.

For the greater part of the stretch from Grafton to Keokuk the target used consisted of four parallel wires fastened at bottom to a circular block by a wire ring, and fastened above by three other horizontal wire rings, which, with the block at bottom divided the target into three sections. Strips of white cloth were fastened to opposite wires of the first and third sections, one strip to each section, and at right angles to each other. A strip of black cloth was fastened at an angle with the white strips to two auxiliary wires attached to the second and third rings.

This target gave no phase, and presented an illuminated surface whether the sun was before or behind it. To support the target a cross-piece was fastened to the top of the platform which supported the observer, and above the observer's head. A hole in the cross-piece was centered over the hole in the marking stone. A nail projecting from the block at bottom of target was placed in this hole, and the target was then plumbed and guyed to the corners of the platform. The target was not disturbed when the station was occupied.

IV.—For the preliminary reduction single triangles were adjusted to closure (quadrilaterals and pentagons were adjusted to satisfy local conditions), side and azimuth equations being neglected. The lengths and azimuths of sides were then computed for the stretches given below. The discrepancies were:

From—	To—	Number of triangles.	Discrepancies.	
			In length.	In azimuth
				Obs.—comp
Cairo	Chester	39	1 : 6,000	+21.
Chester	Saint Louis	23	1 : 100,000	+ 9.
Saint Louis	Grafton	35	1 : 30,000
Grafton	Louisiana	22	1 : 13,000	† -10.
Louisiana	Keokuk	25	1 : 25,000	+ 4.

* Erroneously stated as 12 inches in previous reports.
† Saint Louis to Louisiana.

The final reduction was made separately for each of the five stretches into which the work was divided by the six known lines before enumerated. It consisted of a least square adjustment, in which the observed lengths and azimuths of bases were assumed as correct, and all angles were given equal weight. The conditions to be satisfied by the finally adjusted angles were that all triangles should close, and that the computed lengths and azimuths of bases should agree with their measured lengths and azimuths. The geodetic co-ordinates were then computed, all latitudes and longitudes being referred to the Cairo astronomical post. The final discrepancies between the observed values of latitudes, longitudes, and azimuths and the corresponding values as computed from Cairo, are as follows:

	Latitude.	Longitude.	Azimuth.
	Obs.—comp. "	Obs.—comp. "	Obs.—comp. "
Chester	*+6.13	−0.12
Saint Louis.....	+4.77	−2.90	+0.17
Louisiana	+1.56	−1.09	+0.04
Keokuk	−0.02

* Latitude at Chester only approximate.

A special report on the least square adjustment of the stretch from Cairo to Grafton, prepared by Assistant G. Y. Wisner, who made the computation, may be found in the Report of the Mississippi River Commission for 1882, page 62.

Tabulated results of secondary triangulation from Cairo to Keokuk.

No.	Stations.	Observed angles.	Adjust'd angles.	Distance. <i>Meters.</i>	Azimuth.	Latitude.	Longitude.
		° ' "	"		° ' "	° ' "	° ' "
1	South Base.....	108 19 51.58	50.75	1,646.78	172 32 07.19	37 01 28.97	89 11 23.19
2	North Base.....	88 25 19.24	19.71	2,851.28	30 57 21.09	37 02 21.94	89 11 31.84
3	Bowles.....	23 14 50.76 01.58	49.55 00.01	1,866.65	244 11 35.51	37 01 02.61	89 12 31.18
2	North Base.....	71 57 02.60	01.33	2,851.28	30 57 21.09
3	Bowles.....	68 18 08.10	04.66	4,239.74	142 38 41.30
4	Taylor	39 44 55.05 05.75	54.04 00.03	4,143.21	282 52 44.56	37 02 51.93	89 14 15.28
3	Bowles	26 03 27.60	24.93	4,239.74	142 38 41.30
4	Taylor	69 01 27.70	25.54	1,869.71	253 36 13.06
5	Nimbus	84 55 08.64 03.94	09.55 00.02	3,974.38	348 41 47.25	37 03 09.04	89 13 02.69
4	Taylor	89 57 49.24	49.62	1,869.71	253 36 13.06
5	Nimbus	52 40 08.50	09.45	3,080.67	126 17 06.25
6	Dickey.....	37 21 59.04 56.78	60.94 00.01	2,449.59	343 38 06.61	37 04 08.17	89 14 43.21
4	Taylor	37 20 03.76	01.30	2,449.59	163 38 23.44
6	Dickey.....	63 15 12.28	11.24	1,511.30	46 53 17.85
7	Rowse	79 24 49.15 05.19	47.47 00.01	2,225.37	306 17 38.40	37 03 34.67	89 15 27.87
6	Dickey.....	84 45 43.33	43.71	1,511.30	46 53 17.85
7	Rowse	61 16 55.57	55.08	2,694.42	165 35 55.85
5	Murray	33 57 20.12 59.02	21.22 00.01	2,372.91	311 38 18.28	37 04 59.32	89 15 55.00
7	Rowse	33 24 07.12	06.37	2,694.42	165 35 55.85
5	Murray	86 09 12.54	13.43	1,705.18	71 44 52.92
9	Missouri Sister.....	60 26 40.00 59.66	40.21 00.01	3,090.50	312 10 53.60	37 04 41.99	89 17 00.66
5	Murray	35 17 40.47	40.71	1,705.18	71 44 52.92
9	Missouri Sister.....	116 21 33.05	33.02	2,075.03	135 22 40.37
10	Spiese's Mill	28 20 44.54 58.06	46.27 00.00	3,217.98	287 01 18.52	37 05 29.90	89 17 59.58
9	Missouri Sister.....	57 55 51.09	52.17	2,075.03	135 22 40.37
10	Spiese's Mill	68 25 11.05	13.33	2,183.28	23 47 18.12
11	Scudder	53 38 52.82 54.96	54.51 00.01	2,395.83	257 25 51.13	37 04 25.09	89 18 35.23
10	Spiese's Mill	58 17 21.17	20.01	2,183.28	23 47 18.12
11	Scudder	91 36 10.07	08.19	3,702.50	112 10 48.43
12	Promised Land.....	30 06 33.02 04.26	31.82 00.02	4,350.55	262 02 52.91	37 05 10.41	89 20 54.05

2446 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Tabulated results of secondary triangulation from Cairo to Hankou—Continued.

No.	Stations.	Observed angles.	Adjusted angles.	Distances.	Azimuth.	Latitude.	Longitude.
		D. M. S.	"	Meters.	D. M. S.	D. M. S.	"
10	Spicer's Mill	34 25 25.08	25.71	4,350.55	82 04 30.13
12	Provided Land	115 14 32.82	32.71	4,914.90	146 48 19.29
13	Atherton	30 09 50.13	00.02	7,830.70	230 37 12.82	37 07 22.02	80 23
		52.71	00.05				
12	Provided Land	42 27 04.71	04.94	4,914.90	146 48 19.29
13	Atherton ..	30 32 20.30	30.01	3,347.36	8 30 43.46
14	Goose Island	97 40 34.41	25.00	3,179.40	294 19 50.04	37 05 35.00	80 23
		57.47	00.02				
13	Atherton	84 57 52.40	52.52	3,347.36	8 30 43.46
14	Goose Island	42 50 35.04	34.72	4,230.43	142 48 30.23
15	Powers Island	52 11 31.22	31.77	2,800.90	271 36 26.07	37 07 20.46	80 24
		54.06	00.02				
12	Atherton	36 08 01.16	01.24	2,800.90	91 37 30.00
15	Powers Island ..	86 28 50.25	50.12	2,010.00	185 07 30.45
16	Barnham	87 28 07.00	00.06	3,410.07	307 30 32.19	37 00 31.45	80 24
		50.17	00.01				
15	Powers Island	55 54 43.28	43.91	2,010.00	185 07 30.45
16	Barnham	82 08 10.50	11.23	2,400.07	07 13 02.19
17	Commerce	41 50 05.00	05.75	2,977.70	200 11 57.11	37 00 27.02	80 20
		50.00	00.01				
16	Barnham	07 08 44.00	44.20	2,400.07	07 13 02.19
17	Commerce	07 08 10.04	20.15	3,304.00	200 04 31.20
18	Santa Fé	48 42 51.78	52.07	3,204.02	234 22 04.47	37 10 05.16	80 25
		55.20	00.02				
17	Commerce	43 31 21.05	21.22	3,304.00	200 04 31.20
10	Santa Fé	70 07 32.03	32.02	3,400.26	00 12 31.05
19	Hofner	00 21 04.20	00.17	3,200.22	230 22 25.03	37 10 05.44	80 27
		00.00	00.02				
18	Santa Fé	57 30 42.20	42.28	2,400.26	00 12 31.05
19	Hofner	50 41 32.72	32.16	2,232.26	212 30 00.50
20	Lasser	05 41 20.04	20.50	2,200.20	327 40 51.00	37 11 05.00	80 26
		50.07	00.01				
19	Hofner	50 12 37.58	37.72	2,232.26	212 30 00.50
20	Lasser	03 40 18.54	19.91	3,074.00	117 10 50.50
21	Uncle Joe	38 07 01.23	02.50	3,504.48	325 10 45.93	37 11 51.26	80 26
		57.40	00.03				
20	Lasser	23 42 06.83	06.24	3,074.00	117 10 50.50
21	Uncle Joe	70 55 14.77	13.95	1,702.70	226 14 20.61
22	Thebes	75 22 30.01	20.02	3,002.27	330 52 21.01	37 12 30.01	80 27
		01.21	00.01				
21	Uncle Joe	60 00 20.00	20.00	1,702.70	226 14 20.61
22	Thebes	72 32 18.03	20.10	2,027.48	118 48 20.03
23	Grand Chain	49 17 10.01	11.25	2,232.82	347 04 48.00	37 12 02.50	80 28
		50.23	00.01				
22	Thebes	41 30 41.12	42.17	2,027.48	118 48 20.03
23	Grand Chain	73 28 01.25	01.03	2,510.10	225 19 35.71
24	Day	45 01 14.45	10.21	2,747.74	00 19 03.47	37 14 00.04	80 27 1
		50.02	00.01				
22	Thebes	28 00 43.49	42.06	2,747.74	100 19 03.10
24	Day	76 06 00.20	50.05	1,332.46	75 26 08.12
24'	South Base	70 43 18.12	17.49	2,728.50	322 08 48.00	37 12 40.17	80 28 0
		01.00	00.00				
24	Day	50 51 20.08	20.71	1,332.46	75 26 08.12
24'	South Base	54 10 54.30	54.20	1,240.22	201 00 37.37
24'	North Base	00 51 36.20	30.09	1,176.47	314 17 15.20	37 14 20.00	80 27 4
		00.52	00.00				
23	Grand Chain	20 21 30.02	30.30	2,519.10	225 19 35.71
24	Day	97 25 30.45	30.97	2,070.31	143 45 50.03
25	Cape Lacroix	40 11 30.71	40.74	3,461.25	8 57 09.03	37 14 50.51	80 28 0
		57.48	00.01				
24	Day	00 40 03.00	03.20	2,070.31	143 45 50.03
25	Cape Lacroix	02 40 45.00	47.41	2,070.04	200 04 41.47
26	Horton's	58 30 07.10	10.33	2,163.77	21 26 22.24	37 15 05.07	80 28 4
		00.00	00.00				

Tabulated results of secondary triangulation from Cairo to Keokuk—Continued.

No.	Stations.	Observed angles.	Adjusted angles.	Distance.	Azimuth.	Latitude.	Longitude.
		° ' "	° ' "	Meters.	° ' "	° ' "	° ' "
5	Cape Lacroix.....	83 07 19.71	18.71	2,070.64	260 04 41.47
6	Sexton's.....	86 04 18.03	14.68	10,963.46	166 09 46.26
7	Floral.....	10 48 24.28 02.02	26.66 00.05	11,016.98	356 57 08.36	37 20 50.38	89 28 29.53
16	Sexton's.....	46 56 12.61	10.74	10,963.46	166 09 46.26
17	Floral.....	65 08 54.01	52.96	8,644.05	280 59 48.75
18	Clear Creek.....	67 54 56.38 03.00	56.53 00.22	10,735.88	33 08 21.30	37 19 56.75	89 22 44.64
27	Floral.....	46 41 44.33	42.04	8,644.05	280 59 48.75
28	Clear Creek.....	95 52 55.53	55.47	10,351.34	196 53 13.28
29	Bluff Lake.....	37 25 22.20 02.00	21.82 00.23	14,140.53	54 22 49.55	37 25 17.04	89 20 42.20
38	Clear Creek.....	45 36 20.92	26.69	10,351.34	196 56 13.28
39	Bluff Lake.....	85 49 16.72	17.85	9,865.18	102 46 45.58
40	Moccasin Springs.....	48 34 15.11 58.75	15.73 00.26	13,769.21	331 17 03.42	37 26 28.54	89 27 13.57
49	Bluff Lake.....	38 58 55.32	56.36	9,865.18	102 46 45.58
50	Moccasin Springs.....	89 10 21.69	22.39	7,892.25	103 32 25.31
51	Rich.....	51 50 30.49 56.50	41.45 00.20	12,544.78	321 42 29.64	37 30 37.42	89 25 58.33
52	Moccasin Springs.....	42 46 36.39	36.66	7,892.25	103 32 25.31
53	Rich.....	82 26 58.37	60.65	6,561.56	96 00 11.14
54	Indian Creek.....	54 46 22.35 57.11	23.42 00.13	9,577.75	330 43 52.75	37 30 59.60	89 30 24.06
55	Rich.....	49 40 11.50	11.31	6,561.56	96 00 11.14
56	Indian Creek.....	102 12 07.34	06.61	10,609.97	173 45 22.72
57	Silica.....	28 07 41.20 00.04	42.25 00.17	13,603.45	325 37 11.79	37 36 41.72	89 31 11.11
58	Indian Creek.....	49 50 51.61	50.11	10,609.97	173 45 22.72
59	Silica.....	55 37 47.49	45.46	8,414.61	298 07 08.58
60	Big Muddy.....	74 31 25.60 04.70	24.62 00.19	9,080.99	43 38 48.47	37 34 32.97	89 26 08.67
61	Silica.....	107 18 01.20	01.48	8,414.61	298 07 08.58
62	Big Muddy.....	38 22 06.69	07.74	14,245.30	156 32 20.83
63	Fountain Bluff.....	34 19 50.18 58.07	50.97 00.19	9,261.35	10 49 50.45	37 41 36.77	89 30 00.16
64	Big Muddy.....	35 09 37.54	38.60	14,245.30	156 32 20.83
65	Fountain Bluff.....	65 21 15.42	16.20	8,343.58	271 08 43.28
66	Swallow Rock.....	79 29 03.67 56.63	05.47 00.27	13,168.78	11 43 05.99	37 41 31.23	89 24 19.67
67	Fountain Bluff.....	75 43 59.24	59.09	8,343.58	271 08 43.28
68	Swallow Rock.....	54 17 47.80	48.24	10,560.40	145 29 59.70
69	Worthen.....	49 58 11.70 58.74	12.85 00.18	8,848.50	15 25 42.99	37 46 13.45	89 28 24.07
70	Fountain Bluff.....	83 11 18.03	17.47	8,848.50	195 24 44.10
71	Worthen.....	65 49 39.68	40.26	17,066.99	81 15 23.25
72	Backbone.....	30 59 00.62 58.33	02.62 00.35	15,681.23	292 07 23.96	37 44 48.74	89 39 53.09
73	Worthen.....	29 46 57.20	57.79	17,066.99	81 15 23.25
74	Backbone.....	69 23 07.65	66.55	8,587.07	191 45 14.79
75	O'Harrish.....	80 49 57.19 02.04	58.01 00.35	16,180.86	290 56 02.60	37 49 21.42	89 38 41.57
76	Backbone.....	72 28 46.17	47.92	8,587.07	191 45 14.79
77	O'Harrish.....	68 39 58.40	60.42	13,053.34	80 25 59.04
78	Killion.....	88 51 11.69 50.26	11.92 00.26	12,750.30	299 11 48.38	37 48 10.73	89 47 27.73
79	O'Harrish.....	87 54 52.30	52.99	13,053.34	80 25 59.04
80	Killion.....	49 42 14.13	18.58	8,028.04	210 38 17.88
81	Manskear.....	92 22 45.92 52.35	48.63 00.20	9,902.43	298 17 11.91	37 51 54.74	89 44 40.35
82	Killion.....	36 32 10.16	14.62	8,028.04	210 38 17.88
83	Manskear.....	50 19 06.08	05.64	4,786.68	340 20 54.90
84	Lower Base.....	93 09 39.10 55.43	39.82 00.08	6,187.72	67 12 55.46	37 49 28.52	89 43 34.53

2448 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Tabulated results of secondary triangulation from Cairo to Kerkuk—Continued.

No.	Stations.	Observed angles.	Adjusted angles.	Distance.	Azimuth.	Latitude.	Length
		O' " "	" "	Meters.	O' " "	O' " "	O' "
40	Killion	31 37 43.61	30.41	6,187.73	347 10 32.49
41	Lower Base	85 43 35.84	30.38	3,253.07	133 55 31.89
41	Upper Base	83 49 37.43	00.05	5,684.44	25 44 11.45	27 53 40.41	89 45 1
		55.33					
40	Killion	40 08 30.89	23.22	3,034.04	210 33 17.88
41	Manabear	84 30 30.40	23.58	7,353.36	123 00 22.07
43	Chester	45 21 08.67	08.30	11,218.89	350 29 03.03	27 54 30.05	89 42 1
		04.16	08.15				
40	Killion	48 41 53.59	55.01	11,219.89	170 29 42.53
42	Chester	74 08 16.43	18.22	10,081.77	64 37 13.35
43	Rosier	57 09 47.76	48.94	12,943.01	301 43 30.00	27 51 50.03	89 54 1
		67.83	00.27				
43	Chester	23 49 27.47	23.75	10,081.77	64 37 13.35
43	Rosier	114 30 18.09	12.87	8,531.73	120 12 12.39
44	Vance	35 50 10.89	12.06	15,611.59	274 30 14.03	27 54 42.43	89 59 1
		55.96				
43	Rosier	53 15 22.23	22.14	8,531.73	120 13 12.39
44	Vance	73 08 51.03	51.00	8,092.32	232 08 37.09
45	Kaaskakia	43 30 37.11	47.05	11,101.40	3 28 51.37	27 57 40.43	89 54 1
		41.11	00.19				
44	Vance	50 42 30.88	31.92	9,092.32	232 08 37.09
45	Kaaskakia	43 30 37.11	47.05	8,092.32	125 58 13.35
46	Reagan	45 36 51.34	52.88	12,977.47	1 24 13.00	28 01 20.45	89 59 1
		55.31	00.11				
44	Vance	39 37 22.73	31.59	12,977.47	121 34 05.78
46	Reagan	73 38 02.39	01.78	8,757.99	75 02 15.38
47	Correll	96 54 33.04	36.90	12,223.07	321 53 13.07	33 00 26.00	90 04 5
		03.10	00.27				
46	Reagan	44 46 36.92	23.01	8,757.99	75 02 15.38
47	Correll	54 11 03.79	07.29	6,244.91	200 47 34.43
48	Brewerville	81 02 13.72	14.81	7,189.71	209 46 15.70	33 03 35.25	90 03 1
		57.43	00.11				
47	Correll	73 19 06.22	06.65	6,244.91	200 47 34.43
48	Brewerville	87 17 33.95	33.97	7,390.26	79 06 10.47
49	Magnolia	49 23 12.47	12.49	6,922.23	307 26 09.04	33 02 42.54	90 09 4
		57.64	00.11				
47	Correll	35 25 13.24	14.54	6,922.23	127 28 27.83
49	Magnolia	112 52 41.02	41.10	7,634.70	121 34 05.78
50	County Line	81 42 03.69	04.38	12,136.64	342 52 12.14	33 06 42.21	90 07 2
		58.65	00.12				
49	Magnolia	67 09 08.98	08.01	7,634.70	194 33 27.94
50	County Line	56 24 08.98	09.01	8,442.63	70 58 25.53
51	Brickey	56 28 42.82	41.73	7,630.95	307 21 45.18	33 05 12.52	90 12 4
		1.28	00.14				
50	County Line	58 41 02.09	08.79	8,442.63	70 58 25.53
51	Brickey	72 16 13.48	12.34	9,550.64	178 38 51.10
52	Kidd	49 02 38.89	29.06	10,648.12	309 35 06.32	33 10 23.49	90 12 56
		1.26	00.19				
51	Brickey	43 00 37.90	27.55	9,550.64	178 38 51.10
52	Kidd	81 49 55.06	56.27	7,937.86	80 28 41.65
53	Cesar's	55 09 25.97	28.37	11,512.81	315 34 49.31	33 09 39.79	90 18 19
		58.89	00.19				
52	Kidd	65 19 50.21	58.27	7,937.86	80 28 41.65
53	Cesar's	62 59 02.25	00.69	9,193.83	197 26 22.25
54	Welsenborn	51 41 02.18	01.20	9,013.07	325 46 31.12	33 14 24.24	90 16 26
		03.62	00.16				
53	Cesar's	46 32 53.42	54.70	9,193.83	197 26 22.25
54	Welsenborn	83 16 02.46	04.26	8,689.44	100 43 36.08
55	Herculanum	50 10 59.87	61.14	11,887.10	330 51 00.44	33 15 16.55	90 22 17
		55.75	00.20				
54	Welsenborn	61 59 42.94	43.04	8,689.44	100 43 36.08
55	Herculanum	55 48 00.56	00.03	8,069.98	274 53 59.27
56	Salt Bluff	62 14 17.00	17.09	8,118.54	342 42 13.24	33 18 35.55	90 18 05
		00.18				

Tabulated results of secondary triangulation from Cairo to Keokuk—Continued.

No.	Stations.	Observed angles.	Adjust'd angles.	Distance.	Azimuth.	Latitude.	Longitude.
		° ' "	"	Meters.	° ' "	° ' "	° ' "
25	Herrinsburg	47 20 16.73	10.48	8,660.98	224 53 50.27
26	Salt Bluff	62 21 32.64	33.50	6,773.94	107 21 05.83
27	Sulphur Springs	70 15 09.91	10.15	8,164.13	357 33 33.93	38 19 41.09	90 22 31.84
		58.78	00.13				
28	Salt Bluff	61 00 22.41	24.59	6,773.94	107 21 08.83
27	Sulphur Springs	81 19 49.20	51.50	9,697.15	205 52 32.28
28	Meramec	37 39 43.04	44.07	10,950.69	348 20 36.86	38 24 23.78	90 19 36.79
		55.55	00.16				
28	Salt Bluff	39 36 46.72	45.92	10,959.89	168 21 33.42
28	Meramec	43 37 15.74	14.73	7,037.96	304 47 22.13
29	Boon	96 49 60.52	59.49	7,605.82	27 59 50.50	38 22 13.48	90 15 38.69
		03.62	00.14				
28	Meramec	50 52 43.93	43.67	7,037.96	304 47 22.13
29	Boon	73 36 30.82	31.15	7,074.89	203 26 21.14
29	Gummershimer	50 30 45.56	45.30	8,933.68	73 58 18.51	38 25 43.98	90 13 42.67
		00.31	00.12				
29	Boon	41 07 51.06	51.46	7,074.89	203 26 21.14
29	Gummershimer	90 22 19.62	20.62	6,213.95	113 49 53.82
31	Twin Hollow	48 29 47.63	48.63	9,416.62	342 17 16.12	38 27 05.33	90 17 37.08
		58.31	00.11				
29	Gummershimer	83 55 59.02	60.73	6,213.95	113 49 53.82
31	Twin Hollow	57 48 55.88	50.39	9,080.80	235 58 31.70
32	Dryer	38 15 02.10	03.01	8,494.69	17 47 01.09	38 30 06.33	90 11 55.71
		58.00	00.13				
29	Gummershimer	49 12 45.46	45.76	8,494.69	197 45 54.55
32	Dryer	79 24 40.99	47.88	8,232.67	97 11 48.97
33	Ferder	51 22 26.24	20.52	10,668.27	328 30 45.61	38 30 39.64	90 17 32.83
		58.69	00.17				
32	Dryer	51 05 01.70	01.86	8,232.67	97 11 48.97
33	Ferder	90 46 60.43	50.90	10,373.58	186 21 10.09
34	Inane Asylum	38 07 58.81	58.37	13,331.28	328 13 50.30	38 36 13.99	90 16 43.37
		60.04	00.22				
32	Dryer	84 03 52.01	53.73	13,331.28	148 16 50.83
34	Inane Asylum	49 47 05.37	49.19	18,377.10	278 26 41.11
35	Clark's Mound	46 08 56.16	57.55	11,146.73	52 25 32.25	38 34 45.75	90 04 13.97
		57.94	00.47				
34	Inane Asylum	58 44 17.72	17.70	18,387.10	278 26 41.11
35	Clark's Mound	31 29 45.60	45.63	15,717.51	130 04 14.84
36	Stand Pipe	89 45 57.62	57.65	9,606.16	39 45 01.02	38 40 13.59	90 12 31.51
		00.34	00.38				
35	Clark's Mound	71 47 17.06	18.51	15,717.51	130 04 14.84
36	Stand Pipe	51 12 27.59	28.44	17,801.48	254 46 35.83
37	Sugar Loaf	57 00 12.78	14.60	14,666.56	21 53 53.89	38 42 05.33	90 00 28.91
		58.33	00.55				
36	Stand Pipe	68 30 09.14	68.15	17,801.48	258 46 35.83
37	Sugar Loaf	33 08 35.94	36.81	16,911.19	112 02 41.30
38	Robinson	78 21 16.07	15.46	9,947.31	10 17 13.50	38 45 30.68	90 11 18.10
		01.15	00.42				
38	Stand Pipe	35 09 57.67	57.38	9,937.31	190 16 27.68
38	Robinson	48 24 12.54	12.36	5,758.84	321 40 01.23
39	Soechtig	96 21 50.56	50.37	7,485.29	45 28 43.07	38 43 03.85	90 08 50.74
		00.77	00.11				
38	Robinson	73 34 35.54	36.97	5,758.84	321 40 01.23
39	Soechtig	38 11 55.30	55.63	5,948.35	180 02 30.08
70	Pettingill	68 13 24.08	26.45	3,834.90	68 15 56.64	38 46 10.76	90 08 50.56
		55.82	00.05				
38	Robinson	33 07 51.71	51.80	3,834.90	248 14 24.26
70	Pettingill	107 58 35.98	36.21	3,338.31	176 14 32.85
71	Terrapin	38 53 31.69	32.02	5,809.73	35 07 59.19	38 48 04.79	90 08 59.63
		59.38	00.03				
70	Pettingill	40 06 31.22	32.68	3,338.31	176 14 32.85
71	Terrapin	88 23 24.41	25.86	2,748.09	267 51 01.31
72	Moore	51 29 59.86	61.48	4,263.92	36 22 11.14	38 48 08.12	90 07 03.82
		55.39	00.02				

2450 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Tabulated results of secondary triangulation from Cairo to Keokuk—Continued

No.	Stations.	Observed angles.	Adjust'd angles.	Distance.	Azimuth.	Latitude.	L
		° ' "	"	Meters.	° ' "	° ' "	
71	Terrapin	30 24 58.64	58.44	2,748.09	267 51 01.81
72	Moore	45 18 14.17	14.11	1,435.66	133 10 26.73
73	Missouri River	104 16 47.54 00.35	47.46 00.01	2,015.76	57 26 46.99	38 48 39.97
72	Moore	63 29 37.60	36.82	1,435.66	183 10 26.73
73	Missouri River	86 14 42.46	41.73	2,549.36	226 55 17.81
74	Gillan	30 15 42.05 02.11	41.46 00.01	2,842.70	16 40 24.74	38 49 36.43
73	Missouri River	37 32 38.94	38.88	2,549.36	226 55 17.81
74	Gillan	104 29 09.23	09.27	2,525.02	151 25 15.47
75	Shirley	37 58 11.71 59.88	11.87 00.02	4,011.91	9 22 55.92	38 50 48.33
74	Gillan	82 00 57.88	58.43	2,525.02	151 25 15.47
75	Shirley	65 34 18.65	19.34	1,850.49	265 50 24.72
76	Gesler	82 24 41.55 58.08	42.24 00.01	2,819.29	3 26 17.52	38 50 51.51
75	Shirley	111 01 06.72	07.26	1,850.49	265 50 24.72
76	Gesler	36 48 03.92	04.61	2,367.02	122 39 04.36
77	Ringering	82 10 47.67 58.31	48.14 00.01	1,519.01	834 49 00.65	38 51 32.91
75	Shirley	37 04 16.14	16.83	1,519.01	154 49 17.46
77	Ringering	111 41 31.95	32.49	1,765.77	86 30 33.14
78	Freeman	31 14 09.32 57.41	10.69 00.01	2,721.80	297 43 57.97	38 51 29.42
77	Ringering	58 13 15.31	14.81	1,765.77	86 30 33.14
78	Freeman	72 01 60.25	59.82	1,966.83	194 27 47.46
79	Russell	49 44 45.76 01.32	45.38 00.01	2,200.86	324 43 14.86	38 52 31.18	90
78	Freeman	48 05 30.53	29.11	1,966.83	194 27 47.46
79	Russell	97 14 58.68	57.34	2,573.85	111 42 57.58
80	Glass Works	34 39 34.78 03.99	33.56 00.01	3,430.84	326 21 28.88	38 53 02.06	90
79	Russell	37 16 43.81	43.39	2,573.85	111 42 57.58
80	Glass Works	82 10 49.50	49.18	1,790.45	13 52 44.50
81	Watkins	60 32 27.70 01.01	27.44 00.01	2,928.55	254 25 00.76	38 52 05.69	90
80	Glass Works	72 15 44.93	45.25	1,790.45	13 52 44.50
81	Watkins	61 22 25.59	25.85	2,356.31	132 30 07.46
82	Strong	46 21 48.51 59.03	48.91 00.01	2,171.51	266 07 33.32	38 52 57.31	90
80	Glass Works	30 10 34.97	35.94	2,171.51	86 08 29.75
82	Strong	66 47 50.15	51.25	1,099.69	199 19 42.07
83	Alton	83 01 31.69 56.81	32.82 00.01	2,010.75	206 18 18.73	38 53 30.96	90
82	Strong	34 06 46.40	44.83	1,099.69	199 19 42.07
83	Alton	112 32 09.62	09.18	1,121.77	131 52 00.73
84	Saw Mill	33 21 04.85 00.87	05.99 00.00	1,847.50	345 12 44.95	38 53 55.24	90
82	Strong	29 31 16.35	15.08	1,847.50	165 12 57.24
84	Saw Mill	111 25 50.62	52.13	1,445.05	96 38 37.08
85	Nicholson	39 02 52.32 59.29	52.80 00.01	2,729.91	315 40 52.48	38 54 00.65	90
84	Saw Mill	36 39 16.09	15.86	1,445.05	96 38 37.08
85	Nicholson	100 17 57.97	57.84	1,263.83	176 20 01.84
86	Hop Hollow	43 02 46.33 00.39	46.30 00.00	2,082.90	313 17 13.43	38 54 41.55	90
85	Nicholson	63 11 33.17	33.85	1,263.83	176 20 01.84
86	Hop Hollow	80 17 47.36	47.02	1,895.88	76 37 46.75
87	Weper	36 30 38.33 58.86	39.14 00.01	2,093.78	293 07 37.81	38 54 27.33	90
86	Hop Hollow	47 36 04.34	01.50	1,895.88	76 37 46.75
87	Weper	56 43 03.61	03.06	1,444.92	199 53 55.61
88	Hull	75 40 58.03 05.98	55.44 00.00	1,635.72	304 13 12.99	38 55 11.39	90

Tabulated results of secondary triangulation from Cairo to Keokuk—Continued.

No.	Stations.	Observed angles.	Adjust'd angles.	Distance.	Azimuth.	Latitude.	Longitude.
		° ' "	' "	Meters.	° ' "	° ' "	° ' "
87	Weper	86 46 56.95	57.84	1,444.92	199 53 55.61
88	Hull	62 29 11.24	12.13	2,823.16	82 23 20.56
89	Barwise	30 43 49.01	50.04	2,507.82	293 05 57.63	38 54 59.25	90 16 05.50
		57.20	00.01				
88	Hull	35 00 16.85	14.33	2,823.16	82 23 20.56
89	Barwise	102 36 47.39	45.00	2,402.44	159 45 22.59
90	Reibl	42 23 03.00	00.00	4,087.04	297 22 00.21	38 56 12.34	90 16 40.01
		07.24	00.02				
89	Barwise	41 11 36.23	35.61	2,402.44	159 45 22.59
90	Reibl	105 46 02.28	01.76	2,902.04	85 31 02.66
91	Eagle's Nest	33 02 23.04	22.65	4,240.58	298 32 09.82	38 56 04.97	90 18 40.13
		01.55	00.02				
90	Reibl	37 59 22.39	22.85	2,902.04	85 31 02.66
91	Eagle's Nest	103 11 27.69	28.26	2,849.52	8 41 15.43
92	Echele	38 49 08.25	08.91	4,507.30	227 30 13.12	38 54 33.62	90 18 58.00
		58.33	00.02				
91	Eagle's Nest	50 51 30.83	29.13	2,849.52	8 41 15.43
92	Echele	73 11 21.10	19.46	2,667.27	115 29 44.75
93	Portage	55 57 13.01	11.43	3,292.06	239 31 30.55	38 55 10.84	90 20 37.93
		04.94	00.02				
92	Echele	39 45 07.65	07.09	2,667.27	115 29 44.75
93	Portage	97 54 14.82	14.35	2,532.17	197 34 27.63
94	Starr	42 20 38.94	38.58	3,922.21	335 14 08.99	38 56 29.12	90 20 06.18
		01.41	00.02				
93	Portage	85 44 45.08	45.82	2,532.17	197 34 27.63
94	Starr	52 21 28.20	27.97	3,781.47	69 56 15.54
95	Pourie	41 53 44.83	46.23	3,002.59	201 48 29.10	38 55 47.03	90 22 33.65
		58.11	00.02				
94	Starr	48 06 02.76	02.90	3,781.47	69 56 15.54
95	Pourie	58 48 22.80	22.53	2,941.78	191 06 20.33
96	Elash	73 05 35.04	34.59	3,380.88	298 01 00.53	38 57 20.64	90 22 10.12
		00.60	00.02				
95	Pourie	80 14 53.69	54.81	2,941.78	191 06 20.33
96	Elash	66 17 00.09	01.21	5,257.37	77 23 36.33
97	East Base	33 28 02.76	04.02	4,883.94	290 49 26.42	38 56 43.38	90 25 43.16
		56.54	00.04				
96	Elash	27 29 05.73	06.27	5,257.37	77 23 36.33
97	East Base	111 21 34.13	34.83	3,686.92	145 59 47.57
98	Grafton	41 09 18.15	18.95	7,439.97	284 49 34.76	38 58 22.48	90 27 08.82
		58.01	00.05				
97	East Base	82 11 48.38	48.09	3,686.92	145 59 47.57
98	Grafton	30 32 38.93	37.61	3,960.66	356 31 31.32
99	West Base	67 15 33.10	34.32	2,031.61	243 47 11.91	38 56 14.28	90 26 58.85
		59.81	00.02				
98	Grafton	93 13 05.97	06.27	3,960.66	356 31 31.32
99	West Base	41 18 38.26	39.24	5,547.00	135 12 58.34
100	Rivermouth	45 28 14.35	14.53	3,667.61	269 43 01.77	38 58 21.92	90 29 41.17
		58.58	00.04				
99	West Base	67 19 11.20	11.22	5,547.00	135 12 58.34
100	Rivermouth	68 37 51.04	49.77	7,361.12	23 49 06.07
101	Point Landing	44 02 58.92	59.11	7,429.57	247 50 47.62	38 54 43.53	90 31 44.55
		01.16	00.10				
100	Rivermouth	75 30 15.96	15.48	7,361.12	23 49 06.07
101	Point Landing	31 55 21.75	22.22	7,469.66	171 52 26.29
102	Thompson	72 34 22.54	22.37	4,079.65	279 17 36.35	38 58 43.32	90 32 28.42
		00.25	00.07				
101	Point Landing	63 56 41.36	41.85	7,469.66	171 52 26.29
102	Thompson	34 59 37.55	37.49	6,793.04	26 51 36.21
103	Calhoun	81 03 39.90	40.73	4,336.42	287 53 56.85	38 55 26.78	90 34 35.83
		58.81	00.07				
102	Thompson	63 31 32.71	31.48	6,793.04	26 51 36.21
103	Calhoun	60 15 45.06	45.77	7,316.41	146 34 30.35
104	Droege	56 12 43.34	42.86	7,007.16	270 20 02.23	38 58 44.77	90 37 23.26
		01.11	00.11				

2452 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Tabulated results of secondary triangulation from Cairo to Keokuk—Continued.

No.	Stations.	Observed angles.	Adjust'd angles.	Distance.	Azimuth.	Latitude.	Longt
		° ' "	"	Meters.	° ' "	° ' "	° ' "
103	Calhoun.....	32 57 50.07	50.23	7,316.41	146 34 30.35
104	Droege	70 02 56.18	55.10	4,085.86	36 35 40.19
105	Keel	76 59 14.53	14.74	7,058.55	293 33 51.32	38 56 58.38	90 39
		00.78	00.07				
104	Droege	69 22 37.25	37.08	4,085.86	36 35 40.19
105	Keel	58 46 31.04	31.87	4,862.89	157 48 04.71
106	Cahill.....	51 50 50.64	51.09	4,443.20	285 56 25.61	38 59 24.38	90 40
		58.93	00.04				
105	Keel	38 06 12.65	11.93	4,862.89	157 48 04.71
106	Cahill.....	110 23 29.33	28.49	5,742.28	88 10 45.19
107	Winfield	31 30 18.81	19.65	8,722.42	299 38 34.80	38 59 18.39	90 44
		00.79	00.07				
106	Cahill	88 53 44.86	44.82	5,742.28	88 10 45.19
107	Winfield	44 26 45.67	45.41	7,898.57	223 41 29.74
108	Wilson.....	46 37 29.57	30.35	5,531.83	357 06 22.20	39 02 23.54	90 40
		00.10	00.08				
106	Cahill.....	55 10 00.17	00.16	5,531.83	177 06 29.51
108	Wilson.....	80 44 14.40	13.96	6,525.16	77 50 36.16
109	Kilham	44 05 45.05	45.97	7,845.93	301 53 35.12	39 01 38.90	90 44
		59.62	00.09				
108	Wilson.....	109 36 25.36	23.72	6,525.16	77 50 36.16
109	Kilham	37 30 52.59	52.37	11,322.93	220 16 56.78
110	Peets	32 52 44.64	44.02	7,319.65	7 27 24.78	39 06 18.90	90 39
		02.59	00.11				
109	Kilham	47 50 26.15	34.93	11,322.93	220 16 56.78
110	Peets	42 29 26.50	26.63	8,393.93	82 49 35.43
111	Knox.....	89 39 58.85	58.61	7,648.44	352 25 55.46	39 05 44.76	90 45
		01.50	00.17				
110	Peets	79 33 48.23	48.07	8,393.93	82 49 35.43
111	Knox.....	69 20 02.13	01.86	15,980.34	193 25 54.99
112	Hamburg	31 06 10.62	10.39	15,203.58	342 21 22.36	39 14 08.76	90 43
		00.98	00.32				
111	Knox.....	31 25 42.49	40.65	15,980.34	193 25 54.99
112	Hamburg	88 55 29.94	30.19	9,656.13	102 23 02.94
113	Saltpeter.....	59 38 48.15	49.55	18,515.46	341 57 43.64	39 15 15.73	90 49
		00.58	00.39				
112	Hamburg	53 01 33.22	32.50	9,656.13	102 23 02.94
113	Saltpeter.....	89 21 55.07	56.55	12,640.96	192 56 57.54
114	Bellevue	37 36 30.56	31.26	15,821.88	335 21 41.24	39 21 55.20	90 47
		58.85	00.31				
113	Saltpeter.....	41 23 36.16	37.72	12,640.96	192 56 57.54
114	Bellevue	82 13 05.78	4.66	10,036.63	95 11 17.16
115	Clarksville	56 23 17.90	17.94	15,038.92	331 30 10.22	39 22 24.42	90 54
		59.84	00.32				
114	Bellevue	43 38 49.53	47.84	10,036.63	95 11 17.16
115	Clarksville	100 53 45.52	45.19	11,941.68	174 13 07.09
116	Long	35 27 27.66	27.27	16,989.65	318 45 07.86	39 28 49.67	90 55
		02.71	00.30				
115	Clarksville	46 44 26.79	25.51	11,941.68	174 13 07.09
116	Long	89 57 35.99	39.56	12,680.93	84 10 14.69
117	Salt River.....	43 17 55.19	55.31	17,412.73	307 22 34.49	39 28 07.58	91 04
		57.97	00.38				
116	Long	46 03 22.94	25.58	12,680.93	84 10 14.69
117	Salt River.....	44 24 05.39	05.28	9,130.96	308 28 44.46
118	McLean	89 32 28.79	29.35	8,872.89	218 04 23.65	39 25 03.24	90 59
		57.12	00.21				
117	Salt River.....	61 16 28.52	28.32	9,130.96	308 28 44.46
118	McLean	30 00 55.61	56.03	8,009.27	158 32 50.33
119	Inner Base	88 42 35.69	35.74	4,568.79	67 14 08.18	39 29 04.94	91 01
		59.82	00.00				
117	Salt River.....	34 55 30.33	29.02	4,568.79	247 12 16.14
119	Inner Base	40 17 52.28	52.54	2,705.10	26 56 15.64
120	Outer Base	104 46 39.16	38.46	3,056.00	102 09 04.63	39 27 46.74	91 02
		01.77	00.02				

Tabulated results of secondary triangulation from Cairo to Keokuk—Continued.

No.	Stations.	Observed angles.	Adjust'd angles.	Distance.	Azimuth.	Latitude.	Longitude.
		° ' "	' "	Meters	° ' "	° ' "	° ' "
118	McLean	30 49 13.08	13.98	8,009.27	158 32 50.33
119	Inner Base	62 14 05.84	06.74	4,109.40	40 45 39.18
121	Louisiana	86 56 38.44	39.35	7,097.23	307 41 07.19	39 27 23.99	91 03 11.31
		57.36	00.07				
117	Salt River	100 00 02.93	61.90	9,130.96	308 28 44.46
118	McLean	41 50 56.36	55.41	14,556.82	170 22 49.71
122	Rockport	38 09 05.13	02.92	9,861.65	28 30 47.88	39 32 48.61	91 00 58.40
		04.42	00.23				
117	Salt River	67 05 14.06	13.73	9,861.65	208 28 42.59
122	Rockport	83 16 03.87	04.61	18,364.53	111 46 52.49
122	Red House	29 38 42.67	42.08	19,800.18	321 17 59.16	39 36 28.96	91 12 53.24
		00.54	00.42				
122	Rockport	32 05 49.55	50.16	18,364.53	111 46 52.49
123	Red House	50 46 43.33	42.63	9,834.05	240 52 34.45
124	Gard	97 07 27.35	27.60	14,337.82	323 48 56.68	39 39 03.99	91 06 52.91
		00.23	00.39				
123	Red House	75 11 46.20	45.78	9,834.05	240 52 34.45
124	Gard	72 25 22.71	22.62	17,753.07	133 21 46.90
125	See Horn	32 22 52.17	52.02	17,505.28	345 38 52.52	39 45 38.88	91 15 55.13
		01.08	00.42				
124	Gard	30 07 33.44	32.32	17,753.07	133 21 46.90
125	See Horn	78 34 44.38	43.79	9,407.05	31 50 44.29
126	Hannibal	71 17 45.14	44.31	18,371.82	283 06 15.48	39 41 19.73	91 19 23.43
		02.96	00.42				
125	See Horn	70 10 38.64	38.88	9,407.05	31 50 44.29
126	Hannibal	73 12 38.24	38.24	14,838.64	138 35 52.93
127	Heather	36 36 42.73	43.22	15,100.88	281 54 46.04	39 47 20.42	91 26 15.86
		59.61	00.34				
126	Hannibal	27 35 52.47	51.68	14,838.64	138 35 52.93
127	Heather	96 43 16.73	15.92	8,323.07	221 48 13.34
128	Marble Head	55 40 53.14	52.71	17,842.85	346 09 50.06	39 50 41.52	91 22 22.50
		02.34	00.31				
127	Heather	72 25 15.78	16.36	8,323.07	221 48 13.34
128	Marble Head	63 42 10.74	11.48	11,447.78	105 32 54.25
129	Nelson	43 52 31.48	32.44	10,765.80	320 20 29.26	39 52 20.76	91 30 06.58
		58.00	00.22				
127	Heather	37 22 08.22	08.67	10,765.80	140 22 57.04
129	Nelson	105 13 17.54	17.89	10,755.90	224 07 11.37
130	Quincy	37 24 32.91	33.72	17,099.61	6 45 59.99	39 56 31.00	91 24 51.18
		58.67	00.28				
129	Nelson	43 32 53.63	53.35	10,755.90	224 07 11.37
130	Quincy	103 41 27.95	28.11	13,694.27	147 52 01.82
131	Lagrange	32 45 38.81	38.90	19,311.85	00 34 23.24	40 02 46.88	91 29 58.45
		00.39	00.36				
130	Quincy	32 14 29.35	28.06	13,694.27	147 52 01.82
131	Lagrange	119 49 05.49	03.96	15,591.80	207 59 40.38
132	Lima Lake	27 56 26.82	27.55	25,357.01	00 06 32.09	40 10 13.14	91 24 49.15
		01.66	00.47				
131	Lagrange	43 41 43.43	43.89	15,591.80	207 59 40.38
132	Lima Lake	38 09 05.75	07.69	10,881.18	66 12 07.33
133	Canton University ..	98 09 07.43	08.69	9,730.18	344 16 44.87	40 07 50.57	91 31 49.67
		56.61	00.27				
132	Lima Lake	37 48 27.02	26.92	10,881.18	66 12 07.33
133	Canton University ..	60 11 28.45	28.76	9,735.80	185 56 07.42
134	Congill	82 00 03.52	04.48	9,534.25	283 56 21.93	40 11 27.78	91 31 20.22
		58.99	00.16				
132	Lima Lake	69 34 55.57	54.98	9,534.25	104 00 34.25
134	Congill	74 44 01.99	02.27	15,317.97	209 12 19.66
135	Gillham	35 41 02.13	03.11	15,768.14	353 34 41.08	40 18 41.16	91 26 03.69
		59.69	00.36				
134	Congill	22 27 56.66	56.80	15,317.97	209 12 19.66
135	Gillham	127 07 31.52	32.30	11,564.38	156 23 16.49
136	Yellow Banks	30 24 30.52	31.26	24,129.02	6 45 40.54	40 24 24.65	91 29 20.13
		58.70	00.36				

2454 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Tabulated results of secondary triangulation from Cairo to Keokuk—Continued.

No.	Stations.	Observed angles.	Adjusted angles.	Distance.	Azimuth.	Latitude.	Length.
		O I "	"	Meters.	O I "	O I "	O I "
135	Gillham	44 10 41.79	42.73	11,561.38	156 23 10.48
136	Yellow Banks	82 03 42.00	44.26	0,002.28	58 24 53.54
137	Fox River	53 45 32.14	33.31	14,200.89	292 08 33.13	40 21 34.82	91 25
		50.83	00.29				
136	Yellow Banks	107 55 13.27	14.17	9,992.28	58 24 53.74
137	Fox River	24 09 47.27	48.19	13,787.39	206 30 48.01
138	Warsaw	43 54 50.47	57.80	0,709.60	130 32 01.37	40 22 01.44	91 25
		57.01	00.16				
138	Yellow Banks	40 52 40.38	40.65	0,799.60	310 29 30.37
139	Warsaw	27 41 11.48	12.87	4,985.03	108 16 13.74
139	Boardman	95 23 06.24	06.83	4,120.04	83 38 52.72	40 24 39.68	91 25
		58.10	00.05				
139	Warsaw	35 52 18.26	16.77	4,985.03	168 16 13.74
139	Boardman	77 22 15.74	15.86	3,179.06	170 53 34.04
140	Hughes	60 45 27.24	27.47	5,204.06	24 09 29.93	40 24 33.06	91 24
		59.24	00.04				
138	Warsaw	50 12 55.20	56.15	5,204.08	204 06 30.45
140	Hughes	67 46 52.56	51.80	4,607.46	316 22 38.16
141	Worster	02 00 11.21	12.11	5,550.52	74 23 53.38	40 22 49.90	91 21
		58.97	00.06				
139	Warsaw	33 03 35.00	35.60	5,550.52	254 21 20.00
141	Worster	85 24 20.38	21.09	3,444.29	159 48 15.07
142	Keokuk	61 32 02.31	03.27	6,201.56	41 19 45.06	40 24 34.70	91 23
		57.09	00.05				
141	Worster	32 37 09.55	09.58	3,444.29	159 48 15.07
142	Keokuk	48 13 31.78	31.73	1,886.02	201 34 10.66
143	Hamilton	99 09 18.51	18.72	2,601.80	12 25 40.01	40 24 12.28	91 21
		59.54	00.01				
142	Keokuk	68 28 23.54	24.25	1,886.02	201 34 10.66
143	Hamilton	55 39 35.20	36.28	2,036.22	167 14 35.01
144	Rapids	57 51 58.61	50.48	1,833.75	45 06 22.13	40 25 10.68	91 21
		57.35	00.01				
143	Hamilton	38 21 52.60	53.10	2,070.22	167 14 35.01
144	Rapids	89 15 08.22	08.10	1,595.48	70 20 30.75
145	Lower Base	52 22 40.12	50.81	2,570.40	308 11 47.89	40 25 04.56	91 22
		61.03	00.01				
144	Rapids	35 35 17.50	18.95	1,595.48	70 20 30.75
145	Lower Base	98 43 43.06	44.56	1,297.38	177 46 04.79
146	Upper Base	45 41 54.98	50.04	2,263.60	202 03 53.52	40 25 43.51	91 23
		55.60	00.00				

APPENDIX C.

REPORTS OF ASSISTANT ENGINEERS J. A. PAIGE, J. B. JOHNSON, AND L. L. WHEE
UPON THE FIELD-WORK AND REDUCTION OF PRECISE LEVELS BETWEEN CARROT-
TON, LA., AND BILOXI, MISS., AND BETWEEN CAIRO, ILL., AND FULTON, ILL., E-
CUTED UNDER THE ORDERS OF THE MISSISSIPPI RIVER COMMISSION, 1880-'81—

1. Report of Assistant Engineer J. A. Paige upon the field-work of 1880-'81, Grafton to Ca

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., September 21, 188

SIR: I have the honor to make the following report of field operations on pre-
levels on the Mississippi River, between the mouth of the Illinois River and Ca-
from August 10, 1880, to March 15, 1881.

The organization of the party was as follows: James A. Paige, assistant engin-
in charge; O. W. Ferguson, assistant engineer; E. H. Sankee, recorder; H. P. Bou-
recorder; four rodmen, one cook, and eight axmen.

On October 23, Mr. Sankee, by your orders, was transferred to another party,
Mr. P. P. Sanborne reported for duty on the same day.

Your verbal instructions previous to my taking the field, were: To quarter
party on the quarter-boat Louisiana, obtain the necessary instruments from

office, purchase subsistence stores, and have the outfit towed to Grafton; establish a bench-mark on the right bank of the Illinois River near its mouth, which should be the beginning of the line; transfer the levels across the Illinois River; carry the work (which would consist of two independent lines of levels) down the left bank of the Mississippi River to the mouth of the Missouri; cross here to the right bank of the Mississippi River, in order that permanent bench-marks might be well established in the edge of the bluffs, which form the right bank mainly from Saint Louis to Commerce; and ultimately connect with the bench-marks in Cairo established by General Comstock's parties in 1876.

On August 10, the quarter-boat was furnished and, by the steamer Little Eagle No. 3, was towed to Grafton. The first field-work consisted of determining the constants of Kern levels Nos. 1 and 2, and the level vials belonging to them. Kern level No. 1 was used by O. W. Ferguson with level vial No. 7 till October 7, when it was broken; after that date level vial No. 3 was used. Kern level No. 2 was used by James A. Paige with level vial No. 2 throughout the season. Redeterminations of the value of the constants were made as follows:

Wire intervals of both levels at Neeley's Landing and at Cairo.

Relative size of rings of level No. 2 at Neeley's Landing and at White Sand Depot Landing.

Value of one division of level vial No. 2 at Neeley's Landing and Cairo.

Value of one division of level vial No. 3 was determined at Illinois station, where it was first used, and again at Neeley's Landing and at Cairo.

In reduction of the field-notes the value of these constants found at any time was used until a new determination was made; after that time the last value found was used.

The weather for the first three months of the field season was very favorable to the work. On the 15th of November cold weather set in, and from that date till February 22 there were only 25½ days for both parties of field-work done. While at Neeley's Landing December 18, the ice began running so badly that the quarter-boat could be moved no farther. This hindered the work very much. Finally the river was entirely frozen over, and remained so till February 3, when a cake of ice extending entirely across the river struck the quarter-boat and sunk her. With the aid of a derrick and some other appliances obtained at Grand Tower the boat was raised and repaired, and on February 22 moved to Commerce, Mo., to which point Assistant Ferguson had carried the levels.

The work was completed to Cairo on March 14, the quarter-boat towed to Mound City and turned over to watchman Schoenfeld, and with Mr. Ferguson I reported to you for further duty at Saint Louis.

The general conditions regarding the work during the latter part of the season were unfavorable. Low water prevailed nearly the entire season. To move the quarter-boat by drifting with the current very often resulted in being hung up on a rock or blown on a sand bar. The boat lay at Neeley's Landing nine weeks. Part of the force remained to look after the boat, while Assistant Ferguson continued the work below whenever the weather would permit, subsisting at farm houses.

During this time and for some time previous the ground was frozen, and, as has been found previously, when running over such a surface, it is impossible to keep the level stationary. Also, part of the line was through wheat fields and swampy woods. About 22 per cent. of the whole distance was leveled more than twice, and one per cent. was leveled more than three times.

The whole number of days and parts of days spent in field-work equals 220 days for one party. The whole number of kilometers leveled equals 797.5. Average rate per working day equals 3.6 kilometers.

There were 66 permanent bench-marks established. Eleven of these were of the usual pattern—stone posts in ground with copper bolt in top. The remainder, with one exception, were copper bolts one centimeter in diameter and 7 centimeters long, leaded in brick or stone foundations, or in the natural rock wall. Those of the latter locality, if not interfered with, are as permanent as anything of this nature can be established. Where the copper bolts were set horizontally a small hole in the end of the bolt marks the point of reference. Temporary bench-marks were set about once in every kilometer.

While in the field, a descriptive list of bench-marks was received, established in 1879, by surveys made under direction of Colonel Simpson, Corps of Engineers, between Carondelet and Kaskaskia, with directions that they be connected with. Thirty-three of these sixty-four bench-marks were found and connected with. They are designated in the field-notes and office computations as "B. M.—Holman."

There were six water-gauges connected with the levels, viz: at Grafton, Saint Louis, Rush Tower, Grand Eddy, Gray's Point, and Cairo. At all of these gauges except the Gray's Point gauge, there was a permanent bench-mark left in the immediate vicinity.

The methods used in field-work were, with a few exceptions, the same as have been

used heretofore, and need not be further described, any changes made being incident to the locality, state of the weather, &c.

There were 4 river crossings made by reciprocal leveling—one at the beginning the work across the Illinois River, one at the mouth of the Missouri, one at Chert and one at Commerce. When these crossings were made, a copy of the field-note and computations was forwarded to you.

Very respectfully, your obedient servant,

JAMES A. PAIGR,
Assistant Engineer

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

2. Reports of J. B. Johnson upon the field-work of 1882-'83, Carrollton to Biloxi, and Grapion to Chicago.

a.—CARROLLTON TO BILOXI.

NEW ORLEANS, LA., June 26, 1882

SIR: I have the honor to report upon the field work of the precise level party under my charge, in connecting the United States bench-marks at Carrollton, La., with the tide-gauge at Biloxi, Miss.

The party consisted of J. B. Johnson, assistant engineer in charge; O. W. Ferguson, assistant engineer; A. Rameau, recorder; A. E. Kastl, recorder, together with 14 rodmen and five laborers.

I left Saint Louis May 3, reaching New Orleans on the 5th. A reconnaissance was made on that day, and a line agreed upon for tracking the Mobile and New Orleans railroad by running back of the city. On the 6th instrumental constants were observed, and on Monday, May 8, the regular work commenced.

On the 9th I left the party for five days, under orders to visit the observation point at Red River Landing. Recorder Rameau observed with my instrument while I was on this trip, as well as on all other occasions when it was necessary for me to be absent from the work. The work was completed at Biloxi tide-gauge June 23. Instrumental constants were observed on the 24th, and the party returned to New Orleans on the 26th. A connection was then made with the New Orleans City datum, which could not be found when the work was in that vicinity.

The party was disbanded June 27. Mr. Ferguson taking part of the outfit to Columbus, Ky., and the remainder shipped to Saint Louis by Anchor Line steamers.

DESCRIPTION OF THE LINE.

The total length of the line from Carrollton to the Biloxi gauge is 139 kilometers 87 miles. Of this, 18 kilometers was on wagon roads, 50 kilometers on railroad through swamp, 7 kilometers on railroad bridges and trestles, 64 kilometers on railroad over dry sandy land.

The characteristics of the swamp region were learned from the road master. He says there is a solid sand bottom from 2 to 15 feet below the surface throughout the whole distance. A vegetable growth and mold has formed on the surface, which extends some 2 or 3 feet down. If the sand substratum is deeper than this, the intermediate region is filled with a soft liquid mass which offers no resistance whatever. The road-bed was first made by dredging a canal alongside the line, and depositing the mud on the line. Sand was then brought in scows, on this side canal and put on top of the mud road-bed, until it was stable enough to lay a track.

For several years after the track was laid the road-bed rapidly settled away in places and more sand was constantly hauled to raise it again. Lines of piles were driven in many places between the track and the side canal, to prevent the road-bed from flowing back into the canal. These piles are all driven into the solid sand bottom, however, and are very firm. The road bed now seems to be quite stable, and I think the hill has sunk down to the solid substratum and there will be little more settling away. All the piling under the bridges and trestles are driven in sand. Our lines checked quite as well through the swamp region as on the solid ground. The road-bed for the entire distance, is composed of sand, which makes an excellent base

the foot plates and instruments as it is non-elastic. The 7 kilometers on bridges and trestles were distributed as follows:

	Meters.
Chef Menteur-Bridge.....	560
Rigolets Bridge.....	1,100
Pearl River Bridge.....	520
Bay Saint Louis trestle.....	3,700
Biloxi Bay to gauge trestle.....	1,120
Total kilometers.....	7.000

The bridges were double quadrangular iron truss bridges of 100 feet span, resting on piers made up of sixteen piles each. These piles were well capped and held at top, and also by diagonal tie-iron rods, reaching from top to bottom of piers. The trestle-work rested on piers every fifteen feet, of six piles each. The water was not over 20 feet deep on any of these crossings, except that of the Rigolets, which was as much as 48.

The Chef Menteur, Rigolets, and Pearl River are outlets from Lake Pontchartrain into Lake Borgne, and are subject to strong currents as the tide ebbs and flows, or the wind drives the water in or out. All these bridges and trestles were found very solid, and furnished a good basis for the instruments when there was little wind and current, otherwise work could not be done on them. These were all crossed four times under favorable circumstances, except Pearl River bridge, which was crossed but three times. All these lines agreed as closely as on any other part of the work.

METHODS OF WORK.

The methods employed were, in the main, the same as those heretofore used with the Kern instruments and rods. The two lines were always run in opposite directions, Mr. Ferguson always running west, and I always running east.

In one particular the methods of making the observations have differed from those previously used, and that is *the bubble was always kept in the middle of the tube when taking a reading*.

This method was not adopted arbitrarily or rashly. In my first season's work I found that my bubble changed its value from 2.6 to 3.5 seconds, according to temperature. I therefore kept my bubble corrections *very small* so as not to introduce any large uncertainty from that source. In the first half of last season I followed the same plan, and with many readings would have no bubble correction at all. In the latter half of that season's work I kept the bubble exactly in the middle for almost all readings, and found it could be done as well as not. This, of course, presumes that the observer reads his own bubble, a thing which I have always done. Last season Mr. Ferguson had his recorder read his bubble and so could not pursue this method.

A discussion of these two systems is important.

(I.) Having the recorder read the bubble has some advantages, *provided the bubble will stand*. He then can wait till it settles, inform the observer of the fact, and he can read the bubble *in its true position while* the observer reads the rod.

The objections to this are:

(a.) It is desirable to have as few men about the instrument as possible. If the recorder reads the bubble there are three men, observer, recorder, and umbrella man, standing directly beside the instrument.

(b.) I find that my bubble will seldom stand long enough for me to read the three wires; a single bubble reading is, in this case, certainly erroneous.

(II.) The advantages of the other system are, that it enables the observer to make the complete observation, and also to get all three wire readings with the bubble in one position.

To have one man read the bubble and another to take the shot is like having one to sight a gun and another to pull the trigger, a very good plan with a *fixed gun*, but a very poor plan when the gun is somewhat unsteady and controlled by the man who pulls the trigger. When the bubble is almost constantly in motion, the same man must see both bubble and wires, and at the same time, and keep them both in view, in order that he may know when the bubble is registering correctly. By holding the head to one side the observer can keep his left eye on the bubble and his right eye on the rod, and see the bubble super-imposed on the rod; or, if he finds it difficult to read with both eyes at once, he can see bubble and rod alternately without moving his head and only by opening and closing his left eye. Now with his hand at the elevating screw, under the eye end wye, he brings the bubble to the center and keeps it there, stopping to look at the bubble for each wire reading.

After having read one wire, if the bubble has run, bring it back, read the next wire, again examine the bubble, bring it to the center again, and read the third wire.

Let him do the same also for the second set of readings (for the wire should all read twice), and then, having kept the bubble in the same place, he can confidently assert the reliability of his work. With 100-meter shots, if the bubble is read half division wrong, an error of 0.0007 has been made.

The bubble often seems to have stopped moving when one-half to three-quarters division from its true point of equilibrium, and therefore the second set of wire readings will often differ from the first.

It may be said it requires too much time to bring the bubble exactly in the middle, but I think it requires no more time than to bring it to any other point, for it must be watched and kept to one reading anyway, if good work is to be done, and it may as well be kept in the middle as anywhere else.

I have run $1\frac{1}{2}$ miles per hour by this method of work, on 100-meter shots, and I do not find it at all difficult to make ten settings an hour of 20-meter shots, making one mile an hour on 20-meter shots. This got to be about our normal gait.

Another objection that is made to the observer's reading his own bubble, is that he cannot read it correctly, there being a parallax of about one-half division at the end, caused by the light passing obliquely from the bubble to the mirror, in order to reach the eye.

The instructions say that the eye must be held in such a position that there will be no parallax. This cannot be done. The objection, however, has little force, proving the back and fore sights are kept equal. The error being always constant and affecting back and fore sights alike, their difference is not changed, and if the back and fore sights are very unequal, this one-half division error in bubble reading can be applied, together with the corrections for collimation, inclination, and pivots. In fact, it and the pivot error being sensibly constant, may be combined, and their result used in connection with collimation and inclination errors. For these reasons I terminated on having no bubble corrections in my work for this season, and Mr. Folsom, with some reluctance, adopted the same method. I think our extraordinary agreements amply justify the scheme.

I believe that, when the conditions are favorable, this matter of the bubble readings is the chief source of error. If the saving of time in the computations may be allowed as an argument, this method has a great advantage over the old one.

Our field work has all been reduced in two note-books, instead of on the computation sheets, with a saving of three-quarters of the time it formerly required for the work. This certainly reduces the cost of the field work, for that now never has to be stopped to work up notes. I therefore conclude that the method is more accurate, less laborious, and cheaper than that formerly used. The value of the bubble and the changes in the same, become of no consequence, neither is an accurate value of the wire interval of much account, except as getting the distance run.

In all other respects the methods employed have been the same as those used before. The permanent bench-mark stones have generally been set on side lines, so that settling that may have occurred in them has not affected the accuracy of the line.

Twenty-two permanent bench-marks have been set, twelve of which are stones in the ground, east of Pearl River, and the rest are copper bolts leaded into driers, abutments, brick buildings, &c. Superintendent J. T. Harahan very kindly gave us the use of a hand-car, which was of great service and materially facilitated the work. No other favors were asked or received from the railroad company, and in return for this one, I have prepared a list of our permanent bench-marks with their elevations, and also the elevations of the road-bed at every station, which will amply repay them for the use of the car.

Most of the work has been done from 6 to 8 a. m. and from 4 to 7 p. m. There have been very few days when work could be done between 8 a. m. and 4 p. m.

The party were quartered at but six places between New Orleans and Biloxi, a distance of 80 miles, three of these being club-houses for New Orleans hunters and fishermen.

RESULTS.

The length of line was 139 kilometers (87 miles). This was run in forty-seven days, May 8 to June 23, inclusive. Seven kilometers of this distance (4.4 miles) were required to be run four times. This gives 91.4 miles of duplicate line completed in forty-seven days, 1.9 miles per day. The full party was under pay fifty-one days. Field-work was done on thirty-six days, making an average of 2.6 miles per day every day on which work was done. Of the remaining fifteen days nine were Sunday, four were rainy, one was windy, with the tents inaccessible, and one day was spent connecting with a stone and setting a water-gauge at "West End" on Lake Pontchartrain.

DISCUSSION OF RESULTS.

There were five discrepancies in the season's work beyond the limits; four of these were errors of 10 millimeters, and one of 20 millimeters. It is pretty well determined that these all occurred by allowing the rods to get out of the sockets in the foot-plate.

These sockets are just 10 millimeters in depth; every time a train passes the rod is taken out, and in replacing it the rodman is very careful not to jar the plate. Neither should he incline the rod too much in putting it back for fear of bringing a lateral pressure on the plate and so moving it. He therefore cannot get down to look at it, neither can he let it in so as to hear the click as it drops into the socket, as he can when he first sets up, so that some of those errors may have come in from this cause.

Another cause would be the strong wind, in which we were often able to work on account of the protection afforded the instruments by the tents. The rods, however, had no protection, and it was with the greatest difficulty that the rodmen managed to keep their rods in place. They used a stick to brace up the rod on the leeward side, and if this was held firmly against the rod, the wind against the top, would tend to lift the rod bodily out of the socket. One of the rods was found in this condition one day, the spur resting out on the top of the plate, and it had evidently been done in this way, the rodman not being conscious of the change.

Aside from these five errors, which determinations were rejected in the field computation, there were no discrepancies beyond the limit on the entire line.

A number of stretches were run a third and fourth time to reduce the probable error, although already within the limit, all determinations being used.

There was no marked divergence in the plot of the two lines until the last two weeks. This, I think, was caused by the road-bed becoming very dry, there having been no rain in that time. When trains pass, the whole road-bed is shaken somewhat, and if there is dry sand about the foot-plates it is liable to work under them, and so raise them slightly. The discrepancies are in the direction to indicate a raising of the foot-plates. The results obtained on the bridges and trestles are very satisfactory.

We have for the five such stretches:

Locality.	Distance.	Number of lines.	Maximum discrepancy.	Probable error of mean.
	m.		mm.	mm.
Chef Menteur	560	4	1.3	0.2
Proctor	1,100	4	1.3	0.2
Pearl River	520	3	0.9	0.2
Bay Saint Louis	3,700	4	3.5	0.5
Biloxi Bridge.....	1,120	4	3.5	0.5

Many trains passed, both while crossing these bridges and also between the different crossings. The evidence is conclusive that there is no appreciable settling of these piles for passing trains. The probable error in the mean for the entire line is 7 millimeters. This corresponds to a probable error in the mean of 0.60 millimeters per kilometer, a degree of accuracy not hitherto attained, I believe, in this country.

It will be seen, by comparing their elevations in the summary, that the 6-foot mark on the Biloxi gauge is 25.5 millimeters below the zero of the Carrollton gauge. The keeper thinks mean tide is a little below the 6-foot mark. It is likely, therefore, that the zero of the Carrollton gauge will prove to be some 2 or 3 inches above mean tide.

The work is much indebted to the attention paid to it by Major Harrod. It was through his influence that a hand-car was obtained, and also that the party was allowed to occupy various club-houses through the swamp region. The organization of the party was very satisfactory. Mr. Ferguson is always to be commended for the intelligence, care, and conscientious devotion he brings to the work, and Recorders Ramel and Kastl are well deserving of further employment. Mr. Ramel acted as an observer on 31 stretches, aggregating 24 miles, on only one of which was the discrepancy beyond the limit, and that one by 10 millimeters, probably an error of the rodman

Very respectfully, your obedient servant,

J. B. JOHNSON,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Corps of Engineers, U. S. A., Secretary Mississippi River Commission.

b.—GRAFTON TO CHICAGO.

SAINT LOUIS, September 1, 1883.

SIR: I have the honor to submit the following report of the field work of precise levels from Grafton to Chicago. This work was done in three seasons, viz:

- I. Grafton to Keokuk, 151 miles, done May 21 to August 30, 1881.
- II. Keokuk to Fulton, 170 miles, done September 6 to November 25, 1882.
- III. Fulton to Chicago, 170 miles, done May 2 to August 7, 1883.

The observers for all this work were O. W. Ferguson and J. B. Johnson. Each server had a recorder, two rodmen, and two axmen at his disposal, thus making 6 separate working field parties. Both parties were quartered together, and were in charge of J. B. Johnson. From Grafton to Keokuk they lived on a quarter-boat; from Keokuk to Chicago they found accommodations in the villages, and used a hand-car to go to and from work. Of the 491 miles of line from Grafton to Chicago, 406 miles were run on railroads, and 85 miles along the edge of the river bank. From Grafton to Savanna, the most northerly point reached on the river, railroads were only used when they were in close proximity to the river bank.

BENCH-MARKS.

From Grafton to Chicago 147 permanent bench-marks were set, 110 of which may be found near to the river, between Grafton and Savanna; of the remaining 37, are on the line of the Chicago, Milwaukee and Saint Paul Railway, from Savanna to Chicago, and 6 in the city of Chicago. These bench-marks are nearly all copper bolts leaded into natural rock, bridge piers, and abutments, foundations of buildings, and

in stones set in the ground. They are generally marked with the letters **U S** **P E** arranged in this manner about the bolt-head. Most of them are set horizontally in vertical walls and faces of rock, and the balance vertically in horizontal surfaces. The latter are more convenient to connect with, but are more liable to be disturbed and covered from sight.

In addition to these permanent benches, connection was made with 30 "permanent bench-marks" set in Colonel Farquhar's survey of the Mississippi River, and published in the Report of Chief of Engineers for 1880, page 1520.

Temporary bench-marks were set about every kilometer, or whenever the work was interrupted. There were usually points of natural rock, abutments, spikes in stumps or roots of trees, or in the trestle-work over piles, or else stakes driven in the ground. Where the stability of the temporary bench was not assured, more than one was set in this case, both were connected with again in starting from them, and the mean elevation of the two was used in continuing the line. With but one exception, no temporary bench was ever found to have moved, and this one was a spike in a cattail guard where the timbers were afterwards found to be decayed. This movement was discovered in the field, and the line continued from the next set of benches back to the line.

LOCATION OF LINE.

The location of the line run is as follows:

From Grafton to Clarkville, 58 miles, on the east bank of the river.

From Clarkville to Burlington, 135 miles, on the line of Saint Louis and Keokuk and Chicago, Burlington and Quincy railways, on the west bank.

From Burlington to New Boston, 36 miles, on the line of the Chicago, Burlington and Quincy Railway, on the east bank.

From New Boston to Port Louisa, 9 miles, on the east bank, through the bottom.

From Port Louisa to Muscatine, 18 miles, on the west bank, through the bottom.

From Muscatine to Rock Island, 29 miles, on the line of the Chicago, Rock Island and Pacific Railway, on the west bank.

From Rock Island to Savanna, 58 miles, on the line of the Chicago, Milwaukee and Saint Paul Railway, on the east bank.

From Savanna to Chicago, 148 miles, on the line of the Chicago, Milwaukee and Saint Paul Railway.

This necessitated crossing the river four times with the line of levels, viz., at Clarkville, Burlington, Port Louisa, and Rock Island.

At Clarkville and Port Louisa the crossings were effected by simultaneous reading with two instruments on opposite sides of the river, the midwire bisecting a large target on the opposite shore. Sixteen readings were taken by each instrument, in sets of four, which were as follows:

1. Telescope normal, level direct.
2. Telescope normal, level reversed.
3. Telescope inverted, level direct.
4. Telescope inverted, level reversed.

Then each observer, with his instrument, crossed over, and the same was repeated.

The longest readings thus taken were about 600 meters. Very good results were obtained, the probable error being less than a millimeter.

At Burlington and Rock Island the crossings were made on bridges.

INSTRUMENTS.

The instruments used on this work are the Kern levels, and rods similar to those used in the precise levels of Switzerland, and are made by J. Kern, of Aarau. The instrument, with tripod, weighs 22 pounds. It has three steel leveling screws, with enlarged spherical ends at bottom, which are held to the tripod head by clamps fitting over the spherical enlargements. The wye adjustment is by means of a thumb-screw of very fine thread, so that the last final centering of the bubble is made with this screw. The bubble tube is fixed in a striding wooden case, with brass ends fitting on the collars of the telescope. The bubble case has a glass cover and a mirror that may be raised to the angle of 45° and so reflect the bubble image to the eye of the observer at the eye-piece. The telescope clamps also hold the bubble case in position; this is removed, however, when the instrument is carried. The telescope gives an inverted image. The reticule has three horizontal wires, all of which are read, and the mean taken as the reading of that sight. This also gives a stadia measurement of the distance.

The rods are 3 meters long, made of two pine boards with a T-shaped cross section, provided with an iron spur at bottom with a flat end, and a watch level by which to hold it vertical. They are graduated to centimeters, and are read by estimation to millimeters. No target is used.

FIELD METHODS.

1. *Duplication.*—In all this work the lines between benches have always been duplicated by running the second line in the opposite direction. From Grafton to Keokuk the duplicate lines were run by different observers, Mr. Ferguson always running north and Mr. Johnson south. From Keokuk to Chicago each observer duplicated his own work. It was never attempted to carry two lines simultaneously with one instrument.

2. *Observation.*—Great care was taken to always get the back and fore sights equal in length. Since the interval between extreme wire readings gave a stadia measurement of the distance, the recorder knew, by means of the continued sum of back and fore sight intervals, at all times, what the total difference was, and could instruct the rodman to make the requisite correction. This was carefully attended to.

The bubble was always read by the observer in the mirror set for that purpose. This was read by the observer's left eye, without removing his right eye from the eye piece. There was a small parallax on the bubble when the eye was in this position, but since the error was constant for both back and fore sights, it was eliminated. From Grafton to Keokuk the bubble was brought approximately to the middle and read, and a correction applied for its eccentric position. From Keokuk to Chicago, the bubble was brought carefully to the center and held there by means of the very delicate wye adjusting screw, so that there were no corrections for bubble displacement on this part of the work. The latter method was found to be about as convenient in the field, and it saves much work in reduction.

In connecting with horizontal benches it was the common practice to set the instrument on a plane with the bench and make the middle wire bisect the small hole in the center of the bolt, reading both back sight on rod and fore sight on bolt, with the telescope in both normal and inverted positions. This was necessary, because three wires were read on the rod, and the middle wire did not exactly coincide with the mean of the three.

The rod supports used in 1881 and 1883 were iron foot-plates of some 18 square inches area, triangular in shape, having a handle, 3 spurs at bottom, and a socket in the top, with a convex bottom to receive the spur of the rod. In 1882 iron pins were used in addition to the foot-plates, or, in place of them, on portions of the line where, from our experience, they were thought to be better than the plates. This was on alluvial, moist, or springy ground, where the plates were liable to change their elevation. Sometimes in the woods it would be almost impossible to get good solid earth on which to set the plate. The pins were found to work very well in these places, but in loose earth, as sand or unpacked gravel, the foot-plates are greatly superior. If but one kind of support is to be used under all conditions, the foot-plates are preferable.

INSTRUMENTAL CONSTANTS AND ADJUSTMENTS.

The value of one division of the level bubble in seconds of arc was determined two or three times each field season, also the difference in the diameters of the telescope collars, and the correction therefor, and the value of the wire intervals. The adjustment of the bubble tube, and the line of collimation of the mean of the three wires, to the axis of the telescope collars, was made or examined every time the instruments were set up, and again on closing a stretch. In the former case the error of paral-

levelism was made very small, and in the latter its absolute value, in seconds of arc, was found by reversed readings. These values, found at the close of the stretch, called corrections for "inclination" and "collimation," together with the correction for inequality of collars, called the "pivot" correction, were all evaluated for the residual difference in distance between sums of back and fore sights, and the result correction applied to the computed elevation of the forward benches. The algebraic sums of these corrections seldom amounted to more than one or two tenths of a millimeter, on account of the care taken to keep the back and fore sights equal.

The corrections resulting from the condition of the instrument at the close of the stretch were alone used, because where constant care had been exercised to keep back and fore sights balanced up, the residual difference would usually be made the last one or two settings.

PROGRESS.

The following table shows the rates of progress made in the three seasons:

Item.	Grafton to Keokuk.	Keokuk to Fulton.	Fulton to Chicago.	Grafton Chicago.
Length of line	151	170	170	
Number of days in entire field season	94	81	98	
Number of days in which work was done	73	58	67	
Average daily run in miles for entire season	1.6	2.1	1.7	
Average daily run in miles for working days	2.1	2.9	2.5	

These average runs may be taken as finished duplicate work by the two parties as single line by one party.

The greater progress made in the season of 1882 was due to the good weather and the use of the hand-car and the observing tents. These latter were made to be run on the Gulf coast to protect the instrument from the wind. They are 5 by 6 feet wide, with one 8 foot center pole, held at bottom by eight steel pins. They allow work to be done on many days when it would have been impossible without them.

CONNECTIONS AT CHICAGO.

The object of carrying the line to Chicago was to connect with Lake Michigan. The Lake Survey had determined the elevation of certain bench-marks at Milwaukee as well as the mean elevation of Lake Michigan, for the months of May, June, July and August, 1875, and also the mean elevation of the lake from January 1, 1860, to December 31, 1875, above mean sea-level at New York City.

At Chicago a gauge had been read three times a day at the crib, being the entrance to the tunnel two miles from shore, since 1872. This gauge had apparently remained undisturbed since it was first set. Its zero was set at 8.01 feet above city directrix by spirit levels carried through the tunnel. In 1878 a water-level connection of great accuracy was made by the present city engineer, Mr. S. G. Artingstall, between the crib and the shore, and the crib gauge was found to be 0.246 foot too low by the shore benches. The crib gauge was taken as correct, however, and corrections applied to the shore bench-marks. By this decision the city directrix is a point 8.01 feet below the zero of the crib gauge.

The line of precise levels was joined with eight city benches and with the crib gauge by water levels. These water levels consisted in reading 3 gauges on shore and 2 at the crib every five minutes for seven consecutive hours on a calm day. This connection from shore to crib agreed with that of the city engineer in 1878 to the near thousandth of a foot.

Having thus joined the line of precise levels with the zero of the crib gauge, it remained only to obtain a comparison of gauge-readings at Chicago and Milwaukee and transfer the Milwaukee elevations to Chicago. Thus the Mississippi River line of precise levels is joined to the United States Lake Survey line of levels from New York City. (For a description of the determination of the elevation of the Great Lakes see Professional Papers, Corps of Engineers, No. 24, p. 59.)

The following recorders have assisted on the work: A. Ramel, P. P. Sanborn, L. Aruer, E. K. Woodward, jr., and S. J. Fitzhugh, all of whom discharged their duties with credit. My assistant, Mr. O. W. Ferguson, deserves especial mention for the accuracy and rapidity with which he has always done his work.

Very respectfully, your obedient servant,

J. B. JOHNSON,
United States Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

3. Report on reduction of precise levels, by L. L. Wheeler, assistant engineer.

COTTONWOOD POINT, Mo.,
October 29, 1883.

SIR: I have the honor to submit the following report upon the reduction of precise levels, made under my direction. These levels include the following sections: From Carrollton, La., to Biloxi, Miss., a distance of 140 kilometers; from Grafton, Ill., to Cairo, Ill., a distance of 346 kilometers; from Keokuk, Iowa, to Grafton, Ill., a distance of 242 kilometers; and from Keokuk, Iowa, to Fulton, Ill., a distance of 267 kilometers.

In the reductions made under my direction, the greatest care has been taken that no errors of computation should enter into the results. All reductions have been checked, either by comparison with the corrected field reduction, or by two persons computing the same results independently. It is therefore believed that the results here given may safely be taken as the correct ones resulting from the observations.

In these four sections the instruments used were alike, and the method of field work nearly the same throughout.

The instruments and rods were manufactured by J. Kern, of Aarau, Switzerland, and are similar to those described in the Report of the Chief of Engineers for 1877, page 1190.

Table A shows the various determinations of the instrumental constants up to the date of the completion of the line from Keokuk to Fulton.

Table B shows the instrumental constants used in reducing the notes of each section, and the computers' names. In this table *i* and *i'* are the angular distances of the upper and lower wires, respectively, from the midwire, and *I* is the angular distance between extreme wires. The remainder of the table is sufficiently explained by the headings of the columns.

TABLE A.—Constants for Kern levels and Kern level rods.

[*p* is for "pivot correction," or correction for inequality of telescope rings. It is the angular correction to be applied to the line of collimation to reduce it to the horizontal plane of the upper surface of the rings. *v* is the value of one division of the level tube in seconds of arc. *L* is the length of a three-meter rod.]

Number of instrument.	Constant.	Date.	No. of observations.	Probable error.	Remarks.
Kern level.....					
1	<i>p</i> = - 0.34	Aug. 14, 1880	42	± 0.30	
1	<i>p</i> = - 1.04	May 24, 1881	10	± 0.18	
1	<i>p</i> = - 1.50	Aug. 11, 1881	10	± 0.05	
1	<i>p</i> = - 2.66	Aug. 27, 1881	10	± 0.06	
1	<i>p</i> = - 1.38	Feb. 3, 1882	7	± 0.09	
1	<i>p</i> = - 3.52	May 11, 1882	14	
1	<i>p</i> = - 1.91	June 24, 1882	10	± 0.06	
1	<i>p</i> = - 2.46	Dec. 20, 1882	8	± 0.13	
2	<i>p</i> = + 0.99	Aug. 16, 1880	4	± 0.03	
2	<i>p</i> = + 0.50	Oct. 22, 1880	8	± 0.07	
2	<i>p</i> = + 1.84	Jan. 8, 1881	16	± 0.02	
3	<i>p</i> = + 2.53	May 26, 1881	8	± 0.03	
3	<i>p</i> = + 0.17	Feb. 4, 1882	5	± 0.11	
3	<i>p</i> = + 0.19	May 11, 1882	14	
3	<i>p</i> = + 1.10	June 24, 1882	10	± 0.06	
3	<i>p</i> = + 2.71	Sept. 6, 1882	6	
3	<i>p</i> = - 0.37	Dec. 21, 1882	8	± 0.10	
5	<i>p</i> = - 1.85	Feb. 4, 1882	5	± 0.05	
Kern level tube.....					
2	<i>v</i> = 4.08	Aug. 14, 1880	74	
2	<i>v</i> = 3.83	Aug. 16, 1880	33	
2	<i>v</i> = 4.49	Aug. 19, 1880	37	
2	<i>v</i> = 5.60	Jan. 8, 1881	23	
2	<i>v</i> = 4.61	Mar. 15, 1881	34	
3	<i>v</i> = 3.06	Oct. 7, 1880	24	
3	<i>v</i> = 3.25	Oct. 9, 1880	28	
3	<i>v</i> = 3.27	Jan. 7, 1881	32	
3	<i>v</i> = 3.22	Oct. 14, 1881	30	
3	<i>v</i> = 2.90	May 24, 1881	10	± 0.04	
3	<i>v</i> = 3.24	Aug. 9, 1881	10	± 0.02	
3	<i>v</i> = 3.04	Aug. 27, 1881	10	± 0.03	
3	<i>v</i> = 3.21	May 6, 1882	6	
3	<i>v</i> = 3.19	June 23, 1882	12	
5	<i>v</i> = 2.94	May 25, 1881	6	± 0.02	
5	<i>v</i> = 2.85	Aug. 9, 1881	36	± 0.01	
5	<i>v</i> = 2.76	Aug. 27, 1881	10	± 0.03	
5	<i>v</i> = 2.86	May 7, 1882	6	
7	<i>v</i> = 4.25	Aug. 13, 1880	89	
11	<i>v</i> = 2.66	Aug. 21, 1880	19	

Number of instrument.	Constants of instruments.						Rods.	Mean value of one meter.	Computers.	Remarks.	
	p	i			I	Bubble tube.					v
		i	i'	i''							
Carrollton to Biloxi.....	"	i	"	'	"	"	X	m.	L. L. Wheeler.....	New lower horizontal wire put in No. 3 June 1, 1882.	
	- 2.72	17 24.21	17 27 04	34 51.25	No. 3..	3.20	XII	1.000048	Alex. E. Kastl		
	+ 0.64	17 13.90	17 23.95	34 37.85	No. 5..	2.86	XIV				
		17 18.74	17 24.10	34 42.84			XV				
Grafton to Cairo.....		17 23.90	17 24.31	34 48.21	No. 2..	4.50	X	1.000009	L. L. Wheeler.....	New vertical wire put in No. 3 August 20, 1880.	
	- 0.34	17 31.73	17 20.56	35 01.29	No. 3..	3.21	XI		O. H. Ferguson		
	+ 1.35	17 31.32	17 30.50	35 01.82	No. 7..	4.25	XII		Alex. E. Kastl		
		17 23.86	17 20.60	34 44.46	No. 3..	3.06	XIII		J. B. Johnson		
Keokuk to Grafton.....		17 15.10	17 23.69	34 38.79	No. 5..	2.85	X	1.000010	O. W. Ferguson.....	New wires put in No. 3 August, 1882.	
	+ 1.35	17 42.98	17 28.64	35 11.62			XII		Alex. E. Kastl		
	- 1.85	14 15.99	14 02.38	28 18.87	No. 3..	3.20	XIV		L. L. Wheeler		
	- 2.46	17 13.90	17 23.95	34 37.85	No. 5..	2.86	XV	1.000029	L. L. Wheeler.....		
Fulton to Keokuk.....	+ 1.17						XVI		Alex. E. Karel		
							XVII		T. C. Thomas		

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Accompanying this report are tables of results and descriptions of the permanent bench marks.

In the tables of results column 1 gives the bench-mark, T. B. M., signifying temporary bench mark, and U. S. P. B. M., signifying United States permanent bench-mark.

Column 2 contains the distances in kilometers from the initial bench-mark.

Column 3 gives the direction in which the line was leveled.

Column 4 gives the successive differences of elevation in meters between bench marks, and the mean of such determinations.

Column 5 gives the residuals found by subtracting each determination from the mean.

Column 6 gives the probable error, r , of the mean in column 4, computed by formula

$$r = \pm 0.6745 \sqrt{\frac{[rr]}{n(n-1)}}$$

Column 7 gives the probable error R , of the mean elevation of each permanent bench-mark as computed from the beginning of the section.

Column 8 gives the elevations of all bench-marks referred to the Cairo datum plane, which is 230.84 feet below the zero of the United States Engineers' gauge at Cairo, Ill.

Column 9 gives the corrections which are to be applied to the elevations in column 8 to reduce them to standard meters.

Column 10 gives the corrected elevations referred to the same datum plane.

Column 11 gives the initial of the observer for each determination.

"J" is for Assistant J. B. Johnson.

"F" is for Assistant O. W. Ferguson.

"P" is for Assistant J. A. Paige.

"S" is for Recorder E. H. Sankee.

"B" is for Recorder H. P. Bourne.

"Sn" is for Recorder P. P. Sanborn.

"R" is for Recorder A. Rainel.

Column 12 indicates the nature of the support.

The above report is respectfully submitted.

L. L. WHEELER,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

Results of precise leveling.

CARROLLTON, LA., TO BILOXI, MISS.

[Bench-marks marked with an asterisk are not in main line of levels.]

Bench.	Distance.	Direction.	Difference of elevation.	V	r.	R.	Elevation.	Rod correction.	Corrected elevation.
	Km.		M	Mm.	Mm.	Mm.	M.	Mm.	M.
C. and G. S. 1. Carrollton									19.0272
*B. M. Hampson. (Re established by Maj Howell)			-0.3732	+1.1	0.7		8.0551		
			-0.3710	-1.1					
		Mean	-0.3721						
*B. M. Hampson (William)			-0.1980				8.8292		
*B. M. 3, Ripley			+0.7479	+0.1	0.1		9.7752		
			+0.7483	-0.3					
			+0.7477	+0.3					
		Mean	+0.7480						

*P. B. M. 1, Carrollton, below P. B. M. 1, Greenville - 27.0619 M, furnished in manuscript by the U States Coast and Geodetic Survey Office Report, 641, A. C. P. B. M. 1, Greenville above datum 46.0891 M. Report for 1862, page 74.

Results of precise leveling—Continued.

CARROLLTON, LA., TO BILOXI, MISS.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		Mm.	Mm.	Mm.	Mm.	M.	Mm.	M.	
*B. M. 4, Ripley			+0.4899	+1.0	0.4		9.5181			J. F.
			+0.4910	-0.1						J. F.
			+0.4917	-0.8						J. F.
		Mean	+0.4900							
*B. M. 4, Barney			+0.0032	-0.1	0.1		9.0303			J. F.
			+0.0030	+0.1						J. F.
		Mean	+0.0031							
*4-foot mark of water gauge, Carrollton.			+1.6128	+0.2	0.1		10.6402			J. F.
			+1.6132	-0.2						J. F.
		Mean	+1.6130							
*U. S. P. B. M. "Carrollton."			+0.1206				9.1478	0.0	9.1478	J. F.
*City B. M. marked (X M. B., June, 1874).			-1.2617				7.7055			J. F.
T. B. M. 1	1.03	R.	-1.6588	+1.3	0.8		7.3809			J. F.
		R.	-1.6585	+1.1						J. F.
		W.	-1.6538	-3.6						J. F.
		W.	-1.6585	+1.1						J. F.
		Mean	-1.6574							
T. B. M. 2	2.39	R.	+0.1150	-0.6	0.5		7.4240			J. F.
		W.	+0.1135	+0.7						J. F.
		Mean	+0.1142							
U. S. P. B. M. 1	2.80	R.	-0.5437	0.0	0.0	0.0	6.9403	-0.1	6.9403	J. F.
		W.	-0.5437	0.0						J. F.
		W.	-0.5436	-0.1						J. F.
		Mean	-0.5437							
*City stone at intersection Washington and Carrollton avenues.	3.06		+0.2793				7.7633			J. F.
T. B. M. 3	5.02	R.	-0.4647	+1.8	1.3		6.4774			J. F.
		W.	-0.4611	-1.8						J. F.
		Mean	-0.4629							
*City stone, "Half-way House."	6.65		+1.5096				7.9870			J. F.
*4.5-foot mark of gauge at West End, N. O.	11.48		-0.3475				7.0395			J. F.
*B. M. "Height of Metairie Ridge."	11.74		+0.0359	-0.1	0.0		7.0753			J. F.
			+0.0358	0.0						J. F.
		Mean	+0.0358							
T. B. M. 4	6.06	R.	+0.0250	+1.9	1.3		6.5052			J. F.
		W.	+0.0208	-3.0						J. F.
		Mean	+0.0278							
T. B. M. 5	6.74	R.	+0.7989	-0.3	0.1		7.3039			J. F.
		W.	+0.7985	+0.2						J. F.
		Mean	+0.7987							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

CARROLLTON, LA., TO BILOXI, MISS.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	s.	R.	Elevation.	Rod correction.	Corrected elevation
	Km.		M	Mm	Mm.	Mm.	M.	Mm.	M.
*U. S. P. B. M. 2	0.70	E	+1.8556	-0.2	0.1	2.0	9.1503	0.0	9.1503
		W	+1.8553	+0.2					
		Mean ..	+1.8554						
*City stone in city park.	8.14	E	-1.3546	+0.8	0.5		7.8055		
		W	-1.3530	-0.8					
		Mean ..	-1.3538						
U. S. P. B. M. 3	8.80	E	+0.3701	+0.7	0.5	2.1	7.6747	-0.1	7.6746
		W	+0.3710	-0.8					
		Mean ..	+0.3708						
T. B. M. 7	9.27	E	+0.1131	-0.9	0.6		7.7880		
		W	+0.1133	+0.9					
		Mean ..	+0.1132						
T. B. M. 8	9.63	E	-0.2090	+1.4	0.9		7.5813		
		W	-0.2083	-1.3					
		Mean ..	-0.2076						
T. B. M. 9	11.30	E	+0.2124	+1.6	1.1		7.7958		
		W	+0.2158	-1.6					
		Mean ..	+0.2140						
T. B. M. 10	12.57	E	-0.7277	+0.7	0.4		7.0688		
		W	-0.7264	-0.8					
		Mean ..	-0.7270						
T. B. M. 12	13.88	E	+0.4251	+1.9	1.2		7.4953		
		W	+0.4288	-1.8					
		Mean ..	+0.4270						
T. B. M. 13	14.80	E	+0.0094	-1.2	0.8		7.5035		
		W	+0.0080	+1.3					
		Mean ..	+0.0082						
T. B. M. 14	16.20	E	+0.1884	-0.8	0.6		7.6911		
		W	+0.1867	+0.9					
		Mean ..	+0.1876						
T. B. M. 15	18.55	E	-0.5257	+0.4	0.3		7.1658		
		W	-0.5240	-0.4					
		Mean ..	-0.5253						
T. B. M. 16	19.29	E	-0.0531	+0.1	0.1		7.1126		
		W	-0.0530	-0.2					
		Mean ..	-0.0532						
T. B. M. 17	20.26	E	+0.5513	+0.0	0.6		7.0648		
		W	+0.5530	-0.8					
		Mean ..	+0.5522						
T. B. M. 18	20.90	E	-0.3580	+0.4	0.2		7.3072		
		W	-0.3573	-0.3					
		Mean ..	-0.3576						

Results of precise leveling—Continued.

CARROLLTON, LA., TO BILOXI, MISS.—Continued.

Bench.	Distance.	Direction.	Difference of ele- vation.	V.	r.	R.	Elevation.	Rod correction.	Corrected eleva- tion.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 19	21.79	E	+0.1854	+0.4	0.2	7.4930	J.
		W	+0.1861	-0.3	F.
		Mean ..	+0.1858	
T. B. M. 20 and 20a	22.78	E	-0.2992	0.0	0.0	7.1938	J.
		W	-0.2993	+0.1	F.
		Mean ..	-0.2992	
T. B. M. 21	23.73	E	+0.0510	+0.6	0.4	7.2454	J.
		W	+0.0523	-0.7	F.
		Mean ..	+0.0516	
T. B. M. 22 and 22a	25.04	E	+0.3924	+0.7	0.5	7.6385	J.
		W	+0.3938	-0.7	F.
		Mean ..	+0.3931	
T. B. M. 23	26.76	E	+0.0896	-1.3	0.9	7.7270	J.
		W	+0.0872	+1.3	F.
		Mean ..	+0.0885	
T. B. M. 24 and 24a	28.29	E	-0.0978	-3.0	1.0	7.6262	J.
		W	-0.1050	+4.2	F.
		E	-0.1009	+0.1	J.
		W	-0.0997	-1.1	F.
		Mean ..	-0.1008	
T. B. M. 25 and 25a	29.92	E	-0.2830	+1.0	0.7	7.3442	J.
		W	-0.2810	-1.0	F.
		Mean ..	-0.2820	
T. B. M. 26	31.51	E	+0.3119	+1.9	1.3	7.6580	J.
		W	+0.3158	-2.0	F.
		Mean ..	+0.3138	
T. B. M. 27	33.08	E	-0.2046	-1.5	1.0	7.4519	J.
		W	-0.2076	+1.5	F.
		Mean ..	-0.2061	
T. B. M. 29 and 29a	36.42	E	+0.0807	+3.4	2.4	7.5360	J.
		W	+0.0912	-7.1	F.
		W	+0.0804	+3.7	F.
		Mean ..	+0.0841	
T. B. M. 30 and 30a	37.25	E	+0.5914	-0.4	0.3	8.1270	J.
		W	+0.5905	+0.5	F.
		Mean ..	+0.5910	
T. B. M. 31 and 31a	37.82	E	+0.2347	-0.7	0.2	8.8610	J.
		W	+0.2336	+0.4	F.
		E	+0.2433	+0.7	J.
		W	+0.2342	-0.2	F.
		Mean ..	+0.2340	
•U. S. P. B. M. 4....	38.10	E	+0.4191	-3.4	1.3	4.8	8.5427	0.0	8.5427	J.
		W	+0.4173	-1.6	F.
		W	+0.4101	+5.6	J.
		E	+0.4164	-0.7	J.
		Mean ..	+0.4157	

T OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

CARROLLTON, LA., TO BILOXI, MISS.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.
T. R. M. 32 and 33a.	39.67	E	-0.7311	-1.7	1.1		7.8283		
		W	-0.7345	+1.7					
		Mean ..	-0.7328						
T. R. M. 32½	41.24	E	+0.0944	+1.6	1.1		7.7242		
		W	+0.0994	-3.4					
		E	+0.0942	+1.6					
		Mean ..	+0.0960						
T. R. M. 33 and 33a.	42.32	E	+0.2304	+0.8	0.5		7.9554		
		W	+0.2319	-0.7					
		Mean ..	+0.2312						
T. R. M. 34 and 34a.	44.62	E	-0.5324	-2.4	1.6		7.4206		
		W	-0.5372	+2.4					
		Mean ..	-0.5348						
T. R. M. 35	46.81	E	+0.8453	-1.1	0.8		8.2058		
		W	+0.8440	+1.2					
		Mean ..	+0.8452						
T. R. M. 36	49.51	E	-0.0975	+0.6	0.4		8.1688		
		W	-0.0964	-0.6					
		Mean ..	-0.0970						
T. R. M. 37 and 37a.	51.65	E	-0.8904	-1.4	0.9		7.2710		
		W	-0.8991	+1.8					
		Mean ..	-0.8978						
T. R. M. 37½	52.70	E	+0.0117	+1.0	0.5		7.2387		
		W	+0.0140	-1.2					
		E	+0.0123	+0.4					
		Mean ..	+0.0127						
T. R. M. 38 and 38a.	53.63	E	-0.0449	+0.7	0.7		7.2305		
		W	-0.0420	-2.2					
		W	-0.0456	+1.4					
		Mean ..	-0.0442						
T. R. M. 39 and 39a.	56.57	E	+1.4625	+3.0	2.0		8.7050		
		W	+1.4685	-3.0					
		Mean ..	+1.4655						
*U. S. P. R. M. 5...	56.92	W	-1.7545	+0.6	0.4	5.7	6.9510	-0.1	6.9509
		W	-1.7534	-0.6					
		Mean ..	-1.7540						
T. R. M. 40 and 40a.	57.63	E	+0.0320	-0.5	0.4		8.7365		
		W	+0.0301	+1.4					
		E	+0.0311	+0.4					
		W	+0.0327	-1.2					
		Mean ..	+0.0315						
T. R. M. 41 and 41a.	58.62	E	-1.1105	-0.3	0.2		7.6257		
		W	-1.1111	+0.3					
		Mean ..	-1.1108						

2472 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

CARROLLTON, LA., TO BILOXI, MISS.—Continued.

Bench.	Distance.*	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 53	73.87	E	+0.4800	-1.6	1.0		8.1050			J. F.
		W	+0.4760	+1.5						
		Mean ..	+0.4784							
T. B. M. 54	74.70	E	-0.3155	+0.1	0.1		7.8805			J. F.
		W	-0.3153	-0.1						
		Mean ..	-0.3154							
T. B. M. 55 and 55a.	70.40	E	-0.3100	-0.6	0.4		7.5702			J. F.
		W	-0.3107	+0.5						
		Mean ..	-0.3102							
T. B. M. 56	73.36	E	+0.3038	-0.1	0.1		7.8740			R. F.
		W	+0.3036	+0.1						
		Mean ..	+0.3037							
T. B. M. 57	79.53	E	+0.3254	-1.1	0.7		8.1983			R. F.
		W	+0.3232	+1.1						
		Mean ..	+0.3243							
*U. S. P. B. M. 8...	79.10	E	+1.4204			6.2	9.2944	0.0	9.2944	J.
T. B. M. 58 and 58a.	80.87	E	+0.2752	+0.2	0.1		8.4737			R. F.
		W	+0.2756	-0.2						
		Mean ..	+0.2754							
T. B. M. 59	81.00	E	+1.2051	-0.2	0.1		9.6786			J. F.
		W	+1.2047	+0.2						
		Mean ..	+1.2049							
T. B. M. 60	83.17	E	-0.6781	+3.6	0.9		9.0041			J. F.
		W	-0.6723	-2.2						J. F.
		E	-0.6734	-1.1						J. F.
		W	-0.6741	-0.4						
		Mean ..	-0.6745							
T. B. M. 61 and 61a.	84.68	E	+2.3275	-0.1	0.3		11.3315			J. F.
		W	+2.3063	(†)						J. F.
		E	+2.3167	+0.7						J. F.
		W	+2.3280	-0.6						
		Mean ..	+2.3274							
*U. S. P. B. M. 9...	85.80	E	-0.2700	-1.0	0.6	6.4	11.0605	+2.1	11.0605	J. F.
		W	-0.2719	+0.9						
		Mean ..	-0.2710							
T. B. M. 62	85.43	E	+0.2808	-0.2	0.1		11.6121			J. F.
		W	+0.2804	+0.2						
		Mean ..	+0.2806							
T. B. M. 63	86.45	E	+0.1237	+0.1	0.1		11.7359			J. F.
		W	+0.1240	-0.2						
		Mean ..	+0.1238							
T. B. M. 64	88.28	E	+0.8683	+3.3	1.2		12.6075			J. F.
		W	+0.8744	-2.8						J. F.
		E	+0.8721	-0.5						
		Mean ..	+0.8716							

† Rejected.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
B. M. 8, Holman...	91.78	S.....	+0.9021	+2.6	1.8	135.0967	S. P.
		N.....	+0.9074	-2.7	
		Mean..	+0.9047							
B. M. 9, Holman...	92.75	S.....	-1.3792	-3.8	2.6	133.7137	S. P.
		N.....	-1.3869	+3.9	
		Mean..	-1.3830							
T. B. M. 118.....	93.89	S.....	-0.9828	+3.1	1.1	132.7240	S. P.
		S.....	-0.9777	-2.0	
		N.....	-0.9786	-1.1	
		Mean..	-0.9797							
*U. S. P. B. M. 19.....		S.....	-6.5393	0.0	0.0	10.1	126.1947	+0.2	126.1949	P. P.
		N.....	-6.5393	0.0	
		Mean..	-6.5393							
T. B. M. 119.....	94.68	S.....	+0.6307	+2.1	1.4	133.3668	S. P.
		N.....	+0.6350	-2.2	
		Mean..	+0.6328							
B. M. 10, Holman..	95.12	S.....	+0.0628	-0.4	0.3	133.4292	F. P.
		N.....	+0.0620	+0.4	
		Mean..	+0.0624							
B. M. 11, Holman..	97.10	S.....	+1.1273	+2.4	1.6	134.5589	F. P.
		N.....	+1.1321	-2.4	
		Mean..	+1.1297							
B. M. 12, Holman..	99.36	S.....	-1.8177	-3.7	2.5	132.7375	F. S.
		N.....	-1.8252	+3.8	
		Mean..	-1.8214							
U. S. P. B. M. 20...	99.40	S.....	-1.6422	+1.2	0.9	10.7	131.0965	+0.2	131.0967	F. S. P.
		N.....	-1.6423	+1.3	
		S.....	-1.6384	-2.6	
		Mean..	-1.6410							
T. B. M. 124.....	100.59	S.....	+2.0584	-0.2	0.1	133.1527	F. P.
		S.....	+2.0560	+0.2	
		Mean..	+2.0562							
B. M. 13, Holman..	100.93	S.....	+0.7609	+0.3	0.2	133.9139	F. P.
		N.....	+0.7615	-0.3	
		Mean..	+0.7612							
T. B. M. 125.....	101.45	S.....	-1.1589	+1.3	0.9	132.7563	F. P.
		N.....	-1.1562	-1.4	
		Mean..	-1.1576							
B. M. 14, Holman..	102.49	S.....	-0.4530	+1.8	1.2	132.3051	F. P.
		N.....	-0.4495	-1.7	
		Mean..	-0.4512							
T. B. M. 126.....	102.82	S.....	-0.2059	+0.1	0.0	132.0993	F. P.
		N.....	-0.2058	0.0	
		Mean..	-0.2058							

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.		Mm.	M.	
B. M. 15, Holman	102.90	S.....	+1.0990	+4.5	1.6		130.2037			F. P. S.
		N.....	+1.1078	-3.4						
		S.....	+1.1056	-1.2						
		Mean..	+1.1044							
U. S. P. B. M. 21	104.28	S.....	-2.1576	+0.6	0.4	10.8	130.0467	+0.2	130.0469	F. P. S.
		N.....	-2.1576	+0.6						
		S.....	-2.1550	-1.1						
		Mean..	-2.1570							
T. B. M. 128		S.....	+4.9989	+4.7	2.6		135.0503			F. S. S.
		S.....	+5.0112	-7.6						
		N.....	+5.0008	+2.8						
		Mean..	+5.0036							
U. S. P. B. M. 22	107.16	S.....	-4.3616	+1.2	0.8	11.2	130.6800	+0.2	130.6801	F. S.
		N.....	-4.3593	-1.1						
		Mean..	-4.3604							
B. M. 18, Holman	107.84	S.....	+0.9915	+0.1	0.1		131.0815			F. S.
		N.....	+0.9918	-0.2						
		Mean..	+0.9915							
B. M. 19, Holman	108.64	S.....	+1.6970	+1.4	0.9		132.8799			F. S.
		N.....	+1.6998	-1.4						
		Mean..	+1.6984							
B. M. 20, Holman	110.46	S.....	-2.5190	+0.8	0.6		130.6617			F. F.
		S.....	-2.5178	-0.9						
		Mean..	-2.5182							
U. S. P. B. M. 23	110.74	S.....	-1.5524	+0.8	0.6	11.4	129.3101	+0.2	129.3103	F. F.
		S.....	-1.5507	-0.9						
		Mean..	-1.5516							
T. B. M. 130	111.36	S.....	+1.6780	-0.6	0.4		130.9884			F. F.
		S.....	+1.6777	+0.6						
		Mean..	+1.6783							
B. M. 21 Holman	112.29	S.....	+0.8414	-0.8	0.5		131.8290			F. P.
		N.....	+0.8399	+0.7						
		Mean..	+0.8406							
B. M. 22, Holman	113.90	S.....	+0.5794	-0.6	0.4		132.4078			F. P.
		N.....	+0.5782	+0.6						
		Mean..	+0.5798							
B. M. 23, Holman	115.48	N.....	+4.7903	-2.4	1.6		137.1937			F. P.
		N.....	+4.7855	+2.4						
		Mean..	+4.7879							
T. B. M. 132	115.67	N.....	-0.1324	+0.2	0.1		137.0635			F. P.
		N.....	-0.1321	0.1						
		Mean..	-0.1322							
U. S. P. B. M. 24	116.75	S.....	-5.3121	+0.9	0.6	11.5	131.7523	+0.2	131.7525	F. P.
		N.....	0.3102	-1.0						
		Mean..	-5.3112							

s of precise leveling—Continued.

ON, ILL., TO CAIRO, ILL.—Continued.

		Direction	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
			M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
		S	+7.5875	+3.5	2.3	5.5	141.4302	+0.3	141.4305	F.
		N	+7.5044	-3.4						P.
		Mean ..	+7.5010							
	13.57	S	-9.6157	-3.3	2.2		131.8112			F.
		N	-9.6222	+3.2						P.
		Mean ..	-9.6190							
	14.38	N	+0.1379	+0.7	0.5		131.9498			P.
		S	+0.1393	-0.7						F.
		Mean ..	+0.1386							
	15.39	S	-0.8453	+4.0	2.0		131.1085			F.
		N	-0.8355	-5.8						P.
		N	-0.8431	+1.8						F.
		Mean ..	-0.8413							
	15.83	S	+3.9243	+0.8	0.5	6.3	135.0336	+0.3	135.0339	F.
		N	+3.9259	-0.8						P.
		Mean ..	+3.9251							
	18.03	S	-1.1456	-1.2	0.8		133.8868			F.
		N	-1.1480	+1.2						P.
		Mean ..	-1.1468							
	19.13	N	-2.4954	-4.8	2.1		131.3866			P.
		S	-2.5059	+5.7						F.
		N	-2.4994	-0.8						F.
		Mean ..	-2.5002							
	19.78	S	+0.2832	-2.0	1.3		131.6698			F.
		N	+0.2813	+1.9						P.
		Mean ..	+0.2832							
	21.13	N	-1.6478	-1.6	1.1		130.0204			P.
		S	-1.6510	+1.6						F.
		Mean ..	-1.6494							
M. 25	22.29	S	+5.4806	-1.0	0.4		135.5000			F.
		N	+5.4797	-0.1						P.
		S	+5.4786	+1.0						F.
		Mean ..	+5.4796							
S. P. B. M. 7		S	+8.2185	-0.7	0.4	6.9	143.7178	+0.3	143.7181	P.
		N	+8.2172	+0.6						P.
		Mean ..	+8.2178							
M. 27	23.77	S	-4.7250	+2.0	1.7		130.7779			F.
		N	-4.7169	-5.2						P.
		N	-4.7243	+2.2						F.
		Mean ..	-4.7221							
M. 28	24.93	S	-0.6382	-1.2	0.8		130.1385			F.
		N	-0.6407	+1.3						P.
		Mean ..	-0.6394							
S. P. B. M. 8	27.76	N	+6.8074	+0.6	0.4	7.1	136.9465	+0.3	136.9468	P.
		S	+6.8080	-0.6						F.
		Mean ..	+6.8080							

2486 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
U. S. P. B. M. 29 ...	151.29	N.....	+11.2023	-1.3	0.9	13.0	131.0372	+0.2	131.0374	P. F.
		S.....	+11.1997	+1.8	
		Mean..	+11.2010							
T. B. M. 167	151.66	S.....	-7.4074	-0.2	0.2	123.6296	F. F.
		S.....	-7.4079	+0.8	
		Mean..	-7.4076							
B. M. 45, Holman...	153.51	S.....	-3.3295	+3.3	2.2	120.3034	F. F.
		S.....	-3.3229	-3.3	
		Mean..	-3.3262							
T. B. M. 170	154.62	S.....	-1.6221	-0.4	0.3	118.6809	F. F.
		S.....	-1.6229	+0.4	
		Mean..	-1.6225							
B. M. 46, Holman...	155.18	S.....	+2.8847	+1.0	0.7	121.5606	F. F.
		N.....	+2.8867	-1.0	
		Mean..	+2.8857							
T. B. M. 171	155.91	S.....	-3.0724	-0.8	0.5	118.4934	F. P.
		N.....	-3.0740	+0.8	
		Mean..	-3.0732							
*U. S. P. B. M. 30	+6.1939	-0.4	0.3	13.2	124.6869	+0.2	124.6871	P. P.
		+6.1931	+0.4	
		Mean..	+6.1935							
B. M. 48, Holman...	158.29	S.....	+1.5794	+2.6	1.7	120.0754	F. P.
		N.....	+1.5846	-2.6	
		Mean..	+1.5820							
B. M. 50, Holman...	160.77	S.....	-1.1472	+0.6	0.4	118.9288	F. P.
		N.....	-1.1459	-0.7	
		Mean..	-1.1466							
U. S. P. B. M. 31 ...	161.84	S.....	+9.9707	+4.6	1.6	13.4	128.9041	+0.2	128.9043	F. F. P.
		N.....	+9.9784	-3.1	
		N.....	+9.9769	-1.6	
		Mean..	+9.9753							
B. M. 51, Holman...	162.14	S.....	-8.9848	-0.6	0.4	119.9187	F. F.
		N.....	-8.9860	+0.6	
		Mean..	-8.9854							
T. B. M. 173	162.48	S.....	-1.5273	+0.7	0.5	118.8921	F. F.
		N.....	-1.5258	-0.8	
		Mean..	-1.5266							
T. B. M. 174	162.75	S.....	-2.7524	-1.3	0.9	115.6384	F. P.
		N.....	-2.7550	+1.3	
		Mean..	-2.7537							
T. B. M. 174½	162.80	S.....	+1.1607	+0.1	0.0	116.7992	P. P.
		N.....	+1.1608	0.0	
		Mean..	+1.1608							

Results of precise leveling—Continued.
 GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
33, Holman..	164.88	N.....	+8.7970	-1.4	1.0		125.5948			P.
		S.....	+8.7941	+1.5						P.
		Mean..	+8.7956							
54, Holman..	165.88	N.....	-1.5000	+3.1	2.1		124.0010			P.
		S.....	-1.5006	-8.2						P.
		Mean..	-1.5038							
P. B. M. 32...	166.08	N.....	+1.1535	-0.4	0.8	12.7	123.1543	+0.2	123.1543	P.
		S.....	+1.1537	+0.4						P.
		Mean..	+1.1531							
M. 170.....	166.92	S.....	+1.0474	+0.2	0.2		123.3017			F.
		N.....	+1.0479	-0.2						P.
		Mean..	+1.0476							
S. P. B. M. 33..			+2.1128	+0.4	0.3	15.7	123.3149	+0.2	123.3151	P.
			+2.1137	-0.5						P.
		Mean..	+2.1132							
M. 180.....	171.42	S.....	-4.6547	+5.7	3.3		121.5327			F.
		N.....	-4.6432	-5.8						P.
		Mean..	-4.6490							
P. B. M. 34...	172.86	S.....	+1.0058	+6.5	2.0	14.3	123.2540	+0.2	123.2542	F.
		N.....	+1.7020	-0.7						P.
		N.....	+1.7001	-4.8						P.
		Mean..	+1.7013							
M. 182.....	175.24	S.....	-0.2147	+0.7	0.3		123.0400			F.
		N.....	-0.2132	-0.5						P.
		S.....	-0.2141	+0.1						P.
		Mean..	-0.2140							
M. 183.....	175.74	S.....	+1.4182	-0.8	1.0		124.4554			F.
		N.....	+1.4101	+5.3						P.
		S.....	+1.4198	-4.4						P.
		Mean..	+1.4154							
M. 184.....	176.03	S.....	-3.3225	-0.6	0.4		121.1823			F.
		N.....	-3.3237	+0.6						P.
		Mean..	-3.3231							
M. 185.....	181.04	S.....	+2.5663	+4.3	2.9		123.7029			F.
		N.....	+2.5749	-4.3						P.
		Mean..	+2.5706							
S. P. B. M. 35...	181.47	S.....	+0.9580	-0.3	0.2	14.7	124.6615	+0.2	124.6617	F.
		N.....	+0.9583	+0.3						P.
		Mean..	+0.9580							
S. P. B. M. 36..			+2.1172	-0.2	0.1	14.7	126.7785	+0.2	126.7787	P.
			+2.1168	+0.2						P.
		Mean..	+2.1170							
M. 190.....	181.48	S.....	-0.2277	+0.3	0.2		124.4341			F.
		N.....	-0.2271	-0.3						P.
		Mean..	-0.2274							

T OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.
*U. S. P. B. M. 14 ..		N	+0.9570	+0.6	0.4	8.8	136.1108	+0.8	136.1201
		S	+0.9581	-0.5					
		Mean ..	+0.9576						
*B. M. on high-service chimney, Saint Louis water-works.		N	-1.2800	-0.1	0.1		134.8397		
		S	-1.2802	+0.1					
		Mean ..	-1.2801						
*B. M. on low-service chimney, Saint Louis water-works.		N	+0.4872	-2.6	1.7		135.3243		
		S	+0.4820	+2.6					
		Mean ..	+0.4846						
*B. M. on cotton-wood tree, Saint Louis water-works.		N	-2.2877	-0.7	0.4		133.0359		
		S	-2.2890	+0.6					
		Mean ..	-2.2884						
*20-foot mark of water-gauge at Saint Louis water-works.		N	-4.2632	+0.7	0.5		132.7744		
		S	-4.2608	-0.7					
		Mean ..	-4.2615						
T. B. M. 81	66.53	S	+3.0183	-0.9	0.6		132.1706		
		N	+3.0166	+0.8					
		Mean ..	+3.0174						
T. B. M. 83	67.84	S	+4.8850	+2.2	1.5		143.0624		
		S	+4.8805	-2.3					
		Mean ..	+4.8828						
T. B. M. 85	68.66	S	+8.0580	+3.3	1.1		151.1217		
		N	+8.0615	3.2					
		S	+8.0605	-1.2					
		Mean ..	+8.0593						
T. B. M. 87	69.82	S	-18.9394	+1.0	0.6		132.1833		
		N	-18.9375	-0.9					
		Mean ..	-18.9384						
*U. S. P. B. M. 15 ..		S	+0.9093	+1.0	0.3	9.1	133.0936	+0.2	133.0938
		S	+0.9108	-0.5					
		N	+0.9109	-0.6					
		Mean ..	+0.9103						
City Directrix, Saint Louis, Mo.	70.51	S	+0.0017	1.0	0.7	9.1	132.2740	+0.2	132.2742
		N	+0.0007	+1.0					
		Mean ..	+0.0007						
*20-foot mark of water-gauge at Saint Louis, Mo.							131.1331		
T. B. M. 89	71.37	S	+0.8749	+0.9	0.6		133.1428		
		N	+0.8768	-0.8					
		Mean ..	+0.8758						
T. B. M. 92	73.17	S	+1.0174	+0.9	0.0		134.1631		
		N	+1.0192	-0.9					
		Mean ..	+1.0183						

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. R. M. 85	75.62	S	+22.8696	+0.6	0.4	157.0383	F. S.
		N	+22.8707	−0.5	
		Mean ..	+22.8702	
U. S. P. R. M. 16 ...	77.00	S	+2.3069	+0.5	0.3	9.2	159.8457	+0.4	159.8461	F. S.
		N	+2.3079	−0.6	
		Mean ..	+2.3074	
T. R. M. 100	79.90	S	−0.4785	−0.3	0.2	158.8009	F. P.
		S	−0.4790	+0.2	
		Mean ..	−0.4788	
U. S. P. R. M. 17 ...	82.43	S	−20.1856	+0.4	0.2	9.2	138.6817	+0.3	138.6820	F. P.
		S	−20.1849	−0.3	
		Mean ..	−20.1852	
T. R. M. 104	82.44	S	−0.8865	+0.2	0.1	137.7954	F. P.
		N & S...	−0.8861	−0.2	
		Mean ..	−0.8863	
B. M. 1, Holman		S	−3.2617	+1.1	0.7	134.5348	F. F.
		N	−3.2595	−1.1	
		Mean ..	−3.2606	
T. R. M. 105	83.78	S	−6.9739	−1.0	0.7	130.8205	F. P.
		N	−6.9759	+1.0	
		Mean ..	−6.9749	
T. R. M. 106	84.59	S	+29.7024	−1.3	0.9	160.5216	F. P.
		N	+29.6998	+1.3	
		Mean ..	+29.7011	
T. R. M. 109	86.73	S	−7.7744	+2.7	1.8	152.7499	F. P.
		N	−7.7690	−2.7	
		Mean ..	−7.7717	
T. R. M. 112	88.33	S	+4.0928	−2.0	1.3	156.8407	F. S.
		N	+4.0888	+2.0	
		Mean ..	+4.0908	
U. S. P. R. M. 18		S	+0.0579	+0.2	0.1	9.5	156.8988	+0.4	156.8992	F. F. P.
		N	+0.0584	−0.3	
		S	+0.0581	0.0	
B. M. 6, Holman ...	89.18	S	−24.4483	+0.1	0.0	132.8925	F. P.
		N	−24.4482	0.0	
		Mean ..	−24.4482	
T. R. M. 114	89.63	S	+1.3173	+1.6	1.0	133.7113	F. P.
		N	+1.3203	−1.5	
		Mean ..	+1.3188	
B. M. 7, Holman ...	90.90	S	+0.4811	−0.4	0.2	134.1920	S. P.
		N	+0.4804	+0.3	
		Mean ..	+0.4807	

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAFTON, ILL. TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.
B. M. 8, Holman...	91.73	S.....	+0.0021	+2.6	1.8		135.0967		
		N.....	+0.9074	-2.7					
		Mean..	+0.9047						
B. M. 9, Holman...	92.75	S.....	-1.8792	-3.8	2.6		133.7137		
		N.....	-1.3869	+1.8					
		Mean..	-1.6330						
T. B. M. 118.....	93.86				1.1		133.7340		
		Mean..							
U. S. P. B. M. 19.....		S.....			6.0	10.1	126.1947	+0.2	126.1949
		N.....							
		Mean..							
T. B. M. 119.....	94.68	S.....			1.4		131.3068		
		N.....							
		Mean..							
B. M. 10, Holman...	95.12	S.....			0.3		133.4203		
		N.....							
		Mean..							
B. M. 11, Holman...	97.10	S.....	+1.1273	+2.4	1.6		134.5589		
		N.....	+1.1321	-2.4					
		Mean..	+1.1297						
B. M. 12, Holman...	99.36	S.....	-1.8177	-3.7	2.5		132.7375		
		N.....	-1.8252	+3.8					
		Mean..	-1.8214						
U. S. P. B. M. 20.....	99.40	S.....	-1.6422	+1.2	0.9	10.7	131.0965	+0.3	131.0967
		N.....	-1.6429	+1.3					
		S.....	-1.6384	-2.6					
		Mean..	-1.6410						
T. B. M. 124.....	100.59	S.....	+2.6564	-0.2	0.1		133.1527		
		S.....	+2.6560	+0.2					
		Mean..	+2.6562						
B. M. 13, Holman...	100.93	S.....	+0.7600	+0.8	0.2		133.0139		
		N.....	+0.7615	-0.3					
		Mean..	+0.7612						
T. B. M. 125.....	101.45	S.....	-1.1589	+1.3	0.9		132.7563		
		N.....	-1.1562	-1.4					
		Mean..	-1.1576						
B. M. 14, Holman...	102.49	S.....	-0.4530	+1.8	1.2		132.8051		
		N.....	-0.4495	-1.7					
		Mean..	-0.4512						
T. B. M. 126.....	102.82	S.....	-0.2059	+0.1	0.0		132.0993		
		N.....	-0.2058	0.0					
		Mean..	-0.2058						

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
B. M. 15, Holman.	104.28	S.....	+1.0099	+4.5	1.6	133.2037	F. P. S.
		N.....	+1.1078	-3.4	
		S.....	+1.1036	-1.2	
		Mean..	+1.1044	
U. S. P. B. M. 21	104.28	S.....	-3.1576	+0.6	0.4	10.8	130.0467	+0.2	130.0469	F. P. S.
		N.....	-3.1576	+0.6	
		S.....	-3.1559	-1.1	
		Mean..	-3.1570	
T. B. M. 123	106.37	S.....	+4.0989	+4.7	2.6	135.0503	F. P. S.
		S.....	+5.0112	-7.0	
		N.....	+5.0008	+2.8	
		Mean..	+5.0036	
U. S. P. B. M. 22	107.16	S.....	-4.3616	+1.2	0.3	11.3	120.6699	+0.2	120.6901	F. S.
		N.....	-4.3598	-1.1	
		Mean..	-4.3604	
B. M. 12, Holman.	107.84	S.....	+0.9915	+0.1	0.1	131.6815	F. S.
		N.....	+0.9918	-0.9	
		Mean..	+0.9916	
B. M. 12, Holman.	108.94	S.....	+1.6970	+1.4	0.9	131.3799	F. S.
		N.....	+1.6998	-1.4	
		Mean..	+1.6984	
B. M. 20, Holman.	110.46	S.....	-2.5190	+0.8	0.6	130.6617	F. P.
		S.....	-2.5178	-0.9	
		Mean..	-2.5182	
U. S. P. B. M. 23	110.74	S.....	-1.5524	+0.8	0.6	11.4	129.3101	+0.2	129.3103	F. P.
		S.....	-1.5507	-0.9	
		Mean..	-1.5516	
T. B. M. 120	111.36	S.....	+1.6789	-0.6	0.4	130.9684	F. F.
		S.....	+1.6777	+0.6	
		Mean..	+1.6783	
B. M. 21, Holman.	112.29	S.....	+0.6414	-0.8	0.5	131.8290	F. P.
		N.....	+0.6399	+0.7	
		Mean..	+0.6406	
B. M. 22, Holman.	113.90	S.....	+0.5794	-0.6	0.4	132.4078	F. P.
		N.....	+0.5782	+0.6	
		Mean..	+0.5788	
B. M. 23, Holman.	115.46	N.....	+4.7903	-2.4	1.0	137.1957	F. P.
		N.....	+4.7855	+2.4	
		Mean..	+4.7879	
T. B. M. 133	115.67	N.....	-0.1324	+0.2	0.1	137.0635	F. P.
		N.....	-0.1321	0.1	
		Mean..	-0.1322	
U. S. P. B. M. 24	116.75	S.....	-5.3121	+0.9	0.6	11.5	131.7523	+0.2	131.7525	F. P.
		N.....	-5.3102	-1.0	
		Mean..	-5.3112	

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Change.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 134	117.62	S	-8.9026	2.5	1.0	...	122.7502	F. P.
		S	-9.0046	+2.5	F. P.
		S	-9.0021	0.0	F. P.
		Mean ..	-9.0021	F. P.
B. M. 28, Holman ..	118.25	S	+2.0595	+0.2	0.1	...	124.8009	F. P.
		S	+2.0599	-0.2	F. P.
		Mean	F. P.
T. B. M. 135	119.29	S7	...	122.4959	F. P.
		S	F. P.
		Mean ..	-2	F. P.
T. B. M. 136	120.14	S8	...	122.0847	F. P.
		S	F. P.
		N	F. P.
		Mean ..	-0.4111	F. P.
T. B. M. 138	121.06	S8	...	124.4659	F. P.
		S	F. P.
		N	F. P.
		Mean ..	+5	F. P.
T. B. M. 139	121.80	S5	...	122.9742	F. P.
		S	F. P.
		Mean ..	-0.4916	F. P.
T. B. M. 141	122.97	S	+3.8438	+4.0	1.5	...	127.8215	F. P.
		N	+3.8512	-3.9	F. P.
		S	-3.8478	0.0	F. P.
		Mean ..	+3.8473	F. P.
T. B. M. 142	123.72	S	-0.6375	-1.1	0.8	...	127.1830	F. P.
		N	-0.6398	+1.2	F. P.
		Mean ..	-0.6386	F. P.
U. S. P. B. M. 26 ...	125.22	S	-3.5437	-0.3	0.2	12.0	128.6390	+0.2	128.6392	F. P.
		N	-3.5442	+0.2	F. P.
		Mean ..	-3.5440	F. P.
B. M. 31, Holman ..	126.96	S	0.1413	-2.9	1.0	...	128.4948	F. P.
		N	-0.1471	+2.9	F. P.
		Mean ..	0.1442	F. P.
B. M. 32, Holman ..	128.00	S	-0.6353	+2.5	1.7	...	122.9620	F. P.
		N	-0.6302	-2.6	F. P.
		Mean ..	-0.6328	F. P.
T. B. M. 143	129.58	S	-2.0903	-0.3	0.2	...	120.7714	F. P.
		N	-2.0908	+0.2	F. P.
		Mean ..	-2.0906	F. P.
B. M. 33, Holman ..	130.06	S	+2.8763	-1.8	0.8	...	123.1464	F. P.
		N	+2.8738	+1.2	F. P.
		Mean ..	+2.8750	F. P.
B. M. 34, Holman ..	131.43	S	-1.3906	+2.4	1.0	...	121.7492	F. P.
		N	-1.3947	-2.5	F. P.
		Mean ..	-1.3972	F. P.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CALEO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
B. M. 35, Holman..	132.91	S	+1.0984	—1.0	0.7	122.8466	F.
		N	+1.0984	+1.0	P.
		Mean..	+1.0974							
•U. S. P. B. M. 26	+1.8112	—0.2	0.1	12.4	124.6576	+0.2	124.6578	P.
		+1.8109	+0.1	P.
		Mean..	+1.8110							
U. S. P. B. M. 27 ...	134.63	N	+3.8334	—1.2	0.8	12.4	126.6788	+0.2	126.6790	P.
		S	+3.8311	+1.1	F.
		Mean..	+3.8322							
24-foot mark of water-gauge at Rush Tower, Mo.	123.9558	
T. R. M. 153	136.81	S	—3.3630	+1.2	0.8	123.8170	F.
		S	—3.3606	—1.2	F.
		Mean..	—3.3618							
T. R. M. 156	139.82	S	+0.4072	+0.5	0.3	123.7247	F.
		S	+0.4082	—0.5	P.
		Mean..	+0.4077							
T. R. M. 157	140.75	S	—1.0716	+4.5	1.7	122.6576	F.
		N	—1.0669	—0.2	F.
		S	—1.0629	—4.2	P.
		Mean..	—1.0671							
T. R. M. 160	142.28	S	+0.8712	0.0	0.0	123.5288	F.
		N	+0.8711	+0.1	F.
		Mean..	+0.8712							
T. R. M. 163	143.85	S	—0.8113	+1.7	1.1	122.7192	F.
		N	—0.8079	—1.7	F.
		Mean..	—0.8096							
U. S. P. B. M. 28 ...	144.41	S	—1.1708	+0.2	0.2	12.6	121.5486	+0.1	121.5487	F.
		N	—1.1703	—0.3	F.
		Mean ..	—1.1706							
B. M. 40, Holman..	145.64	S	—1.7538	—1.8	2.8	119.7930	F.
		S	—1.7622	+6.6	F.
		N	—1.7508	—4.8	F.
		Mean..	—1.7556							
B. M. 41, Holman..	146.40	S	+1.4165	+1.3	0.9	121.2108	F.
		S	+1.4191	—1.3	F.
		Mean..	+1.4178							
B. M. 43, Holman..	149.72	S	—2.8154	—1.0	0.6	118.8944	F.
		N	—2.8173	+0.9	P.
		Mean..	—2.8164							
B. M. 44, Holman..	150.97	N	+1.4443	—2.5	1.6	119.8362	P.
		S	+1.4394	+2.4	F.
		Mean..	+1.4418							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAPTON, ILL. TO CAIRO, ILL.—Continued.

Reach.	Distance.	Direction.	Difference of elevations.	T.	C.	R.	Elevation.	Heat correction.	Corrected elevation.	Observed.
U. S. P. B. M. 29 ..	151.29	N	+11.2023	-1.3	0.0	13.0	131.6572	+0.2	131.6574	F. P.
		S	+11.1907	+1.3						F. P.
		Mean ..	+11.2010							
T. B. M. 167	151.06	S	-3.0674	-0.2	0.2		121.6296			F. P.
		S	-3.0679	+0.2						F. P.
		Mean ..								
B. M. 45, Holman ..	152.51	S					120.3034			F. P.
		S								F. P.
		Mean ..	-1							
T. B. M. 170	154.02	S	-1	-0.4			112.0500			F. P.
		S	-1	+0.4						F. P.
		Mean ..	-1							
B. M. 46, Holman ..	155.15	S	+1	+1.0	0.7		121.5006			F. P.
		N	+1	-1.0						F. P.
		Mean ..	+2.8087							
T. B. M. 171	165.91	S	-3.0734	-0.8	0.5		118.4024			F. P.
		N	-3.0740	+0.8						F. P.
		Mean ..	-3.0732							
U. S. P. B. M. 30 ..			+6.1930	-0.4	0.3	13.2	124.6500	+0.3	124.6571	F. P.
			+6.1931	+0.4						F. P.
		Mean ..	+6.1935							
B. M. 48, Holman ..	158.29	S	+1.5794	+2.6	1.7		120.0754			F. P.
		N	+1.5846	-2.6						F. P.
		Mean ..	+1.5820							
B. M. 50, Holman ..	160.77	S	-1.1472	+0.6	0.4		118.9208			F. P.
		N	-1.1459	-0.7						F. P.
		Mean ..	-1.1465							
U. S. P. B. M. 31 ...	161.84	S	+9.9707	+4.6	1.6	13.4	123.9041	+0.2	123.9043	F. P.
		N	+9.9764	-3.1						F. P.
		N	+9.9709	-1.6						F. P.
		Mean ..	+9.9763							
B. M. 51, Holman ..	162.16	S	-8.9848	-0.6	0.4		119.9187			F. P.
		N	-8.9800	+0.6						F. P.
		Mean ..	-8.9854							
T. B. M. 173	162.48	S	-1.5273	+0.7	0.5		118.3921			F. P.
		N	-1.5258	-0.8						F. P.
		Mean ..	-1.5265							
T. B. M. 174	162.75	S	-2.7524	-1.3	0.9		115.0384			F. P.
		N	-2.7550	+1.3						F. P.
		Mean ..	-2.7637							
T. B. M. 174½	162.80	S	+1.1607	+0.1	0.0		116.7902			F. P.
		N	+1.1608	0.0						F. P.
		Mean ..	+1.1608							

Results of precise leveling—Continued.
GRAFTON, ILL., TO CAIRO, ILL.—Continued.

bench.	Distance.	Direction.	Difference of elevation.	V.	F.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
J. Holman...	Km. 164.85	N..... S..... Mean..	M. +8.7970 +8.7941 +8.7956	Mm. -1.4 +1.5	Mm. 1.0	Mm.	M. 125.8948	Mm.	M.	P. F.
A. Holman...	165.88	N..... S..... Mean..	-1.5909 -1.5906 -1.5933	+3.1 -3.2	2.1	124.0010	P. F.
P. B. M. 32...	166.06	N..... S..... Mean..	+1.1535 +1.1537 +1.1531	-0.4 +0.4	0.3	13.7	125.1541	+0.2	125.1543	P. F.
M. 178	168.92	S..... N..... Mean..	+1.0474 +1.0479 +1.0476	+0.2 -0.3	0.2	126.2017	F. P.
P. B. M. 33 Mean..	+2.1129 +2.1137 +2.1132	+0.4 -0.5	0.3	13.7	123.3149	+0.2	123.3151	P. P.
M. 180	171.42	S..... N..... Mean..	-4.6547 -4.6432 -4.6490	+5.7 -5.8	3.3	121.5527	F. P.
P. B. M. 34	172.25	S..... N..... N..... Mean..	+1.0052 +1.7020 +1.7061 +1.7013	+5.5 -0.7 -4.8	2.0	14.3	123.2540	+0.2	123.2542	F. F. P.
M. 182	175.24	S..... N..... S..... Mean..	-0.2147 -0.2132 -0.2141 -0.2140	+0.7 -0.8 +0.1	0.3	123.0400	F. P. P.
M. 183	175.74	S..... N..... S..... Mean..	+1.4182 +1.4101 +1.4198 +1.4154	-0.8 +5.3 -4.4	1.0	124.4554	F. P. P.
B. M. 184	176.03	S..... N..... Mean..	-3.3225 -3.3237 -3.3231	-0.6 +0.6	0.4	121.1323	F. P.
B. M. 185	181.04	S..... N..... Mean..	+2.5663 +2.5749 +2.5706	+4.3 -4.3	2.9	123.7029	F. P.
S. P. B. M. 35	181.47	S..... N..... Mean..	+0.9589 +0.9583 +0.9586	-0.3 +0.3	0.2	14.7	124.6615	+0.2	124.6617	F. P.
S. P. B. M. 36 Mean..	+2.1172 +2.1166 +2.1170	-0.2 +0.2	0.1	14.7	126.7785	+0.2	126.7767	P. P.
B. M. 190	181.49	S..... N..... Mean..	-0.2277 -0.2271 -0.2274	+0.3 -0.3	0.2	124.4341	F. P.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 345	309.06	N.....	-1.0015	+0.7	0.4	103.4036	F. F.
		S.....	-1.0002	-0.6	F. F.
		Mean ..	-1.0008							
*U. S. P. B. M. 59	N.....	+15.3483	+2.0	0.7	20.8	118.7539	+0.1	118.7549	F. F.
		S.....	+15.3515	-1.2	F. F.
		S.....	+15.3512	-0.9	F. F.
		Mean ..	+15.3503							
*U. S. P. B. M. 60	N.....	-8.2528	-2.0	1.3	20.9	110.5031	+0.1	110.5032	F. F.
		S.....	-8.2488	+2.0	F. F.
		Mean ..	-8.2508							
*U. S. P. B. M. 61	S.....	+6.1278	-0.8	0.2	20.9	116.6306	+0.1	116.6307	F. F.
		N.....	+6.1272	+0.8	F. F.
		Mean ..	+6.1275							
*H. W. mark, 1858, Commerce, Mo.	107.1321			
T. B. M. 349	309.15	N.....	-0.7183	+0.1	0.1	102.6854	F. F.
		S.....	-0.7180	-0.2	F. F.
		Mean ..	-0.7182							
T. B. M. 350	309.54	S.....	+1.5212	-0.1	1.3	104.2065	F. F.
		N.....	+1.5178	+3.3	F. F.
		S.....	+1.5243	-3.2	F. F.
		Mean ..	+1.5211							
T. B. M. 351	309.66	S.....	-0.4190	+2.4	0.0	103.7899	F. F.
		N.....	-0.4163	-0.3	F. F.
		S.....	-0.4159	-0.7	F. F.
		N.....	-0.4157	-0.9	F. F.
		S.....	-0.4163	-0.3	F. F.
		Mean ..	-0.4166							
T. B. M. 353	310.06	S.....	-0.7842	-2.9	1.0	103.0028	F. F.
		N.....	-0.7888	+1.7	F. F.
		S.....	-0.7883	+1.2	F. F.
		Mean ..	-0.7871							
T. B. M. 355	310.14	S.....	+5.3542	+0.5	0.3	108.3575	F. F.
		N.....	+5.3552	-0.5	F. F.
		Mean ..	+5.3547							
*U. S. P. B. M. 62	S.....	-3.7507	+1.0	0.7	20.9	104.6078	0.0	104.6078	F. F.
		N.....	-3.7487	-1.0	F. F.
		Mean ..	-3.7497							
*U. S. P. B. M. 63	S.....	+4.1882	+0.7	0.5	20.9	108.7967	0.0	108.7967	F. F.
		N.....	+4.1896	-0.7	F. F.
		Mean ..	+4.1889							
T. B. M. 357	313.07	S.....	-1.4364	+0.6	0.4	106.9217	F. F.
		N.....	-1.4353	-0.5	F. F.
		Mean ..	-1.4358							
T. B. M. 359	314.34	S.....	-0.9348	-1.4	1.3	105.9855	F. F.
		N.....	-0.9400	+3.8	F. F.
		S.....	-0.9339	-2.3	F. F.
		Mean ..	-0.9362							

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
P. B. M. 39.....		S.....	+2.5103	−0.3	0.2	15.2	122.2671	+0.2	122.2673	F.
		N.....	+2.5096	+0.4						F.
		Mean..	+2.5100							
M. 208.....	194.69	S.....	+6.8116	−0.2	0.1		120.4908			F.
		N.....	+6.8113	+0.1						F.
		Mean..	+6.8114							
M. 209.....	195.91	S.....	−0.3889	+3.2	2.1		120.1051			F.
		N.....	−0.3795	−6.2						F.
		S.....	−0.3887	+3.0						F.
		Mean..	−0.3857							
M. 211.....	197.97	N.....	−0.9232	+4.1	2.7		119.1860			P.
		S.....	−0.9150	−4.1						P.
		Mean..	−0.9191							
M. 213.....	199.95	N.....	−0.1146	+0.6	0.4		119.0720			P.
		S.....	−0.1133	−0.7						P.
		Mean..	−0.1140							
M. 215.....	201.46	N.....	−1.2221	+0.5	0.3		117.8504			P.
		S.....	−1.2211	−0.5						F.
		Mean..	−1.2216							
S. P. B. M. 40.....		S.....	+0.2030	−1.6	1.1	15.6	118.0518	+0.1	118.0519	F.
		N.....	+0.1997	+1.7						F.
		Mean..	+0.2014							
M. 217.....	202.73	S.....	+1.8685	+2.6	1.7		119.7215			F.
		N.....	+1.8737	−2.6						F.
		Mean..	+1.8711							
M. 218.....	203.97	S.....	−1.3034	+2.4	2.1		118.4205			F.
		N.....	−1.2948	−6.2						F.
		S.....	−1.3049	+3.9						F.
		Mean..	−1.3010							
M. 219.....	204.52	S.....	+0.7416	+0.6	0.2		119.1627			F.
		N.....	+0.7424	−0.2						P.
		S.....	+0.7427	−0.5						P.
		Mean..	+0.7422							
B. M. 221.....	205.73	S.....	−0.3961	+3.1	1.1		118.7697			F.
		N.....	−0.3918	−1.2						P.
		S.....	−0.3910	−2.0						P.
		Mean..	−0.3930							
B. M. 223.....	206.93	S.....	−0.9955	+1.5	1.0		117.7757			F.
		N.....	−0.9924	−1.6						P.
		Mean..	−0.9940							
S. P. B. M. 41.....		S.....	−1.2012	+1.4	1.3	15.9	116.5759	+0.1	116.5760	F.
		N.....	−1.1944	−5.4						F.
		S.....	−1.2004	+0.6						P.
		N.....	−1.2030	+3.2						P.
		Mean..	−1.1993							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAPTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Observer.
	Kms.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 234	209.04	S	+0.8431	-1.3	0.9	116.8175	P.
		N	+0.8405	+1.8	P.
		Mean..	+0.8418	
T. B. M. 237	210.12	S	2.5950	+4.8	3.2	116.9272	P.
		N	-2.5865	-4.7	P.
		Mean..	
T. B. M. 239	212.17	S	4	117.2081	P.
		N	P.
		Mean..	
T. B. M. 242	214.53	S	+2.7	2.5	118.6543	P.
		N	-2.8	P.
		Mean..	
T. B. M. 243	214.96	S	+	+3	3	117.4064	P.
		N	+	-1	P.
		N	+	-1	P.
		Mean..	
T. B. M. 245	216.97	S	5	117.9569	P.
		N	P.
		Mean..	
T. B. M. 246	218.02	S	-1.0710	+2.2	2.5	116.2940	P.
		N	-1.0532	-2.9	P.
		N	1.0625	-0.3	P.
		N	-1.0644	+1.6	P.
		Mean..	-1.0628	
T. B. M. 248	219.07	S	-2.1197	+2.5	2.3	114.1778	P.
		N	-2.1128	-2.4	P.
		Mean..	2.1163	
T. B. M. 249	219.99	S	-0.2346	+5.5	2.3	113.9496	P.
		N	-0.2232	4.8	P.
		N	-0.2263	-1.7	P.
		Mean..	-0.2280	
T. B. M. 240	221.10	S	+2.8857	+3.1	2.1	116.8435	P.
		N	+2.8085	-4.7	P.
		N	+2.8085	4.7	P.
		N	+2.8923	+1.5	P.
		Mean..	+2.8938	
U. S. P. B. M. 43 ...	221.70	S	+2.5818	0.0	0.0	17.8	119.4254	+0.1	119.4255	P.
		N	+2.5817	+0.1	P.
		Mean..	+2.5816	
*39 ft. mark of water-gauge at Grand Eddy, Mo.				116.3140	
T. B. M. 241	222.43	N	-1.5931	+0.2	0.1	117.8325	P.
		S	-1.5927	-0.2	P.
		Mean..	-1.5929	

Results of precise leveling—Continued.

KROOK, IOWA, TO GRAFTON, ILL.

Back.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
1 P.M. 1 to U.S. Engineer's gauge on and, Kookuk, etc.		S.....	-4.7081	-4.2	2.9		150.5368	+0.2	150.5370	J. F. H.
		N.....	-4.7715	+4.2			151.7895			
		N.....	-4.9131	(t)						
		Mean ..	-4.7673							
Cont'd B.M. of Jesse Bick- my.		S.....	-0.0108	-1.8	1.4	1.4	150.5243			J. J. F. H.
		S.....	-0.0103	-2.3						
		N.....	-0.0189	+6.3						
		N.....	-0.0105	-2.1						
		Mean ..	-0.0126							
'B.M. of Cap- tain Mackenzie.	0.31	S.....	+1.5121	-4.9	1.8	1.8	158.0440			J. J. F. H.
		S.....	+1.5039	+3.3						
		N.....	+1.5016	+5.6						
		N.....	+1.5113	-4.1						
		Mean ..	+1.5072							
1 P.M. 3 ..	0.45	S.....	+0.2179	-3.3	1.8	1.8	150.7514	+0.2	150.7516	J. J. F. H.
		S.....	+0.2169	-2.0						
		N.....	+0.2066	+8.0						
		N.....	+0.2174	-2.8						
		Mean ..	+0.2140							
End of U.S. Sig- nal Service trip.		S.....	-5.3178	+9.6			151.4431			J. F.
		N.....	-5.2968	-0.5						
		Mean ..	-5.3083							
1 P.M. 4 ..	0.89	S.....	+4.6300	-1.0	0.4	1.8	161.3894	+0.2	161.3896	J. F. J.
		N.....	+4.6308	+1.2						
		S.....	+4.6382	-0.2						
		Mean ..	+4.6380							
B.M. 1 ..	2.05	S.....	4.2501	+0.8	1.4		157.1309			J. F. J.
		N.....	-4.2547	-3.8						
		S.....	-4.2016	+3.1						
		Mean ..	-4.2585							
B.M. 2 ..	2.37	S.....	-0.5248	+4.3	1.5		156.6104			J. F. J.
		N.....	-0.5102	-1.3						
		S.....	-0.5176	-2.9						
		Mean ..	-0.5205							
1 P.M. 4 ..	5.25	S.....	+1.8158	-2.1	0.8	2.9	158.4241	+0.2	158.4243	J. F. H.
		N.....	+1.8117	+2.0						
		N.....	+1.8135	+0.2						
		Mean ..	+1.8137							
B.M. 4 ..	7.50	S.....	-2.7100	-0.2	0.1		165.7139			J. F.
		N.....	-2.7103	+0.1						
		Mean ..	-2.7102							
1 P.M. 5 ..	9.10	S.....	+2.2941	+0.5	0.4	2.9	158.0085	+0.2	158.0087	J. F.
		N.....	+2.2953	-0.6						
		Mean ..	+2.2946							
B.M. 5 of Cap- tain Mackenzie.		S.....	-0.3069	0.0	0.0	2.9	157.6416			J. H.
		N.....	-0.3069	0.0						
		Mean ..	-0.3069							

† Rejected.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAYTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.
T. H. M. 3004	243.70	N	-1.0412	+0.1	0.1		115.4300		
		S	-1.0411	-0.1					
		Mean ..	-1.0412						
T. H. M. 3007	244.50	N	-8.4535	+0.4	0.3		106.9772		
		S	-8.4527	-0.4					
T. H. M. 3008	245.01				5.0		109.0003		
		Mean ..							
U. S. P. H. M. 47 ..					0.1	12.1	111.0030	+0.1	111.0021
		Mean ..							
T. H. M. 3009	245.03	N			1.2		106.9808		
		N							
		N							
		Mean ..							
T. H. M. 3011	245.70	N			0.4		106.9856		
		N							
		Mean ..	+1						
U. S. P. H. M. 48 ..	203.00	N	+1.	-2.4	2.9	12.3	110.0816	+0.1	110.0817
		S	+1.	+2.4					
		Mean ..	+1.3060						
T. H. M. 3014	202.04	N	-3.4783	-1.9	1.3		106.5514		
		N	-3.4821	+1.9					
		Mean ..	-3.4802						
T. H. M. 3015	202.00	N ..	-0.5078	+0.4	1.1		106.9870		
		N ..	-0.5028	-1.0					
		N ..	0.5027	-1.7					
		Mean ..	0.5044						
T. H. M. 3016	202.00	N ..	+2.8704	-0.8	0.5		108.9656		
		N ..	+2.8778	+0.8					
		Mean ..	+2.8790						
U. S. P. H. M. 49 ..	200.00	N ..	+1.0158	0.4	0.3	10.4	110.2010	+0.1	110.2011
		N ..	+1.0200	+0.0					
		Mean ..	+1.0154						
T. H. M. 3018	200.18	S ..	3.7123	-0.0	0.4		106.4582		
		N ..	-3.7134	+0.0					
		Mean ..	-3.7128						
T. H. M. 2021	201.03	S	+5.8008	+2.3	1.5		112.2912		
		N	+5.8004	-2.3					
		Mean ..	+5.8031						
T. H. M. 2022	201.20	S	-0.0784	+2.8	1.1		112.2152		
		N	-0.0728	-2.8					
		N	-0.0771	+1.0					
		Mean ..	-0.0761						

Results of precise leveling—Continued.

GRAPTON, ILL., TO CAIRO, ILL.—Continued.

Reach.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
P. R. M. 50	264.06	S.....	-1.9892	-0.4	0.3	19.5	110.2256	+0.1	110.2257	F. P.
		N.....	-1.9901	+0.3						F. P.
		Mean..	-1.9896							
M. 287	265.17	S.....	-3.0334	-4.6	1.7		107.1876			F. P.
		N.....	-3.0389	+0.6						F. P.
		N.....	-3.0419	+2.9						F. P.
		Mean..	-3.0380							
M. 289	265.54	S.....	-0.2684	+2.6	1.7		106.9218			F. P.
		N.....	-0.2682	-2.6						F. P.
		Mean..	-0.2658							
M. 291	268.49	S.....	-1.8695	-5.9	4.0		105.0484			F. P.
		N.....	-1.8614	+6.6						F. P.
		Mean..	-1.8754							
M. 293	270.00	S.....	-0.7045	-3.4	1.2		104.8385			F. P.
		N.....	-0.7108	+2.9						F. P.
		S.....	-0.7084	+0.5						F. P.
		Mean..	-0.7079							
M. 295	270.16	S.....	+0.7342	-0.3	0.4		105.0725			F. P.
		N.....	+0.7349	-0.9						F. P.
		S.....	+0.7329	+1.1						F. P.
		Mean..	+0.7340							
P. R. M. 51	270.79	S.....	+4.0609	+0.7	0.5	20.1	109.1341	0.0	109.1341	F. P.
		N.....	+4.0624	-0.3						F. P.
		Mean..	+4.0610							
M. 298	271.64	S.....	+2.6249	-0.5	0.3		111.7585			F. P.
		N.....	+2.6240	+0.4						F. P.
		Mean..	+2.6244							
M. 299	272.68	S.....	+1.7080	0.0	0.0		112.5565			F. P.
		N.....	+1.7081	-0.1						F. P.
		Mean..	+1.7080							
M. 301	273.30	S.....	-1.8182	-0.1	0.1		111.7382			F. P.
		N.....	-1.8184	+0.1						F. P.
		Mean..	-1.8183							
S. M. 302 1/2	274.06	S.....	-1.4306	-1.2	0.8		110.3064			F. P.
		N.....	-1.4320	+1.1						F. P.
		Mean..	-1.4318							
S. M. 303	274.79	S.....	-0.2885	-4.1	1.5		110.0138			F. P.
		N.....	-0.2930	+0.4						F. P.
		S.....	-0.2963	+3.7						F. P.
		Mean..	-0.2926							
S. P. R. M. 52	275.49	S.....	+0.5587	+1.8	1.2	20.2	110.5743	+0.1	110.5744	F. P.
		N.....	+0.5623	-1.8						F. P.
		Mean..	+0.5605							
M. M. 305	276.46	S.....	-2.6277	+2.8	1.0		107.9484			F. P.
		N.....	-2.6231	-2.6						F. P.
		Mean..	-2.6249							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
T. B. M. 26	Kw. 52.16	S	M. +0.8658	Mm. -0.8	Mm. 0.5	Mm.	M. 151.2506	Mm.	M.	J. F.
		N	+0.8643	+0.7						
		Mean..	+0.8650							
T. B. M. 27	53.72	S	+0.3691	+0.8	0.2	151.6290	J. F.
		N	+0.3697	-0.8						
		Mean..	+0.3694							
T. B. M. 28	56.47	S	-0.9717	+0.1	0.0	150.6574	J. F.
		N	-0.9716	0.0						
		Mean..	-0.9716							
T. B. M. 29	58.12	S	+0.0508	+1.0	0.7	150.7182	J. F.
		N	+0.0618	-1.0						
		Mean..	+0.0608							
U. S. P. B. M. 12 ...	60.57	N	+0.9949	+5.5	1.5	5.7	151.7186	+0.1	151.7187	F. J. J. F.
		S	+0.9997	+0.7						
		S	+1.0050	-5.5						
		N	+1.0011	-0.7						
		Mean..	+1.0004							
*P. B. M. 57 of Capt. Mackenzie.	60.55	S	-0.1712				151.5474			J.
*P. B. M. 59 of Capt. Mackenzie.	60.57	N	-0.1725				151.5461			F.
T. B. M. 31	62.04	S	-1.0519	+0.8	0.5	150.6675	J. F.
		N	-1.0503	-0.8						
		Mean..	-1.0511							
T. B. M. 32	63.81	S	+0.4306	+0.6	0.4	151.0987	J. F.
		N	+0.4317	-0.6						
		Mean..	+0.4312							
T. B. M. 33	65.82	S	-1.0042	+0.4	0.8	5.7	150.0949	J. F.
		N	-1.0033	-0.6						
		Mean..	-1.0038							
U. S. P. B. M. 13 ...	67.18	S	+1.8197	-0.1	0.1	151.9145	+0.1	151.9146	J. F.
		N	+1.8195	+0.1						
		Mean..	+1.8196							
T. B. M. 35	70.76	S	-2.3169	-0.4	0.8	149.5972	J. F.
		N	-2.3177	+0.4						
		Mean..	-2.3173							
U. S. P. B. M. 14 ...	71.84	S	+1.2115	-2.3	1.5	5.9	150.8064	+0.1	150.8065	J. F.
		N	+1.2069	+2.3						
		Mean..	+1.2092							
T. B. M. 37	74.12	S	-1.5722	+2.8	1.9	149.2370	J. F.
		N	-1.5666	-2.8						
		Mean..	-1.5694							
T. B. M. 38	75.90	S	-0.7520	-2.3	1.5	148.4827	J. F.
		N	-0.7566	+2.3						
		Mean..	-0.7543							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 54	97.53	S	—0.5377	+0.9	0.6	147.4344	J.
		N	—0.5359	—0.9	F.
		Mean ..	—0.5368							
T. B. M. 56	100.73	S	—0.9690	—0.4	0.3	146.4650	J.
		N	—0.9698	+0.4	F.
		Mean ..	—0.9694							
U. S. P. B. M. 18 ...	102.04	S	+0.9168	—1.8	1.2	7.4	147.3800	+0.1	147.3801	J.
		N	+0.9131	+1.9	F.
		Mean ..	+0.9150							
T. B. M. 59	104.69	S	—0.0033	—1.7	1.1	147.3750	J.
		N	—0.0067	+1.7	F.
		Mean ..	—0.0050							
T. B. M. 60	106.33	S	+0.1227	(†)	0.4	147.5083	J.
		N	+0.1339	—0.6	F.
		S	+0.1322	+1.1	J.
		N	+0.1339	—0.6	F.
		Mean ..	+0.1333							
T. B. M. 63	108.41	S	—0.0055	+3.3	2.2	147.5061	J.
		N	+0.0012	—3.4	F.
		Mean ..	—0.0022							
T. B. M. 64	109.73	S	—0.0031	+0.4	1.2	147.5034	J.
		N	+0.0032	—5.9	F.
		S	—0.0042	+1.5	S.
		N	—0.0072	+4.5	R.
		N	—0.0020	—0.7	F.
		Mean ..	—0.0027							
*U. S. P. B. M. 19 ...	110.65	S	+4.2446	+1.6	1.1	7.9	151.7496	+0.1	151.7497	J.
		N	+4.2479	—1.7	F.
		Mean ..	+4.2462							
T. B. M. 65	110.46	S	+0.6272	+1.0	0.6	148.1316	J.
		N	+0.6291	—0.9	F.
		Mean ..	+0.6282							
T. B. M. 66	112.86	S	—2.0781	+0.1	0.1	146.0536	J.
		N	—2.0779	—0.1	F.
		Mean ..	—2.0780							
T. B. M. 67	115.61	S	+4.1836	—1.1	0.7	150.2361	J.
		N	+4.1814	+1.1	F.
		Mean ..	+4.1825							
*U. S. P. B. M. 20 ...	115.73	S	+0.3403	—0.3	0.2	7.9	150.5761	+0.1	150.5762	J.
		N	+0.3396	+0.4	F.
		Mean ..	+0.3400							
T. B. M. 68	116.38	S	—0.8351	—1.4	0.9	149.8096	J.
		N	—0.8379	+1.4	F.
		Mean ..	—0.8365							

† Rejected.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevations.	W.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. R. M. 70	119.02	S	-4.1408	-4.8	1.8		145.2540			J. F.
		N	-4.1502	+4.6						J. F.
		S	-4.1458	+0.2						
		Mean ..	-4.1456							
T. R. M. 73	122.70	S	+1.3550	-0.9	0.6		145.6190			J. F.
		N	+1.3640	+1.0						J. F.
		Mean ..	+1.3550							
*T. & P. R. M. 21 ..	122.00	S	-1.4127	-0.9	0.6	8.2	145.2054	+0.1	145.2065	J. F.
		N	-1.4145	+0.9						J. F.
		Mean ..	-1.4136							
T. R. M. 75	126.51	S	-1.2050	+1.0	0.7		145.4150			J. F.
		N	-1.2030	-1.0						J. F.
		Mean ..	-1.2040							
T. R. M. 76	129.02	S	+2.6030	-0.8	0.6		148.0172			J. F.
		N	+2.6013	+0.9						J. F.
		Mean ..	+2.6022							
*T. & P. R. M. 22 ..	129.04	S	+0.9030			8.2	148.9802	+0.1	148.9803	J.
T. R. M. 79	130.26	S	+0.2980	-0.7	0.6		148.3154			J. F.
		N	+0.2974	+0.8						J. F.
		Mean ..	+0.2982							
T. & P. R. M. 23 ..	132.30	S	+0.6582	-1.8	1.2	8.3	148.9718	+0.1	148.9719	J. F.
		N	+0.6547	+1.7						J. F.
		Mean ..	+0.6564							
*P. R. M. 51, Mac-	131.39	S	-1.9095	+1.0	0.7	8.4	147.0633			J. F.
kenzie.		N	+1.9076	-1.0						J. F.
		Mean ..	-1.9085							
*H. W. 1851, at	131.86	N	-2.8545				146.1172			F.
Louisiana, Mo.										
*H. W. 1880, at	132.26	N	-4.3271				144.8447			F.
Louisiana, Mo.										
*H. W. 1881 (April),	132.26	N	-4.0681				144.9037			F.
Louisiana, Mo.										
T. & P. R. M. 24 ..	133.74	S	-0.2803	-0.9	0.6	8.4	148.0908	+0.1	148.0907	J. F.
		N	-0.2821	+0.9						J. F.
		Mean ..	-0.2812							
*H. W. 1881 (April)	132.42	N	-4.0285				144.9433			F.
Louisiana, Mo.										
*H. W. 1880, Lou-	132.42	N	-4.3252				144.8456			F.
isiana, Mo.										
*H. W. April 26,		N	-4.0678				144.9228			F.
1881, Louisiana,										
Mo.										
*Zero of gauge on	134.05		-9.2708	-11.4	5.7		139.4312			F.
bridge at Loui-			-9.2537	+5.7						J.
siana, Mo.		Mean ..	-9.2594							
T. R. M. 82	136.00	S	-3.9939	+0.3	0.2		144.6970			J. F.
		N	-3.9934	-0.2						J. F.
		Mean ..	-3.9936							

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M
T. B. M. 308	278.04	S	+0.8636	+0.5	0.3	108.6134
		N	+0.8644	-0.4
		Mean ..	+0.8640
T. B. M. 309	279.11	S	+0.2051	+3.6	1.8	109.0231
		N	+0.2117	-3.0
		N	+0.2094	-0.7
		Mean
T. B. M. 311	279.80	N	0.0	110.8192
		S
		Mean ..	+1.1
T. B. M. 314	281.89	S	-1	1.1	108.7160
		N	-1
		Mean ..	-1.6032
U. S. P. B. M. 53 ..	285.34	N	+0.0515	-3.5	2.2	20.5	108.7640	0.0	108.7640
		S	+0.0445	+3.5
		Mean ..	+0.0480
T. B. M. 318	285.61	S	+2.5516	0.2	0.1	111.3153
		N	+2.5511	+0.2
		Mean ..	+2.5513
T. B. M. 320	286.83	S	-0.7217	-0.5	0.4	110.8991
		N	-0.7228	+0.6
		Mean ..	-0.7222
T. B. M. 321	287.74	S	+0.0083	+2.8	1.0	110.6042
		N	+0.0128	1.7
		S	+0.0123	1.2
		Mean ..	+0.0111
U. S. P. B. M. 54 ...	288.51	S	+1.1415	+3.7	1.3	30.5	111.7494	+0.1	111.7495
		N	+1.1464	-1.2
		N	+1.1477	3.5
		Mean ..	+1.1452
*H. W. mark July, 1844.	+0.2050	112.0149
		+0.2000
		Mean ..	+0.2055
U. S. P. B. M. 55 ..	289.41	S	+3.0238	+0.2	0.1	20.5	114.7729	+0.1	114.7730
		N	+3.0237	-0.2
		Mean ..	+3.0235
U. S. P. B. M. 56	290.71	S	-7.6481	-0.1	0.1	20.5	107.1247	0.0	107.1247
		N	-7.6484	+0.2
		Mean ..	-7.6482
T. B. M. 324	291.22	S	+2.0458	+0.6	0.4	109.1711
		N	+2.0471	-0.7
		Mean ..	+2.0464
T. B. M. 326	292.93	N	-0.5109	+0.6	0.4	108.6608
		S	-0.5097	-0.6
		Mean ..	-0.5108

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
T. B. M. 228	Km. 294.14	N..... S..... Mean ..	M. -0.4683 -0.4689 -0.4691	Mm. -0.8 +0.8	Mm. 0.5	Mm.	M. 108.1917	Min.	M.	F. F.
U. S. P. B. M. 57 ...	297.49	S..... N..... Mean ..	+2.7111 +2.7166 +2.7138	+2.7 -2.8	1.8	20.6	110.9055	+0.1	110.9066	F. F.
T. B. M. 231½	297.86	N..... S..... Mean ..	-8.6692 -8.6690 -8.6691	+0.1 -0.1	0.1	102.2364	F. F.
Shot mark of upper gauge at Gray's Point, Mo. Mean ..	-1.8066 -1.8031 -1.8048	100.4316	F. F.
T. B. M. 232	299.05	N..... S..... S..... Mean ..	-1.7321 -1.7417 -1.7376 -1.7371	-5.0 +4.6 +0.5	1.9	100.4993	F. F. F.
U. S. B. M. 74 (Old B. M.)	299.37	S..... N..... Mean ..	+2.0451 +2.0459 +2.0455	+0.4 -0.4	0.3	20.7	102.5448	0.0	102.5448	F. F.
H. W. mark, July, 1844, at Gray's Point, Mo. Mean ..	+8.7797 +8.7788 +8.7792	111.3240	F. F.
T. B. M. 234	300.53	S..... N..... Mean ..	+5.2311 +5.2298 +5.2304	-0.7 +0.6	0.4	107.7752	F. F.
T. B. M. 235	301.66	S..... N..... Mean ..	+0.1470 +0.1458 +0.1464	-0.6 +0.6	0.4	107.9216	F. F.
T. B. M. 238	304.16	S..... N..... Mean ..	+1.7995 +1.8029 +1.8012	+1.7 -1.7	1.1	109.7228	F. F.
U. S. P. B. M. 58 ...	305.24	S..... N..... Mean ..	+0.9547 +0.9542 +0.9544	-0.3 +0.2	0.2	20.8	110.6772	+0.1	110.6773	F. F.
T. B. M. 240	306.18	N..... S..... Mean ..	-2.4323 -2.4301 -2.4312	+1.1 -1.1	0.7	108.2460	F. F.
T. B. M. 242	307.32	N..... S..... N..... Mean ..	-0.3806 -0.3850 -0.3795 -0.3817	-1.1 +3.3 -2.2	1.1	107.8643	F. F. F.
T. B. M. 243	308.10	S..... N..... Mean ..	-3.4597 -3.4601 -3.4599	-0.2 +0.2	0.1	104.4044	F. F.

Results of precise leveling—Continued.

KROOK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 85	128.59	S	+2.1509	-1.6	1.1		147.8522			J. F.
		N	+2.1537	+1.6						
		Mean..	+2.1553							
U. S. P. B. M. 25 ...	140.02	S	-0.5688	-0.8	0.6		147.2827	+0.1	147.2828	J. F.
		N	-0.5705	+0.9						
		Mean..	-0.5696							
T. B. M. 87	141.07	S	-1.3650	+0.4	0.2		145.9181			J. F.
		N	-1.3643	-0.3						
		Mean..	-1.3646							
T. B. M. 88	142.29	S	+0.0446	-5.0	1.2		145.9577			J. F.
		N	+0.0376	+2.0						J. F.
		S	+0.0394	+0.2						J. F.
		N	+0.0366	+3.0						
		Mean..	+0.0396							
*U. S. P. B. M. 26 ...	143.64	S	+0.6903	-0.9	0.6	8.6	146.6471	+0.1	146.6472	J. F.
		N	+0.6884	+1.0						
		Mean..	+0.6894							
T. B. M. 89	144.08	S	-2.3480	-1.6	1.1		143.6081			J. F.
		N	-2.3512	+1.6						
		Mean..	-2.3496							
T. B. M. 91	145.68	S	-0.6939	-1.1	0.7		142.9131			J. F.
		N	-0.6960	+1.0						
		Mean..	-0.6950							
T. B. M. 92	147.02	S	+0.0963	-1.8	1.2		143.0076			J. F.
		N	+0.0927	+1.8						
		Mean..	+0.0945							
T. B. M. 94	147.95	S	+4.4392	-2.3	0.7		147.4445			J. F.
		N	+4.4346	+2.3						J. F.
		S	+4.4360	+0.9						J. F.
		N	+4.4379	-1.0						
		Mean..	+4.4369							
*U. S. P. B. M. 27 ...	148.07	S	+0.5737	0.0	0.0	8.8	148.0182	+0.1	148.0183	J. F.
		N	+0.5737	0.0						
		Mean..	+0.5737							
T. B. M. 95	148.93	S	-1.0499	+0.1	0.1		146.3947			J. F.
		N	-1.0497	-0.1						
		Mean..	-1.0498							
*U. S. P. B. M. 28 ...	149.07	S	+0.1658	+0.4	0.3	8.8	146.5609	+0.1	146.5610	J. F.
		N	+0.1666	-0.4						
		Mean..	+0.1662							
*H. W. 1876, Clarksville, Mo.	149.15	N	-3.4625				142.9322			F.
*H. W. 1851, Clarksville, Mo.	149.13	S	-1.5284				144.8663			J.
Rod station 1, Clarksville, Mo.	148.98	S	-3.7384	-0.4	0.3		142.6550			J. F.
		N	-3.7392	+0.4						
		Mean..	-3.7388							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	v.	B.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Am.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
Red station 2, Island 452.	149.58		+0.0771 +0.0783	-0.5 +0.4	0.3		142.7325			J. F.
		Mean	+0.0766							
Red station 3	149.80	S	+0.0777	-0.5	0.3		142.8097			J. F.
		N	+0.0768	+0.4						
		Mean	+0.0772							
Red station 4	150.46		-0.7212 -0.7190	+1.1 -1.1	0.7		142.0696			J. F.
		Mean	-0.7201							
Red station 5	150.73		+0.8106 +0.8126	+1.0 -1.0	0.7		142.9012			J. F.
		Mean	+0.8116							
T & P. R. M. 29	150.83	S	-0.0161	-0.7	0.5	8.8	142.8844	+0.0	142.8844	J. F.
		N	-0.0175	+0.7						
		Mean	-0.0168							
T. R. M. 97	152.75	S	-0.2629	+0.9	0.6		142.6393			J. F.
		N	-0.2612	-0.8						
		Mean	-0.2620							
T. R. M. 99	153.15	S	+1.2067	0.0	0.0		142.8479			J. F.
		N	+1.2087	0.0						
		Mean	+1.2087							
T. S. P. R. M. 30	155.60	S	-0.9795	-3.3	0.2	8.8	142.8681	0.0	142.8681	J. F.
		N	-0.9801	+0.3						
		Mean	-0.9798							
T. R. M. 101	157.80	S	-2.2617	-2.4	1.6		141.5838			J. F.
		N	-2.2685	+2.4						
		Mean	-2.2641							
T. R. M. 102	159.76	S	+1.2608	-0.8	0.6		142.8498			J. F.
		N	+1.2651	+0.9						
		Mean	+1.2600							
U. S. P. R. M. 31	161.16	S	-0.8302	-0.4	0.2	9.0	142.0102	0.0	142.0102	J. F.
		N	-0.8399	+0.3						
		Mean	-0.8398							
T. R. M. 104	162.18	S	-0.9919	-0.9	0.6		141.0174			J. F.
		N	-0.9936	+0.8						
		Mean	-0.9928							
T. R. M. 106	165.62	S	+0.3240	+2.1	1.4		141.3435			J. F.
		N	+0.3282	-2.1						
		Mean	+0.3261							
U. S. P. R. M. 32	165.96	S	+7.2578	-1.4	0.9	9.2	148.5909	+0.1	148.6000	J. F.
		N	+7.2551	+1.3						
		Mean	+7.2564							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

GRAFTON, ILL., TO CAIRO, ILL.—Continued.

	Distance.	Direction.	Difference of elevation.	V.	r.	H.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 335	333.13	S	+0.6551	+1.1	0.7		102.0641			F.
		N	+0.6572	-1.0						F.
		Mean ..	+0.6562							
T. B. M. 337	333.42	S	-0.2534	+2.4	1.6		102.8121			F.
		N	-0.2486	-2.4						F.
		Mean ..	-0.2510							
T. B. M. 338	340.51	S	-1.2920	+3.8	1.6		101.6240			F.
		N	-1.2849	-4.2						F.
		N	-1.2896	+0.5						F.
		Mean ..	-1.2891							
*T. B. M. 338½	340.97	S	+1.0554	+0.7	0.5		101.6271			F.
		N	+1.0568	-0.7						F.
		Mean ..	+1.0501							
*U. S. P. B. M. 66 ..	341.46	N	-1.1030	+0.6	0.4	21.5	101.4777	0.0	101.4777	B.
		S	-1.1010	-0.5						B.
		Mean ..	-1.1024							
T. B. M. 339	341.94	S	-0.0876	+2.8	1.1		101.4392			F.
		N	-0.0822	-3.6						F.
		N	-0.0845	-0.3						F.
		Mean ..	-0.0848							
T. B. M. 331	342.07	S	-0.7814	-3.4	2.9		102.6494			B.
		N	-0.7952	+5.4						B.
		S	-0.7928	+3.0						B.
		Mean ..	-0.7898							
B. M. 65 (old B. M.)	344.64	S	+1.2974	-1.2	0.8		101.9456			B.
		N	+1.2950	+1.2						P.
		Mean ..	+1.2962							
U. S. P. B. M. 2, Cairo, Ill.	344.88	S	+1.4601	-1.0	0.7	21.7	103.4047	0.0	103.4047	B.
		S	+1.4581	+1.0						B.
		Mean ..	+1.4591							
U. S. P. B. M. 1, Cairo, Ill.	345.23	S	-0.4015	-2.7	1.8	21.8	103.0005	0.0	103.0005	B.
		S	-0.4068	+2.6						B.
		Mean ..	-0.4042							
U. S. P. B. M. 3, Cairo, Ill.	345.63	S	+2.8234	+0.7	0.5	21.8	105.8246	0.0	105.8246	F.
		N	+2.8246	-0.7						F.
		Mean ..	+2.8241							
45-foot mark of water gauge, Cairo, Ill.		S	-3.4546	+0.4	0.3		102.3764			F.
		N	-3.4538	-0.4						F.
		Mean ..	-3.4542							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
U.S.P.B.M. 1							156.5368	+0.2	156.5370	
•Zero U.S. Engineer's gauge on canal, Keokuk, Iowa.		S	−4.7631	−4.2	2.8		151.7695			J.
		N	−4.7715	+4.2						F.
		N	−4.9131	(†)						F.
		Mean	−4.7673							
•“Canal” B.M. of Captain Stickney.		S	−0.0108	−1.8	1.4	1.4	156.5242			J.
		S	−0.0103	−2.8						J.
		N	−0.0189	+6.8						F.
		N	−0.0105	−2.1						F.
		Mean	−0.0126							
•P.B.M. 52 of Captain Mackenzie.	0.31	S	+1.5121	−4.9	1.8	1.8	158.0440			J.
		S	+1.5039	+3.8						J.
		N	+1.5016	+5.6						F.
		N	+1.5113	−4.1						F.
		Mean	+1.5072							
U.S.P.B.M. 2	0.45	S	+0.2179	−3.8	1.8	1.8	156.7514	+0.2	156.7516	J.
		S	+0.2166	−2.0						J.
		N	+0.2066	+8.0						F.
		N	+0.2174	−2.8						F.
		Mean	+0.2146							
•Zero of U.S. Signal Service gauge.		S	−5.3178	+9.5			151.4431			J.
		N	−5.2988	−9.5						F.
		Mean	−5.3083							
C.S.P.B.M. 3	0.60	S	+4.6390	−1.0	0.4	1.8	161.3894	+0.2	161.3896	J.
		N	+4.6308	+1.2						F.
		S	+4.6382	−0.2						J.
		Mean	+4.6390							
T.B.M. 1	2.05	S	−4.2591	+0.6	1.4		157.1309			J.
		N	−4.2547	−3.8						F.
		S	−4.2616	+3.1						J.
		Mean	−4.2585							
T.B.M. 2	2.37	S	−0.5248	+4.3	1.5		156.6104			J.
		N	−0.5192	−1.8						F.
		S	−0.5176	−2.9						J.
		Mean	−0.5205							
U.S.P.B.M. 4	5.35	S	+1.8158	−2.1	0.8	2.9	158.4241	+0.2	158.4243	J.
		N	+1.8117	+2.0						F.
		N	+1.8135	+0.2						F.
		Mean	+1.8137							
T.B.M. 4	7.59	S	−2.7100	−0.2	0.1		155.7139			J.
		N	−2.7103	+0.1						F.
		Mean	−2.7102							
U.S.P.B.M. 5	9.19	S	+2.2941	+0.5	0.4	2.9	158.0065	+0.2	158.0067	J.
		N	+2.2952	−0.6						F.
		Mean	+2.2946							
•P.B.M. 53 of Captain Mackenzie.		S	−0.3669	0.0	0.0	2.9	157.6416			J.
		N	−0.3669	0.0						F.
		Mean	−0.3669							

† Rejected.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KNOX, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	P.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.		Mm.	M.	
T. B. M. 6	10.87	S	-2.7041	-0.1	0.0		155.8043			J. W.
		N	-2.7042	0.0						J. W.
		Mean ..	-2.7042							
T. B. M. 7	13.74	S	+0.0407	+2.5	1.7		155.8475			J. W.
		N	+0.0457	-2.5						J. W.
		Mean ..	+0.0432							
T. B. M. 8	15.68	S	-0.1265	-3.0	2.0	3.9	155.8180			J. W.
		N	-0.1225	+3.0						J. W.
		Mean ..	-0.1295							
T. B. M. 10	16.77	S	-0.3650	+0.4	0.2		154.8534			J. W.
		N	-0.3643	-0.2						J. W.
		Mean ..	-0.3646							
P. B. M. 54 of Captain Mackenzie.	19.45	S	-0.8687	-1.3	0.9	4.0	153.9854			J. W.
		N	-0.8694	+1.4						J. W.
		Mean ..	-0.8690							
* H. W. Apr., 1881, at Gregory Ldg.	19.60	N	+1.1620				155.1474			J. W.
* U. S. P. B. M. 6	19.97	S	+0.7838	-0.2	0.1	4.0		+0.2	154.7600	J. W.
		N	+0.7832	+0.2						J. W.
		Mean ..	+0.7834							
T. B. M. 11	21.70	S	+0.1007	-3.6	1.7		154.0630			J. W.
		N	+0.0985	+2.6						J. W.
		Mean ..	+0.0981							
T. B. M. 12	24.19	S	-0.5573	+1.9	1.3		153.5243			J. W.
		N	-0.5611	-1.9						J. W.
		Mean ..	-0.5592							
T. B. M. 13	26.50	S	+0.0472	+0.2	0.1		153.5717			J. W.
		N	+0.0476	-0.2						J. W.
		Mean ..	+0.0474							
U. S. P. B. M. 7	28.13	S	+3.6614	+1.6	1.1	4.7	157.2347	+0.2	157.2349	J. W.
		N	+3.6646	-1.6						J. W.
		Mean ..	+3.6630							
T. B. M. 15	30.94	S	-0.3452	+2.0	1.3		156.8915			J. W.
		N	-0.3412	-2.0						J. W.
		Mean ..	-0.3432							
T. B. M. 16	32.21	S	-3.9274	0.0	0.0		152.9641			J. W.
		N	-3.9274	0.0						J. W.
		Mean ..	-3.9274							
T. B. M. 17	33.86	S	+0.8802	+0.2	0.1		153.8245			J. W.
		N	+0.8806	-0.2						J. W.
		Mean ..	+0.8804							
* H. W. 1844, 1½ miles above Canton, Mo.		S	-0.3000				153.5245			J. W.
* H. W. 1851, 1½ miles above Canton, Mo.		S	+0.5700				154.1945			J. W.

Results of precise leveling—Continued.

KNOX, IOWA, TO GRANTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevations.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
B. M. 12	34.30	S	-0.8500	+2.4	1.3		152.9890			J.
		N	-0.8530	-5.5						F.
		S	-0.8505	+1.0						J.
		N	-0.8007	+2.2						F.
		Mean	-0.8585							
B. P. B. M. 9	37.34	S	+2.8201	-0.7	0.5	5.1	150.7854	+0.2	150.7850	J.
		N	+2.8187	+0.7						F.
		Mean	+2.8194							
B. P. B. M. 9	37.33	S	-0.2000	+0.2	0.1	5.1	150.5847	+0.2	150.5849	J.
		N	-0.2005	-0.2						F.
		Mean	-0.2007							
B. M. 12	38.37	S	-0.1098	-0.4	0.3		152.7658			J.
		N	-0.2005	+0.4						F.
		Mean	-0.2003							
B. M. 20	40.67	S	+0.3848	+0.1	0.1	5.0	153.1507			J.
		N	+0.3856	-0.1						F.
		Mean	+0.3849							
B. M. 21	42.46	S	-0.6062	+0.7	0.5		152.5452			J.
		N	-0.6048	-0.7						F.
		Mean	-0.6055							
B. P. B. M. 10	44.06	S	+1.0656	+1.1	0.7	5.1	153.6119	+0.1	153.6120	J.
		N	+1.0678	-1.1						F.
		Mean	+1.0667							
B. M. 56 of Captain Mackenzie.	46.38	N	-1.4532	+1.8	1.2		152.1005			F.
		S	-1.4496	-1.8						J.
		Mean	-1.4514							
U. S. P. B. M. 11	46.98	S	+1.4188	-0.2	0.1	5.2	153.5791	+0.1	153.5792	F.
		S	+1.4184	+0.2						F.
		Mean	+1.4186							
H. W. April, 1861, at La Grange, Mo.			+0.1072	-0.2	0.2		152.2875			F.
			+0.1067	+0.2						J.
		Mean	+0.1070							
H. W. 1851, (?) at La Grange, Mo.			+1.5075	-4.1			153.6636			F.
			+1.4903	+13.1						J.
			+1.5123	-8.9						J.
		Mean	+1.5034							
B. M. 23	47.80	S	-0.0617	-1.3	1.0		152.0970			J.
		N	-0.0678	+4.3						F.
		S	-0.0612	-2.3						J.
		N	-0.0632	-0.3						F.
		Mean	-0.0625							
B. M. 25	50.14	S	-1.7030	+0.6	0.6		150.3945			J.
		N	-1.7014	-0.6						F.
		S	-1.7046	+2.2						J.
		N	-1.7001	-2.2						F.
		Mean	-1.7024							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KROOK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
T. B. M. 26	Kw. 52.15	S	M. +0.8658	Mm. -0.8	Mm. 0.5	Mm.	M. 151.2596	Mm.		J. F.
		N	+0.8643	+0.7						F.
		Mean..	+0.8650							
T. B. M. 27	53.72	S	+0.3691	+0.8	0.2		151.6200			J. F.
		N	+0.3697	-0.8						F.
		Mean..	+0.3694							
T. B. M. 28	56.47	S	-0.9717	+0.1	0.6		150.6574			J. F.
		N	-0.9716	0.0						F.
		Mean..	-0.9716							
T. B. M. 29	58.12	S	+0.0599	+1.0	0.7					J. F.
		N	+0.0618	-1.0						F.
		Mean..	+0.0608							
U. S. P. B. M. 12 ...	60.67	N	+0.9849	+5.5	1.5	5.7	151.7186	+0.1	151.7187	J. F.
		S	+0.9897	+0.7						J. F.
		S	+1.0059	-5.5						J. F.
		N	+1.0011	-0.7						F.
		Mean..	+1.0004							
*P. B. M. 57 of Capt. Mackenzie.	60.55	S	-0.1712				151.5474			J.
*P. B. M. 59 of Capt. Mackenzie.	60.57	N	-0.1725				151.5451			F.
T. B. M. 31	62.04	S	-1.0519	+0.8	0.5		150.6675			J. F.
		N	-1.0503	-0.8						F.
		Mean..	-1.0511							
T. B. M. 32	63.81	S	+0.4308	+0.6	0.4		151.0967			J. F.
		N	+0.4317	-0.5						F.
		Mean..	+0.4312							
T. B. M. 33	65.62	S	-1.0042	+0.4	0.3	5.7	150.0949			J. F.
		N	-1.0033	-0.5						F.
		Mean..	-1.0038							
U. S. P. B. M. 13 ..	67.18	S	+1.8197	-0.1	0.1		151.9145	+0.1	151.9146	J. F.
		N	+1.8195	+0.1						F.
		Mean..	+1.8196							
T. B. M. 35	70.76	S	-2.3189	-0.4	0.3		149.5972			J. F.
		N	-2.3177	+0.4						F.
		Mean..	-2.3173							
U. S. P. B. M. 14 ...	71.64	S	+1.2115	-2.3	1.5	5.9	150.8064	+0.1	150.8065	J. F.
		N	+1.2069	+2.3						F.
		Mean..	+1.2092							
T. B. M. 37	74.12	S	-1.5722	+2.8	1.9		149.2270			J. F.
		N	-1.5666	-2.8						F.
		Mean..	-1.5694							
T. B. M. 38	75.90	S	-0.7520	-2.3	1.5		148.4827			J. F.
		N	-0.7566	+2.3						F.
		Mean..	-0.7543							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Station.	Distance.	Direction.	Difference of elevation.	V.	r.	B.	Elevation.	Red correction.	Corrected elevation.	Observer.
	Km.		m.	Mm.	Mm.	Mm.	M.	Mm.		
T. R. M. 39	77.80	S	+0.0084	0.0	0.0	148.4921	J. F.
		N	+0.0085	-0.1	F.
		Mean..	+0.0084	
T. R. M. 40	79.49	S	+0.2576	-3.4	2.2	148.7482	J. F.
		N	+0.2509	+3.3	F.
		Mean..	+0.2542	
U. S. P. R. M. 15	80.90	S	+1.0065	-2.1	1.4	6.9	149.7507	+0.1	149.7508	J. F.
		N	+1.0023	+2.1	F.
		Mean..	+1.0044	
T. R. M. 41	84.13	S	-0.2368	+0.2	0.1	149.5141	J. F.
		N	-0.2365	-0.1	F.
		Mean..	-0.2366	
T. R. M. 47	86.95	S	-0.7815	+1.3	0.9	148.7339	J. F.
		N	-0.7788	-1.4	F.
		Mean..	-0.7802	
• U. S. P. R. M. 16	88.97	S	+6.5296	+1.4	0.9	7.0	155.2049	+0.2	155.2051	J. F.
		N	+6.5323	-1.3	F.
		Mean..	+6.5310	
T. R. M. 48	S	+4.0618	+1.1	0.7	152.7968	J. F.
		N	+4.0640	-1.1	F.
		Mean..	+4.0629	
• P. R. M. 50 of Capt. Mackenzie.	89.90	S	+0.0037	-0.1	0.1	7.0	152.8004	J. F.
		N	+0.0034	+0.2	F.
		Mean..	+0.0036	
• H. W. 1881, at Hannibal Bridge.	89.90	-3.6321	148.9047	F.
• Zero of upper gauge at Hannibal Bridge.	89.12	-0.6481	143.1487	F.
• Zero of gauge on draw pier of Hannibal Bridge.	89.12	-0.6261	143.1707	F.
T. R. M. 49	90.86	S	-4.4287	+2.1	1.0	148.3680	J. F.
		N	-4.4338	+3.0	F.
		S	-4.4290	-0.9	J.
		Mean..	-4.4308	
• H. W., 1881, at Hannibal, Mo.	90.20	S	+1.3648	+2.8	1.9	149.7236	J. F.
		N	+1.3005	-2.9	F.
		Mean..	+1.3576	
• H. W., 1881, at Hannibal, Mo.	90.25	+0.5584	148.9244	J.
U. S. P. R. M. 17	92.81	S	-0.5664	+1.3	7.1	147.8008	+0.1	147.8009	J. F.
		N	-0.5640	-1.2	F.
		Mean..	-0.5652	
T. R. M. 53	94.31	S	+0.1685	+1.9	1.3	147.9712	J. F.
		N	+0.1724	-2.0	F.
		Mean..	+0.1704	

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 54	97.63	S	-0.5877	+0.9	0.6		147.4344			J. F.
		N	-0.5350	-0.9						J. F.
		Mean ..	-0.5308							
T. B. M. 55	100.73	S	-0.9090	-0.4	0.8		148.4650			J. F.
		N	-0.9098	+0.4						J. F.
		Mean ..	-0.9094							
U. S. P. B. M. 18 ..	102.04	S			2	7.4	147.3800	+0.1	147.3801	J. F.
		N								J. F.
		Mean ..	+0.0150							
T. B. M. 56	104.00	S	-0.0033	-1.7	1.1		147.2750			J. F.
		N	-0.0067	+1.7						J. F.
		Mean ..	-0.0050							
T. B. M. 59	106.83	S	+0.1227	(†)	0.4		147.5083			J. F.
		N	+0.1389	-0.6						J. F.
		S	+0.1322	+1.1						J. F.
		N	+0.1830	-0.6						J. F.
		Mean ..	+0.1338							
T. B. M. 63	108.41	S	-0.0055	+3.3	2.2		147.5081			J. F.
		N	+0.0012	-3.4						J. F.
		Mean ..	-0.0022							
T. B. M. 64	109.73	S	-0.0081	+0.4	1.2		147.5034			J. F.
		N	+0.0032	-5.9						J. F.
		S	-0.0042	+1.5						J. F.
		N	-0.0072	+4.5						J. F.
		N	-0.0020	-0.7						J. F.
		Mean ..	-0.0027							
*U. S. P. B. M. 19	110.05	S	+4.2446	+1.6	1.1	7.9	151.7496	+0.1	151.7497	J. F.
		N	+4.2479	-1.7						J. F.
		Mean ..	+4.2462							
T. B. M. 65	110.48	S	+0.0272	+1.0	0.6		148.1310			J. F.
		N	+0.0291	-0.9						J. F.
		Mean ..	+0.0282							
T. B. M. 66	112.86	S	-2.0781	+0.1	0.1		146.9536			J. F.
		N	2.0779	0.1						J. F.
		Mean ..	-2.0780							
T. B. M. 67	115.01	S	+4.1836	-1.1	0.7		150.2861			J. F.
		N	+4.1814	+1.1						J. F.
		Mean ..	+4.1825							
*U. S. P. B. M. 20	115.73	S	+0.3403	-0.3	0.2	7.9	150.5761	+0.1	150.5762	J. F.
		N	+0.3396	+0.4						J. F.
		Mean ..	+0.3400							
T. B. M. 68	116.28	S	-0.8351	-1.4	0.9		149.3090			J. F.
		N	-0.8379	+1.4						J. F.
		Mean ..	-0.8365							

† Rejected.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON ILL.—Continued.

Bench.	Distance.	Line.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
T. R. M. 70	112.67	S	-4.1408	-4.6	1.8	Min.	145.2540	Min.		J. F.
		N	-4.1502	+4.6						J.
		S	-4.1456	+0.2						J.
		Mean ..	-4.1456							
T. R. M. 70	112.29	S	+1.3639	-0.9	0.6		145.6190			J. F.
		N	+1.3640	+1.0						J.
		Mean ..	+1.3650							
*C. S. P. R. M. 31 ..	112.08	S	-1.4127	-0.9	0.6	8.2	145.2054	+0.1	145.2055	J. F.
		N	-1.4145	+0.9						J.
		Mean ..	-1.4136							
T. R. M. 75	112.61	S	-1.2050	+1.0	0.7		145.4150			J. F.
		N	-1.2030	-1.0						J.
		Mean ..	-1.2040							
T. R. M. 73	112.02	S	+2.6040	-0.8	0.6		145.0172			J. F.
		N	+2.6013	+0.9						J.
		Mean ..	+2.6022							
*C. S. P. R. M. 22 ..	112.04	S	+0.9630			8.2	145.9802	+0.1	145.9803	J.
T. R. M. 79	112.26	S	+0.2980	-0.7	0.5		145.8154			J. F.
		N	+0.2974	+0.8						J.
		Mean ..	+0.2982							
U. S. P. R. M. 21 ..	112.30	S	+0.6582	-1.8	1.2	8.2	145.9718	+0.1	145.9719	J. F.
		N	+0.6547	+1.7						J.
		Mean ..	+0.6564							
*P. R. M. 61, Mac- bride.	111.30	S	-1.9005	+1.0	0.7	8.4	147.0633			J. F.
		N	+1.9075	-1.0						J.
		Mean ..	-1.9085							
*H. W. 1851, at Louisiana, Mo.	111.68	N	-2.8545				146.1173			F.
*H. W. 1880, at Louisiana, Mo.	111.28	N	-4.3771				144.8447			F.
*H. W. 1861 (April), Louisiana, Mo.	112.26	N	-4.0681				144.9037			F.
C. S. P. R. M. 24 ..	112.74	S	-0.2808	-0.9	0.6	8.4	145.0906	+0.1	145.0907	J. F.
		N	-0.2821	+0.9						J.
		Mean ..	-0.2813							
*H. W. 1861 (April) Louisiana, Mo.	112.42	N	-4.0285				144.8423			F.
*H. W. 1880, Lou- isiana, Mo.	112.42	N	-4.3252				144.8406			F.
*H. W. April 25, 1861, Louisiana, Mo.		N	-4.0678				144.8223			F.
*Zero of gauge on bridge at Loui- siana, Mo.	114.05		-0.2709	-11.4	5.7		139.4312			F. J.
			-0.2537	+5.7						
		Mean ..	-0.2594							
T. R. M. 83	110.00	S	-2.9089	+0.8	0.2		144.9870			J. F.
		N	-2.9034	-0.2						J.
		Mean ..	-2.9066							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 85	139.50	S	+3.1509	-1.6	1.1		147.8523			J. F.
		N	+3.1537	+1.6						J. F.
		Mean..	+3.1553							
U. S. P. B. M. 25 ..	140.02	S	-0.5688	-0.8	0.6		147.2827	+0.1	147.2828	J. F.
		N	-0.5705	+0.8						J. F.
		Mean..	-0.5697							
T. B. M. 87	141.07	S			1.2		145.9181			J. F.
		N								J. F.
		Mean..								
T. B. M. 88	142.29	S			1.2		145.9577			J. F.
		N								J. F.
		Mean..								J. F.
*U. S. P. B. M. 26 ..	143.64	S	+0		1.6	8.6	146.6471	+0.1	146.6472	J. F.
		N	+0							J. F.
		Mean..	+0							
T. B. M. 89	144.06	S			1.1		143.6081			J. F.
		N								J. F.
		Mean..								
T. B. M. 91	145.69	S	-0.6930	-1.1	0.7		142.9181			J. F.
		N	-0.6900	+1.0						J. F.
		Mean..	-0.6950							
T. B. M. 92	147.02	S	+0.6983	-1.8	1.2		143.0076			J. F.
		N	+0.6927	+1.8						J. F.
		Mean..	+0.6945							
T. B. M. 94	147.95	S	+4.4392	-2.3	0.7		147.4445			J. F.
		N	+4.4346	+2.3						J. F.
		S	+4.4360	+0.9						J. F.
		N	+4.4379	-1.0						J. F.
		Mean..	+4.4369							
*U. S. P. B. M. 27 ..	148.07	S	+0.5737	0.0	0.0	8.5	148.0183	+0.1	148.0183	J. F.
		N	+0.5737	0.0						J. F.
		Mean..	+0.5737							
T. B. M. 95	148.93	S	-1.0499	+0.1	0.1		146.3947			J. F.
		N	-1.0497	-0.1						J. F.
		Mean..	-1.0498							
*U. S. P. B. M. 28 ..	149.07	S	+0.1658	+0.4	0.3	8.8	146.5609	+0.1	146.5610	J. F.
		N	+0.1666	-0.4						J. F.
		Mean..	+0.1662							
*H. W. 1876, Clarksville, Mo.	149.15	N	-3.4025				142.9322			J. F.
*H. W. 1851, Clarksville, Mo.	149.13	S	-1.5284				144.8683			J. F.
Rod station 1, Clarksville, Mo.	149.96	S	-3.7384	-0.4	0.3		142.6559			J. F.
		N	-3.7392	+0.4						J. F.
		Mean..	-3.7388							

Results of precise leveling—Continued.**KNOX, IOWA, TO GRAFTON, ILL.—Continued.**

Bench.	Distance.	Direction.	Difference of elevations.	V.	v.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
Red station 2, Island 453.	149.58		M. +0.0771 +0.0762	Mm. -0.5 +0.4	Mm. 0.8		M. 142.7825	Mm.	M.	J. F.
		Mean..	+0.0766							
Red station 3	149.80	S	+0.0777	-0.5	0.8		142.8097			J. F.
		N	+0.0769	+0.4						
		Mean ..	+0.0772							
Red station 4	150.46		-0.7212 -0.7190	+2.1 -1.1	0.7		142.0896			J. F.
		Mean ..	-0.7201							
Red station 5.	150.72		+0.8106 +0.8126	+1.0 -1.0	0.7		142.8011			J. F.
		Mean..	+0.8116							
T. S. P. B. M. 29 ..	150.83	S	-0.0161	-0.7	0.5	8.8	142.8844	+0.0	142.8844	J. F.
		N	-0.0175	+0.7						
		Mean..	-0.0168							
T. B. M. 97	152.75	S ...	-0.2629	+0.8	0.6		142.6392			J. F.
		N	-0.2612	-0.8						
		Mean ..	-0.2620							
T. B. M. 99	153.15	S	+ 1.2087	0.0	0.0		142.8011			J. F.
		N	+ 1.2087	0.0						
		Mean ..	+ 1.2087							
T. S. P. B. M. 30 ..	153.60	S	- 0.9795	-0.3	0.2	8.8	142.8881	0.0	142.8881	J. F.
		N	- 0.9801	+0.3						
		Mean..	- 0.9798							
T. B. M. 101	157.80	S	- 2.2617	-2.4	1.6		141.5838			J. F.
		N	- 2.2605	+2.4						
		Mean..	- 2.2611							
T. B. M. 102	159.76	S	+ 1.2668	-0.8	0.6		142.8498			J. F.
		N	+ 1.2651	+0.9						
		Mean ..	+ 1.2660							
U. S. P. B. M. 31 ..	161.18	S ...	- 0.8392	-0.4	0.2	9.0	142.0102	0.0	142.0102	J. F.
		N	- 0.8399	+0.3						
		Mean ..	- 0.8398							
T. B. M. 104	162.18	S	- 0.9919	-0.9	0.6		141.0174			J. F.
		N	- 0.9936	+0.8						
		Mean ..	- 0.9928							
T. B. M. 106	165.62	S	+ 0.3240	+2.1	1.4		141.2435			J. F.
		N	+ 0.3282	-2.1						
		Mean ..	+ 0.3261							
U. S. P. B. M. 32 ..	165.96	S	+ 7.2578	-1.4	0.9	9.2	143.8099	+0.1	143.8000	J. F.
		N	+ 7.2551	+1.3						
		Mean..	+ 7.2564							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise levelling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 108	167.64	S.	7.8388	-0.1	0.1		140.7610			J. F.
		N.	7.8380	+0.1						
		Mean ..	7.8389							
T. B. M. 109	168.93	S.	+2.4512	-3.3	1.1		143.2090			J. F.
		N.	+2.4458	+2.5						J. F.
		S.	+2.4474	+0.6						J. F.
		Mean ..	+							
U. S. P. B. M. 33 ...	170.24	S.	+1	6	3	2.2	133.0370	+0.3	133.0372	J. F.
		N.	+1	6						J. F.
		Mean ..	+10.8280							
T. B. M. 111	171.62	S.	-21.3869	-0.1	0.0		141.6500			J. F.
		N.	-21.3870	0.0						J. F.
		Mean ..	-21.3870							
T. B. M. 112	174.58	S.	-1.3173	+1.3	0.8		140.3340			J. F.
		N.	-1.3148	-1.3						J. F.
		Mean ..	-1.3160							
T. B. M. 114	175.74	S.	+2.9823	-1.7	1.1		142.3148			J. F.
		N.	+2.9789	+1.7						J. F.
		Mean ..	+2.9806							
*H. W., 1876, at Hamburg, Ill.	175.08	S.	-2.0093				141.3153			J.
*H. W., April, 1881, at Hamburg, Ill.	175.08	S.	-2.8126				141.0010			J.
*U. S. P. B. M. 34	175.84	S.	-1.0244	+0.8	0.5	9.4	141.6910	0.0	141.6910	J. F.
		N.	-1.0228	-0.8						J. F.
		Mean ..	-1.0236							
T. B. M. 115	176.76	S.	+4.0688	-1.0	0.7		148.2834			J. F.
		N.	+4.0677	+1.1						J. F.
		Mean ..	+4.0688							
T. B. M. 116	177.85	S.	-0.8379	+1.8	1.2		138.4473			J. F.
		N.	-0.8343	-1.8						J. F.
		Mean ..	-0.8361							
U. S. P. B. M. 35	180.63	S.	+1.4701	-2.3	1.6	9.6	139.9151	0.0	139.9151	J. F.
		N.	+1.4654	+2.4						J. F.
		Mean ..	+1.4678							
T. B. M. 119	181.60	S.	+0.4750	-0.8	0.6		140.3893			J. F.
		N.	+0.4724	+1.0						J. F.
		N.	+0.4751	-0.9						J. F.
		Mean ..	+0.4742							
U. S. P. B. M. 36	182.96	S.	-0.7301	+1.2	0.8	9.6	139.6604	0.0	139.6604	J. F.
		N.	-0.7277	-1.2						J. F.
		Mean ..	-0.7289							
T. B. M. 120	186.24	S.	-1.0281	-1.1	0.7		138.6912			J. F.
		N.	-1.0303	+1.1						J. F.
		Mean ..	-1.0292							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 134	187.28	S.	+ 0.6818	-4.4	1.0	139.8086	J. F.
		N.	+ 0.6753	+2.1	J. F.
		S.	+ 0.6767	+0.7	J. F.
		N.	+ 0.6760	+1.4	J. F.
		Mean..	+ 0.6774							
U. S. P. B. M. 37 ...	187.92	S.	+ 0.2593	+0.9	0.6	9.7	139.5688	0.0	139.5688	F. F.
		N.	+ 0.2612	-1.0	F. F.
		Mean..	+ 0.2602							
T. B. M. 125	189.28	S.	- 1.1051	-2.5	1.7	138.4612	J. F.
		N.	- 1.1102	+2.6	J. F.
		Mean..	- 1.1076							
T. B. M. 126	189.99	S.	- 0.1387	+0.5	0.3	138.3230	J. F.
		N.	- 0.1377	-0.5	J. F.
		Mean..	- 0.1382							
T. B. M. 127	191.95	S.	- 0.4808	-0.6	0.4	137.8416	J. F.
		N.	- 0.4820	+0.6	J. F.
		Mean..	- 0.4814							
T. B. M. 128	192.72	S.	+ 5.7191	-0.2	0.1	143.5605	J. F.
		N.	+ 5.7187	+0.2	J. F.
		Mean..	+ 5.7189							
T. B. M. 129	194.10	S.	- 5.2789	+0.1	0.1	138.2817	J. F.
		N.	- 5.2786	-0.2	J. F.
		Mean..	- 5.2788							
U. S. P. B. M. 38 ...	195.45	S.	+ 0.4248	+0.4	0.3	9.9	138.7069	0.0	138.7069	J. F.
		N.	+ 0.4256	-0.4	J. F.
		Mean..	+ 0.4252							
T. B. M. 130	196.95	S.	+ 0.2804	-2.2	1.5	138.9851	J. F.
		N.	+ 0.2760	+2.2	J. F.
		Mean..	+ 0.2782							
U. S. P. B. M. 39 ...	196.97	S.	+ 0.5897	-0.1	0.1	10.0	139.5747	0.0	139.5747	J. F.
		N.	+ 0.5895	+0.1	J. F.
		Mean..	+ 0.5896							
T. B. M. 131	197.93	S.	+ 0.8111	-1.3	0.9	139.7949	J. F.
		N.	+ 0.8084	+1.3	J. F.
		Mean..	+ 0.8098							
T. B. M. 132	200.00	S.	- 1.1569	+0.3	0.2	138.6383	J. F.
		N.	- 1.1562	-0.4	J. F.
		Mean..	- 1.1566							
U. S. P. B. M. 40 ...	200.51	S.	- 0.0020	-1.2	0.8	10.1	138.6351	0.0	138.6351	J. F.
		N.	- 0.0043	+1.1	J. F.
		Mean..	- 0.0032							
T. B. M. 133	201.87	S.	- 0.6435	+0.9	0.6	137.9925	J. F.
		N.	- 0.6417	-0.9	J. F.
		Mean..	- 0.6426							

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued

Bench.	Distance.	Direction.	Difference of elevation.	V	r.	R.	Elevation.	Red correction.	Corrected elevation.	Observer.
	Fms.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. R. M. 135	204.91	S	- 0.8927	-1.5	1.0		137.0093			J. F.
		N	- 0.8958	+1.4						F.
		Mean ..	- 0.8042							
T. R. M. 136	205.93	S	+ 4.2970	-4.8	1.1		141.3005			J. F.
		N	+ 4.2800	+2.2						F.
		N	+ 4.2003	+1.9						J.
		S	+ 4.2913	+0.9						
		Mean ..	+ 4.2022							
U. S. P. R. M. 41 ..	206.04	S	+ 0.5742	+0.4	0.3	10.2	141.9051	0.0	141.9051	J. F.
		N	+ 0.5750	-0.4						F.
		Mean ..	+ 0.5746							
T. R. M. 137	206.74	S	- 6.8958	-0.1	0.1		134.4948			J. F.
		N	- 6.8060	+0.1						F.
		Mean ..	- 6.8950							
T. R. M. 138	207.02	S	+ 4.2674	-2.0	1.0		138.7501			J. F.
		N	+ 4.2620	+1.6						F.
		S	+ 4.2031	+1.4						J.
		Mean ..	+ 4.2645							
T. R. M. 139	209.24	S	- 1.4616	+1.2	0.8		137.2787			J. F.
		N	- 1.4792	-1.2						F.
		Mean ..	- 1.4804							
T. R. M. 140	209.98	S	-2.5327	-3.9	0.9		134.7421			J. F.
		N	-2.5370	+1.0						F.
		S	-2.5381	+1.5						J.
		N	-2.5382	+1.0						F.
		Mean ..	-2.5366							
U. S. P. R. M. 42 ..	210.09	S	+ 0.3458	+0.4	0.3	10.2	141.0863	0.0	141.0863	F. F.
		N	+ 0.3446	-0.4						F.
		Mean ..	+ 0.3442							
T. R. M. 141	211.52	S	+ 0.1215	-3.9	1.2		134.8508			J. F.
		N	+ 0.1133	+4.4						F.
		S	+ 0.1187	-1.0						J.
		N	+ 0.1174	+0.3						F.
		Mean ..	+ 0.1177							
T. R. M. 141½	212.41	S	-0.8184	-3.9	0.8		134.0381			J. F.
		N	-0.8234	+1.7						F.
		N	-0.8229	+1.2						J.
		S	-0.8220	+0.3						J.
		Mean ..	-0.8217							
T. R. M. 143	214.52	S	+ 3.3567	-1.7	1.1		137.3931			J. F.
		N	+ 3.3534	+1.6						F.
		Mean ..	+ 3.3550							
U. S. P. R. M. 43 ..	214.53	S	+ 1.5071	+0.1	0.0	10.5	138.9003	0.0	138.9003	J. F.
		N	+ 1.5072	0.0						F.
		Mean ..	+ 1.5072							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 145	217.02	S	-2.7711	-0.5	0.8	133.6215	J. F.
		N	-2.7721	+0.5	
		Mean ..	-2.7716	
T. B. M. 146	217.53	S	+2.6297	-0.1	0.1	136.2511	J. F.
		N	+2.6294	+0.2	
		Mean ..	+2.6296	
U. S. F. B. M. 44 ..	217.54	S	+2.5244	0.0	0.0	10.5	138.7755	0.0	138.7755	J. F.
		N	+2.5245	0.1	
		Mean ..	+2.5244	
T. B. M. 149	218.65	S	-0.2916	0.0	0.0	135.9395	J. F.
		N	-0.2915	-0.1	
		Mean ..	-0.2916	
T. B. M. 150	222.16	S	-0.3725	-0.7	0.4	135.5969	J. F.
		N	-0.3738	+0.6	
		Mean ..	-0.3732	
T. B. M. 151	222.46	S	-0.1989	-0.3	0.2	135.3871	J. F.
		N	-0.1993	+0.3	
		Mean ..	-0.1992	
U. S. F. B. M. 45 ..	222.60	S	+1.6279	-0.1	0.0	10.5	137.0149	0.0	137.0149	J. F.
		N	+1.6278	0.0	
		Mean ..	+1.6278	
T. B. M. 152	224.47	S	-0.2608	+0.8	0.6	135.1271	J. F.
		N	-0.2591	-0.9	
		Mean ..	-0.2600	
T. B. M. 153	224.85	S	-1.8767	+2.3	1.5	131.2497	J. F.
		N	-1.8751	-2.3	
		Mean ..	-1.8774	
U. S. F. B. M. 46 ..	226.84	S	+11.4218	-0.1	0.1	10.6	144.6714	+0.1	144.6715	J. J.
		N	+11.4216	+0.1	
		Mean ..	+11.4217	
T. B. M. 155	229.14	S	+0.6094	-1.0	0.7	132.8581	J. F.
		N	+0.6074	+1.0	
		Mean ..	+0.6084	
T. B. M. 156	230.23	S	+3.5679	+2.1	1.4	137.4281	J. F.
		N	+3.5720	-2.0	
		Mean ..	+3.5700	
U. S. F. B. M. 47 ..	230.24	S	+0.4071	+0.3	0.2	10.7	137.8355	0.0	137.8355	J. F.
		N	+0.4078	-0.4	
		Mean ..	+0.4074	
T. B. M. 157	231.62	S	-1.1733	-2.9	1.9	136.2519	J. F.
		N	-1.1791	+2.9	
		Mean ..	-1.1762	
W. W., spring of 1892.	231.69	-0.6074	135.6445	F.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO GRAFTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 158	233.88	S.	-0.6812	+2.0	1.3	135.5027	J.
		N.	-0.6572	-2.0	F.
		Mean..	-0.6592	
T. B. M. 160	234.10	S.	+0.8102	-0.2	0.2	136.4027	J.
		N.	+0.8097	+0.3	F.
		Mean..	
T. B. M. 161	237.21	S.	2.5	123.7233	J.
		N.	R.
		Mean..	-1.87	
U. S. P. B. M. 1 (Grafton).	239.29	S.	+1	2.0	11.2	124.5085	0.0	124.5085	J.
		N.	+1	F.
		Mean..	+0.7802	
Red Station 1....	239.49	S.	-3.5792	-0.6	130.9237	J.
		N.	-3.5606	+0.8	F.
		S.	-3.5787	-1.1	R.
		N.	-3.5608	+1.0	
		Mean..	-3.5793	
Red Station 2 (crossing Illi- nois River).	239.85	S.	+0.0927	-4.3	2.7	131.0121	J.
		N.	+0.0628	+5.6	F.
		N.	+0.0806	+7.8	F.
		S.	+0.0976	-9.2	F.
		Mean..	+0.0684	
U. S. P. B. M. 2 (Grafton).	240.03	S.	+5.3498	+0.1	0.1	11.5	124.8020	0.0	124.8020	J.
		N.	+5.3500	-0.1	R.
		Mean..	+5.3499	
*H. W., April, 1881	241.36	-0.0425	132.3193	F.
U. S. P. B. M. 3 (Grafton).	242.17	S.	+2.9592	-0.6	0.4	11.5	+139.8116	F.
		N.	+2.9491	+0.5	R.
		Mean..	+2.9490	
*P. B. M. 86 of Cap- tain Mackenzie. Referred to Mackenzie B. M.	S.	-4.7040	+0.2	0.2	134.7258	F.
		N.	-4.7035	-0.3	F.
		Mean..	-4.7038	

Elevation, Mackenzie B. M., 139.4266. See page —.

[The elevation of U. S. P. B. M. 3, as given on page —, is taken as the initial elevation for all points north of Grafton. This bench-mark is on the Catholic church steps, and is believed to be more like to have remained undisturbed than U. S. P. B. M.'s 1 and 2, which are stone posts set in the ground. The discrepancy between the determinations of difference of elevations of U. S. P. B. M. 1 and 3, was in 1880 and 1881, is 6.6^{mm}, that of 1881 being the larger.

Results of precise leveling—Continued.

KROOK, IOWA, TO FULTON, ILL.—Continued.

Lev.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	P.	F.
TRM 10 and 96a	132.22	N.....	-0.0056	-1.4	0.9		169.5484			P.	F.
		S.....	-0.0084	+1.4						P.	F.
		Mean..	-0.0070								
TRM 11	133.37	N.....	+1.1632	-0.4	0.3		170.7062			P.	F.
		S.....	+1.1624	+0.4						P.	F.
		Mean..	+1.1628								
TRM 12	134.64	N.....	-0.5868	-0.6	0.4		170.1160			P.	J.
		S.....	-0.5877	+0.6						P.	J.
		Mean..	-0.5873								
TRM 13	135.45	N.....	-0.6478	+0.9	0.6		169.4721			P.	J.
		S.....	-0.6460	-0.9						P.	J.
		Mean..	-0.6469								
TRM 14	136.03	N.....	-0.2514	+2.0	0.6		169.2227			P.	F.
		S.....	-0.2470	-2.4						P.	F.
		N.....	-0.2492	-0.1						P.	F.
		S.....	-0.2501	+0.7						P.	F.
		Mean..	-0.2494								
TRM 15	136.18	N.....	-0.3069	-0.6	0.4		169.9158			P.	F.
		S.....	-0.3060	+0.6						P.	F.
		Mean..	-0.3074								
TRM 16	136.42	N.....	+0.0031	-0.2	0.1		169.9182			P.	J.
		S.....	+0.0027	+0.2						P.	J.
		Mean..	+0.0029								
TRM 16	136.76	N.....	-0.0307	+0.4	0.3		169.9178			(*)	J.
		S.....	+0.0290								J.
		N.....	-0.0212	-0.5							F.
		S.....	+0.0214								F.
		Mean..	-0.0004								
TRM 16	136.80	N.....	+2.1153	+4.0	1.1		171.0371			P.	J.
		S.....	+2.1231	-3.6						P.	J.
		N.....	+2.1168	+0.5						P.	J.
		S.....	+2.1199	-0.6						P.	J.
		Mean..	+2.1193								
TRM 17 and Mason's R. M. 5	138.63	S.....	+1.2687	+0.1	0.0	7.7	172.3069	+0.5	172.3074		J.
		S.....	+1.2696	0.0							F.
		Mean..	+1.2696								
TRM 17	139.61	N.....	-1.1292	+4.3	1.0		169.9121			P.	J.
		S.....	-1.1232	-1.8						P.	J.
		N.....	-1.1250	0.0						P.	F.
		S.....	-1.1228	-2.2						P.	F.
		Mean..	-1.1250								
TRM 18 and Ma	141.24	N.....	-0.6700	+0.4	0.2		169.2425			P.	F.
		S.....	-0.6693	-0.3						P.	F.
		Mean..	-0.6696								
TRM 18	142.86	N.....	+1.0217	-0.1	0.0		170.2641			P.	F.
		S.....	+1.0216	0.0						P.	F.
		Mean..	+1.0216								

* River crossing.

2524 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KNOX, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Support.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
*H. W. Mark, 1881, Port Louisa, Iowa.	141.86	S	+1.0536				171.8177			P.
T. B. M. 110.....	144.03	N	+0.8250	-2.9	1.1		170.5862			P.
		S	+0.8194	+2.7						P.
		N	+0.8218	+0.3						P.
		Mean..	+0.8221							
T. B. M. 111.....	145.71	N	+0.8340	-0.5	0.3		170.9397			P.
		S	+0.8530	+0.5						P.
		Mean..	+0.8535							
T. B. M. 112.....	146.30	N	-0.8593	-1.3	1.2		170.5786			P.
		S	-0.8629	+1.3						P.
		Mean..	-0.8611							
T. B. M. 113.....	146.98	N	+0.4048	+0.1	0.1		170.9825			P.
		S	+0.4050	-0.1						P.
		Mean..	+0.4049							
T. B. M. 114 and 114a.	147.81	N	+1.3335	-1.5	1.0		172.2165			P.
		S	+1.3306	+1.4						P.
		Mean..	+1.3320							
T. B. M. 115.....	148.80	N	+0.2448	-3.2	1.1		172.5571			P.
		S	+0.2398	+1.3						P.
		N	+0.2401	+1.6						P.
		Mean..	+0.2416							
T. B. M. 116.....	149.82	N	-1.0220	-0.8	0.4		171.5845			P.
		S	-1.0231	+0.6						P.
		Mean..	-1.0226							
T. B. M. 117.....	150.72	N	+0.0247	-1.1	0.7		171.5381			P.
		S	+0.0225	+1.1						P.
		Mean..	+0.0236							
*U. S. P. B. M. 25	150.85	S	+0.4415	+0.3	0.6	3.1	172.0006	+4.6	172.0010	P.
		N	+0.4434	-1.0						P.
		Mean..	+0.4424							
*H. W. Mark, June, 1880.	150.85	N	+0.3606				171.5187			
*H. W. Mark, 1851	150.90	N	+0.0010				172.0015			
*H. W. Mark, Oct., 1881.	150.90	N	-0.0157				171.9848			
T. B. M. 118.....	151.65	N	+1.5861	+1.0	1.3		172.1461			P.
		S	+1.5899	-1.0						P.
		Mean..	+1.5880							
*U. S. P. B. M. 26	151.68	N	+0.1078			3.2	172.2539	+0.5	172.2544	
T. B. M. 119.....	152.95	N	-1.8469	-0.5	0.3		171.2987			P.
		S	-1.8478	+0.4						P.
		Mean..	-1.8474							
T. B. M. 120 and 120a.	154.62	N	+0.0604	-0.6	0.4		172.2785			P.
		S	+0.0791	+0.7						P.
		Mean..	+0.0798							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Line.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red. correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.		
M. 14 and 15a	30.42	S.	+5.7398	+1.4	0.9		177.1123			P.	J.
		N.	+5.7426	-1.4						P.	J.
		Mean ..	+5.7412								
M. 15 and 16a	31.91	S.	-5.9833	-1.8	1.3		171.1271			P.	J.
		N.	-5.9870	+1.9						P.	J.
		Mean ..	-5.9851								
L.M. 20	32.64	S.	-1.2307	-0.6	0.4		159.9058			P.	J.
		N.	-1.2319	+0.6						P.	J.
		Mean ..	-1.2313								
L.M. 21	35.32	N.	-1.1248	+0.5	0.3		169.7815			P.	F.
		S.	-1.1239	-0.4						P.	F.
		Mean ..	-1.1243								
L.M. 22	36.87	N.	-2.5940	-1.4			169.1861			P.	F.
		S.	-2.5908	+1.4						P.	F.
		Mean ..	-2.5954								
L.M. 23	38.66	S.	-0.0346	-0.7	0.5		169.1806			P.	F.
		N.	-0.0360	+0.7						P.	F.
		Mean ..	-0.0358								
L.S.P.M. 7	39.68	N.	+2.8397	+0.1	0.1	3.6	169.9906	+0.4	169.9910	P.	J.
		S.	+2.8400	-0.2						P.	F.
		Mean ..	+2.8398								
L.M. 25	39.50	N.	-2.7120	-0.3	0.2		169.2763			P.	J.
		S.	-2.7126	+0.3						P.	F.
		Mean ..	-2.7123								
L.S.P.M. 8	39.57	N.	+4.2845	-0.4	0.2	2.9	170.5624	+0.4	170.5628	P.	J.
		S.	+4.2838	+0.3						P.	F.
		Mean ..	+4.2841								
L.M. 26	40.29	N.	-1.4030	-0.2	0.2		164.8751			P.	F.
		S.	-1.4035	+0.3						P.	F.
		Mean ..	-1.4032								
L.M. 27 and 27a	41.00	N.	+0.6605	+1.9	1.3		165.5375			P.	F.
		S.	+0.6644	-2.0						P.	F.
		Mean ..	+0.6624								
L.M. 28	42.23	N.	+5.8031	0.0	0.0		170.8406			P.	F.
		S.	+5.8032	-0.1						P.	F.
		Mean ..	+5.8031								
L.M. 29 and 29a	44.87	N.	-5.8617	+2.2	0.6		165.4811			P.	J.
		N.	-5.8605	+1.0						P.	J.
		S.	-5.8552	-4.8						P.	J.
		S.	-5.8592	-0.3						P.	J.
		S.	-5.8604	+0.0						P.	J.
		S.	-5.8601	-0.6						P.	J.
		Mean ..	-5.8595								

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 20.....	45.52	N.....	+4.9114	+0.6	0.2		170.2921			P.
		N.....	+4.9121	-0.1						P.
		S.....	+4.9117	+0.3						P.
		S.....	+4.9129	-0.9						P.
		Mean..	+4.9120							
U. S. P. B. M. 9...	45.70	N.....	+2.9006	+0.6	0.2	4.1	172.4908	+0.5	172.4903	P.
		S.....	+2.9002	-1.0						P.
		Mean..								
T. B. M. 31.....	45.77	N.....			0.1		171.5786			P.
		N.....								P.
		S.....								P.
		S.....	+1							P.
		Mean..	+2							
T. B. M. 32.....	45.78	N.....		+2.5	0.9		165.7078			P.
		S.....		-2.2						P.
		S.....		-0.1						P.
		Mean..	-5.7610							
T. B. M. 33 and 33a.	47.53	N.....	+0.9247	+0.9	0.5		169.7321			P.
		S.....	+0.9263	-0.9						P.
		Mean..	+0.9255							
T. B. M. 34.....	48.94	N.....	+4.9363	-0.1	0.1		171.6546			P.
		S.....	+4.9361	+0.1						P.
		Mean..	+4.9362							
T. B. M. 35 and 35a.	50.58	N.....	-1.5205	+2.3	0.6		170.1321			P.
		N.....	-1.5236	-1.4						P.
		S.....	-1.5264	-0.5						P.
		S.....	-1.5271	-0.1						P.
		Mean..	-1.5272							
T. B. M. 36.....	52.19	N.....	+0.0061	-3.6	0.9		170.1346			P.
		N.....	+0.0004	+2.1						P.
		S.....	+0.0005	+2.0						P.
		S.....	+0.0030	-0.6						P.
		Mean..	+0.0025							
U. S. P. B. M. 10...	53.71	N.....	+2.9911	-2.2	1.4	4.6	172.1235	+0.5	172.1240	P.
		S.....	+2.9868	+2.1						P.
		Mean..	+2.9889							
T. B. M. 37.....	54.92	N.....	+2.6084	+1.6	1.2		175.8237			P.
		S.....	+2.7020	-1.8						P.
		Mean..	+2.7002							
T. B. M. 38 and 38a.	55.70	N.....	-1.6402	+1.9	0.7		174.1704			P.
		N.....	-1.6456	+1.3						P.
		S.....	-1.6417	-2.6						P.
		S.....	-1.6438	-0.5						P.
		Mean..	-1.6443							
T. B. M. 39.....	56.48	S.....	-0.0606	-2.6	0.8		174.1072			P.
		S.....	-0.0707	-1.5						P.
		N.....	-0.0749	+2.7						P.
		N.....	-0.0735	+1.3						P.
		Mean..	-0.0729							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Point.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	P.	F.
M. 39 and 40a.	57.74	N.....	+0.0444	+0.5	0.3		174.1521			P.	F.
		S.....	+0.0454	-0.5						P.	F.
		Mean..	+0.0449								
M. 41 and 41a.	59.28	N.....	-0.5881	-1.5	1.1		178.5034			P.	F.
		S.....	-0.5914	+1.7						P.	F.
		Mean..	-0.5897								
P. R. M. 11.	59.65	N.....	-2.8540	+0.3	0.3	5.0	170.7087	+0.4	170.7091	P.	J.
		N.....	-2.8535	-0.3						P.	J.
		Mean..	-2.8537							P.	F.
M. 42 and 42a.	60.83	S.....	-5.1504	-2.7	0.9		168.3009			P.	J.
		S.....	-5.1628	-0.3						P.	J.
		N.....	-5.1652	+2.1						P.	J.
M. 43 and 43a.	61.12	N.....	-5.1631	+2.0						P.	J.
		S.....	-1.0536	+1.0	0.5		167.8467			P.	J.
		S.....	-1.0535	+0.9						P.	J.
M. 44 and 44a.	61.39	N.....	-1.0504	-2.3						P.	J.
		N.....	-1.0529	+0.3						P.	J.
		Mean..	-1.0526								
M. 45 and 45a.	61.52	S.....	+0.4902	+1.7	1.2		167.9386			P.	F.
		N.....	+0.4937	-1.8						P.	F.
		Mean..	+0.4919								
M. 46 and 46a.	61.52	S.....	+0.1928	-0.5	0.3		168.0909			P.	F.
		N.....	+0.1918	+0.5						P.	F.
		Mean..	+0.1923								
P. R. M. 12.	61.37	S.....	+0.1333	+1.2	0.8	5.3	168.1654	+0.3	168.1657	P.	F.
		N.....	+0.1357	-1.3						P.	F.
		Mean..	+0.1345								
M. 47.....	61.93	S.....	+2.2135	-0.6	0.4		170.8438			P.	F.
		N.....	+2.2124	+0.5						P.	F.
		Mean..	+2.2129								
P. R. M. 13.....	62.06	S.....	+1.0521	+0.5	0.3	5.2	171.2964	+0.4	171.2968	P.	J.
		S.....	+1.0519	+0.3						P.	J.
		N.....	+1.0541	-1.5						P.	J.
ft. mark of ex-gauge at Arlington Ips, Iowa.	62.58	N.....	+1.0526	0.0						P.	J.
		Mean..	+1.0526								
M. 47.....	62.58		-3.8399	+5.4	3.0		167.5619			P.	J.
			-3.8291	-5.4						P.	J.
		Mean..	-3.8345								
M. 47.....	62.74	N.....	+0.0382	-1.2	0.6		171.4234			(1)	J.
		S.....	+0.0386	-1.6						(1)	J.
		N.....	+0.0365	+0.5						(1)	F.
M. 47.....	62.74	S.....	+0.0348	+2.3						(1)	F.
		Mean..	+0.0370								

1 Bridge crossing.

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	B.	Elevation.	Red correction.	Corrected elevation.	Remarks.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
*T. B. M. 49, Mackinac.	69.77	N.....	+0.0071			5.3	171.4405	+0.4	171.4409	P.
U. S. P. B. M. 14...	69.78	N.....	+0.0011	+0.3	0.2	5.3	171.4346	+0.4	171.4352	P.
		S.....	+0.0017	-0.3						P.
		Mean..	+0.0014							
T. B. M. 47 $\frac{1}{2}$	70.80	N.....	-2.9537	-1.7	1.0		168.6794			P.
		S.....	-2.9600	+4.6						P.
		S.....	-2.9542	-1.2						P.
		S.....	-2.9538	-1.6						P.
		Mean..	-2.9554							
T. B. M. 49.....	71.29	N.....	-0.6537	+0.2	0.1		167.7939			P.
		S.....	-0.6833	-0.7						P.
		Mean..	-0.6685							
T. B. M. 49 and 49a.	72.75	N.....	-0.1559	-0.9	0.4		167.6894			P.
		S.....	-0.1571	+0.6						P.
		Mean..	-0.1565							
U. S. P. B. M. 15...	73.17	S.....	+0.0361	+0.6	0.4	5.4	167.6761	+0.3	167.6764	P.
		N.....	+0.0373	-0.6						P.
		Mean..	+0.0367							
T. B. M. 50 and 50a.	74.51	S.....	+0.2400	+1.0	0.7		167.9171			P.
		N.....	+0.2421	-1.1						P.
		Mean..	+0.2410							
T. B. M. 51.....	75.45	N.....	-0.0500	-0.5	0.4		167.8006			P.
		S.....	-0.0511	+0.6						P.
		Mean..	-0.0505							
T. B. M. 52 and 52a.	76.23	N.....	+0.0799	+0.9	0.6		167.9474			P.
		S.....	+0.0818	-1.0						P.
		Mean..	+0.0808							
T. B. M. 53.....	77.13	N.....	+0.2068	-1.1	0.7		168.1531			P.
		S.....	+0.2046	+1.1						P.
		Mean..	+0.2057							
T. B. M. 54.....	78.58	N.....	+0.0198	-2.6	1.8		168.1612			P.
		S.....	+0.0055	+2.7						P.
		Mean..	+0.0082							
*U. S. P. B. M. 16.	78.00	N.....	+0.0018	+0.1	0.1	5.8	168.1632	+0.3	168.1635	P.
		N.....	+0.0021	-0.2						P.
		Mean..	+0.0019							
T. B. M. 55.....	79.80	N.....	+0.4836	+1.6	1.1		168.6455			P.
		S.....	+0.4869	-1.7						P.
		Mean..	+0.4852							
T. B. M. 56 and 56a.	81.17	N.....	+3.3703	+1.4	0.9		172.0182			P.
		S.....	+3.3730	-1.2						P.
		Mean..	+3.3717							
T. B. M. 56 A.....	83.07	S.....	-0.3153	+0.3	0.2		171.7032			P.
		N.....	-0.3147	-0.3						P.
		Mean..	-0.3150							

Results of precise leveling—Continued.

KROOK, IOWA, TO FULTON, ILL.—Continued.

Point.	Distance.	Direction.	Difference of elevations.	V.	r.	M.	Elevation.	Rod correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.		M.		M.		
I. K. and 29.	22.22	S.....	-2.8508	+0.8	0.6		162.8674			P.	J.
		N.....	-2.8551	-0.7						P.	J.
		Mean..	-2.8558								
I. K. F.....	24.24	S.....	+1.4624	+0.8	0.5		170.2108			P.	J.
		N.....	+1.4639	-0.7						P.	J.
		Mean..	+1.4632								
I. K. and 25a	25.30	S.....	-1.3500	+3.4	0.7		169.0540			P.	J.
		N.....	-1.3501	-0.5						P.	J.
		N.....	-1.3557	-0.9						P.	J.
		N.....	-1.3557	-0.9						P.	J.
		S.....	-1.3576	+0.9						P.	J.
		S.....	-1.3582	-0.4						P.	J.
		N.....	-1.3584	+1.8						P.	J.
		N.....	-1.3589	+2.2						P.	J.
		Mean..	-1.3508								
M. 59 and 59a	26.63	S.....	-0.7065	-1.1	0.2		169.2464			P.	F.
		N.....	-0.7088	+1.2						P.	F.
		Mean..	-0.7076								
M. 60.....	27.24	N.....	+0.5054	+0.6	0.4		169.7324			P.	F.
		S.....	+0.5067	-0.7						P.	F.
		Mean..	+0.5060								
M. 61 and 61a	29.06	N.....	-0.6258	+1.0	0.7		169.1276			P.	F.
		S.....	-0.6237	-1.1						P.	F.
		Mean..	-0.6248								
M. 62.....	29.11	N.....	+0.7707	+1.5	1.0		169.8908			P.	F.
		S.....	+0.7737	-1.5						P.	F.
		Mean..	+0.7722								
P. R. M. 17.	29.66	S.....	+0.6258	+0.2	0.1	6.3	169.5258	+0.4	169.5262		F.
		N.....	+0.6262	-0.2							J.
		Mean..	+0.6260								
P. R. M. 18.	29.84	N.....	+4.2359	+0.5	0.3	6.3	173.1362	+0.5	173.1367		J.
		S.....	+4.2369	-0.5							F.
		Mean..	+4.2364								
M. 63, Mack- in.	29.66	N.....	-0.0034	-0.2	0.1	6.3		+0.4	169.8966		F.
		N.....	-0.0038	+0.2							J.
		Mean..	-0.0036								
F. mark, 1851, m.w.k., Ill.	29.69	N.....	+0.0617	-2.5	1.0		169.9590				J.
		N.....	+0.0598	+2.4							F.
		Mean..	+0.0593								
M. 63 and 63a	29.40	N.....	+5.1117	-1.0	0.7		174.0106			P.	F.
		S.....	+5.1097	+1.0						P.	F.
		Mean..	+5.1107								
M. 64.....	22.14	N.....	+3.8968	0.0	0.0		177.9071			F.	J.
		S.....	+3.8965	+0.1						F.	J.
		Mean..	+3.8966								

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Support.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
*U. S. P. B. M. 39..	209. 02	N.....	—0. 0061	+0. 1	0. 1	2. 7	180. 8742	+0. 7	180. 8749
		S.....	—0. 0059	—0. 1					
		Mean..	—0. 0060							
T. B. M. 173.....	209. 08	N.....	—1. 4397	—0. 5	0. 3		179. 4400			F.
		S.....	—1. 4407	+0. 5						F.
		Mean..	—1. 4402							
*Zero of gauge at Rock Island Bridge.	209. 96	N.....	—8. 0315				171. 4085			
*U. S. P. B. M. 40..	209. 80	N.....	+2. 6728	+0. 4	0. 2	2. 7	182. 1132	+0. 7	182. 1139
		S.....	+2. 6735	—0. 3					
		Mean..	+2. 6732							
*Astronomical post, Rock Is- land.	210. 07	N.....	—0. 4391	+0. 1	0. 1		179. 0010	+0. 7	179. 0017
		S.....	—0. 4388	—0. 2					
		Mean..	—0. 4390							
*H. W., 1890.....	209. 96	N.....	—2. 4233				177. 0167			
T. B. M. 175.....	211. 52	N.....	+0. 6892	—1. 3	0. 9		180. 1279			F.
		S.....	+0. 6896	+1. 3						F.
		Mean..	+0. 6879							
*U. S. P. B. M. 41..	211. 86	N.....	+3. 1766	0. 0	0. 0	2. 7	183. 3045	+0. 8	183. 3053
		S.....	+3. 1767	—0. 1					
		Mean..	+3. 1766							
T. B. M. 176 and 176a.	213. 51	N.....	+1. 5206	0. 0	0. 0		181. 6485			F.
		S.....	+1. 5207	—0. 1						F.
		Mean..	+1. 5206							
T. B. M. 177.....	214. 36	N.....	—1. 3763	+1. 9	1. 2		180. 2741			F.
		S.....	—1. 3726	—1. 8						F.
		Mean..	—1. 3744							
*U. S. P. B. M. 42..	214. 55	N.....	—0. 7034	—0. 6	0. 4	2. 8	179. 5701	+0. 7	179. 5708
		S.....	—0. 7046	+0. 6					
		Mean..	—0. 7040							
T. B. M. 178.....	215. 15	N.....	+0. 5246	+0. 4	0. 2		180. 7991			F.
		S.....	+0. 5253	—0. 3						F.
		Mean..	+0. 5250							
T. B. M. 179.....	216. 22	N.....	+0. 1589	+1. 6	1. 1		180. 9596			F.
		S.....	+0. 1621	—1. 6						F.
		Mean..	+0. 1605							
T. B. M. 180.....	217. 28	N.....	+0. 3918	—2. 0	1. 3		181. 3494			F.
		S.....	+0. 3879	+1. 9						F.
		Mean..	+0. 3898							
T. B. M. 181.....	218. 27	N.....	—1. 4885	—0. 1	0. 0		179. 8008			F.
		S.....	—1. 4886	0. 0						F.
		Mean..	—1. 4886							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.		
I. & M. 79 and 79a	111.00	N.....	-1.7230	-0.5	0.3	169.3046	F.	F.
		S.....	-1.7240	+0.5	F.	F.
		Mean..	-1.7235								
U. & P. R. M. 19..	111.47	N.....	+1.3198	+0.4	0.2	6.9	170.6248	+0.4	170.6252	F.	J.
		S.....	+1.3205	-0.3	F.	J.
		Mean..	+1.3202								
U. & P. R. M. 20..	111.30	N.....	+4.3437	6.9	173.6483	+0.5	173.6488	F.	J.
T. R. M. 47, Mack-	111.54	N.....	+1.3181	6.9	170.6227	+0.4	170.6231	F.	J.
" " " " "	111.54	N.....	+1.0881	170.3927	F.	J.
" " " " "	111.62	N.....	+0.6733	169.9779	F.	J.
" " " " "	111.62	N.....	+0.6733	169.9779	F.	J.
I. & M. 80.....	111.40	N.....	+1.0671	-0.3	0.2	170.3714	F.	F.
		S.....	+1.0664	+0.4	F.	F.
		Mean..	+1.0668								
I. & M. 81 and 81a	111.87	N.....	+2.6500	-0.6	0.4	173.0208	F.	F.
		S.....	+2.6487	+0.7	F.	F.
		Mean..	+2.6494								
I. & M. 82 and 82a	112.40	N.....	+6.2676	-1.6	1.1	179.2868	F.	F.
		S.....	+6.2643	+1.7	F.	F.
		Mean..	+6.2660								
I. & M. 83 and 83a	114.63	N.....	+0.8725	+0.2	0.1	180.1595	F.	F.
		S.....	+0.8729	-0.2	F.	F.
		Mean..	+0.8727								
I. & M. 84.....	116.10	N.....	+0.7559	+4.0	1.1	180.9194	F.	J.
		S.....	+0.7039	-4.0	F.	J.
		N.....	+0.7596	+0.3	F.	J.
		S.....	+0.7603	-0.4	F.	J.
		Mean..	+0.7599								
I. & M. 85 and 85a	117.45	N.....	-0.0186	+1.3	0.9	180.9021	F.	J.
		S.....	-0.0160	-1.3	F.	J.
		Mean..	-0.0173								
I. & M. 86.....	118.75	N.....	-0.6858	-0.6	0.4	180.2157	F.	J.
		S.....	-0.6870	+0.6	F.	J.
		Mean..	-0.6864								
I. & M. 87.....	119.81	N.....	-1.1346	-1.8	1.2	179.0793	F.	J.
		S.....	-1.1383	+1.9	F.	J.
		Mean..	-1.1364								
I. & M. 88 and 88a	120.82	N.....	-3.8750	-1.2	0.8	175.2031	F.	J.
		S.....	-3.8775	+1.3	F.	J.
		Mean..	-3.8762								
U. & P. R. M. 21..	120.84	N.....	+0.0590	-0.4	0.2	7.3	175.2617	+0.5	175.2622	F.
		S.....	+0.0583	+0.3	F.
		Mean..	+0.0586								

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Remarks.
	Km.			Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 89 and 89a	124.24	N.....	+2.0934	-0.3	0.2		177.2962			
		S.....	+2.0928	+0.3						
		Mean..	+2.0931							
U. S. P. B. M. 92 ..	124.56	N.....	-5.0325	-0.3	0.3	7.8	172.2634	+0.5	172.2639	
		S.....	-5.0331	+0.3						
		Mean..								
*P. B. M. 40, Mac- kensie.	124.77	N.....			0.0		170.5779	+0.4	170.5783	
		S.....								
		Mean..								
*U. S. P. B. M. 23..	124.82	N.....	+1	1	0.3	7.3	180.0110	+0.7	180.0117	
		S.....	+1	1						
		Mean..	+1							
*H. W. Mark, 1881, New Boston, Ill.	124.62	N.....	-1	1			170.8588			
		S.....	-1		0.9	0.6	167.4543			
		Mean..	-1		0.9					
T. B. M. 90.....	124.77	N.....	-1							
		S.....	-1							
		Mean..	-1							
T. B. M. 91.....	125.14	N.....	-1		0.8	0.0	167.4345			
		S.....	-1							
		Mean..	-0.0198							
T. B. M. 92 and 92a	125.23	N.....	+0.5673	-0.1	0.0		168.0017			P.
		S.....	+0.5672	0.0						P.
		Mean..	+0.5672							
T. B. M. 93.....	126.81	N.....	+1.6575	-1.1	0.8		168.6581			P.
		S.....	+1.6562	+0.2						P.
		Mean..	+1.6564							P.
T. B. M. 94.....	127.18	N.....	-1.5050	-0.5	0.2		168.1526			P.
		S.....	-1.5053	-0.2						P.
		Mean..	-1.5055							P.
T. B. M. 95	128.40	N.....	+1.8817	+1.3	0.8		170.0856			P.
		S.....	+1.8803	+2.7						P.
		Mean..	+1.8830							P.
T. B. M. 96.....	129.89	N.....	-1.0376	+0.6	0.4		168.0986			P.
		S.....	-1.0364	-0.6						P.
		Mean..	-1.0370							
T. B. M. 97.....	130.81	N.....	+0.6417	-0.9	0.6		169.6404			P.
		S.....	+0.6410	+0.8						P.
		Mean..	+0.6418							

* Crossing New Boston Bay.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	P.	F.
T.R.M. 9 and 98a	132.22	N.....	-0.0056	-1.4	0.9	169.5434	P.	F.
		S.....	-0.0084	+1.4	P.	F.
		Mean..	-0.0070
T.R.M. 10.....	133.37	N.....	+1.1632	-0.4	0.3	170.7062	P.	F.
		S.....	+1.1624	+0.4	P.	F.
		Mean..	+1.1628
T.R.M. 10.....	134.64	N.....	-0.5806	-0.6	0.4	170.1190	P.	J.
		S.....	-0.5877	+0.5	P.	J.
		Mean..	-0.5872
T.R.M. 11.....	135.46	N.....	-0.6478	+0.9	0.6	169.4721	P.	J.
		S.....	-0.6460	-0.9	P.	J.
		Mean..	-0.6469
T.R.M. 12.....	136.03	N.....	-0.2514	+2.0	0.6	169.2227	P.	F.
		S.....	-0.2470	-2.4	P.	F.
		N.....	-0.2493	-0.1	P.	F.
		S.....	-0.2501	+0.7	P.	F.
		Mean..	-0.2494
T.R.M. 12.....	136.18	N.....	-0.3069	-0.5	0.4	168.9153	P.	F.
		S.....	-0.3080	+0.6	P.	F.
		Mean..	-0.3074
T.R.M. 14.....	136.42	N.....	+0.0031	-0.2	0.1	168.9182	P.	J.
		S.....	+0.0027	+0.2	P.	J.
		Mean..	+0.0029
T.R.M. 15.....	136.56	N.....	-0.0307	+0.4	0.3	168.9178	(*)	J.
		S.....	+0.0290								
		N.....	-0.0212	-0.5	F.
		S.....	+0.0214								
		Mean..	-0.0004
T.R.M. 16.....	138.60	N.....	+2.1153	+4.0	1.1	171.0371	P.	J.
		S.....	+2.1231	-3.8	P.	J.
		N.....	+2.1188	+0.5	P.	J.
		S.....	+2.1199	-0.6	P.	J.
		Mean..	+2.1193
T.R.P.R.M. 24— Mechanic R.M. a	138.62	S.....	+1.2697	+0.1	0.0	7.7	172.3069	+0.5	172.3074	J.
		S.....	+1.2698	0.0	F.
		Mean..	+1.2698
T.R.M. 17.....	139.61	N.....	-1.1292	+4.2	1.0	169.9121	P.	J.
		S.....	-1.1232	-1.8	P.	J.
		N.....	-1.1250	0.0	P.	F.
		S.....	-1.1228	-2.2	P.	F.
		Mean..	-1.1250
T.R.M. 108 and 108a	141.24	N.....	-0.6700	+0.4	0.2	169.2425	P.	F.
		S.....	-0.6693	-0.3	P.	F.
		Mean..	-0.6696
T.R.M. 109.....	142.36	N.....	+1.0217	-0.1	0.0	170.2641	P.	F.
		S.....	+1.0216	0.0	P.	F.
		Mean..	+1.0216

* River crossing.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	P.	F.
*H. W. Mark, 1881, Port Louisa, Iowa.	141.86	S	+1.0536	171.8177	P.	F.
T. B. M. 110	144.03	N	+0.3250	—2.9	1.1	170.5862	P.	J.
		S	+0.3194	+2.7	P.	J.
		N	+0.3218	+0.3	P.	J.
		Mean ..	+0.3221								
T. B. M. 111	145.71	N	+0.3540	—0.5	0.3	170.9397	P.	J.
		S	+0.3530	+0.5	P.	J.
		Mean ..	+0.3535								
T. B. M. 112	146.30	N	—0.3593	—1.8	1.2	170.5786	P.	F.
		S	—0.3629	+1.8	P.	F.
		Mean ..	—0.3611								
T. B. M. 113	146.98	N	+0.4048	+0.1	0.1	170.9835	P.	F.
		S	+0.4050	—0.1	P.	F.
		Mean ..	+0.4049								
T. B. M. 114 and 114a.	147.81	N	+1.3335	—1.5	1.0	172.3155	P.	F.
		S	+1.3306	+1.4	P.	F.
		Mean ..	+1.3320								
T. B. M. 115	148.80	N	+0.2448	—3.2	1.1	172.5571	P.	F.
		S	+0.2398	+1.8	P.	F.
		N	+0.2401	+1.5	P.	F.
		Mean ..	+0.2416								
T. B. M. 116	149.82	N	—1.0220	—0.6	0.4	171.5345	P.	F.
		S	—1.0231	+0.5	P.	F.
		Mean ..	—1.0226								
T. B. M. 117	150.72	N	+0.0247	—1.1	0.7	171.5581	P.	J.
		S	+0.0225	+1.1	P.	J.
		Mean ..	+0.0236								
*U. S. P. B. M. 25.	150.85	S	+0.4415	+0.9	0.6	8.1	172.0005	+0.5	172.0010	P.	J.
		N	+0.4434	—1.0	P.	F.
		Mean ..	+0.4424								
*H. W. Mark, June, 1880.	150.85	N	+0.3606	171.9187	F.
*H. W. Mark, 1851	150.90	N	+0.0010	172.0015	F.
*H. W. Mark, Oct., 1881.	150.90	N	—0.0157	171.9848	F.
T. B. M. 118	151.65	N	+1.5861	+1.9	1.3	173.1461	P.	J.
		S	+1.5899	—1.9	P.	J.
		Mean ..	+1.5880								
*U. S. P. B. M. 26.	151.68	N	+0.1078	8.2	173.2539	+0.5	173.2544	J.
T. B. M. 119	152.95	N	—1.8469	—0.5	0.3	171.2987	P.	J.
		S	—1.8478	+0.4	P.	J.
		Mean ..	—1.8474								
T. B. M. 120 and 120a.	154.62	N	+0.9804	—0.6	0.4	172.2785	P.	F.
		S	+0.9791	+0.7	P.	F.
		Mean ..	+0.9798								

Results of precise leveling—Continued.

KNOX, IOWA, TO FULTON, ILL.—Continued.

Point	Distance.	Direction	Difference of elevation.	V.	r.	B.	Elevation.	Rod correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.		
T.R.M. 121.....	155.77	N.....	-2.5465	+1.0	0.7		169.7800			P.	F.
		S.....	-2.5475	-1.0						P.	F.
		Mean..	-2.5465								
T.R.M. 122.....	156.40	N.....	+0.8871	+1.7	1.1		170.6188			P.	F.
		S.....	+0.8804	-1.4						P.	F.
		Mean..	+0.8888								
T.R.M. 123.....	157.79	N.....	+2.0078	0.4	0.0		172.6284			P.	F.
		S.....	+2.0077	-0.1						P.	F.
		Mean..	+2.0078								
T.R.M. 124.....	158.30	N.....	+0.1844	+0.2	0.1		173.8110			P.	J.
		S.....	+0.1848	-0.2						P.	J.
		Mean..	+0.1846								
T.R.M. 125.....	159.21	N.....	+0.0618	+1.1	0.7		173.8683			P.	J.
		S.....	+0.0640	-1.1						P.	J.
		Mean..	+0.0629								
*H.W.M., Apr. 2, 1878, 23 miles below Muscatine, Iowa.	159.30	N.....	-0.3710				172.6229				J.
*H.W.M., June 2, 1880.	159.36	N.....	-0.1720				172.7219				J.
*H.W.M., Oct., 1881.	159.36	N.....	-0.1350				172.7580				J.
T.R.M. 126.....	160.23	N.....	-1.0263	+1.1	0.7		171.8687			P.	J.
		S.....	-1.0241	-1.1						P.	J.
		Mean..	-1.0252								
T.R.M. 127 and 127a.	160.86	N.....	-0.1105	-0.6	0.4		171.7677			P.	J.
		S.....	-0.1116	+0.6						P.	J.
		Mean..	-0.1110								
*U.S.P.R.M. 27.	161.06	N.....	+2.0790	-0.1	0.1	8.4	173.8368	+0.5	173.8371	P.	J.
		S.....	+2.0788	+0.1						P.	J.
		Mean..	+2.0789								
T.R.M. 128 and 128a.	162.04	N.....	+1.3444	-1.2	0.8		173.1009			P.	J.
		S.....	+1.3419	+1.3						P.	J.
		Mean..	+1.3432								
*H.W.M., June, 1880, Muscatine, Iowa.	162.10	N.....	-0.0277				173.0782				J.
*H.W.M., Oct., 1881.	162.10	N.....	-0.0027				173.0983				J.
T.R.M. 129.....	164.06	N.....	+0.0176	-1.6	1.1		173.1169			P.	F.
		S.....	+0.0144	+1.6						P.	F.
		Mean..	+0.0160								
*U.S.P.R.M. 28.	164.06	N.....	+1.1794	0.0	0.0	8.5	174.2903	+0.5	174.2968		F.
		S.....	+1.1794	0.0							F.
		Mean..	+1.1794								
*P.R.M. 44, Muscatine.	164.12	N.....	+0.2029	+0.1	0.1	8.5	173.8199	+0.5	173.8304		F.
		S.....	+0.2031	-0.1							F.
		Mean..	+0.2030								

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Support.
	Mm.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
*26 ft. mark in well of water works, Muscatine, Iowa.	194.15	N.....	-0.6287	-0.1	0.1		172.6911			
		S.....	-0.6290	+0.2						
		Mean.	-0.6288							
*H. W. M., Oct., 1881, Muscatine, Iowa.	194.14	N.....	-0.0128	+0.3	0.3		172.1843			
		S.....	-0.0123	-0.4						
		Mean.	-0.0125							
U. S. P. B. M. 29...	194.25	N.....			2	2.5	174.4344	+0.5	174.4349	P.
		S.....								P.
		Mean.								
T. B. M. 130 and 130a.	195.44	N.....			2		173.5382			P.
		S.....								P.
		Mean.								
T. B. M. 131 and 131a.	195.99	N.....			7		173.5688			P.
		S.....								P.
		Mean.	-1.0							
T. B. M. 132 and 132a.	198.84	N.....			4		172.8320			P.
		S.....								P.
		Mean.								
*U. S. P. B. M. 30.	199.47	N.....				2.7	174.7930	+0.5	174.7935	P.
T. B. M. 133 and 133a.	170.10	N.....	+1.5424	-1.8	1.2		175.3726			P.
		S.....	+1.5389	+1.7						P.
		Mean.	+1.5406							
T. B. M. 134 and 134a.	171.58	N.....	+0.3503	+1.5	1.0		175.7244			P.
		S.....	+0.3534	-1.6						P.
		Mean.	+0.3518							
U. S. P. B. M. 31.	172.65	N.....	-1.1705	+0.3	0.2	2.8	174.5542	+0.5	174.5547	P.
		S.....	-1.1699	-0.2						P.
		Mean.	+1.1702							
T. B. M. 135.....	173.66	N.....	+1.3195	-0.8	0.5		175.8729			P.
		S.....	+1.3179	+0.8						P.
		Mean.	+1.3187							
*U. S. P. B. M. 32.	173.68	N.....	+1.3146			2.2	177.1875	+0.6	177.1881	J.
T. B. M. 136.....	174.15	N.....	+0.3607	-1.3	0.8		176.2323			P.
		S.....	+0.3582	+1.2						P.
		Mean.	+0.3594							
T. B. M. 137 and 137a.	175.50	N.....	+0.4745	-0.7	0.4		177.7061			P.
		S.....	+1.4732	+0.6						P.
		Mean.	+1.4738							
T. B. M. 138 and 138a.	176.72	N.....	-0.5076	+0.3	0.2		177.1988			P.
		S.....	-0.5070	-0.3						P.
		Mean.	-0.5073							
*U. S. P. B. M. 33.	176.96	N.....	-1.8109	+0.7	0.4	2.9	175.3896	+0.5	175.3891	P.
		S.....	-1.8096	-0.6						P.
		Mean.	-1.8102							

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Support.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.	
T. B. M. 148 and 148a.	188.12	N.....	+2.2801	-1.5	1.0	178.4864	F.
		S.....	+2.2830	+1.4	F.
		Mean..	+2.2816							
T. B. M. 149 and 149a.	188.86	N.....	+0.2240	-0.2	0.1	178.7102	F.
		S.....	+0.2236	+0.2	F.
		Mean..	+0.2238							
T. B. M. 150 and 150a.	190.18	N.....	+1.1952	0.0	0.0	179.9054	F.
		S.....	+1.1951	+0.1	F.
		Mean..	+1.1952							
T. B. M. 151 and 151a.	190.69	N.....	-0.6553	+0.3	0.2	179.2504	F.
		S.....	-0.6546	-0.4	F.
		Mean..	-0.6550							
T. B. M. 152 and 152a.	192.10	N.....	-3.4540	-0.6	0.4	175.7058	F.
		S.....	-3.4553	+0.7	F.
		Mean..	-3.4546							
T. B. M. 153.....	192.43	N.....	-0.0522	-0.1	0.1	175.7435	F.
		S.....	-0.0524	+0.1	F.
		Mean..	-0.0523							
T. B. M. 154.....	192.93	N.....	+0.1140	+2.5	0.6	175.8000	F.
		S.....	+0.1182	-1.7	F.
		N.....	+0.1162	+0.8	F.
		S.....	+0.1177	-1.2	F.
		Mean..	+0.1165							
*U. S. P. B. M. 36..	193.12	N.....	+2.5400	0.0	0.0	9.2	178.4000	+0.6	178.4006	F.
		S.....	+2.5399	+0.1	F.
		Mean..	+2.5400							
T. B. M. 155 and 155a.	193.49	N.....	+0.0378	+0.2	0.1	175.8080	F.
		S.....	+0.0381	-0.1	F.
		Mean..	+0.0380							
T. B. M. 156.....	194.45	N.....	+0.5318	+3.4	1.0	176.4832	F.
		S.....	+0.5379	-2.7	F.
		N.....	+0.5372	-2.0	F.
		S.....	+0.5341	+1.1	F.
		Mean..	+0.5352							
*U. S. P. B. M. 37..	194.52	N.....	+3.0326	+0.4	0.2	9.2	179.4002	+0.7	179.4009	...
		S.....	+3.0333	-0.3
		Mean..	+3.0330							
T. B. M. 157 and 157a.	195.10	N.....	+0.6062	+1.0	0.7	177.0404	F.
		S.....	+0.6083	-1.1	F.
		Mean..	+0.6072							
T. B. M. 158.....	196.06	N.....	+0.9024	+1.8	0.9	178.0041	F.
		S.....	+0.9650	-1.8	F.
		Mean..	+0.9637							

Results of precise leveling—Continued.

KROOK, IOWA, TO FULTON, ILL.—Continued.

Point.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Rod correction.	Corrected elevation.	Support.	Observer.
M. 138 and L.	198.89	N..... S..... N..... S.....	M. +0.2235 +0.2269 +0.2259 +0.2248	+1.7 -1.6 -0.7 +0.4	Mm. 0.5	Mm.	M. 178.2299	Mm.	M.	F. F. F. F.	F. F. F. F.
		Mean..	+0.2253								
M. 139 and L.	199.88	N..... S..... N..... S.....	+1.0638 +1.0664 +1.0650 +1.0652	+1.3 -1.3 +0.1 -0.1	0.4		178.2944			F. F. F. F.	F. F. F. J.
		Mean..	+1.0651								
L. 141 and L.	199.23	N..... S.....	-0.2918 -0.2953	-1.6 +1.7	1.3		178.0006			F. F.	J. J.
		Mean..	-0.2936								
.142.....	199.46	N..... S..... N..... S.....	-2.3250 -2.3325 -2.3290 -2.3303	-4.2 +2.3 -0.3 +1.1	1.1		178.6716			F. F. F. F.	J. J. J. J.
		Mean..	-2.3302								
L. 143 and L.	200.48	N..... S.....	+0.2766 +0.2731	-2.3 +2.3	1.5		178.9460			F. F.	J. J.
		Mean..	+0.2744								
.144.....	201.66	N..... S.....	+1.3340 +1.3365	+1.2 -1.3	0.8		178.2812			F. F.	F. F.
		Mean..	+1.3352								
L. 145.....	202.85	N..... S.....	-1.6418 -1.6423	-0.2 +0.2	0.1		178.6892			F. F.	F. F.
		Mean..	-1.6420								
K. 146 and L.	204.15	N..... S..... N..... S.....	+0.2803 +0.2839 +0.2876 +0.2878	-2.9 +3.5 -0.3 -0.4	0.9		178.9206			F. F. F. F.	F. F. F. F.
		Mean..	+0.2874								
M. 148 and L.	205.70	N..... S.....	+0.4104 +0.4112	+0.4 +0.4	0.3		177.3374			F. F.	J. J.
		Mean..	+0.4108								
P. H. M. 38..	205.77	N..... S.....	+1.0909 +1.0913	+0.1 -0.2	0.1	R. 7	178.0284	+0.7	178.0291		F. F.
		Mean..	+1.0910								
M. 170 and L.	206.78	N..... S.....	+0.6787 +0.6764	-0.1 +0.2	0.1		178.6140			F. F.	J. J.
		Mean..	+0.6766								
M. 171 and L.	208.17	N..... S.....	+1.7992 +1.7976	-0.8 +0.8	0.5		178.8124			F. F.	F. F.
		Mean..	+1.7984								
M. 172 and L.	208.80	N..... S.....	+1.0681 +1.0676	-0.3 +0.2	0.2		180.8802			F. F.	F. F.
		Mean..	+1.0678								

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

MINNEAPOLIS, MINN. TO FULTON, ILL.—Continued.

Point	Distance	Instrument	Difference of elevations	V.	W.	R.	Elevation	Mod correction	Corrected elevation	Support.
U. S. P. R. M. 11	222.02	N	-4.0002	-4.1	0.1	0.7	122.8242	+0.7	122.8249	
		S	-4.0002	-4.1						
		Mean	-4.0002							
T. R. M. 112	222.09	N	-1.4007	-4.3	0.3		172.4000			F.
		S	-1.4007	-4.3						F.
		Mean	-1.4007							
Base of gauge at Rock Island Bridge.	222.25	N	-2.0015				171.0005			
U. S. P. R. M. 12	222.29	N	-2.0729	-4.4	0.2	0.7	122.1122	+0.7	122.1129	
		S	-2.0729	-4.3						
		Mean	-2.0729							
Astronomical point, Rock Island	222.07	N	-2.4201	-4.1	0.1		172.0010	+0.7	172.0017	
		S	-2.4201	-4.3						
		Mean	-2.4201							
W. W. 120	222.25	N	-2.4201				171.0007			
T. R. M. 113	211.22	N	+2.0000	-1.2	0.0		122.1279			F.
		S	+2.0000	-1.2						F.
		Mean	+2.0000							
U. S. P. R. M. 11	211.25	N	-2.1700	0.0	0.0	0.7	122.2005	+0.8	122.2003	
		S	-2.1700	-0.1						
		Mean	-2.1700							
T. R. M. 176 and 177	211.51	N	-1.5200	0.0	0.0		121.0005			F.
		S	-1.5200	-0.1						F.
		Mean	-1.5200							
T. R. M. 177	214.22	N	-1.3703	-1.9	1.2		122.3741			F.
		S	-1.3703	-1.6						F.
		Mean	-1.3703							
U. S. P. R. M. 13	214.55	N	-0.7004	-0.6	0.4	0.8	172.5701	+0.7	172.5708	
		S	-0.7004	+0.6						
		Mean	-0.7004							
T. R. M. 178	213.16	N	+0.5205	-0.4	0.2		120.7001			F.
		S	+0.5205	-0.2						F.
		Mean	+0.5205							
T. R. M. 179	216.22	N	+0.1600	+1.6	1.1		120.2006			F.
		S	+0.1601	-1.6						F.
		Mean	+0.1600							
T. R. M. 180	217.28	N	+0.3018	2.0	1.3		121.3404			F.
		S	+0.3079	+1.9						F.
		Mean	+0.3096							
T. R. M. 181	218.27	N	-1.4885	-0.1	0.0		170.0008			F.
		S	-1.4886	0.0						F.
		Mean	-1.4886							

Results of precise leveling—Continued.

KEOSAU, IOWA, TO FULTON, ILL.—Continued.

Point.	Distance.	Direction.	Difference of elevation.	V.	v.	R.	Elevation.	Rod correction.	Corrected elevation.	Support.	Observer.
	Km.		M.	Mm.	Mm.	Mm.	M.	Mm.	M.		
T. R. M. 182.....	212.27	N.....	+1.2212	-0.7	0.5		181.0812			P.	J.
		S.....	+1.2198	+0.7						P.	J.
		Mean..	+1.2205								
T. R. M. 183.....	220.17	N.....	+0.8765	+4.2	0.7		181.0628			P.	F.
		S.....	+0.8794	+1.2						P.	F.
		N.....	+0.8815	-0.8						P.	F.
		S.....	+0.8847	-1.0						P.	F.
		N.....	+0.8818	-0.6						P.	F.
		S.....	+0.8808	-0.1						P.	F.
		Mean..	+0.8807								
T. R. M. 184 and 185.	221.45	N.....	-1.6218	+4.1	1.1		180.8443			P.	F.
		S.....	-1.6180	-0.8						P.	F.
		N.....	-1.6142	-3.5						P.	F.
		S.....	-1.6179	+0.2						P.	F.
		Mean..	-1.6177								
T. R. M. 186.....	222.24	N.....	-1.3258	-0.7	0.5		179.0173			P.	J.
		S.....	-1.3272	+0.7						P.	F.
		Mean..	-1.3265								
T. R. M. 186 and 187.	222.17	N.....	-0.2976	+0.2	0.1		178.7204			P.	J.
		S.....	-0.2973	-0.1						P.	J.
		Mean..	-0.2974								
U. S. P. R. M. 43.	222.28	N.....	+2.7073	-0.1	0.0	10.1	181.4276	+0.7	181.4268	P.	J.
		S.....	+2.7072	0.0						P.	J.
		Mean..	+2.7072								
T. R. M. 187.....	224.40	N.....	+2.3067	-0.2	0.2		181.0286			P.	J.
		S.....	+2.3061	+0.3						P.	J.
		Mean..	+2.3064								
T. R. M. 188 and 189.	225.12	N.....	+1.3826	-1.0	0.7		182.4104			P.	J.
		S.....	+1.3806	+1.0						P.	J.
		Mean..	+1.3816								
U. S. P. R. M. 44.	225.93	N.....	-0.5884	-0.8	0.5	10.1	182.9980	+0.8	182.9968	P.	F.
		S.....	+0.5869	+0.7						P.	F.
		Mean..	+0.5876								
T. R. M. 189 and 190.	225.98	N.....	+0.1590	-1.0	0.6		182.5684			P.	F.
		S.....	+0.1571	+0.9						P.	F.
		Mean..	+0.1580								
U. S. P. R. M. 45 R. W., June, 1896.	226.51	N.....	-2.6251	-0.3	0.2	10.1	179.8420	+0.7	179.8427	P.	J.
		S.....	-2.6257	+0.3						P.	J.
		Mean..	-2.6254								
T. R. M. 190 and 191.	227.21	N.....	+1.6510	-2.1	1.4		184.2773			P.	F.
		S.....	+1.6508	+2.1						P.	F.
		Mean..	+1.6509								
T. R. M. 191 and 192.	228.46	N.....	-0.9000	-2.4	1.6		183.2649			P.	J.
		S.....	-0.9047	+2.3						P.	J.
		Mean..	-0.9024								

Results of precise leveling—Continued.

KNOX, IOWA, TO FULTON, ILL.—Continued.

	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Support.	Observer.
I 200.....	243.76	N..... S..... Mean..	M. -0.5781 -0.5740 -0.5760	Mm. -0.5 +0.4	Mm. 0.3	Mm.	180.7251	Mm.		P. P.	J. J.
B. M. 80..	244.06	N..... S..... Mean..	-5.8715 -5.8712 -5.8714	+0.1 -0.2	0.1	10.6	181.0597	+0.7	181.0544	P. P.	F. F.
L 201 and 1870.....		N..... N.....	+0.0154 +2.0384			10.6	181.0681	+0.7	181.0686		F. F.
B. M. 51..	244.13	N.....	+0.7885			10.6	187.5126	+0.9	187.5145		J.
I 201 and	244.50	N..... S..... Mean..	+2.4419 +2.4432 +2.4426	+0.7 -0.6	0.4		189.1677			P. P.	J. J.
I 202 and	246.56	N..... S..... Mean..	+0.6109 +0.6077 +0.6098	-1.6 +1.6	1.1		189.7779			F. F.	J. J.
I 203 and	247.56	N..... S..... Mean..	+0.4328 +0.4332 +0.4330	+0.2 -0.2	0.1		190.2106			F. F.	J. J.
I 204 and	248.56	N..... S..... Mean..	+0.9696 +0.9723 +0.9709	+1.3 -1.3	0.9		191.1808			F. F.	F. F.
I 205.....	249.44	N..... S..... Mean..	+1.2849 +1.2839 +1.2844	-0.5 +0.5	0.3		192.4653			F. F.	F. F.
B. M. 200 and	251.41	N..... S..... Mean..	-0.0492 -0.0481 -0.0486	+0.6 -0.5	0.4		192.4187			F. F.	F. F.
I 207.....	252.79	N..... S..... Mean..	-3.0692 -3.0729 -3.0710	-1.8 +1.9	1.2		199.8457			F. F.	J. J.
B. M. 200 and	254.24	N..... S..... Mean..	-1.6063 -1.6093 -1.6068	-0.6 +0.5	0.3		197.4409			F. F.	J. J.
B. Hennes- sall.	250.27	N..... S..... Mean..	-4.9827 -4.9840 -4.9834	-0.7 +0.6	0.4	10.8	182.6835	+0.8	182.6849	F. F.	J. J.
B. Hennes- sall.	250.22	N..... S..... Mean..	-0.0691 -0.0688 -0.0690	+0.1 -0.2	0.1	10.8	182.6145	+0.9	182.6153	F. F.	J. J.
I 209 and	250.53	N..... S..... Mean..	+2.3604 +2.3596 +2.3600	-0.4 +0.4	0.3		185.0436			F. F.	F. F.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Results of precise leveling—Continued.

KEOKUK, IOWA, TO FULTON, ILL.—Continued.

Bench.	Distance.	Direction.	Difference of elevation.	V.	r.	R.	Elevation.	Red correction.	Corrected elevation.	Support.
T. B. M. 210.....	Km. 359.57	N..... S..... Mean ..	M. -1.7114 -1.7101 -1.7108	Mm. +0.6 -0.7	Mm. 0.4	Mm.	M. 183.3327	Mm.	■	W. W.
*U.S.P.B.M. 53 .	360.57	N..... S..... Mean ..	+4.8659 +4.8650	-0.6 +0.4	■	10.8	187.6981	+0.9	187.6990	F. F.
*P. B. M. 37, Mac. Kendle.		N.....				10.8	184.5199	+0.5	184.5207	...
*H. W., 1870.....		N.....					184.2672			...
*H. W., 1899.....		N.....					184.4259			...
T. B. M. 211 and 211a.	360.23	N..... S..... Mean ..					183.7454			F. F.
T. B. M. 212.....	361.23	N..... S..... Mean ..					184.8900			F. F.
*U.S.P.B.M. 53 .	361.23	N..... S..... Mean ..					183.8000	+0.9	183.8009	F. F.
T. B. M. 213 and 213a.	362.24	N..... S..... N..... S..... Mean ..	-0.7..... -0.7417 -0.7377 -0.7379 -0.7380	-2.4 +2.7 -0.3 -0.1	1.0		184.1620			F. F. F. F.
U.S.P.B.M. 54 .	363.33	N..... S..... Mean ..	-1.8437 -1.8426 -1.8432	+0.5 -0.6	0.4	10.9	182.2983	+0.7	182.2995	P. P.
T. B. M. 214 and 214a.	365.23	N..... S..... Mean ..	+3.4398 +3.4408 +3.4403	+0.5 -0.5	0.3		185.7391			P. P.
U.S.P.B.M. 55 ..	366.94	N..... S..... Mean ..	-2.4423 -2.4418 -2.4420	+0.3 -0.2	0.2	11.0	183.2971	+0.7	183.2978	P. P.
U.S.P.B.M. 56 ..	368.99	N..... S..... Mean ..	+0.3828 +0.3832 +0.3830	+0.2 -0.2	0.1	11.0	182.6801	+0.8	182.6809	... F.

DESCRIPTION OF PERMANENT BENCH-MARKS BETWEEN CARROLLTON, LA., AND BILOXI MISS.


U. S. C. S. B. M. No. 1 is a small cross (+) cut on iron sill of walled-up door, near northwest corner of seventh district Babcock engine-house, Carrollton, La. Elevation, 9^m.0272.


HAMPSON BENCH (WILLIAMS).—The old Hampson Bench is a spike in N. W. corner of N. O. and C. R. R. machine-shop at Carrollton, La. It is between the 19th and 20th courses of bricks below the window-sill, and about six inches (6") below the surface of the ground. Elevation, 8^m.8292.

HAMPSON BENCH (*Re-established by Major Howell*) is a spike in the N. W. corner of N. O. and C. R. R. machine-shop at Carrollton, La. It is between the 21st and 22d courses of brick below the window-sill. Elevation, 8^m.6551.

B. M. 3 (*Ripley*, 1875) is the top of a broken spike driven into the north face of the car-house of the N. O. and C. R. R. It is two feet (2') west of west side of door, on a level with the course of bricks upon which the door-sill rests. Elevation, 9^m.7752.

B. M. 4 (*Ripley*, 1875) is the top of a ship-spike driven in the north side of the machine-shop of the N. O. and C. R. R., 0.2 ft. from N. W. corner. The spike is driven between the bricks, 37 courses from top of window casing. Elevation, 9^m.5181.

B. M. 5 (*Burney*, 1875), is mark  cut on the west end of iron sill of the north door of the N. O. and C. R. R. depot. Elevation 9^m.0303.

U. S. P. B. M. "CARROLLTON" is the center of small hole in center of copper bolt, leaded horizontally in north face of masonry of northwest corner pillar of old courthouse, at Carrollton, La. The bolt is in the middle, about 0.03 ft. from water table of pillar and about 2.5 ft. above the ground. The letters  are cut near the bolt. Elevation, 9^m.1478.

CITY B. M. x x STONE is top of granite marking stone set in ground, in line of trees, on the west side of Carrollton ave., about half-way between 3d st. and Zimple st.,

Carrollton, La., The stone is marked thus:

X	X	M	B
JUNE			
+			
1874.			

 The mark + denotes the

point where the rod was held. Elevation, 7^m.7655.

CITY STONE (*corner Washington and Carrollton avenues*). This stone is set at southeast corner of crossing of Washington and Carrollton avenues, near New Orleans, La. Elevation, 7^m.7633.

U. S. P. B. M. 1 is a copper bolt leaded vertically in the top of the northwest portion of draw-pier of bridge, called the "White Bridge," crossing the new canal, on the Carrollton road, near New Orleans, La. Elevation, 6^m.9402.

City Stone "Halfway House" is a granite marking-stone set in ground on west side of navigable canal (New Basin), near Metairie Ridge Bridge, between the Halfway House and the gate to Metairie Cemetery. It is said to be the line-stone of the Orleans and Metairie Parishes of New Orleans, La. The stone is marked on top with a cross. Elevation, 7^m.9870.


Bench-mark "Height of Metairie Ridge" is a granite marking-stone set in ground 12 ft. southeast from southeast abutment of Lake Bridge, on east side of canal (New Basin). The bridge crosses the canal (New Basin) opposite Toney's House, West End,

near New Orleans, La. The top of the stone is 8" x 13", and is marked

BENCHMARK
HEIGHT OF
METAIRIE
RIDGE.

Elevation, 7^m.6753.

Bench-mark (near Lake House, West End, La.). This bench-mark is the top of a stone, set in ground between the Lake House and Toney's House. It is on line with front fence of Toney's House, 160 ft. from center of canal and about 30 ft. from road, crossing the canal on the Lake Bridge, at West End, near New Orleans, La. Elevation, 7^m.1244.

U. S. P. B. M. 2 is the center of a copper bolt leaded horizontally in the northwest face of the south one of two brick abutments, at northwest end of draw-bridge across the Bayou St. John, on the Esplanade Road, New Orleans, La. The letters  are cut near the bolt. Elevation 9^m.1593.

U. S. P. B. M. 3 is center of copper bolt leaded horizontally in the east face of mid-

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

the brick gate of Gentilly gate on east side of Fair Grounds, New Orleans. The bolt is lead in the middle brick of the fifth (5th) course above the surface of ground. The letters UO8 are cut near the bolt. Elevation, 7^m.6746.

U. S. P. B. M. 4 is the center of a copper bolt leaded horizontally in wall of Macomb, Chef Menteur, La., on right-hand side (as you go in) of entrance. The

U S

a most around the wall. The letters 18082 are cut about the bolt. Elevation, 8^m.5

P B M

U. S. P. B. M. 5 is a copper bolt leaded vertically near center of old draw-bridge pier, just north of iron truss bridge over the Rigolets, near Rigolets Station, on N. O. and M. R. R., La. Elevation, 6^m.9509.

U. S. P. B. M. 6 is a copper bolt leaded in top of marking-stone set to within 6 ft. of its top, in high point of ground just east of East Pearl River, in Miss. It is 5 meters east of the eastern pier of iron truss bridge over the East Pearl River, on N. O. and M. R. R., and 27.2 meters south of the center of main railroad track, fence in front of land of Mrs. Sarah Selph. Elevation, 9^m.5649.

U. S. P. B. M. 7 is center of cross-cut in top of marking-stone, marked U. S., set in ground just north of north fence of house lot of Pat. Ferril, near Claiborne Station on N. O. and M. R. R., Miss. It is 18 meters south of center of main track, 12 meters east of east end of station house, and 22 meters west of west end of wood-shed on N. O. and M. R. R.; the center of cross-cut is 36 meters, being measured parallel to railroad track. Elevation, 9^m.5649.

U. S. P. B. M. 8 is top of marking-stone, marked U. S., set in ground in northwest corner of small yard, in front of station, N. O. and M. R. R., Miss. It is about 10 meters south of center of main track. Elevation, 9^m.5649.

U. S. P. B. M. 9 is top of marking-stone, marked U. S., set within the southeast corner of fence surrounding the land of Mr. Shaw, between the lands of Mr. Shaw and the land of Mr. Shaw, southwest corner of station-house. Elevation, 11^m.0606.

U. S. P. B. M. 10 is center of copper bolt leaded horizontally in face of south wall of vestibule of Catholic Church, Saint Louis (Shieldsboro'), Miss. It is about half way between side wall and main front wall, and about 1 meter above the ground. Elevation, 12^m.8623.

U. S. P. B. M. 11 is a copper bolt leaded in top of marking-stone, marked U. S., set in ground, by fence, and near the corner of fence of southwest plot of land at intersection of N. O. and M. R. R. Front street, Bay Saint Louis, Miss. It is about 12 meters south of center of track, and 514 meters west of west end of bridge over Bay St. Louis. Elevation, 12^m.8623.

U. S. P. B. M. 12 is copper bolt leaded in top of marking-stone, marked U. S., set in ground within northwest corner of fence surrounding plot of ground on which the tool-house of N. O. and M. R. R. section-house No. 9 is situated, at Henderson's Point, Miss. Stone is about 32 meters west of west side of house, and 8 meters south of center of track. Elevation, 9^m.3391.

U. S. P. B. M. 13 is copper bolt leaded in top of marking-stone, marked U. S., set in ground between pump-house and water-tank at Pass Christian Station, N. O. and M. R. R., Miss. It is a little inside of north line of pump-house and tank, and about 3 meters from west side of pump-house. Pump-house is about 9 meters south of track. Elevation, 9^m.7359.

U. S. P. B. M. 14 is top of copper bolt leaded in top of marking-stone set in ground directly opposite the New Orleans 62-mile post and 8 meters north of center of track of N. O. and M. R. R. Elevation, 15^m.7654.

U. S. P. B. M. 15 is top of marking-stone set in ground 24 meters north of center of track, about 873 meters east of New Orleans 65-mile post, and about 639 meters west of New Orleans 66-mile post, on the N. O. and M. R. R. Three pine trees, each marked with five narrow blazes, are near the stone. Elevation, 14^m.0703.

U. S. P. B. M. 16 is center of copper bolt, leaded horizontally in center of fifth (5th) brick of the fifteenth (15th) course above water-table, in the west wall of jail at Mississippi City, Miss. The bricks are counted from northwest corner of building. It is marked U S

is marked O Elevation, 12^m.7423.

B M

U. S. P. B. M. 17 is copper bolt leaded in top of marking-stone set in ground near west end of depot platform, and 11 meters south of center of track at Beauvoir Station, N. O. & M. R. R., Miss. Elevation, 14^m.2322.

U. S. P. B. M. 18 is center of copper bolt leaded horizontally in center of second (2nd) brick of the fourteenth (14th) course above sidewalk, in east wall, near southeast corner of brick building on southwest corner of Back Bay road (or Mule street) and Jackson street, Biloxi, Miss. Elevation, 13^m.1006.

mouth of Illinois River. It is 60 meters from edge of woods on Illinois and 150 meters from edge of woods on Mississippi River. Elevation, 134^m.5101.

P. B. M. 2 is top of copper bolt in top of stone in ground in woods at mouth of River on left bank, 157 meters back from river, 4 meters east of fence, 15 south of road, 2,100 meters above Catholic Church in Grafton, Ill., and within formed by three pecan trees. Elevation, 136^m.3645.

P. B. M. 3 is copper bolt in top surface of doorstep of Catholic Church, Ill. It is 22 centimeters from front of step, and 13 centimeters from north Elevation, 139^m.3116.

P. B. M. 4 is copper bolt in east end of doorstep of eastern door in Allen's building, adjoining Grafton Flouring Mills, Grafton, Ill. It is 104 millimeters at surface of step. Elevation, 142^m.0719.

P. B. M. 5 is copper bolt leaded in the natural rock on side of bluff above river mark. It is 450 meters below flour mill at Jersey Landing, Ill., and about below Grafton, Ill. The letters U. S. P. B. M. are cut in the rock near the copper. Elevation, 141^m.4305.

P. B. M. 6 is copper bolt leaded vertically in the natural flat rock; top of rock at surface of ground. It is 5,600 meters below flour mill at Jersey Landing, lies near high-water mark and about 9 meters west of the mouth of small which comes out of valley facing the "Eagle's Nest." Elevation, 135^m.0339.

P. B. M. 7 is copper bolt in natural rock on hillside, in woods 19 meters above river mark, and 3,150 meters below mouth of Piassa Creek. The letters U. S. P. are cut near bolt. Elevation, 143^m.7181.

P. B. M. 8 is copper bolt leaded vertically in east end of water-table, on the side of the Alton water works building in sixth window from corner, Alton, the letters U. S. cut near the bolt. Elevation, 136^m.9468.

P. B. M. 9 is copper bolt leaded vertically in south end of doorstep, in north corner of German Catholic Church in Alton, Ill. Elevation, 154^m.4612.

P. B. M. 10 is top of copper bolt in stone post in ground in woods on land of Bringerling, about three hundred meters east of his house, and 5 miles below Ill. It is about 500 meters from river bank. Elevation, 136^m.0457.

P. B. M. 11 is top of copper bolt in stone in ground in woods 450 meters back angulation station Gillen, 2 meters north of honey-locust tree, about 10 meters of road, and about 11 miles below Alton, Ill. There is a road leading back river past this bench-mark. Elevation, 132^m.2312.

P. B. M. 12 is top of copper bolt in stone in ground in corner of grove 20 meters Columbia road, 12.8 miles above steel railroad bridge at St. Louis, Mo. It is of —. —. Chambers, about opposite lower end of Wilson's Island No. 5. Elevation, 145^m.6611.

P. B. M. 13 is top of copper bolt in top of stone in ground in small grove on east Baden and Saint Louis street-car track, 6.4 miles above the railroad bridge at St. Louis, Mo. It is 110 meters south of northern terminus Baden street-car track,

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

is 29.5 centimeter from front face and 10 centimeters west of buttress adjoining step. Elevation, 59^m.3461.

U. S. P. B. M. 17 is top of copper bolt leaded vertically in north end of north step of E. Mueller's store, north of northeast corner of Main and Franklin streets, Carondelet, Mo. Elevation, 133^m.6820.

U. S. P. B. M. 18 is center of copper bolt leaded horizontally in water-table in northeast corner of guard-house, at Jefferson Barracks, Mo. Elevation, 156^m.8992.

U. S. P. B. M. 19 is center of copper bolt leaded horizontally in east face of stone in fourth course from top in east end of culvert at Cliff Cave, Mo., on Iron Mountain Railroad. Elevation, 126^m.1949.

U. S. P. B. M. 20 is top of copper bolt leaded vertically in upper surface of stone from top, in south-west retaining wall of arched culvert, over White Horse Creek, on Iron Mountain Railroad. Elevation, 131^m.0967.

U. S. P. B. M. 21 is top of copper bolt leaded vertically in top stone directly above keystone of arch on north side of arched culvert, 650 meters below Jefferson Station, Mo., on Iron Mountain Railroad. The letters U. S. P. B. M. are cut near the bolt. Elevation, 130^m.0469.

U. S. P. B. M. 22 is top of copper bolt leaded vertically in southern abutment of southern approach to railroad bridge on Iron Mountain Railroad at Kimmberly, Mo. Elevation, 130^m.6894.

U. S. P. B. M. 23 is center of copper bolt leaded horizontally in east face of stone at northeast corner of south approach to bridge, 400 meters below station-house at Sulphur Springs, Mo. Elevation, 131^m.7525.

U. S. P. B. M. 24 is center of copper bolt leaded horizontally in natural rock overhanging bluff 1,000 meters from the first bluff that is seen from the Iron Mountain Railroad leaves Mississippi River. Elevation, 131^m.7525.

U. S. P. B. M. 25 is top of copper bolt leaded vertically in Cornice Rock, about 1,000 meters south of foot of Cornice Island, near mouth of Platte River, Jefferson Co., Mo. Elevation, 123^m.6392.

U. S. P. B. M. 26 is top of copper bolt leaded vertically in top of Robber's Rock, north side, and 1,736 meters above Rush Creek, Mo. Robber's Rock is large sandstone on beach, and is plainly visible for three miles of a mile up or down the river. Elevation, 124^m.6578.

U. S. P. B. M. 27 is center of copper bolt leaded horizontally in limestone wall (natural rock), at Rush Tower, Mo., and 11 meters from post-office building. Elevation, 126^m.6790.

U. S. P. B. M. 28 is top of copper bolt leaded vertically in large limestone bowlder on beach, 1,000 meters above Brickey's Mill, Cliff P. O., Ste. Genevieve Co., Mo. The beach is a little lower than extreme high-water mark. Elevation, 121^m.5487.

U. S. P. B. M. 29 is center of copper bolt leaded horizontally in limestone wall (natural rock) at end of bluff about 4 meters north of a red oak tree, about 30 meters north of ——— Maple's farm-house and three miles below Cliff P. O., Ste. Genevieve Co., Mo. This bench-mark is about one foot above surface of ground at base of bluff and is about 8 meters above high water-mark. Elevation, 131^m.0374.

U. S. P. B. M. 30 is center of copper bolt leaded horizontally in natural rock 1,500 meters above White Sand Depot Landing, Ste. Genevieve Co., Mo. It is about 20 meters north of southern end of bluff. The letters U. S. P. B. M. are cut near the bolt. Elevation, 124^m.6471.

U. S. P. B. M. 31 is center of copper bolt leaded horizontally in natural rock wall 14 meters north of a spring at Limestone Point, Ste. Genevieve Co., Mo., and is about 2 1/2 miles above Ste. Genevieve, Mo. The letters U. S. P. B. M. are cut around the bolt. Elevation, 122^m.9043.

U. S. P. B. M. 32 is top of copper bolt leaded vertically in west end of doorstep on south side of Rozier's warehouse, southwest corner Main and Washington streets, Ste. Genevieve, Mo. Elevation, 125^m.1543.

U. S. P. B. M. 33 is center of copper bolt leaded horizontally in south side at southeast corner of public school building in Ste. Genevieve, Mo., four inches from corner in fifth course of stones below the bricks. The letters U. S. P. B. M. are cut near the bolt. Elevation, 128^m.3151.

U. S. P. B. M. 34 is center of copper bolt leaded horizontally in east face of large corner-stone of engine-house of Quarrytown Grindstone Works, at Quarrytown, Mo., three miles below Ste. Genevieve, Mo. The letters U. S. P. B. M. are cut near the bolt. Elevation, 123^m.2542.

U. S. P. B. M. 35 is center of copper bolt leaded horizontally in west end of water-table in southwest corner of storehouse belonging to E. S. Lanbaugh, on northern corner of Second and Walnut streets, Ste. Mary's, Mo. The bolt is countersunk about 5 millimeters in the stone. The letters U. S. P. B. M. are cut near the bolt. Elevation, 124^m.6617.

U. S. P. B. M. 36 is center of copper bolt leaded horizontally in southwest corner of Martin Roundstone's ice-house on east side of Walnut street, Ste. Mary's, Mo. The letters U. S. P. B. M. are cut near the bolt. The bolt is in fifth course of stones from bottom. Elevation, 126^m.7787.

U. S. P. B. M. 37 is top of copper bolt leaded vertically in stone post set in ground in woods about 4 miles below Ste. Mary's, Ste. Genevieve Co., Mo. It is 990 meters back from river and 24 meters west of lane running south from river road. Lane turns off from river road in vicinity of John Lawrence's house. This bench-mark is S. 48° W. from farm-house, 7 meters N. 75° W. from ash tree, and 4½ meters N. 52° E. from box-elder tree. Elevation, 118^m.1124.

U. S. P. B. M. 38 is horizontal copper bolt in water-table of drug store northeast corner of Schuchert's Block, Chester, Ill. Elevation, 122^m.0907.

U. S. P. B. M. 39 is horizontal copper bolt in front face of Cole Brothers' stone elevator, 1.32 meters east of the southwest corner and the same distance above the ground, 1,240 meters below Chester, Ill. Elevation, 122^m.2673.

U. S. P. B. M. 40 is top of copper bolt in stone monument set in southeast corner of woods 576 meters back from a long lane just west of large wheatfield from turn of road, 40 meters north of farm-house of Marcus Peto. It is 2 meters south of elm tree 4 feet in diameter, 12 meters west from hackberry tree 18 inches in diameter, and 200 meters northwest of house not occupied. Elevation, 118^m.0519.

U. S. P. B. M. 41 is top of copper bolt in stone in ground 50 meters south of end of lane, 1 meter from fence, 1,420 meters back from river at Bois Brulé P. O., Perry Co., Mo. Elevation, 116^m.5760.

U. S. P. B. M. 42 is center of copper bolt set horizontally in vertical face of natural rock at upper extremity of bluff 643 metres below Grand Eddy post-office, Perry Co., Mo. It is about 3½ meters below upper end of U. S. water-gauge, and 14 meters below extreme upper point of the bluff rocks. The letters U. S. P. B. M. are cut in the rock near the bolt. Elevation, 119^m.4255.

U. S. P. B. M. 43 is center of copper bolt leaded horizontally in a large rock in the woods about 4 miles below Grand Eddy, Perry Co., Mo. It is 740 meters below a house, 175 meters back from the river, and 30 meters back from edge of timber, and at the upper end of a stretch of prairie land which extends down to 76 landing. Elevation, 118^m.7714.

U. S. P. B. M. 44 is top of copper bolt leaded vertically in a large boulder, 10 feet by 10 feet by 6 feet, 6 meters from edge of bank, 17 meters above second gate above farm-house of Napoleon Gill, 100 meters above barn on Cape Cinque Hommes, Perry Co., Mo., and 3¼ miles above Wittenberg, Mo. Elevation, 118^m.5512.

U. S. P. B. M. 45 is center of copper bolt leaded horizontally in stone foundation-wall of Wittenberg Flouring-Mill, at Wittenberg, Mo., on side facing the river between the ground-floor door and down-river corner of mill. Elevation, 116^m.5964.

U. S. P. B. M. 46 is center of copper bolt leaded horizontally in east face of rock, 2 meters east of road, 400 meters below Wittenberg, Mo. It is situated between the houses of Denny and Tucker, 23 meters from the former and 31 meters above the latter's house. It is 11 meters below Denny's shop and 29 meters above Tucker's barn. Elevation, 116^m.4716.

U. S. P. B. M. 47 is top of copper bolt leaded vertically in the point of rocks 95 meters below "Tower Rock," Perry Co., Mo., and opposite the upper end of Grand Tower, Ill. It is 15 meters east of an iron bolt leaded vertically in the rock and marked "U. S. 53." The letters U. S. P. B. M. are cut near the copper bolt. Elevation, 111^m.0031.

U. S. P. B. M. 48 is center of copper bolt leaded horizontally in face of rock at Birmingham Point, Perry Co., Mo. It is 813 meters above the mouth of Apple Creek, and 28½ meters above a scrubby, gnarled sycamore tree growing in the rocks. The rocks here are conglomerate in horizontal strata, and from the river present the appearance of a stairway. The letters U. S. P. B. M. are cut near the bolt in the rock. It is about 30 meters above a living spring, which comes up out of the gravel just below the strata of rock. Elevation, 110^m.0317.

U. S. P. B. M. 49 is top of copper bolt leaded vertically in the bluff rock 3,655 meters below mouth of Apple Creek, Cape Girardeau Co., Mo. In front of this bench-mark are three very large rocks standing out from the bluff and partly detached therefrom. Elevation, 110^m.2011.

U. S. P. B. M. 50 is center of copper bolt leaded horizontally in natural rock in river bluff 712 meters below rock called "The Devil's Tea Table," in Cape Girardeau Co., Mo. Elevation, 110^m.2257.

U. S. P. B. M. 51 is center of copper bolt leaded in the steeply-inclined face of the last reliable ledge of rocks of the chain extending south from Moccasin Springs, Mo., and at the point where the bluffs begin to recede from the river 2,500 meters above Bainbridge Creek. The letters U. S. are cut in the rock. Elevation, 109^m.1341.

U. S. P. B. M. 52 is a horizontal copper bolt set in vertical face of ledge of rocks 35 centimeters thick. The bolt is 1.2 meters above the ground, is 775 meters below Henry

T OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Shineman's house and 565 meters above the foot of the bluffs. These bluffs are 4 m above north end of Cape Rock, Cape Girardeau Co., Mo., $\frac{3}{4}$ mile from river, and land of Eliaba Sheppard's heirs. Elevation, 110^m.5744.

U. S. P. B. M. 53 is center of horizontal copper bolt, set in vertical face of ledge just below a ravine at the lower end of Cape Rock. Its elevation is about 1 meter above water. Elevation, 108^m.7640.

U. S. P. B. M. 54 is a horizontal copper bolt in the outer vertical face of a step, which extends under buttress at the northeast corner, second entrance from north, to Marble City Hotel, on Water street, Cape Girardeau, Mo. Elevation, 111^m.7496.

U. S. P. B. M. 55 is horizontal copper bolt in vertical face of good homogeneous hard rock, just below and near the southeast corner of St. Vincent's College, about 45 meters west of river, in south part of Cape Girardeau, Mo. Elevation, 114^m.77.

U. S. P. B. M. 56 is horizontal brass key, in vertical face of solid rock of fine hard homogeneous sandstone, or granite, very white when cut. Ledge forms bank of river, and is at lower end of Cape Girardeau, in front of St. Vincent College. It is about 35 meters east of railroad track. Elevation, 107^m.1247.

U. S. P. B. M. 57 is center of horizontal copper bolt, set in smooth vertical face in ledge of blue, or gray, limestone, at its upper, or western, extremity, on the land of the Taylor estate. It is 1 meter above the ground, 1 meter below top of vertical face, and disappears under the ground. It is 75 meters from the creek, and 1,574 meters above low water. U. S. water-gauge at Gray's. Elevation, 110^m.9056.

U. S. P. B. M. 58 is center mark in vertical face, looking toward the river, of largest of which forms the bank or "Standing Rock of the Grand Commerce," 80 meters above the line between Wray's Landing on the land of H. S. Wray, 600 meters above Commerce, Mo. It is about 0.6 meters above the ground. The letters U. S. P. B. M. are cut in the rock. Elevation, 110^m.9056.

U. S. P. B. M. 59 is the center of a vertical copper bolt leaded in the steep face of a large silicious rock mostly covered with earth, being one of a group of many in a ravine 1,190 meters above U. S. P. B. M. 58, and about 60 meters back from the river, the ground rising in this distance 15 meters. It is in a shallow, rocky ravine at upper side of the first strip of cultivated land, near the river, south of the bluff on land of Mrs. C. Halfner. The letters U. S. P. B. M. are cut in the rock. Elevation, 118^m.7540.

U. S. P. B. M. 60 is point in center of horizontal copper bolt leaded in vertical face of ledge, looking toward the river 0.55 metres above the ground and 3.37 metres above the high water of 1858. The top surface of this rock or ledge, which extends across the street, forms the road bed. It is just in front of a point about 30 meters above Wm. Anderson's large brick house on elevated site at the north or upper end of Commerce, Mo. There are a large number of large pieces of rock lying on the bank here that have from time to time rolled down from the same general ledge, but the one selected is so large and extends back in the bank so far that it is reliable. Elevation, 110^m.5032.

U. S. P. B. M. 61 is center of horizontal copper bolt set in front or east face of foundation of Wm. Anderson's large brick dwelling-house at the upper end of Commerce, Mo. It is 2 meters north of center of front entrance and 36 centimeters above the ground. Elevation, 116^m.6307.

U. S. P. B. M. 62 is mark in center of horizontal copper bolt set in the vertical face of the northwest abutment of stone culvert under road over Muddy Creek, 1 meter above the ground, 75 meters from the top of the river bank and 1,960 meters above Santa Fé Store, which latter is opposite Commerce, Mo., in the State of Illinois. The foundation or masonry rests on the natural rock. The letters U. S. P. B. M. are cut in the rock near the bolt. Elevation, 104^m.6078.

U. S. P. B. M. 63 is 185 meters right up the same creek (Muddy Creek) in the left hand ravine going up from the culvert in which is U. S. P. B. M. 62. It is center of copper bolt set in vertical face of a very large rock on part of the ledge just on the right of the creek going up, 1.5 meters above the ground, 1.5 meters below the top of the rock, and 2 meters from the projecting end. Elevation, 108^m.7967.

U. S. P. B. M. 64 is top of copper bolt in top of stone in ground 1,260 meters back from river, 1 meter north of fence on north side of road leading east from Goose Island P. O., or Atherton's Landing, about 19 miles above Cairo, Ill. Elevation, 107^m.5416.

U. S. P. B. M. 65 is top of copper bolt in top of stone in ground in woods about 1,500 meters back from river, and $8\frac{1}{4}$ miles above Cairo Post-Office, Alexander Co.

It is 26 meters from graded road (otherwise known as levee), and 93 meters school-house for negroes, and $2\frac{1}{2}$ miles below Spies' Mills. Elevation, 103^m.4605. P. B. M. 66 is top of copper bolt in stone post in open woods. It is 61 meters a point on the I. C. R. R., which point on the railroad is 391 meters north of three-mile post" from Cairo, Ill. Elevation, 101^m.4777.

LOCATION OF PERMANENT BENCH-MARKS BETWEEN KEOKUK, IOWA, AND GRAFTON, ILL.

P. B. M. 1 is top of copper bolt leaded vertically into coping of shore side of rock of Des Moines Rapids Canal, Keokuk, Iowa. Bench is in recess between steps and stone pier of lower hydraulic tower, on south side of pier. Elevation, 570.

P. B. M. 2 is copper bolt leaded horizontally in south face of Iowa shore pier bridge, Keokuk, Iowa, 8 inches above bench of pier, in the tenth stone from pier. Elevation, 156^m.7516.

P. B. M. 3 is copper bolt leaded horizontally in southwest corner of three-story building, owned by Mr. Patterson, facing on Water street, second door from corner of Johnson street, Keokuk, Ia., 8 inches above west door-sill, on inner side of outer wall 10 feet from corner of Water and Johnson streets. Elevation, 161^m.3896.

P. B. M. 4 is small conical hole in rock at intersection of cross-cut in upper part of top stone of buttress of Des Moines River bridge. Elevation, 158^m.4243.

P. B. M. 5 is copper bolt leaded horizontally into north wall of brick building, from northeast corner, and three feet from ground. Building is in upper end of slough, facing river, and 60 feet from bank. The north wall faces slough opening into river, and 50 meters from it. Building owned by Chas. Bocker; postulated in building. Elevation, 158^m.0087.

P. B. M. 6 is copper bolt leaded horizontally in upper corner of stone masonry at side of northeast corner of Baptist Church at Gregory's Landing, Mo. It is 150 meters north from junction of railroad and wagon road. Elevation, 1390.

P. B. M. 7 is copper bolt leaded vertically in marking-stone set at root of oak 1.7 meters west of railroad. Stone is 1.7 meters west of tree in northeast corner of field, 10 meters south of small ravine, 650 meters below bridge No. 14. Tree is 12 inches in diameter. Elevation, 157^m.2349.

P. B. M. 8 is copper bolt leaded horizontally in north wall of Down's Hotel, Keokuk, Mo. Bolt is in fifth stone from ground, fourth stone from corner of wall made of brick door entrance, and in second stone from first window west of office entrance. It is on southwest corner of Lewis and Fifth streets. Elevation, 156^m.7856.

P. B. M. 9 is copper bolt leaded horizontally in east side of back foundation of a Methodist Episcopal Church, corner of Sixth and Washington streets, Canaan, Mo. Bolt is in third stone from ground and in second from north corner, and under window facing east. Elevation, 156^m.5849.

P. B. M. 10 is copper bolt leaded vertically in top surface of southeast corner of abutment of railroad bridge No. 35 over Wyaconda Creek. Bolt is 2 feet from face, 4 feet from east face of abutment, and about 1 mile above La Grange, Mo. Elevation, 153^m.6120.

P. B. M. 11 is copper bolt leaded horizontally in northeast corner stone of Berry & Schneider's tobacco works, situated on southwest corner of Washington street and K and St. L. R. R. at Lagrange, Mo. Bolt is in east face, 15 inches from corner of stone and 2 feet from ground. Elevation, 153^m.5792.

P. B. M. 12 is center of copper bolt leaded horizontally in third course of masonry at bottom and ninth from top of west abutment of Quincy R. R. bridge, West Plains, Mo. Bolt is in north face 2 inches from east corner. Elevation, 151^m.7187.

P. B. M. 13 is copper bolt leaded vertically in top surface of top stone of north corner of north pier forming south face of north abutment of covered railroad over the Fabius River. Bolt is near the center of stone 5 feet below and 8 feet from rail. Elevation, 151^m.9146.

P. B. M. 14 is top of copper bolt leaded vertically in top surface of stone, form-end of north pier to railroad bridge over North River. Bolt is 8 inches from edge of stone, 2 feet from west edge, and 14 inches from base of strut. Elevation, 150^m.8065.

P. B. M. 15 is copper bolt leaded vertically in stone post set in northeast corner of field, 5 meters from wagon road, 15 meters west of railroad, 20 meters from one of two elm trees standing alone in wagon road, fence forming line between cultivated and ground, 466 meters north of Hilton Station. Elevation, 149^m.7508.

P. B. M. 16 is copper bolt leaded horizontally in face of natural rock at east end of tunnel at Missouri end of railroad bridge at Hannibal, Mo. Bolt is in

LIST OF THE CHIEF OF ENGINEERS, U. S. ARMY.

and on south side of tunnel, 7 feet south of entrance and about 4 feet from west end of tunnel. Elevation, 155^m.2651.

17 is copper bolt leaded vertically in top surface of east stone of small railroad bridge 1 mile below Hannibal, Mo., and 50 meters west of Mr. Johnson. Elevation, 147^m.8009.

18 is copper bolt leaded vertically in top of top course of masonry north end of principal abutment of railroad bridge across Lick Creek depot at Saverton, Mo. Elevation, 147^m.3401.

U. S. P. L. 19 is marking-stone planted in corner of yard of Catharine Hay, 1½ miles south of Saverton, 1¼ miles above Ashburn. Stone is 8 meters southwest corner of house, and 25 meters from river bank, a little below dam at Bert's Island. Elevation, 151^m.7497.

U. S. P. B. M. 20 is copper bolt set vertically in top of marking-stone set on east side of rail fence 8 meters east of large maple tree on east bank of small creek bed, 3 meters north of bridge over creek. Stone is 7 meters south of wagon road, 17 meters west of railroad, 23 meters south of south corner of house of Mr. Warner, and ¼ mile north of Ashburn, Mo. Elevation, 150^m.5762.

U. S. P. B. M. 21 is marking-stone planted in east edge of cultivated field about 100 meters from south bank of Salt River, at place where Keokuk and Saint Louis Railroad crosses the river. Stone is set about 10 meters to the west of track, nearly opposite the south end of the trestle. Elevation, 145^m.2055.

U. S. P. B. M. 22 is copper bolt set vertically in marking-stone in south corner of fence on east and west fence. Stone is set on east and west fence. Stone is set on east and west fence. Stone is set on east and west fence. Elevation, 148^m.9719.

U. S. P. B. M. 23 is copper bolt set horizontally in first layer of stone in northeast corner of Water and Power Building north of door in same wall of building. Elevation, 148^m.9719.

U. S. P. B. M. 24 is copper bolt set vertically in top surface of top stone of railroad bridge over Mississippi River. Elevation, 148^m.6907.

U. S. P. B. M. 25 is center of copper bolt in side of natural rock 7 meters south of railroad, 9 meters west of railroad bridge across Mississippi River at Ashburn. Elevation, 147^m.2828.

U. S. P. B. M. 26 is copper bolt leaded vertically in top of marking-stone set at intersection of two fences on south side of lane and west of railroad. Lane is 5 meters wide. The north fence stops before it reaches as far east as the south fence. A small creek is 3 meters north of the north fence. A row of apple trees is just inside the north fence. Stone is 5½ meters west of railroad and 15 meters west of river; about 60 meters east of old log-house of Peter Yaeger, and about 3 miles above Clarksville, Mo. Elevation, 146^m.6472.

U. S. P. B. M. 27 is center of horizontal copper bolt leaded in the natural rock side of small bluff bank 3½ meters east of railroad track, below wagon road, 12 meters from river bank, 440 meters above vinegar works at Clarksville, Mo., and 120 meters below mouth of Calumet Creek. It is between railroad and house of Philip Beda. Elevation, 148^m.0183.

U. S. P. B. M. 28 is copper bolt leaded horizontally in the southeast corner stone of Carroll House, Clarksville, Mo. Stone is at the head of stairs leading to basement. Bolt is set in south face of stone about 10 inches above the sidewalk. Elevation, 146^m.5610.

U. S. P. B. M. 29 is top of copper bolt leaded vertically in top surface of marking-stone set in the ground 5 meters east of the Sny Levee, opposite Clarksville, Mo., about 50 meters east of ferry landing in Calhoun County, Illinois. Stone is 220 meters along the levee below where levee crosses chute. Elevation, 142^m.8844.

U. S. P. B. M. 30 is copper bolt leaded vertically in top surface of marking-stone set in the ground on east side of Sny Levee at intersection of plantation road, on south side of river, which crosses levee and continues to the river. Levee is 50 meters east of river. A large elm stump 6 feet in diameter and 10 feet tall stands in the road 20 meters west of levee. Stone is opposite Island No. 463, about one-third its length above the lower end, and about 3¼ miles below U. S. P. B. M. 29, opposite Clarksville. Elevation, 142^m.8681.

U. S. P. B. M. 31 is copper bolt leaded vertically in top of marking-stone set on east side of levee at its base, 4 meters east of the middle of levee, in fence corner closing field with woods on north side and levee on west side. It is about 100 meters east of river and 175 meters northwest of house occupied by Mr. Gain and owned by Messrs. Rock and Baker. Elevation, 142^m.0102.

U. S. P. B. M. 32 is conical hole in top surface of rock projecting from side of wagon road, about half way up steep hill on north bank of small stream, 10 meters north of middle of stone culvert. Rock is at root of two poplar trees growing about 1 foot apart. Bench is at intersection of cross, 6 inches from west edge and 10 inches from south edge of rock, and about 50 meters east of east shore of Hamburg Bay. Elevation, 148^m.6000.

U. S. P. B. M. 33 is top of copper bolt leaded vertically in top surface of natural rock projecting from east side of wagon road about 240 meters south of house of Mr. Blacksmith, and about 4 miles north of Hamburg, Ill. The bolt is 18 inches from corner, and 10 inches from the two sides of the stone, only one corner of which projects. Elevation, 163^m.0372.

U. S. P. B. M. 34 is copper bolt leaded horizontally in the north face of natural rock forming south side of the first creek south of Hamburg, Calhoun County, Illinois. Bench is about 120 meters east on road from where the road makes a sharp bend from south to east. There are a mill and two houses at the turn of the road. Bench is about 5 meters north of fence around orchard. Bolt is about 1 foot below the top surface of rock, and about 4½ feet above creek bottom, which is of stone. Rock is in layers, the bolt being in top layer. Elevation, 141^m.6910.

U. S. P. B. M. 35 is point 1½ inches from south corner and ¼ inch from east side of shore line triangulation stone set by Assistant Engineer John Eisenmann. Stone is 38 meters east of river bank, about 250 meters below Island No. 482, and 3½ meters north west of large elm tree marked with two triangles opposite midway between two houses on Westport Island. Elevation, 139^m.9151.

U. S. P. B. M. 36 is top of copper bolt leaded in the top of marking-stone set about 8 meters from the river bank, on the Illinois shore, a short distance south of a point opposite the head of Islands Nos. 487, 486, and 485, and about 1,190 meters above warehouses at Red's Landing, Calhoun County, Illinois. It is ½ meter south of lower fence of two on land of one Ira Lawson, about opposite the head of the aforesaid islands, and about 50 meters north of the boundary line between the land of the above-named Ira Lawson and the land of one John M. Lewis. Elevation, 139^m.6604.

U. S. P. B. M. 37 is cross about in the middle of triangulation stone set by Assistant Engineer John Eisenmann at the root of a large poplar tree about 10 meters from small house and 5 meters from fence surrounding house. The house is opposite the foot of Sterling Island. Elevation, 139^m.5688.

U. S. P. B. M. 38 is top of marking-stone set by Assistant Engineer John Eisenmann 1½ meters west of foot of sycamore tree blazed and marked with a triangle. Stone is 50 meters east of river bank and 27 meters east of road running to Hogville. It is about 800 meters south from Church's Landing, and about 400 meters north from warehouses at Hogville Landing, Calhoun County, Illinois. Elevation, 138^m.7069.

U. S. P. B. M. 39 is top of copper bolt leaded vertically in top of marking-stone set in the ground ½ meter inside the fence on the west side of the field of J. H. Eildemann, about 100 meters north from upper landing warehouse at Turner's Landing, Calhoun County, Illinois. Elevation 139^m.5747.

U. S. P. B. M. 40 is top of triangulation shore line marking-stone set by Assistant Engineer John Eisenmann about 90 meters back from Illinois bank of Mississippi River, about 600 meters south of foot of Island No. 197, and about 2,900 meters south from the lower Turner's Landing warehouse. Elevation, 138^m.6351.

U. S. P. B. M. 41 is center of copper bolt leaded horizontally in solid sand rock above and back of the road, 74 meters east and below top of a hill at point of bluff at West Point, Calhoun County, Illinois, facing the north. It is about 1 meter above level of road, and is about 150 meters around the point from the warehouse at West Point. Elevation, 141^m.9651.

U. S. P. B. M. 42 is center of copper bolt leaded horizontally in the north face of large boulder rock, imbedded partly in the ground about 40 meters around east from northwest corner of the bluff rocks below Hastings' Landing, Calhoun Co., Ill., about 225 meters below warehouse on the land of E. B. Brown. It is third large boulder at foot of hill on the north side of corner west from the top of bank of small branch that empties in the river below the warehouse, and is about 8 meters east from fence that leads about southwest from the east side of warehouse at landing. Elevation. 141^m.0863.

U. S. P. B. M. 43 is center of copper bolt leaded horizontally in the west face of bluff rock about 2½ meters underneath where the upper surface of rocks commence to be exposed at the foot of the hill, about 20 meters around north on west side of hill from southwest projecting corner of the bluffs on the north side of the valley, second one north of Martin's Landing, Calhoun Co., Ill., and first one south of valley where John Zarley lives. Elevation, 138^m.9003.

U. S. P. B. M. 44 is center of horizontal copper bolt set in solid bluff rock facing northwest about 900 meters south of Martin's Landing, and about 1,300 meters north of Miller's Landing, Calhoun Co., Ill. It is about 500 meters below a dwelling-house. The bolt is in the upper stratum of exposed rock. Elevation, 138^m.7755.

REPORT OF THE SURVEY OF THE U. S. ARMY.

... solid bluff rock at ... east end of the coal mine.

... west end of solid bluff rock at high water's edge at high ... one mile below

... solid bluff rock about ... Point Landing, 25 ... Navar about 5 meters below ... Navar's dwelling.

REPORT OF THE SURVEY OF THE U. S. ARMY.

... top of west wall of ... Iowa. Eleva-

... top of west wall ... U. S. P. B. M. Ele-

... top of west wall ... U. S. P.

... west end of south ... of Vile Station,

... northeast corner stone of ... mile south of

... aboutment of ... of Vile Station, Iowa.

... bolt leaded vertically ... It is near the ... 168^m.9910.

... bolt set ... on north- ... chimney. ... 170^m.5628.

... Madison, Iowa. ... stone on ... west of C.,

... Shank River, 9 ... in north

... 4 miles south of ... in copper ... from the ground.

... bridge, in natural ... saw-mill, is 4 ... in copper ... Marked U. S. P.

... bridge over ... vertically in

... of copper ... M. 49 is on ... 42^m.9.

... Slough, ... Marked U. S. P.

... about 4 1/2 miles

of the east end of the Burlington bridge, on the line of the C., B. & Q. R. R. of copper bolt leaded vertically in abutment. Marked U. S. P. B. M. Elevation, 1635.

P. B. M. 17 is on Robt. Moir's brick store building at Oquawka, Ill. It is center in copper bolt leaded horizontally in stone pillar at southwest corner, about above the water-table. The building stands on the northwest corner of First and Second streets, and is also used for the Journal office. Marked U. S. Mackenzie B. M. 48 is on step of same building. Elevation, 169^m.5262.

P. B. M. 18 is on brick building on the southeast corner of Third and Schuyler at Oquawka, Ill. It is center of hole in copper bolt set horizontally on east side of northwest corner, 2½ feet above the ground. Marked U. S. P. B. M. Elevation, 173^m.1367.

P. B. M. 19 is on brick building on the northwest corner of Main and Second at Keithsburg, Ill. It is top of copper bolt leaded vertically in stone step on east side of the building, and marked U. S. P. B. M. The building is owned by J. W. Keith, and used for a furniture store. Elevation, 170^m.6252.

P. B. M. 20 is on step of Mr. Rife's brick dwelling on the northwest corner of Third and Fifth streets, Keithsburg, Ill. It is top of copper bolt leaded vertically in stone step on southwest corner of upper stone step on south side of house, and is not marked. Elevation, 173^m.6488.

P. B. M. 21 is on foundation of water-tank 2 miles east of New Boston, Ill., on line of C., B. & Q. R. R. It is center of hole in copper bolt set horizontally on east side of tank, under a strut, below top of foundation. It is 150 meters east of railroad bridge over Edwards' River. Marked U. S. P. B. M. Elevation, 172^m.2639.

P. B. M. 22 is on foundation of Keokuk Northern Line Packet Company's wharf at New Boston, Ill. It is center of hole in copper bolt set horizontally in north wall near the northeast corner in top of stone foundation, 0.7 meter from northeast corner. Marked U. S. P. B. M. Elevation, 172^m.2639.

P. B. M. 23 is on Union Hotel, New Boston, Ill. It is center of hole in copper bolt set horizontally in north wall, 0.4 meter from the northeast corner and 1.1 meters from the northeast corner. Marked U. S. P. B. M. Elevation, 180^m.0117.

P. B. M. 24 is on top of southeast corner of stone foundation of tall chimney of mill at Port Louisa, Iowa. Mill now torn down. This is the same bench-mark as Mackenzie B. M. 45. Elevation, 172^m.3074.

P. B. M. 25 is top of stone set in ground 22 meters south of gate leading to Esq. house, 7½ miles south of Muscatine, Iowa. Stone is a height of high water of 2½ meters north of wagon road, and 15 meters from edge of river bank. A stone set over the stone, three marking-stakes set 3 feet off, and three small black trees blazed near by. Stone is said to have been set by Major Allen several years ago. Top of stone is about 1 foot below the surface of the ground. Elevation, 170.

P. B. M. 26 is on brick foundation of Mr. E. Beatty's dwelling on right bank of river about 7 miles below Muscatine, Iowa. It is center of hole in copper bolt set horizontally in east side of northeast corner of foundation. Marked U. S. P. B. M. Elevation, 175.2544.

P. B. M. 27 is on brick chimney of Hershey's lower saw-mill, Muscatine, Iowa. It is center of hole in copper bolt set horizontally on the middle of the east face of chimney, 3 feet above ground. Marked U. S. P. B. M. Elevation, 173^m.8371.

P. B. M. 28 is on water-works chimney, at Muscatine, Iowa. It is center of hole in copper bolt set horizontally in north face of chimney, about 1.1 meters from the northeast corner. Marked U. S. P. B. M. Elevation, 174^m.2068.

P. B. M. 29 is on north abutment of wagon bridge, 50 meters north of station at Muscatine, Iowa. It is top of copper bolt set vertically in northeast corner of abutment. Marked U. S. P. B. M. Elevation, 174^m.4349.

P. B. M. 30 is on abutment of C., R. I. & P. R. R. bridge, 3 miles north of Muscatine, Iowa. It is top of copper bolt set vertically in top of stone coping of south end of abutment. Marked U. S. P. B. M. Elevation, 174^m.7935.

P. B. M. 31 is on abutment of C., R. I. & P. R. R. bridge over Sweetland Creek, 5 miles north of Muscatine, Iowa. It is top of copper bolt leaded vertically in east side of north abutment. Marked U. S. P. B. M. Elevation, 174^m.5547.

P. B. M. 32 is in natural rock on line of C., R. I. and P. R. R., about 6 miles above Muscatine, Iowa. It is center of hole in copper bolt set horizontally in face of rock, which has been blasted off for railroad bed. It is 4 feet above the track, 20 feet from center of track, and 740 meters west of bridge 77. Marked U. S. P. B. M. Elevation, 177^m.1881.

P. B. M. 33 is on foundation of pottery owned by John Feasted, at Fairport, Iowa. It is center of hole in copper bolt set horizontally in west side, near southeast corner of stone foundation. This pottery is about 350 meters above railroad bridge and near the river bank. Marked U. S. P. B. M. Elevation, 175^m.3891.

U. S. P. B. M. 34 is on middle pier of bridge over Pine Creek, about 2 miles north of Montpelier, Iowa, on the line of the C., R. I. and P. R. R. It is top of brass bolt lead vertically in north end of pier. Bridge is No. 60. Marked U. S. P. B. M. Elevation, 175^m. 0998.

U. S. P. B. M. 35 is on south pier of C., R. I. and P. R. R. bridge No. 52, 1 kilometer south of Montpelier, Iowa. It is top of brass bolt set vertically in west end of pier. Marked U. S. P. B. M. Elevation, 178^m. 3111.

U. S. P. B. M. 35 a is on west abutment of C., R. I. and P. R. R. bridge No. 45, about 1 mile east of the depot at Montpelier, Iowa. It is top of brass bolt lead vertically in south end of abutment. Marked U. S. P. B. M. Elevation, 175^m. 9233.

U. S. P. B. M. 36 is on Wm. Karge's brick store and post-office building at Boone, Iowa. It is center of hole in brass bolt lead horizontally in the east side, at southeast corner, 3 feet above the foundation. The building is on the northwest corner of Hecker and Second streets. It is unmarked. Elevation, 178^m. 4006.

U. S. P. B. M. 37 is on foundation of brick house of Eliza M. Dodge, $\frac{1}{4}$ mile east of Buffalo, Iowa. It is center of hole in brass bolt set horizontally in upper foundation stone on west side, near southwest corner, about 1 meter from ground. House stands about 100 meters north of line of C., R. I. and P. R. R. Marked U. S. P. B. M. Elevation, 179^m. 4669.

U. S. P. B. M. 38 is on foundation of vinegar works at lower end of West Day port, Iowa, near the river bank. It is center of brass bolt set horizontally in west side, near the southwest corner, about 0.4 meters from ground. Marked U. S. P. B. M. Elevation, 179^m. 0291.

U. S. P. B. M. 39 is on north abutment of Rock Island and Davenport Railroad bridge over the main channel of the Mississippi River. It is top of copper bolt lead vertically in coping of east or upper side of abutment, on a plane with the sidewalk. It is 4.1 meters from river face of abutment, and 0.1 meter inside of railing. Marked U. S. P. B. M. Elevation, 180^m. 8749.

U. S. P. B. M. 40 is on base of stone tower of U. S. arsenal stone building, A, M, at lower end of Arsenal Island. It is center of hole in copper bolt lead horizontally in east side of northeast corner, about 4 feet from the ground. Marked U. S. P. B. M. Elevation, 182^m. 1139.

U. S. P. B. M. 41 is on foundation of the Atlantic Brewery, near C. R. I. and P. R. depot at Rock Island, Ill. It is center of hole in copper bolt set horizontally in upper foundation stone on the north side at the northeast corner. Marked U. S. P. B. M. Elevation, 183^m. 3053.

U. S. P. B. M. 42 is on south abutment of wagon-bridge crossing from Moline, Ill. to head of Rock Island. It is top of copper bolt set vertically on east end of abutment. Marked U. S. P. B. M. Elevation, 179^m. 5708.

U. S. P. B. M. 43 is on brick basement of H. Smith's dwelling-house at Watertown, Ill. It is center of hole in copper bolt lead horizontally in the west side near the northwest corner. The house stands 50 meters southeast of the C., M. and St. P. R. depot. It is marked U. S. P. B. M. Elevation, 181^m. 4283.

U. S. P. B. M. 44 is on brick school-house at Hampton, Iowa. It is center of hole in copper bolt set horizontally 0.5 meters from ground on east side near southeast corner of large new public-school building. It is marked U. S. P. B. M. Elevation, 182^m. 9968.

U. S. P. B. M. 45 is on stone foundation of Baker and Hayward's brick store building on levee at Hampton, Ill. It is center of hole in copper bolt lead horizontally in north side of northwest corner of building, and is at the H. W. mark of 1890. Marked U. S. P. B. M. Elevation, 179^m. 9437.

U. S. P. B. M. 46 is on stone foundation of H. M. Gilchrist's brick store building at Rapids City, Ill. It is center of hole in copper bolt lead horizontally in west side of northwest corner, 4 feet above ground. The building is on the river bank. Marked U. S. P. B. M. Elevation, 181^m. 8416.

U. S. P. B. M. 47 is on abutment of bridge of C, M. and St. P. R. R. over Barber Creek, $\frac{1}{4}$ mile south of Port Byron, Ill. It is top of copper bolt lead vertically in west end of north abutment. Marked U. S. P. B. M. Elevation, 182^m. 9513.

U. S. P. B. M. 48 is on foundation of Mr. N. Dorrance's brick store building at Port Byron, Ill. It is center of hole in copper bolt lead horizontally in west side of southwest corner of stone foundation, and marked U. S. P. B. M. The building stands between Main street and the R. R. track, and about 75 feet from the river bank. Elevation, 183^m. 4013.

U. S. P. B. M. 49 is on iron doorstep of new brick store building of A. H. Wandt at Port Byron, Ill. It is top of north bolt head of front row of bolts on south doorstep on east side of building on east side of Main street. Bolt-head marked with a cross cut through its center by a cold-chisel. Marked U. S. P. B. M. on bricks below. Elevation, 185^m. 2033.

U. S. P. B. M. 50 is on stone warehouse of Northern Line Packet Co., at Cordova, Ill. It is center of hole in copper bolt set horizontally in south side, near southwest corner.

miles north of Albany, Ill. It is center of hole in copper bolt leaded horizontally into the base of cliff 1 foot above ground and about 3.5 meters above a road, and marked U. S. P. B. M. It is 15 meters east of wagon-road and 90 feet of C., M. and St. P. R. R. Elevation, 182^m.6009.

P. B. M. 54 is on abutment of C., M. and St. P. R. R. bridge, 2½ miles north of Ill. It is top of copper bolt set vertically in west side of south abutment. C. S. P. B. M. Elevation, 182^m.2995.

P. B. M. 55 is on south abutment of bridge over Cat Tail Creek of C., M. and St. P. R. It is top of copper bolt set vertically in top of east end of abutment. Edge is just south of the line of the C., B. and Q. R. R., and about 2 miles south of Ill. Elevation, 183^m.2978.

P. B. M. 56 is on east end of north abutment of C., M. and St. P. R. R. bridge at Tail Creek, 2 miles south of Fulton, Ill., and about 200 meters south of St. Q. R. R. crossing. It is top of copper bolt set vertically in top of abutment. Elevation, 183^m.6809.

C 1.

OF ASSISTANT ENGINEER L. L. WHEELER, UPON CUMULATIVE ERRORS IN PRECISE LEVELING.

SAINT LOUIS, October 6, 1883.

I have the honor to submit the following report upon the results of investigation of the subject of cumulative errors in leveling.

Investigation was commenced some time since, and an incomplete report made of the results obtained, with the intention of completing the report when additional data, which was being reduced, should be available. In the meantime, considerable additional field-work has been done, under instructions from yourself to continue the operations in such a manner as to throw additional light upon the subject. The notes of this work have been reduced, and the results show either that the discussion has had a practical value in avoiding operations which introduced cumulative errors in the work, or that the observers had attained a proficiency not previously shown.

The preliminary report has been read by those interested in the subject, some corrections have been noted, and some sharp criticisms made. I have, therefore, in writing this report, had the advantage of these facts and the additional data at hand, and have endeavored to show more clearly that the results of leveling operations may be vitiated by such large cumulative errors as to make them unreliable, and that these cumulative errors may be avoided by proper care in the field-work.

The fact that errors appear in the results of leveling which are nearly constant in amount has frequently been noticed and various theories have been advanced.

... point is the sum of all the errors ...
 ... a single polygon, we would be ...
 ... errors or to some general ...
 ... however, an observer had ...
 ... showed a preponderance ...
 ... of some law of the distribu ...
 ... the same time it must be ...
 ... errors, to which all obser ...
 ... be so large as to apparently ...
 ... series of observations, however ...
 ... while the existence of a gen ...
 ... It frequently happens ...
 ... that the arrangement of the ...
 ... some law of distribution, bu ...
 ... further extended. In this di ...
 ... used to base conclusions upon ...
 ... the portions of the discussion

... more clearly ... relative errors in the example ...
 ... sums of ... point in the line and plotted ...
 ... as abscissas.

... consecutive accidental errors ...
 ... same sign, the ... curve to one side of the mean ...
 ... been counterbalanced by acci ...
 ... explain the sinusoidal form which ...
 ... in any series ...
 ... as has been the case here.

... leveling lines in opposite direc ...
 ... also true of different observer ...
 ... the relative errors would b ...
 ... given on page 425 of "*Nivellement de la Suisse*," ...
 ... leveled the entire perimete

... The polygon has 4 sides, and ...
 ... The discrepancies between ...
 ... positive, 8 negative, and 2 equal t ...
 ... at the end is $+247^{mm}.2$

... results obtained by the tw ...
 ... but in this case we hav

... too great a ...
 ... by $2^{mm}.6$. The mean ...
 ... by $95^{mm}.3$; or the secon ...
 ... It is evident, ther

... caused by errors of th ...
 ... may be applied to this poly ...
 ... than those of the se ...
 ... were in operatio ...
 ... whole polygon.

... between the north and south line ...
 ... Columbus and Memphis, and between Friar

... are not consecutive, but are sea ...
 ... about 404 kilometers. They at ...
 ... The abscissas are twice the sun ...
 ... and the ord ...
 ... The dotte ...
 ... mean line dete ...
 ... different equation ...
 ... of the observatio ...
 ... of observation.

... north and south lines le ...
 ... The ... give ...
 ... consecutive.

... leveled l ...
 ... The line ...
 ... were not ...
 ... not be ...
 ... a straight

... which th

vergence continued for 110 kilometers.

> all attempts to arrive at a value of the precision of levels have been based on the assumption that the errors increase with the square root of the distance. This assumption would be true if accidental errors were the only ones made, if the number of observations were strictly proportional to the distance leveled. As of discrepancies between results in instructions for precise leveling have been based on the same principle, and are open to the same objection. It has frequently been noticed that while the results of each of a number of lines leveled were in limits which were prescribed to be in proportion to the square root of the distance, yet when the sum of several lines was considered, the total discrepancy exceeded the limit prescribed. In other words, the errors were not proportional to the square root of the distances and did not follow the law of distribution of accidental errors. Plus and minus errors were not equally prevalent.

It is conclusively shown by results given on the plots referred to. Numerous examples of this unequal distribution of errors may be found in published reports of the U. S. Lake Survey, and in the results of levels in Switzerland, Germany, and India.

Examination of the several plots shows that the results there given are affected by systematic errors, that these errors vary in sign and amount with different observers, with the exception of that on Plate III, that they are nearly if not quite proportional to the distance leveled. Theoretically, if the results of levels were affected by systematic error, the effect of that error would be proportional to the number of observations or instrument stations; but these are so nearly proportional to the distance, that the distance has been substituted for the number of observations in this discussion. Since the cumulative errors vary with different observers, they have been called personal errors.

In a study of all the reliable levels at hand, we are led to believe that the error in a polygon is made up of two parts: First, a constant error which is proportional to the perimeter, and may be determined with more or less precision from all polygons leveled; and, second, the sum of the accidental errors to which all observations are subject. Having made this assumption, what follows are but logical consequences from it, and the proof of the assumption will lie in the results obtained when applied to practical examples.

Let $2K$ = equal the perimeter of a polygon,

$a - s$ = the error of closing the polygon,

x = the personal error of the observer,

and e = the sum of the accidental errors in the polygon.

Each polygon would give an equation of the form

$$2Kx - (a - s) = e$$

In all the equations we would obtain the normal equation

$$[4K^2]x - [2K(a - s)] = 0.$$

rections, can be determined with four times the precision that the relative personal equation of two observers can be obtained from the same lines leveled once by each observer. In the case of a single observer, the sign of the error is determined, and the error eliminated from the mean of results in both directions, while with two observers we are in ignorance as to the sign and amount of the error made by each, and hence, of the error remaining in the mean, unless we have additional evidence. From this we arrive at the practical conclusion that each observer should duplicate his work in opposite directions.

Having obtained the value of x (or x') from equations (2) or (4) and substituted in the several equations, the several values of v are obtained.

Let r_0 = probable error of a single observation upon the value of x ,

$[vv]$ = sum of the squares of the several values of v ,

n = number of observations = number lines leveled.

$$(5) \text{ Then, } r_0 = \pm 0.6745 \sqrt{\frac{[vv]}{n-1}}$$

Having found r_0 we may compute the probable error of the unknown quantity by the formulæ

$$(6) \quad r_x = \frac{r_0}{\sqrt{p}}, \quad p_x \text{ being the weight of } x.$$

The formulæ obtained above relate to either (2) or (4), but what follows relates to (2) alone. Since the several values of v represent the accidental errors of observations, and as these are proportional to the square root of the number of observations we have, letting $n, n_1, n_2, \&c.$, represent the number of observations (instrument stations.)

$$\frac{v_1 v_1}{n_1} = \frac{v_2 v_2}{n_2} = \frac{v_3 v_3}{n_3} \&c., = \frac{v_m v_m}{n_m}$$

Since, however, in any particular case, the values of n will be very nearly proportional to the distances, we may write

$$\frac{v_1 v_1}{2K_1} = \frac{v_2 v_2}{2K_2} = \frac{v_3 v_3}{2K_3} \&c. = \frac{v_m v_m}{2K_m}$$

The expressions $\frac{v_1 v_1}{2K_1}, \frac{v_2 v_2}{2K_2}, \&c.$, represent the squares of the errors of closing

polygons whose perimeters equal unity, which is here taken as one kilometer. We find, then, the probable error of closing a polygon whose perimeter equals one kilometer, or what is the same thing, the probable error of a single leveling per kilometer, we have

$$(7) \quad r = \pm 0.6745 \sqrt{\frac{1}{n} \left[\frac{vv}{2K} \right]}$$

r may be taken as a measure of the precision of an observer's work, but in comparing different observers' work it should be remembered that the relation of n to $2K$ may be quite different for different observers.

One observer may make his observations under such conditions as to necessitate the mean 12 instrument stations per kilometer, and the other may only make 6 instrument stations in the same distance.

r being the probable error of a single leveling per kilometer, the probable error of the mean of two levelings would be $\frac{r}{\sqrt{2}}$, and the probable error of the difference of elevation of two bench-marks at the ends of a section consisting of n lines whose aggregate length was $[K]$ would be

$$(8) \quad R = \frac{r}{\sqrt{2}} \sqrt{[K]} = \pm 0.6745 \sqrt{\frac{[K]}{2n} \left[\frac{vv}{2K} \right]}$$

The above formulæ have been applied to the results of the levels along the Mississippi River, which now extend from Biloxi, Miss., on the Gulf of Mexico, to Fulton, Ill., a distance of 2,100 kilometers. The results will be taken up in sections as they

* The above formulæ for computing the values of r and R are identical in form with those given in "Précision Nivellement der Elbe," but were deduced by the writer before he was aware that the same formulæ had previously been obtained. Their use here, however, is restricted to examples where the leveling has been performed by the same observer in opposite directions and the personal error eliminated from the results. It is not believed that the formulæ for computing probable errors are applicable to the results of levels, except that the above conditions are fulfilled. The formulæ for personal error and the method of treating the results in order to arrive at an estimate of the precision of the work is believed to be new.

reled, but it will not be necessary to give full explanations in every case. As times happens that more than one result is obtained in one or both directions, some rule has been adopted of combining the mean of the results in one direction with the mean of the results in the other. The unit of length is one kilometer, unit of vertical measurement is one millimeter. The equations have been so adjusted that the values of x have the signs of corrections; when positive the closing is too low, and when minus too high.

PRECISE LEVELS FROM AUSTIN TO FRIAR'S POINT, MISS.

This section is 43 kilometers in length, and the results of the leveling are published in the report of the Chief of Engineers for 1879, page 1944. All lines were leveled in the same directions an equal number of times by the same observer, and the conditions under which the work was done, aside from changes of weather, may be supposed to have remained nearly the same throughout. An examination of the table of results shows 19 positive and 9 negative discrepancies, and one equal to zero. The sum of the positive discrepancies exceeds the sum of the negative by $+36^{\text{mm}}.3$. The sum of the positive discrepancies is $+47^{\text{mm}}.6$, and their mean size $+2^{\text{mm}}.50$, and the sum of the negative discrepancies is $-11^{\text{mm}}.3$ and their mean size $-1^{\text{mm}}.26$. It is evident that the discrepancies are quite unequally distributed, both with regard to sign and to magnitude.

Applying the results of this section by the method previously explained, we obtain the following values:

$$328.22x - 164.05 = 0$$

$$x = +0^{\text{mm}}.50 \pm 0^{\text{mm}}.063$$

$$[w] = +138.06$$

$$r_0 = \pm 1^{\text{mm}}.50$$

$$r_x = \pm 0^{\text{mm}}.063$$

$$r = \pm 0^{\text{mm}}.88$$

$$R = \pm 4^{\text{mm}}.04$$

To express these results in words, we would say that this observer makes elevations, as he advances by $+0^{\text{mm}}.50 \pm 0^{\text{mm}}.063$ per kilometer, that the probable error of a single leveling was $\pm 0^{\text{mm}}.88$ per kilometer, and that the probable error of difference of elevation between Austin and Friar's Point was $\pm 4^{\text{mm}}.04$. The number of observations and the work of obtaining these results is given on page 28.

PRECISE LEVELS FROM COLUMBUS, KY., TO MEMPHIS, TENN., AND FROM FRIAR'S POINT TO PRENTISS, MISS.

These two sections include about 404 kilometers, and were leveled by the same observer, with the same party and outfit, during the same field season, and are here considered as one section.

The manner of doing the work was quite varied; sometimes an observer duplicated his work in opposite directions, sometimes in the same direction, either north or south, and, again, two observers would level the same lines, in the same direction, or in opposite directions. This section, then, furnishes us with examples of all the combinations of observers possible, and is, therefore, a valuable one for this discussion. The work was done between November 4, 1879, and April 22, 1880. As examples of combinations are scattered along throughout the entire distance, the separate results have been numbered consecutively from Columbus and Friar's Point, the latter results being distinguished by accents.

The following exhibits in tabular form the results of leveling this section:

Observer.	Distance.	Number of discrepancies.			Sum of discrepancies.			Mean size of discrepancies.		Values of x and x' .
		+	-	Total.	+	-	Total.	+	-	
	km.				mm.	mm.	mm.	mm.	mm.	mm.
Age	86.7	39	7	46	+328.9	-20.1	+308.8	+8.38	-2.87	$+2.63 \pm 0.18$
Wat	23.4	7	11	18	+37.3	-48.2	-10.9	+5.33	4.38	-0.53 ± 0.35
Worce	18.4	2	7	9	+4.8	-38.3	-33.5	+2.40	-5.19	-0.81 ± 0.21
Front	216.8	25	95	120	+92.0	-539.7	-447.7	+3.72	-6.21	$+2.02 \pm 0.16$
Front	22.0	11	8	19	+76.5	-11.4	+65.1	+6.95	-3.80	$+1.47 \pm 0.74$
Worce	15.3	1	3	4	+3.0	-29.2	-26.2	+3.00	-8.73	$+6.12 \pm 1.33$
-Front	14.6	0	5	5	0.0	-21.9	-21.9	0.0	-4.38	$+4.79 \pm 0.71$

* Leveled in opposite directions.

† Leveled in same directions.

The first observer makes elevations too low as he advances by $+2^{\text{mm}}.11 \pm 0^{\text{mm}}.8$ kilometer, and makes elevations lower than the second observer when leveling in same or opposite directions, and also lower than the third observer when leveling in the same direction. We have so many observations on this point that it cannot be doubted that this observer's results were affected by an error which remained nearly constant throughout the entire season, and where the error has not been eliminated by his leveling in both directions, that a correction to his results is needed. The sign of the correction is certain, and we may consider that a close approximation to the amount of the correction has been obtained from the 46 equations of condition obtained from lines leveled in opposite directions. This correction applied to the line between Columbus and Memphis for the lines leveled in one direction by this observer would amount to $+220^{\text{mm}}$, and to the part between Friar's Point and Prentiss $+140^{\text{mm}}$ or a total correction at Prentiss of $+327^{\text{mm}} = 1.07$ feet.

The constant error of this observer must have been independent of direction, for he gets the same results, as compared with the second observer, whichever direction he levels. The condition of the ground and changes of weather evidently have nothing to do with the error, for it lasts throughout the entire season, and the second observer when leveling over the same ground at the same time does not obtain the same results.*

The results obtained by this observer the following season between Grafton and Cairo, Ill., contained no evidence of such a constant error as here shown. It is evident, then, that a duplication in an opposite direction the second season, of the lines leveled in one direction during the first, would not have eliminated the constant error from the mean.

From this we have the practical conclusion that an observer should duplicate his work as soon as possible under, as nearly as practicable, the same conditions. The error of this observer cannot be attributed to a settling of the rod supports, but can be explained by supposing that the rods or instrument raised a small amount gradually throughout the season.

The discrepancies of the second observer show that his errors were accidental, which fact is also shown by the probable error of determining his personal error.

The third observer made elevations too high as he advanced, but he did not obtain enough lines to compensate in any appreciable degree the effect of the first observer's personal error.

The fourth observer did so little work that no conclusion could safely be drawn from the results, but the evidence is all in one direction.

The numerical work of obtaining the results contained in the preceding tables is given on pages 150 and 151. No attempt has been made to compute the probable error of the resulting difference of elevation of this section, as it is believed that the formulæ for probable errors are not applicable to a large portion of the work.

PRECISE LEVELS FROM PRENTISS, MISS., TO GREENVILLE, MISS.

This section of 72 kilometers was leveled by Assistant J. B. Johnson, and all lines were leveled in opposite directions. After 44.2 kilometers had been leveled with the rods supported on foot-plates, stakes with nails in their tops were driven and the rods supported on these for the remainder of the distance. This section has been cited as furnishing an example of rods settling when supported on foot-plates and rising when supported on stakes. It has, therefore, been divided into two parts, according to the character of supports, and each part analyzed separately, to ascertain if the manner of supporting the rods has introduced a constant error in the results.

Letting x , and x'' , represent the constant error in the two parts, respectively, then by the formulæ previously given we obtain

$$\begin{aligned} x &= -0.62 \pm 0.12, & r_0 &= \pm 2.70 \\ x'' &= +0.35 \pm 0.17, & r_{0''} &= \pm 2.79 \end{aligned}$$

These results would seem to indicate that the manner of supporting the rods has introduced constant errors in the results, but the proof is not positive. An inspection of the discrepancies and residuals in the first part shows—

14 negative discrepancies, whose sum is	-6
8 positive discrepancies, whose sum is	+11
13 negative residuals, whose sum is	-3
9 positive residuals, whose sum is	+8

The sum of the discrepancies, without regard to sign, is $77^{\text{mm}}.6$, and of the residuals $62^{\text{mm}}.9$.

* It might be well to state in this connection that in all the work done on the Mississippi River, the principle of eliminating instrumental errors by equal fore and back sights has been followed, and therefore the accumulation of errors cannot be attributed to errors of adjustment of instruments.

come $-0^{\text{mm}}.31$ and $+0^{\text{mm}}.07$, respectively, and their difference would scarcely that would be expected from their probable errors.

suspicion that these discrepancies are the result of accidental errors is strengthened by the fact that this was the observer's first experience in this work, and also by the fact that all his subsequent work shows occasional errors of approximately the same size. For the later errors the explanation has been offered that they were caused by the rodmen, but as errors of reading the rod of 10^{mm} or 20^{mm} frequently are detected in the field or in the reduction, it is quite likely that this is the explanation of the errors in the first work.

From the examples could be drawn from the note-books of this office where the readings of the three wires are inconsistent, and show that an error of 10^{mm} has been made in reading either one or two wires, with no evidence to decide which is the correct reading. An uncertainty of 10^{mm} , therefore, remains in the mean of the three readings. The explanation of the way errors of that size are made is not confined to this observer or to this observer.

It is concluded, then, that the proof that changing the manner of supporting the rods affected the results is not sufficient. That the cumulative error was not the result of motion of rod supports, would have been inferred from the results of the work between Columbus and Memphis, where two observers with rods supported obtained so dissimilar results while leveling the same lines at the same time. To explain the results obtained by the first observer there by a motion of the supports, it would be necessary to suppose that a foot plate and rod weighing in pounds, had risen nearly uniformly throughout an entire season. As the pressure on the foot plate would probably be increased by the rodman about 20 pounds, such a position is inadmissible.

He has, therefore, combined all the results in this section, and obtained the following values:

$$769.52x + 205.87 = 0, \quad x = -0^{\text{mm}}.96 \pm 0^{\text{mm}}.11, \quad [vv] = 744.94 \\ r_1 = \pm 3^{\text{mm}}.07, \quad r_2 = \pm 0^{\text{mm}}.11, \quad r_3 = \pm 1^{\text{mm}}.48, \quad R = \pm 6^{\text{mm}}.68.$$

PRECISE LEVELS FROM GRAFTON, ILL., TO CAIRO, ILL.

The only results obtained in this section of 345 kilometers bearing upon the subject of discussion were those obtained by Assistant O. W. Ferguson in the 221 kilometers south from Grafton. These results are shown on the plot on Plate III, and no use to them has previously been made. This observer made elevations too low in the advanced, but the error did not remain constant, and the method here given has been applied to the results. As, during the time that he leveled the lines on the plot, he also leveled many lines to the south without duplicating them in the opposite direction, it is probable the difference of elevation obtained between

As the plot of the discrepancies on Plate V, shows that this error was practically constant throughout, its value has been found by the formulae.

$$\begin{aligned}x &= -0^{\text{mm}}.62 \pm 0^{\text{mm}}.11 \\ r_0 &= \pm 1^{\text{mm}}.61 \\ r_x &= \pm 0^{\text{mm}}.11\end{aligned}$$

As it is more probable that this error was made by one observer than that the two observers made equal errors of opposite signs, the difference of elevation between Keokuk and Grafton is probably in error by 45^{mm} from this cause. The sign of the error is not determined. The numerical work of obtaining these results is given on page 157.

PRECISE LEVELS FROM CARROLLTON, LA., TO BILOXI, MISS.

The levels of this section of 140 kilometers were run by the same observers and in the same manner as those between Keokuk and Grafton. After about 60 kilometers had been leveled, the results of the two observers commenced to diverge until at the end of the line their results differed by about 50^{mm} . The same remarks are applicable to this section as the preceding one.

PRECISE LEVELS FROM CAIRO, ILL., TO COLUMBUS, KY., AND FROM MEMPHIS, TENN., TO AUSTIN, MISS.

The leveling of these sections, with the exception of about 6 miles, was all done in one direction, the observer carrying along two lines by means of two rods, run independently. There is, therefore, no information as to whether or not there was any accumulation of errors in these sections.

PRECISE LEVELS FROM GREENVILLE, MISS., TO CARROLLTON, LA.

The levels of this section of 470 kilometers were run by parties of the United States Coast and Geodetic Survey, and the method pursued was to level alternate sections in opposite directions, in order "to prevent the gradual accumulation of error, supposed to be due to running constantly in one direction" (C. S. Report, 1880, page 137). It is probable that this method prevented any accumulation of error, but it fails to give any evidence on the subject.

The following are the values of r and R , computed by the method given in "Précision-Nivellement der Elbe," which method is in use by the United States Coast and Geodetic Survey:

$$\begin{aligned}r &= \pm 0^{\text{mm}}.90 \\ R &= \pm 11^{\text{mm}}.6\end{aligned}$$

PRECISE LEVELS FROM KEOKUK, IOWA, TO FULTON, ILL.

The results of all the sections previously mentioned were known before this section was leveled, although the final reductions were not quite completed.

The conclusions to be drawn from them had been pointed out in the preliminary report, and some experimental work had been done with reference to obtaining additional information upon the subject, but the results indicated that the work was not of a character to make it valuable in this discussion.

When the parties took the field they received instructions that each observer should duplicate his own work in opposite directions. In order to throw additional light on the question whether or not the accumulation of errors noticed in some of the sections was caused by a motion of the rod supports, the parties were provided with steel pins, to be used as they saw fit in supporting the rods.

A slight modification was also made in the form of the spur in which the rod terminates. This modification consisted in having the rod terminate in a plane surface, which rested on a conical surface on the foot-plates or pins, instead of terminating in a spherical surface, which rested on a concave spherical surface of larger diameter. The observers were the same as those employed in the sections Carrollton to Biloxi and Keokuk to Grafton.

On pages 158 and 159 is given a tabulation of the results obtained in this section. As the observers leveled alternate portions of the line, the numbering of the bench-marks, which is consecutive, will indicate the order in which the results occur in the line. Sometimes an observer obtained two results at the same time by using both foot-plates and pins. In the tabulation such results are indicated by an asterisk in the column of bench-marks. An examination of the table shows that the discrepancies of either observer are well distributed, both with regard to sign and amount, throughout the season's work, whether leveling on pins or foot-plates; and that the work upon the

s slightly better than that upon pins. These facts are shown by the fol-
of discrepancies :

	O. W. F., OBSERVER.				J. B. J., OBSERVER.			
	Pins.		Foot plates.		Pins.		Foot plates.	
	Discrepancies.				Discrepancies.			
	No.	Sum.	No.	Sum.	No.	Sum.	No.	Sum.
.....	41	mm. +83.2	23	mm. +35.8	31	mm. +60.9	32	mm. +71.0
.....	34	-62.8	28	-51.1	29	-76.2	32	-56.5
.....	75	+19.4	46	-15.3	60	-15.3	64	+14.5
.....	1.96	1.89	2.28	1.99

discrepancy in all the first observer's work is +4.1^{mm} and in the second
in the whole section +3.3^{mm}.

rkable counterbalancing of errors may partly be accidental, but is prob-
to be attributed to increased care in the work. There is nothing in the
shows that an accumulation of error was prevented by changing from
support to the other.

ding sections include all the levels along the Mississippi River, except
Fulton to connect with Lake Michigan, at Chicago, which are not yet
ced. It is believed that the following conclusions can safely be drawn
sults set forth in the preceding pages.

results of leveling may be effected by cumulative errors, which vary with
servers, and do not always remain constant with the same observer.
mean of several results obtained by the same or different observers may re-
siderable correction.

these cumulative errors are nearly proportional to the distances leveled,
e cases are independent of the nature of the ground, the direction in which
done, the season, or the manner of supporting the rods.

in order, as far as possible, to eliminate the effect of such errors, each ob-
ld duplicate his own work in opposite directions, under the same condi-

long lines of levels, even if leveled in duplicate, should be independently

re report is submitted in hopes that it may add information in regard to
nd increase the accuracy of future operations. It is hoped that it may
your approval.

respectfully, your obedient servant,

L. L. WHEELER.

ent. SMITH S. LEACH,
tary Mississippi River Commission.

ion of personal error of Assistant L. L. Wheeler from the results of levels from
Austin to Friar's Point, Miss.

$-(n-s)=v$		$4 K^2 x-2 K (n-s)$		v	vv	$\frac{vv}{2 K}$
km.	mm.			mm.		
...3.1	+ 2.8	+ 9.61	+ 8.68	- 1.2	1.44	0.47
...2.4	+ 0.1	+ 5.76	+ 0.24	+ 1.1	1.21	0.50
...1.7	+ 2.9	+ 2.89	+ 4.93	- 2.1	4.41	2.60
...2.0	- 0.7	+ 4.00	- 1.40	+ 1.7	2.89	1.44
...2.6	+ 4.2	+ 6.76	+ 10.92	- 2.9	8.41	3.23
...2.1	+ 1.2	+ 4.41	+ 2.52	- 0.2	0.04	0.02
...2.1	- 1.1	+ 4.41	- 2.31	+ 2.1	4.41	2.10
...1.5	0.0	+ 2.25	0.00	+ 0.8	0.64	0.04
...4.2	+ 3.2	+ 17.64	+ 13.44	- 1.1	1.21	0.30
...3.4	+ 0.2	+ 11.56	+ 0.68	+ 1.5	2.25	0.66
...2.3	+ 0.8	+ 5.29	+ 1.84	+ 0.4	0.16	0.08
...4.0	+ 3.5	+ 16.00	+ 14.00	- 1.5	2.25	0.56
...1.8	- 0.3	+ 3.24	- 0.54	+ 1.2	1.44	0.90
...6.4	+ 0.8	+ 40.96	+ 5.12	+ 2.4	5.76	0.96

Determination of personal error of Assistant L. L. Wheeler, &c.—Continued.

$2 Kx - (n - s) = v$		$4 K^2x - 2 K(n - s)$		r	vv
in.	mm.			mm.	
(15).....	2.5 — 0.8	+ 6.25	— 2.00	— 2.0	4.00
(16).....	4.3 + 4.0	+ 18.49	+ 17.20	— 1.8	3.24
(17).....	1.2 — 3.0	+ 1.44	— 3.36	+ 4.4	19.36
(18).....	3.2 — 1.5	+ 10.24	— 4.80	+ 3.1	9.61
(19).....	5.0 + 3.5	+ 25.00	+ 17.50	— 1.0	1.00
(20).....	2.7 + 2.8	+ 7.29	+ 5.94	— 0.8	0.64
(21).....	4.0 — 2.7	+ 16.00	— 10.80	+ 4.7	22.09
(22).....	1.7 + 0.9	+ 2.89	+ 1.53	— 0.1	0.01
(23).....	4.9 + 3.8	+ 24.01	+ 18.62	— 1.4	1.96
(24).....	4.0 — 0.2	+ 16.00	— 0.80	+ 2.2	4.84
(25).....	1.0 + 0.6	+ 1.00	+ 0.60	— 0.1	0.01
(26).....	6.0 + 4.7	+ 36.00	+ 32.20	— 5.7	32.49
(27).....	4.7 + 1.7	+ 22.09	+ 7.99	+ 0.7	0.49
(28).....	2.5 + 2.5	+ 6.25	+ 6.25	— 1.2	1.44
(29).....	0.7 — 0.2	+ 0.49	— 0.14	+ 0.6	0.36
		333.22	+164.05	[vv] =	138.06

Normal equation :

$$333.22x - 164.05 = 0$$

$$s = +0.50 \pm 0.083$$

$$n = 29$$

$$p = 1$$

$$p = 328$$

$$r_s = \frac{57.45 \sqrt{[vv]}}{\sqrt{p(n-p)}} = \pm 0.083$$

$$R = \pm 0.6745 \sqrt{\frac{43}{29} \times \frac{49.47}{2}} = \pm 4.04$$

$$r = \pm 0.68$$

Determination of personal error of Assistant J. A. Paige, from the results of levels Columbus to Memphis and from Frier's Point to Prentiss.

No. of line.	$2 Kx - (n - s)$	r	vv	$4 K^2 - 2 K(n - s)$
3.....	0.8 + 5.4 = +	7.0	49.00	0.64 +
4.....	2.1 + 1.4 = +	5.7	32.49	4.41 +
9.....	1.4 — 4.4 = —	1.6	2.56	1.96 —
12.....	1.8 — 10.3 = —	6.6	43.56	3.24 —
13.....	0.9 + 0.7 = +	2.5	6.25	0.81 +
14.....	2.3 — 4.1 = +	0.6	0.36	5.29 —
15.....	6.3 — 14.3 = —	1.5	2.25	39.69 —
16.....	1.7 — 15.0 = —	11.6	134.56	2.89 —
17.....	0.8 + 3.2 = +	4.8	23.04	0.64 +
19.....	4.4 — 21.5 = —	12.6	158.76	19.36 —
20.....	8.9 — 12.3 = +	5.8	33.64	79.21 —
21.....	2.2 — 4.3 = +	0.2	0.04	4.84 —
22.....	6.1 — 5.2 = +	7.2	51.84	37.21 —
23.....	3.0 — 6.6 = —	0.5	0.25	9.00 —
24.....	2.1 — 8.7 = —	4.4	19.36	4.41 —
25.....	3.5 — 6.8 = +	0.3	0.09	12.25 —
28.....	1.3 — 1.9 = +	0.7	0.49	1.69 —
29.....	2.2 — 17.8 = —	13.3	176.89	4.84 —
30.....	4.0 — 24.5 = —	16.4	268.96	16.00 —
31.....	5.9 — 14.5 = —	2.5	6.25	34.81 —
32.....	0.6 — 1.9 = —	0.7	0.49	0.36 —
35.....	3.7 — 3.3 = +	4.2	17.64	13.69 —
41.....	1.4 — 3.8 = —	1.0	1.00	1.96 —
43.....	2.5 — 4.3 = +	0.8	0.64	6.25 —
44.....	4.5 — 5.6 = +	3.5	12.25	20.25 —
50.....	1.3 — 0.4 = +	2.2	4.84	1.69 —
51.....	5.2 + 3.1 = +	13.6	184.96	27.04 +
66.....	7.9 — 8.0 = +	8.0	64.00	62.41 —
68.....	1.9 — 4.7 = —	0.8	0.64	3.61 —
82.....	2.1 — 3.4 = +	0.9	0.81	4.41 —
83.....	2.3 — 5.1 = —	0.4	0.16	5.29 —

Determination of personal error of Assistant J. A. Paige, &c.—Continued.

no.	2 Kx — (n — s)			v	vv	4 K² — 2 K (n — s)		
.....	1.9	—	2.4	= +	1.4	1.96	3.61	— 4.56
.....	1.3	—	7.5	= —	4.9	24.01	1.69	— 9.75
.....	5.8	—	7.8	= +	4.0	16.00	33.64	— 45.24
.....	1.4	—	9.7	= —	6.9	47.61	1.96	— 13.58
.....	3.9	—	19.0	= —	11.1	123.21	15.21	— 74.10
.....	3.4	—	6.6	= +	0.3	0.09	11.56	— 22.44
.....	2.7	—	14.8	= —	9.3	86.49	7.29	— 39.96
.....	2.6	—	12.4	= —	7.1	50.41	6.76	— 32.24
.....	0.7	+	0.4	= +	1.8	3.24	0.49	+ 0.28
.....	3.5	—	8.1	= —	1.0	1.00	12.25	— 28.35
.....	2.3	+	5.9	= +	10.6	112.36	5.29	+ 13.57
.....	1.7	—	5.9	= —	2.4	5.76	2.89	— 10.03
.....	3.1	—	11.2	= —	4.9	24.01	9.61	— 34.72
.....	2.0	—	2.1	= +	1.9	3.61	4.00	— 4.20
.....	2.0	—	5.7	= —	1.6	2.56	4.00	— 11.40
					1800.39	550.40	—1118.31	

al equation: 550.40 x — 1118.31 = 0. x = + 2.03mm

npute prob. error of x:
P. E. of x = 0.6745 √ [vv] / p(m-μ) = 0.6745 √ 1800.39 / 550.40 × 45 = ± 0.18mm
x = + 2.03mm ± 0.18mm

error of a single observation:
r₀ = ± 0.6745 √ 1800.39 / 45 = ± 4.27mm

nations of personal error of Assistant B. D. Frost from results of levels from Columbus to Memphis and from Friar's Point to Prentiss.

no.	2 Kx — (n — s) =			v	vv	4 K² — 2 K (n — s)		
.....	2.8x	—	11.7	= —	13.2	174.24	+ 7.84	—32.76
.....	4.8	+	11.0	= +	8.5	72.25	+ 23.04	+52.80
.....	1.9	—	0.2	= —	1.2	1.44	+ 3.61	— 0.38
.....	3.1	—	3.6	= —	5.2	27.04	+ 9.61	—11.16
.....	2.3	+	2.1	= +	0.9	0.81	+ 5.29	+ 4.83
.....	1.7	+	1.9	= +	1.0	1.00	+ 2.89	+ 3.23
.....	4.8	+	11.0	= +	8.5	72.25	+ 23.04	+52.80
.....	2.7	+	5.9	= +	4.5	20.25	+ 7.20	+15.93
.....	4.3	+	2.0	= —	0.3	0.09	+ 18.49	+ 8.60
.....	2.9	—	3.0	= —	4.5	20.25	+ 8.41	— 8.70
.....	2.1	+	5.9	= +	4.8	23.04	+ 4.41	+12.39
.....	2.2	—	2.5	= —	3.7	13.69	+ 4.84	— 5.50
.....	2.4	+	0.1	= —	1.2	1.44	+ 5.76	+ 0.24
.....	2.0	+	4.9	= +	3.8	14.44	+ 4.00	+ 9.80
.....	1.3	+	1.9	= +	1.2	1.44	+ 1.69	+ 2.47
.....	1.5	+	1.5	= +	0.7	0.49	+ 2.25	+ 2.25
.....	2.0	—	11.7	= —	12.8	163.84	+ 4.00	—23.40
.....	2.0	—	4.6	= —	5.7	32.49	+ 4.00	— 9.20
					640.49	+140.46	+74.24	

al equation: 140.46 x + 74.24 = 0 x = — 0.53mm

. error of a single observation:
r₀ = ± 0.6745 √ 640.49 / 17 = ± 4.14mm

. error of x:
rₓ = ± r₀ / √ pₓ = ± 4.14 / √ 140.46 = ± 0.349mm x = — 0.53mm ± 0.349mm

Determination of difference of personal errors of *Messrs. Frost and Stevens.*

ine.	$Kx' - (F - S) = v$			vv	$K^2 - K (F - S)$		
.....	0.7	—	0.4 = +	2.9	8.41	0.49	— 0.28
.....	1.2	—	5.9 = —	0.2	0.04	1.44	— 7.08
.....	1.0	—	7.2 = —	2.7	7.29	1.00	— 7.20
.....	1.1	—	3.9 = +	1.4	1.96	1.21	— 4.29
.....	0.6	—	4.5 = —	1.6	2.56	0.36	— 2.70
					20.26	4.50	—21.55

al equation : $4.50x' - 21.55 = 0$ $x' = + 4.79^{mm}$

$\pm 0.6745 \sqrt{\frac{20.26}{4}} = \pm 1.51^{mm}$ $r_s' = \frac{r_0}{\sqrt{p_s'}} = \pm \frac{1.51}{\sqrt{4.50}} = \pm 0.71^{mm}$

nation of difference of personal errors of *Assistants Paige and Frost from the results of levels from Columbus to Memphis and from Friar's Point to Prentiss.*

ine.	$Kx' - (P - F) = v$				vv	$K^2 - K(P - F)$		
.....	2.0x'	+	5.9	= + 1.9	3.61	4.00	+	11.80
.....	2.4	+	16.3	= + 11.5	132.25	5.76	+	39.12
.....	2.0	+	8.2	= + 4.2	17.64	4.00	+	16.40
.....	1.6	—	2.0	= — 5.2	27.04	2.56	—	3.20
.....	2.4	+	12.3	= + 7.5	56.25	5.76	+	29.52
.....	3.0	+	15.1	= + 9.0	81.00	9.00	+	45.30
.....	4.6	+	6.6	= — 2.7	7.29	21.16	+	30.36
.....	3.4	+	3.7	= — 3.2	10.24	11.56	+	12.58
.....	0.7	—	2.4	= — 3.8	14.44	0.49	—	1.68
.....	4.0	—	9.1	= — 17.2	295.84	16.00	—	36.40
.....	1.3	+	0.7	= — 1.9	3.61	1.69	+	0.91
.....	2.3	—	5.4	= — 10.0	100.00	5.29	—	12.42
.....	3.9	+	8.1	= + 0.2	0.04	15.21	+	31.59
.....	0.9	—	1.2	= — 3.0	9.00	0.81	—	1.08
.....	1.6	+	7.6	= + 4.4	19.36	2.56	+	12.16
.....	1.0	+	2.5	= + 0.5	0.25	1.00	+	2.50
.....	1.5	+	10.3	= + 7.3	53.29	2.25	+	15.45
.....	1.2	+	7.6	= + 5.2	27.04	1.44	+	9.12
.....	1.3	+	4.0	= + 1.4	1.96	1.69	+	5.20
.....	0.8	+	7.5	= + 5.9	34.81	0.64	+	6.00
.....	1.5	—	1.3	= — 4.3	18.49	2.25	—	1.95
.....	2.0	+	4.1	= + 0.1	0.01	4.00	+	8.20
.....	0.5	+	0.1	= — 0.9	0.81	0.25	+	0.05
.....	2.4	+	8.4	= + 3.6	12.96	5.76	+	20.16
.....	0.5	—	3.8	= — 4.8	23.04	0.25	—	1.90
.....	3.9	+	17.6	= + 9.7	94.09	15.21	+	68.64
.....	1.4	+	9.6	= + 6.8	46.24	1.96	+	13.44
.....	2.3	—	7.5	= — 12.2	148.84	5.29	—	17.25
.....	3.8	+	12.4	= + 4.7	22.09	14.44	+	47.12
.....	1.0	+	8.0	= + 6.0	36.00	1.00	+	8.00
.....	0.2	+	1.8	= + 1.4	1.96	0.04	+	0.36
.....	4.3	+	4.6	= — 4.1	16.81	18.49	+	19.78
.....	0.5	+	5.1	= + 4.1	16.81	0.25	+	2.55
.....	1.6	+	10.2	= + 7.0	49.00	2.56	+	16.32
.....	2.9	—	4.9	= — 10.8	116.64	8.41	—	14.21
.....	2.2	+	1.4	= — 3.0	9.00	4.84	+	3.08
.....	1.4	+	5.5	= + 2.7	7.29	1.96	+	7.70
.....	2.2	+	3.4	= — 1.0	1.00	4.84	+	7.48
.....	1.3	+	10.4	= + 7.8	60.84	1.69	+	13.52
.....	0.9	+	5.2	= + 3.4	11.56	0.81	+	4.68
.....	1.1	+	2.3	= + 0.1	0.01	1.21	+	2.53
.....	1.5	+	0.4	= — 2.6	6.76	2.25	+	0.60
.....	1.3	+	6.1	= + 3.5	12.25	1.69	+	7.93
.....	1.6	+	5.4	= + 2.2	4.84	2.56	+	8.64
.....	1.7	+	10.7	= + 7.3	53.29	2.89	+	18.19
.....	1.6	—	2.2	= — 5.4	29.16	2.56	—	3.52
.....	1.0	+	7.0	= + 5.0	25.00	1.00	+	7.00

2560 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Determination of difference of personal errors of Assistants Peige and Frost, &c.—Continued.

No. of line.	$Kx' - (P - F) =$	Σ	Σ	$K^2 - K(E)$
110	1.0 + 9.0 = + 7.0	49.00	1.00 +	
117	1.9 - 4.5 = - 8.3	68.89	3.61 -	
118	0.9 + 8.6 = + 6.8	46.24	0.81 +	
119	0.5 + 9.1 = + 8.1	65.61	0.25 +	
120	1.4 + 5.7 = + 2.9	8.41	1.96 +	
121	2.8 + 2.7 = - 3.0	9.00	7.84 +	
122	0.9 + 8.3 = + 6.5	42.25	0.81 +	
123	2.2 + 5.3 = + 0.9	0.81	4.84 +	
124	1.2 + 10.2 = + 7.6	60.84	1.44 +	
125	1.3 - 1.3 = - 3.9	15.21	1.69 -	
126	1.2 + 4.7 = + 2.3	5.29	1.44 +	
127	1.0 + 2.3 = + 0.3	0.09	1.00 +	
128	1.2 + 1.5 = - 0.9	0.81	1.44 +	
129	2.3 - 4.2 = - 8.8	77.44	5.29 -	
130	0.4 - 3.4 = - 4.2	17.64	0.16 -	
131	0.6 + 1.0 = - 0.2	0.04	0.36 +	
132	0.5 + 0.7 = - 0.3	0.09	0.25 +	
133	3.2 + 12.9 = + 6.4	40.96	10.24 +	
134	4.0 + 16.2 = + 6.3	39.69	24.01 +	
135	4.2 + 5.6 = - 2.9	8.41	17.64 +	
136	1.2 + 10.2 = + 7.6	60.84	1.44 +	
137	1.2 - 1.3 = - 3.7	13.69	1.44 -	
138	3.4 + 5.7 = - 1.2	1.44	11.56 +	
140	4.0 + 9.6 = + 1.5	2.25	16.00 +	
147	1.0 + 4.5 = + 2.5	6.25	1.00 +	
148	0.8 - 3.7 = - 5.3	28.09	0.64 -	
149	1.3 + 0.8 = - 1.8	3.24	1.69 +	
150	0.8 + 9.8 = + 8.2	67.24	0.64 +	
151	1.0 + 1.5 = - 0.5	0.25	1.00 +	
152	0.9 + 2.0 = + 0.2	0.04	0.81 +	
153	3.4 + 5.7 = - 1.2	1.44	11.56 +	
154	0.9 + 6.5 = + 4.7	22.09	0.81 +	
155	0.9 - 2.7 = - 4.5	20.25	0.81 -	
156	1.6 + 2.6 = - 0.6	0.36	2.56 +	
157	2.3 + 7.8 = + 3.2	10.24	5.29 +	
158	2.0 + 3.1 = - 0.9	0.81	4.00 +	
159	5.4 + 7.1 = - 3.8	14.44	29.16 +	
160	1.8 + 6.5 = + 2.9	8.41	3.24 +	
161	1.0 - 7.3 = - 9.3	86.49	1.00 -	
162	0.9 + 7.4 = + 5.6	31.36	0.81 +	
163	1.2 + 6.5 = + 4.1	16.81	1.44 +	
164	2.2 + 11.2 = + 6.8	46.24	4.84 +	
165	2.8 + 9.5 = + 3.8	14.44	7.84 +	
34'	3.1x' + 0.6 = - 5.7	32.49	9.61 +	
35'	2.3 - 1.7 = - 6.4	40.96	5.29 -	
36'	1.0 + 6.5 = + 4.5	20.25	1.00 +	
37'	3.1 + 5.3 = - 1.0	1.00	9.61 +	
38'	1.0 - 2.0 = - 4.0	16.00	1.00 -	
39'	0.6 - 1.1 = - 2.3	5.29	0.36 -	
40'	1.0 + 4.0 = + 2.0	4.00	1.00 +	
41'	2.4 + 5.0 = + 0.2	0.04	5.76 +	
42'	2.1 + 2.7 = - 1.5	2.25	4.41 +	
44'	0.7 + 5.4 = + 4.0	16.00	0.49 +	
45'	0.9 - 7.9 = - 9.7	94.09	0.81 -	
46'	1.9 + 10.9 = + 7.1	50.41	3.61 +	
47'	2.6 + 6.5 = + 1.2	1.44	6.76 +	
48'	2.8 - 5.5 = - 11.2	125.44	7.84 -	
49'	2.1 + 2.7 = - 1.5	2.25	4.41 +	
50'	1.7 - 4.1 = - 7.5	56.25	2.89 -	
51'	2.1 + 6.8 = + 2.6	6.76	4.41 +	
52'	1.8 - 2.4 = - 6.0	36.00	3.24 -	
53'	0.8 + 3.0 = + 1.4	1.96	0.64 +	
54'	1.0 + 1.3 = - 0.7	0.49	1.00 +	
55'	1.5 + 0.7 = - 2.3	5.29	2.25 +	
56'	2.2 + 5.3 = + 0.9	0.81	4.84 +	
57'	2.0 + 5.6 = + 1.6	2.56	4.00 +	

Determination of difference of personal errors of Assistants Paige and Frost, &c.—Continued.

No. of line.	$Kx' - (P - F) = v$			vv	$K^2 - (P - F)$		
17	0.8	+ 7.0 =	+ 5.4	29.16	0.64	+	5.60
20	1.1	+ 2.7 =	+ 0.5	0.25	1.21	+	2.97
27	1.0	+ 3.4 =	+ 1.4	1.96	1.00	+	3.40
31	2.0	+15.8 =	+11.8	139.24	4.00	+	31.60
32	3.3	+ 2.1 =	- 4.6	21.16	10.89	+	6.93
33	1.0	+ 5.5 =	+ 3.5	12.25	1.00	+	5.50
34	1.8	+ 3.0 =	- 0.6	0.36	3.24	+	5.40
				3459.59	+ 524.20	+1060.34	

Normal equation :

$+524.20x' + 1060.34 = 0$

$x' = -2.02^{mm}$

Prob. error of a single observation :

$r_0 = \pm 0.6745 \sqrt{\frac{3459.59}{119}} = \pm 3.64^{mm}$

Prob. error of x' :

$r_{x'} = \pm \frac{r_0}{\sqrt{p_{x'}}} = \pm \frac{3.64}{\sqrt{524.20}} = \pm 0.16^{mm}$

$x' = -2.02^{mm} \pm 0.16^{mm}$

Determination of difference of personal errors of Messrs. Paige and Sankee.

No. of line.	$Kx' - (P - S) = v$			vv	$K^2 - K(P - S)$		
17	0.8	- 3.0 =	- 7.9	62.41	0.64	-	2.40
20	1.8	+15.7 =	+ 4.7	22.09	3.24	+	28.26
27	1.9	+11.9 =	+ 0.3	0.09	3.61	+	22.61
32	0.8	+ 1.6 =	- 3.3	10.89	0.64	+	1.28
				95.48	8.13	+	49.75

Normal equation :

$8.13x' + 49.75 = 0$

$x' = -6.12^{mm}$

Prob. error of a single observation :

$r_0 = \pm .6745 \sqrt{\frac{95.48}{3}} = \pm 3.80^{mm}$

Prob. error of x' :

$r_{x'} = \frac{r_0}{\sqrt{p_{x'}}} = \pm \frac{3.80}{\sqrt{8.13}} = \pm 1.33^{mm}$

$x' = -6.12^{mm} \pm 1.33^{mm}$

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

normal error of Assistant Johnson from results of from Prentiss to Greenville.

	$2Kx - (n-s) = v'$	v'/v'	$4K^2 - 2K(n-s) = v''$	v''
1	$5.3x' + 4.1 = + 0.8$	0.64	$28.09 + 21.73 + 2.7$	7.29
2	$6.9 + 6.3 = + 2.0$	4.00	$47.61 + 43.47 + 4.5$	20.25
3	$2.9 - 3.8 = - 5.6$	31.36	$8.41 - 11.02 - 4.6$	21.16
4	$2.2 - 0.3 = - 1.7$	2.89	$4.84 - 0.66 - 0.9$	0.81
5	$2.0 - 0.7 = - 1.9$	3.61	$4.00 - 1.40 - 1.2$	1.44
6	$2.4 + 4.1 = + 2.6$	6.76	$5.76 + 9.84 + 3.5$	12.25
7	$1.0 - 1.9 = - 2.5$	6.25	$1.00 - 1.90 - 2.2$	4.84
8	$0.9 + 5.3 = + 1.0$	1.00	$47.61 + 36.57 + 3.5$	12.25
9	$5.2 + 14.2 = + 11.0$	121.00	$27.04 + 73.84 + 12.6$	163.84
10	$1.0 + 1.0 = + 0.4$	0.16	$1.00 + 1.00 + 0.7$	0.49
11	$9.1 + 0.3 = - 5.3$	28.09	$82.81 + 2.73 - 2.7$	7.29
12	$3.7 - 3.9 = - 0.2$	38.44	$13.69 - 14.43 - 4.9$	24.01
13	$5.3 + 10.4 = + 7.1$	50.41	$28.09 + 55.12 + 9.0$	81.00
14	$4.2 + 0.3 = - 2.9$	8.41	$17.64 - 1.26 - 1.4$	1.96
15	$5.2 + 2.7 = - 0.5$	0.25	$27.04 + 14.04 + 1.4$	1.96
16	$0.8 + 3.4 = - 0.8$	0.64	$46.24 + 23.12 + 1.6$	2.56
17	$1.8 + 0.4 = - 0.7$	0.49	$3.24 + 0.72 - 0.1$	0.01
18	$0.5 + 1.8 = + 1.5$	2.25	$0.25 + 0.90 + 1.7$	2.89
19	$3.7 + 2.0 = - 0.3$	0.09	$13.69 + 7.40 + 1.0$	1.00
20	$1.0 - 1.5 = - 2.1$	4.41	$1.00 - 1.50 - 1.8$	3.24
21	$8.2 + 6.2 = + 1.1$	1.21	$67.24 + 50.84 + 4.1$	16.81
22	$3.1 - 3.0 = - 4.9$	24.01	$9.61 - 9.30 - 3.8$	14.44
		<u>336.37</u>	<u>485.90 + 299.85</u>	<u>401.79</u>
23	$3.7x'' + 4.9 = + 6.2$	38.44	$13.69 + 18.13 + 3.9$	15.21
24	$0.5 - 1.0 = - 0.5$	0.64	$0.25 - 0.50 - 1.1$	1.21
25	$5.5 + 0.7 = + 2.6$	6.76	$30.25 + 3.85 - 0.7$	0.49
26	$7.1 - 5.0 = - 2.5$	6.25	$50.41 - 35.50 - 6.8$	46.24
27	$8.2 + 3.4 = + 6.3$	39.69	$67.24 + 27.89 + 1.3$	1.69
28	$1.6 - 0.2 = + 0.4$	0.16	$2.56 - 0.32 - 0.6$	0.36
29	$3.3 - 4.4 = - 3.2$	10.24	$10.89 - 14.52 - 5.3$	28.09
30	$3.5 + 1.6 = + 2.8$	7.84	$12.25 + 5.60 + 0.7$	0.49
31	$2.9 - 1.0 = - 0.0$	0.00	$8.41 - 2.90 - 1.8$	3.24
32	$4.0 + 2.5 = + 3.9$	15.21	$16.00 + 10.00 + 1.5$	2.25
33	$2.3 - 0.4 = + 0.4$	0.16	$5.29 - 0.92 - 1.0$	1.00
34	$6.9 - 11.2 = - 9.4$	88.36	$47.61 - 81.42 - 13.6$	184.96
35	$3.8 - 5.0 = - 3.7$	13.69	$14.44 - 19.00 - 6.0$	36.00
36	$1.7 - 4.0 = - 3.4$	11.56	$2.89 - 6.80 - 4.4$	19.36
37	$1.2 - 1.3 = - 0.9$	0.81	$1.44 - 1.56 - 1.6$	2.56
		<u>239.81</u>	<u>283.62 - 97.98</u>	<u>744.94</u>

Normal equations:

$$+ 485.90x' + 299.85 = 0$$

$$x' = - 0.62$$

Prob. error of a single observation:

$$r_o' = \pm 0.6745 \sqrt{\frac{336.37}{21}} = \pm 2.70$$

Prob. error of unknown quantity:

$$r_{x'} = \frac{r_o'}{\sqrt{p_{x'}}} = \pm \sqrt{\frac{2.70}{485.90}} = \pm 0.12$$

$$x' = - 0.62 \pm 0.12$$

Supposing no change in unknown quantity, we have the normal equation:

$$+ 769.52x + 201.87 = 0$$

$$r_o = \pm 0.6745 \sqrt{\frac{744.94}{36}} = \pm 3.07$$

$$x = - 0.26 \pm 0.11$$

$$+ 283.62x'' - 97.98 = 0$$

$$x'' = + 0.35$$

$$r_o'' = \pm 0.6745 \sqrt{\frac{239.81}{14}} = \pm 2.79$$

$$r_{x''} = \frac{r_o''}{\sqrt{p_{x''}}} = \pm \sqrt{\frac{2.79}{283.62}} = \pm 0.10$$

$$x'' = + 0.35 \pm 0.17$$

$$r_x = \pm \sqrt{\frac{r_o^2}{p_x}} = \pm \sqrt{\frac{3.07}{769.52}} = \pm 0.10$$

Rods supported on stakes.

Determination of relative personal equation of Assistants Johnson and Ferguson from the results of that portion of the line from Keokuk, Iowa, to Grafton, Ill., lying between temporary bench-marks 65 and 151.

L.M.	Kx'	(J—F)	v	vv	K ²	K(J—F)
65	2.4x'	— 0.2 = —	0.7	0.49	5.76	— 0.48
67	2.8	+ 2.2 = +	0.5	0.25	7.84	+ 6.16
68	0.8	+ 2.8 = +	2.3	5.29	0.64	+ 2.24
70	2.6	+ 6.9 = +	5.3	28.09	6.76	+ 17.94
73	3.3	+ 1.9 = —	0.1	0.01	10.89	+ 6.27
75	4.2	— 2.0 = —	4.6	21.16	17.64	— 8.40
78	2.5	+ 1.7 = +	0.2	0.04	6.25	+ 4.25
79	1.2	+ 1.5 = +	0.8	0.64	1.44	+ 1.80
83	2.0	+ 3.5 = +	2.3	5.29	4.00	+ 7.00
84	1.4	+ 1.8 = +	0.9	0.81	1.96	+ 2.52
88	2.3	— 0.5 = —	1.9	3.61	5.29	— 1.15
88	2.6	+ 3.2 = +	1.6	2.56	6.76	+ 8.32
88	1.4	+ 1.7 = +	0.8	0.64	1.96	+ 2.38
87	1.1	— 0.7 = —	1.4	1.96	1.21	— 0.77
88	1.2	+ 4.9 = +	4.2	17.64	1.44	+ 5.88
89	1.8	+ 3.2 = +	2.1	4.41	3.24	+ 5.76
91	1.6	+ 2.1 = +	1.1	1.21	2.56	+ 3.36
92	1.3	+ 3.6 = +	2.8	7.84	1.69	+ 4.68
94	0.9	+ 1.4 = +	0.8	0.64	0.81	+ 1.26
95	1.0	— 0.2 = —	0.8	0.64	1.00	— 0.20
97	2.0	— 1.7 = —	2.9	8.41	4.00	— 3.40
99	2.4	0.0 = —	1.5	2.25	5.76	0.00
101	2.6	+ 4.8 = +	3.2	10.24	6.76	+ 12.48
102	2.0	+ 1.7 = +	0.5	0.25	4.00	+ 3.40
31	1.4	+ 0.7 = —	0.2	0.04	1.96	+ 0.98
104	1.0	+ 1.7 = +	1.1	1.21	1.00	+ 1.70
106	3.4	— 4.2 = —	6.3	39.69	11.56	— 14.28
32	0.3	+ 2.7 = +	2.5	6.25	0.09	+ 0.81
108	1.7	+ 0.2 = —	0.8	0.64	2.89	+ 0.34
109	1.3	+ 3.8 = +	3.0	9.00	1.69	+ 4.94
33	1.3	+ 0.6 = —	0.2	0.04	1.69	+ 0.78
111	1.4	+ 0.1 = —	0.8	0.64	1.96	+ 0.14
113	3.0	— 2.5 = —	4.4	19.36	9.00	— 7.50
114	1.2	+ 3.4 = +	2.7	7.29	1.44	+ 4.08
115	1.0	+ 2.1 = +	1.5	2.25	1.00	+ 2.10
116	1.1	— 3.6 = —	4.3	18.49	1.21	— 3.96
35	2.8	+ 4.7 = +	3.0	9.00	7.84	+ 13.16
119	1.0	+ 1.3 = +	0.7	0.49	1.00	+ 1.30
36	1.4	— 2.4 = —	3.3	10.89	1.96	— 3.36
123	3.3	+ 2.2 = +	0.2	0.04	10.89	+ 7.26
124	1.0	+ 3.6 = +	3.0	9.00	1.00	+ 3.60
37	0.7	— 1.9 = —	2.3	5.29	0.49	— 1.33
125	1.4	+ 5.1 = +	4.2	17.64	1.96	+ 7.14
126	0.7	— 1.0 = —	1.4	1.96	0.49	— 0.70
127	2.0	+ 1.2 =	0.0	0.00	4.00	+ 2.40
128	0.8	+ 0.4 = —	0.1	0.01	0.64	+ 0.32
129	1.4	— 0.3 = —	1.2	1.44	1.96	— 0.42
38	1.4	— 0.8 = —	1.7	2.89	1.96	— 1.12
130	1.5	+ 4.4 = +	3.5	12.25	2.25	+ 6.60
131	1.0	+ 2.6 = +	2.0	4.00	1.00	+ 2.60
132	2.1	— 0.7 = —	2.0	4.00	4.41	— 1.47
40	0.5	+ 2.3 = +	2.0	4.00	0.25	+ 1.15
133	1.4	— 1.8 = —	2.7	7.29	1.96	— 2.52
135	3.0	+ 2.9 = +	1.0	1.00	9.00	+ 8.70
136	1.0	+ 4.0 = +	3.4	11.56	1.00	+ 4.00
137	0.8	+ 0.2 = —	0.3	0.09	0.64	+ 0.16
138	0.9	+ 2.3 = +	1.7	2.89	0.81	+ 2.07
139	1.6	— 2.4 = —	3.4	11.56	2.56	— 3.84
140	0.7	+ 2.5 = +	2.1	4.41	0.49	+ 1.75
141	1.6	+ 4.7 = +	3.7	13.69	2.56	+ 7.52
141½	0.9	+ 3.0 = +	2.4	5.76	0.81	+ 2.70
143	2.1	+ 3.3 = +	2.0	4.00	4.41	+ 6.93
145	2.5	+ 1.0 = —	0.6	0.36	6.25	+ 2.50
146	0.5	+ 0.3 =	0.0	0.00	0.25	+ 0.15
148	2.1	+ 0.1 = —	1.4	1.96	4.41	— 0.21
150	2.5	+ 1.3 = —	0.2	0.04	6.25	+ 3.25
151	0.3	+ 0.6 = +	0.4	0.16	0.09	+ 0.18
				376.94 +	228.74 +	141.90

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY

$$22.74 + 121.9 = 144.64$$

$$r = -0.62$$

$$\pm \sqrt{144.64} = \pm 12.23$$

$$r = \pm \sqrt{\frac{1.61}{223.74}} = \pm 0.085$$

$$r = -0.62$$

Measurements between north and south lines of levee between Keokuk, Iowa, and
by Lieutenants J. R. Johnson and O. W. Ferguson.

O. W. Ferguson, observer.				J. R. Johnson, observer.			
No. of bench-mark.	Distance.	Time.	Post- photos.	No. of bench-mark.	Distance.	Time.	Post- photos.
1	1.7	1.1	- 4.9	1	1.4	+ 2.7	+
2	1.9	- 4.6	- 4.3	2	2.6	- 2.6	+
3	1.2	+ 4.1		3	2.4	- 0.2	+
4	1.7	- 1.2		4	1.7	- 2.9	+
5	1.6	- 1.8		5	1.2	- 0.2	+
6	0.9	- 2.6		6	2.4	- 3.5	+
7	1.6	- 2.5		7	2.2	- 5.0	+
8	0.7	- 4.2		8	1.6	- 2.9	+
9	1.1	- 4.6		9	1.4	+ 2.8	+
10	0.8	- 1.5		10	1.6	- 2.3	+
11	1.4	- 2.7		11	1.5	- 2.8	+
12	1.7	- 2.8		12	1.9	- 2.7	+
13	1.6	- 2.5		13	1.7	- 1.2	+
14	1.7	- 1.4		14	1.5	- 2.9	+
15	1.9	- 2.5		15	0.6	- 0.3	+
16	1.4	- 2.2		16	0.2	+ 0.7	+
17	1.4	- 4.1		17	1.5	- 2.1	+
18	0.9	- 2.7		18	1.6	+ 5.6	+
19	0.9	- 1.8		19	0.8	- 4.5	+
20	1.4	+ 0.3		20	0.8	- 5.3	+
21	1.2	- 4.2		21	1.6	- 5.8	+
22	1.2	- 2.6		22	1.3	+ 2.2	+
23	1.1	- 1.9		23	1.1	+ 2.0	+
24	1.3	- 1.3		24	0.5		+
25	1.4	- 1.5		25	0.9		+
26	1.7	- 1.4		26	0.9		+
27	1.4	- 2.1		27	1.4		+
28	1.5	- 1.2		28	0.6	+ 1.5	+
29	0.4	- 1.2		29	0.5	+ 1.5	+
30	1.3	- 1.1		30	1.0	+ 4.1	+
31	1.4	- 2.7		31	0.7		+
32	1.9	- 2.6		32	1.0		+
33	1.3	- 2.1		33	1.1		+
34	1.2	- 2.1		34	1.2		+
35	1.6	- 1.0		35	1.4		+
36	0.8	+ 2.0		36	1.1		+
37	1.7	- 2.0		37	1.1		+
38	0.6		+ 3.3	38	1.3		+
39	1.3		- 0.2	39	0.8		+
40	2.5		+ 2.7	40	1.3		+
41	1.7		+ 1.3	41	1.6		+
42	1.1		+ 1.0	42	1.3		+
43	0.4		+ 0.7	43	1.3		+
44	0.5		+ 1.3	44	1.1		+
45	1.3		+ 1.3	45	1.0		+
46	1.2		+ 0.4	46	0.3		+
47	3.4		+ 0.6	47	1.2	- 3.4	+
48	0.8		+ 0.6	48	1.0	- 1.2	+
49	0.1	+ 0.3		49	0.9	+ 1.7	+
50	1.1	+ 1.3	- 5.6	50	1.3	+ 1.1	+
51	0.9	+ 0.3	- 0.5	51	0.8	- 1.8	+
52	1.9	+ 2.8		52	0.3	+ 0.4	+
53	1.2	+ 0.8		53	1.6	- 4.5	+
102	0.6	- 1.8		104	1.0	- 6.0	+
103	0.1	+ 1.1		107	1.7	- 4.0	+
107	1.0	- 2.2		110	1.5	- 1.0	+
108	1.4	- 0.7		111	1.4	+ 2.2	+
109	1.1	+ 0.1		117	0.9	- 3.8	+

Discrepancies between north and south lines of level, &c.—Continued.

G. W. Ferguson, observer.				J. B. Johnson, observer.			
No. of bench-mark.	Distance.	n—s		No. of bench-mark.	Distance.	n—s	
		Pins.	Foot-plates.			Pins.	Foot-plates.
112	0.7	+ 3.6		110	1.3	+ 0.9	
113	0.7	— 0.2		124	0.6	— 0.4	
114	0.9	+ 2.9		125	1.0	— 2.2	
115	1.0	+ 2.6		126	0.9	— 2.2	
116	0.5	+ 1.1		127	0.6	+ 1.1	
120	1.7	+ 1.3		128	2.2	+ 2.5	
121	0.6	— 2.0		129	1.8	+ 1.2	
122	1.2	— 3.3		132	1.3	+ 3.5	
123	1.2	— 0.1		137	1.2	+ 1.3	
129	1.0	+ 3.2		138	1.3	— 0.6	
U. S. 20	0.3	+ 0.6		139	1.5		— 0.6
130	1.1	— 0.5		U. S. 34	0.7		— 1.0
131	1.0	— 5.1		142	0.7		+ 0.5
134	1.5	— 3.1		143	1.2		+ 2.6
U. S. 31	1.1	— 0.6		85 A	0.9		— 0.3
135	1.0	+ 1.6		147	0.5		— 1.4
136	0.5	+ 2.5		148	0.7		— 2.9
140	1.4		+ 1.6	151	0.5		— 0.7
141	1.1		— 2.4	152	1.4		+ 1.3
144	1.1		— 2.5	156	1.0		— 1.5
145	0.7		— 0.1	157	0.6		— 2.1
148	1.1		+ 3.5	161	1.4		+ 3.5
149	0.7		+ 0.4	162	1.1		+ 4.4
150	1.3		+ 0.1	163	1.0		+ 4.5
153	0.3		+ 0.2	168	1.5		— 0.6
154	0.5		— 2.0	170	1.1		+ 0.3
155	0.6		— 0.2	173	0.7		+ 1.0
156	1.0		— 2.6	175	1.3		+ 2.6
159	0.6		— 1.1	179	1.1		— 3.2
160	0.2		— 2.0	180	1.1		+ 3.9
164	1.2		— 2.5	181	1.0	+ 0.1	
165	1.2		+ 0.4	182	1.0	+ 1.4	
166	1.3		+ 3.2	186	0.8	— 0.3	
171	1.4		+ 1.6	187	1.2	+ 0.6	
172	0.6		+ 0.5	188	0.7	+ 2.0	
176	2.0		— 0.1	191	1.3	+ 4.7	
177	0.9		— 3.7	192	1.0	+ 2.1	
178	0.6		— 0.7	194	0.9	+ 2.8	
183	0.9	+ 0.5	— 2.0	195	1.4	— 0.1	
184	1.2	+ 3.7	— 4.9	199	1.3	+ 0.5	
186	0.9	+ 1.9		200	1.2	+ 0.9	
190	1.2	+ 4.2		201	0.8	— 1.3	
192 A	2.1	— 1.3		202	2.0		+ 3.2
193	0.7	— 1.5		203	1.0		— 0.4
196	2.9	— 3.2		207	1.4		+ 3.7
197	1.4	+ 4.5	+ 0.2	208	1.4		+ 1.0
198	1.6	+ 4.2		63 A	2.0		+ 1.3
204	1.0		— 2.0	212	1.0		— 3.5
205	0.8		+ 1.0	213	1.0		+ 3.6
206	2.0		— 1.1				
209	2.3		+ 0.8				
210	1.0		— 1.3				
211	0.7		— 1.6				

+ 32.2 + 35.8
— 62.6 — 51.1
+ 12.4 — 15.2

+ 4.1

Positive discrepancies
Negative discrepancies

41 28
24 29

Mean discrepancies

0.50 1.00
1.96 1.96

+ 60.9 + 71.0
— 76.2 — 56.5
— 15.3 + 14.5

— 0.8

31 32
29 32

0.50 1.00
2.36 1.96

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Discrepancies between north and south lines leveled by Assistant Paige between Columbus Memphis and Friar's Point and Prentiss.

No. of line.	[2 K]	[P - S]	No. of line.	[2 K]	[S - P]
	<i>k. m.</i>	<i>m. m.</i>		<i>k. m.</i>	<i>m. m.</i>
2	0.8	+ 5.4	43	80.9	-174.8
4	2.9	+ 6.8	44	74.4	-180.4
9	4.3	+ 2.4	50	73.7	-180.8
12	11.1	- 7.9	51	80.9	-177.7
13	7.0	- 2.2	66	63.8	-185.7
14	0.3	- 11.2	68	60.7	-190.4
15	15.0	- 25.6	72	92.8	-193.8
16	17.3	- 40.8	83	95.1	-198.9
17	14.1	- 27.4	84	97.0	-201.3
18	32.5	- 50.9	85	98.3	-208.8
20	31.4	- 71.2	86	104.3	-216.6
21	33.6	- 75.5	94	105.5	-222.3
22	30.7	- 80.7	95	109.4	-243.3
23	43.7	- 87.3	98	112.8	-251.9
24	44.8	- 90.0	99	115.5	-266.7
25	49.3	-102.8	101	118.1	-270.1
26	49.6	-104.7	120	118.8	-278.7
29	51.8	-122.5	10'	122.3	-286.8
30	55.8	-147.0	11'	124.0	-280.9
31	61.7	-161.5	18'	126.3	-286.8
32	62.3	-163.4	23'	129.4	-298.0
33	66.8	-166.7	27'	131.4	-300.1
41	67.4	-170.5	36'	133.4	-305.8

Discrepancies between results of levels by Assistants Paige and Frost from levelling between Columbus and Memphis and Friar's Point and Prentiss.

No. of line.	[K]	[F - P]	No. of line.	[K]	[F - P]
26	2.0	+ 5.0	129	108.3	+278.7
27	4.4	+ 22.2	130	108.7	+270.3
28	6.4	+ 30.4	131	109.8	+271.3
34	8.0	+ 29.4	132	109.8	+272.0
37	10.4	+ 40.7	133	112.0	+284.9
38	12.4	+ 55.8	134	117.9	+301.1
39	18.0	+ 64.4	135	122.1	+306.7
40	21.4	+ 68.1	136	123.3	+316.9
41	23.1	+ 63.7	137	124.5	+315.6
43	28.1	+ 54.0	138	127.9	+321.3
43	27.4	+ 50.3	146	131.9	+330.9
45	29.7	+ 44.0	147	132.9	+335.4
48	33.6	+ 47.0	148	133.7	+331.7
49	34.5	+ 50.8	149	135.0	+332.6
52	36.1	+ 64.4	150	135.8	+342.3
53	37.1	+ 60.0	151	136.8	+343.8
54	38.6	+ 77.2	152	137.7	+345.8
55	39.8	+ 84.8	153	141.1	+351.5
58	41.1	+ 88.8	154	14	+359.0
57	41.0	+ 90.3	155	14.8	+355.3
59	43.4	+ 95.0	156	144.5	+357.0
60	45.4	+ 99.1	157	140.8	+365.7
61	45.9	+ 90.2	158	148.8	+368.8
62	47.3	+107.6	159	144.2	+375.9
65	48.8	+103.8	160	150.0	+382.4
66	52.7	+121.4	161	157.0	+375.1
67	54.1	+131.1	162	157.9	+382.5
69	56.4	+123.5	163	159.1	+369.0
70	60.2	+135.9	164	161.3	+400.2
71	61.2	+143.9	165	164.1	+409.7
72	61.4	+145.7	34'	167.2	+410.3
73	63.7	+150.3	35'	169.5	+408.0
74	66.2	+155.4	36'	170.5	+415.1
75	67.8	+165.0	37'	172.0	+420.4
97	70.7	+161.7	38'	174.6	+418.4
98	72.0	+162.1	39'	175.2	+417.8
99	74.3	+167.0	40	176.2	+421.3
100	70.5	+171.0	41	178.0	+426.3
101	77.8	+181.4	42'	180.7	+429.0
102	78.7	+186.0	43	181.4	+434.4
103	79.8	+188.7	45'	182.3	+436.5
104	81.3	+189.3	47'	184.2	+437.4
105	82.0	+195.4	47	186.8	+443.9
106	84.2	+200.8	48'	189.0	+438.4
107	85.9	+211.5	49'	191.7	+441.1
108	87.5	+209.3	50'	193.4	+437.0
109	88.5	+216.8	51'	195.5	+443.8

Discrepancies between results of levels by Assistants Paige and Frost, &c.—Continued.

No. of line.	[K]	[F—P]	No. of line.	[K]	[F—P]
116	89.5	+225.3	52'	197.3	+441.4
117	91.4	+220.8	53'	198.1	+444.4
118	92.3	+229.4	54'	199.1	+445.7
119	92.8	+238.5	55'	200.6	+446.4
120	94.2	+244.2	56'	202.8	+451.7
121	97.0	+246.9	57'	204.8	+457.8
122	97.9	+255.2	58'	205.6	+464.8
123	100.1	+260.5	59'	206.7	+467.0
124	101.3	+270.7	60'	207.7	+470.4
125	102.6	+269.4	61'	209.7	+486.2
126	103.8	+274.1	62'	213.0	+488.8
127	104.8	+276.4	63'	214.0	+493.8
128	106.0	+277.9	64'	215.8	+496.8

Discrepancies between north and south lines of levels, run by L. L. Wheeler, between Austin and Friar's Point, Miss.

B. M.	[K]	[s—n]	B. M.	[K]	[s—n]
U. S. 1	0.0	0.0	U. S. 14	21.0	+16.8
1	1.6	+2.8	15	23.1	+20.8
2	2.7	+2.9	16	23.7	+17.0
3	3.6	+5.8	17	25.3	+15.5
4	4.6	+5.1	18	27.8	+19.0
5	5.9	+9.3	19	29.1	+21.2
6	6.9	+10.5	20	31.1	+18.5
7	7.9	+9.4	21	31.9	+19.4
8	8.7	+9.4	22	34.4	+23.2
9	10.8	+12.0	23	36.4	+23.0
10	12.5	+12.8	U. S. 23	36.9	+23.6
11	13.6	+13.6	24	39.9	+32.3
12	15.6	+17.1	U. S. 24	42.2	+34.0
U. S. 13	16.5	+16.8	U. S. 43.5		+36.5
	19.7	+17.6			

Precise levels from Keokuk, Iowa, to Grafton, Ill.

B. M.	Distance.	S.—N.	[S.—N.]	B. M.	Distance.	S.—N.	[S.—N.]
	km.	m. m.	m. m.		km.	m. m.	m. m.
66	112.86	—0.2	—0.2	115	176.76	+2.1	+52.8
67	115.61	+2.2	+2.0	116	177.85	—3.6	+48.7
68	116.38	+2.8	+4.8	35	180.63	+4.7	+53.3
70	119.02	+6.9	+11.7	119	181.60	+1.3	+54.6
73	122.29	+1.9	+13.6	36	182.96	—2.4	+52.2
75	126.51	—2.0	+11.6	123	186.24	+2.2	+54.4
78	129.02	+1.7	+13.3	124	187.26	+3.6	+57.8
79	130.26	+1.5	+14.8	37	187.92	—1.9	+55.9
23	132.30	+3.5	+18.3	125	189.28	+5.1	+61.0
24	133.74	+1.8	+20.1	126	189.99	—1.0	+60.0
82	136.00	—0.5	+19.6	127	191.95	+1.2	+61.2
85	138.59	+3.2	+22.8	128	192.72	+0.4	+61.6
25	140.02	+1.7	+24.5	129	194.10	—0.3	+61.3
87	141.07	—0.7	+23.8	38	195.45	—0.8	+60.5
88	142.29	+4.9	+28.7	130	196.95	+4.4	+64.9
89	144.08	+3.2	+31.9	131	197.93	+2.6	+67.5
91	145.68	+2.1	+34.0	132	200.00	—0.7	+66.8
92	147.02	+3.6	+37.7	40	200.51	+2.3	+69.1
94	147.95	+1.4	+39.1	133	201.87	—1.8	+67.3
*95	148.93	—0.2	+38.9	135	204.91	+2.9	+70.2
97	152.75	—1.7	+37.2	136	205.92	+4.0	+74.2
99	155.15	0.0	+37.2	137	206.74	+0.2	+74.4
101	157.80	+4.8	+42.0	138	207.62	+2.3	+76.7
102	159.76	+1.7	+43.7	139	209.24	—2.4	+74.3
81	161.18	+0.7	+44.4	140	209.93	+2.5	+76.8
104	162.18	+1.7	+46.1	141	211.52	+4.7	+81.5
106	163.62	—4.2	+41.9	141½	212.41	+3.0	+84.5
32	165.96	+2.7	+44.6	143	214.52	+3.3	+87.8
108	167.64	+0.2	+44.8	145	217.02	+1.0	+88.8
109	168.93	+3.8	+48.6	146	217.53	+0.3	+89.1
33	170.24	+0.6	+49.2	148	219.65	—0.1	+89.2
111	171.62	+0.1	+49.3	150	222.15	+1.3	+90.5
112	174.58	—2.5	+46.8	151	222.48	+0.6	+91.1
114	175.74	+3.4	+50.2				

* Between 95 and 97 there is a river crossing.

Discrepancies between north and south lines of levels run by Assistant Ferguson between Grafton and Cairo. The lines beyond T. B. M. 240 are not used because methods are changed.

B. M.	2 (distance).	S.—N.	2 (sum distance).	Sum (S.—N.).		2 (distance).	S.—N.	2 (sum distance).	Sum (S.—N.).
20	2.2	—0.5	2.2	—0.5	191	2.0	—4.9	39.1	—42.6
37	2.0	—0.7	5.1	—7.2	192	1.2	—1.1	39.2	—43.7
39	1.7	+0.3	6.8	—0.9	194	2.5	—0.7	41.6	—50.4
44	2.6	—4.6	10.4	—5.4	195	2.5	—2.8	44.8	—52.9
45	1.7	+4.8	12.1	—0.6	196	2.7	—9.2	47.0	—52.1
85	1.7	—2.3	12.8	—3.9	197	1.8	—3.8	48.8	—55.9
87	2.3	—1.9	14.1	—5.8	208	2.2	+0.2	51.0	—55.6
157	1.1	—4.7	17.2	—10.5	209	2.4	—9.9	51.0	—74.9
180	3.0	+0.1	20.2	—10.4	217	2.5	—5.2	55.9	—80.1
183	3.1	—2.4	23.2	—12.8	218	2.5	—0.4	58.4	—80.5
28	1.1	—0.5	24.4	—14.3	232	4.7	—7.6	63.1	—97.0
40	2.4	—7.2	26.8	—21.5	233	0.8	—5.7	63.9	—102.7
46	1.1	—2.0	27.9	—23.5	236	4.0	—20.2	67.9	—122.9
31	2.1	—7.7	30.0	—21.2	237	2.1	—12.2	70.0	—136.1
51	0.6	+1.2	30.6	—20.6	238	1.8	—11.4	71.8	—147.5
173	0.7	—1.5	31.3	—81	239	2.2	—12.8	74.0	—160.3
34	4.8	—5.2	36.1	—87					

APPENDIX D.

REPORTS OF CHIEFS OF PARTIES, UPON FIELD WORK OF TOPOGRAPHY AND HYDROGRAPHY, 1882-'83.

1.—REPORT OF ASSISTANT ENGINEER J. A. ORKINSON, ARKANSAS CITY TO GREENVILLE AND NATCHEZ.

OFFICE

MISSISSIPPI RIVER COMMISSION,
St. Louis, Mo., September 15, 1883.

SIR: I have the honor to submit the report on the field operations under my direction during the season of 1882.

In accordance with your instructions, the party left Saint Louis on September 12, 1882, for Arkansas City, arriving at the latter point on September 15. The quarter-boats Mississippi and Louisiana and the tug Frolic, which were assigned to the party, arrived on the 17th, and work was begun at once. The organization of the party was as follows: J. A. Orkinson, chief of party; topographers, B. H. Colby, N. B. Craig, J. C. Quintus, L. C. Jones, F. Felkel, G. M. Anderson, and W. Garvin; hydrographers, C. W. Clark and D. S. Flower; levelers, F. B. French and R. C. Hoyer; draughtsman, Edwin J. Jelley. E. E. Haskell was attached to the party until October 19th, when he received orders to report for duty to Assistant L. L. Wheeler at Vicksburg. F. Felkel and G. M. Anderson joined the party on October 16, and W. Garvin on October 28. R. B. Whiteford, who started out with the party, was disabled, and was ordered to Saint Louis on September 29. The laboring force was about the same as the previous season.

The topographical work began on the right bank at Arkansas City, and on the left bank at Offutt's Landing, where the work of last season ended.

The survey was completed on November 4 to Barnes' Landing, about 2 miles above Greenville, where it joins the work of Assistant G. Y. Wisner.

On the completion of this reach the party was ordered to Natchez to resume the survey and continue down the river. The party left Greenville with quarter-boats in tow of the tug Frolic on November 5, and arrived at Natchez on November 8.

The survey was completed to Bayou Sara, where it joined the work of Assistant C. M. Winchell, on February 19, when orders were received to disband the party and return to Saint Louis.

The stage of the river was unusually favorable for surveys during the entire season. At the beginning of the work there were many places which were impassable from the deposits of mud left by the previous high water, and in such cases considerable detail was necessarily omitted.

From the beginning of the season till the middle of October there was a great deal of sickness in the party. At one time one-third of the entire party were sick with malarial fevers. Of the original party, twenty were discharged before October 25, on account of sickness. Judging from this experience, it is evident that it is not safe to take the field prior to the middle of October.

There were thirty-three days of rain and fog, or a little more than one-third of the entire season.

The progress of the work is due to the hearty co-operation of my assistants, who are deserving of credit for their fidelity and energy.

TERTIARY TRIANGULATION.

The secondary triangulation was not carried over Spanish Moss Bend, and at other points so many stations had caved into the river, that a tertiary system became necessary over the entire reach above Greenville. Below Natchez the tertiary work became necessary because the data, such as azimuths and lengths of triangle sides, was not furnished to the party.

The tertiary work was always connected with the secondary stations when found, and a comparison has been made with the secondary data on file in this office. The results are given in a table below. The tertiary angles were measured with Würdemann, No. 152, reading to 10 seconds, and Gambey, No. 2, reading to 5 seconds. Angles were read by J. A. Ockerson and B. H. Colby.

Comparison of tertiary with secondary triangulation.

Lines compared.	No. of tertiary triangles.	Tertiary lengths.	Secondary lengths.	Ratio of discrepancies.
		<i>meters.</i>	<i>meters.</i>	
Walwood-Carter	34	1389.67	1389.7	1 in 46323
Winn-Oliver	10	2818.4	2819.5	1 in 2562
Will--Allway	18	1938.6	1939.6	1 in 4846
Island-Pullen	38	1518.6	1518.2	1 in 3798
S. W. Base-Rock Hill	58	3152.0	3152.6	1 in 10509
Lathernan-Stump	88	1547.2	1547.3	1 in 15472
Stevenson-Douglas	96	2223.8	2223.5	1 in 7412
N. W. Base-St. P. church spire.	25	1389.7	1389.7	Lengths equal.

The following method was used in reading the angles. The system was laid out and the angles generally read in advance of the topographers, so that the lengths of sides and azimuths could be used to check the stadia work. The A point was marked by a pole about 2 inches in-diameter, and bearing a red-and-white flag to distinguish it from the ordinary sounding flags. A strip of white cloth was fastened around the pole near the bottom, to which the pointings were made, thus obviating errors from swaying of the pole in the wind, or from its being out of plumb. In observing, the theodolite was placed on an ordinary instrument tripod centered over the hole, after removing the pole. The angles were read three times on different parts of the limb to check errors of reading. Most of them were measured with Gambey No. 2. No attempt was made to confine the measuring to favorable conditions of atmosphere, but angles were read whenever the target could be seen at all.

Flags can be set and the angles read over a reach of 5 miles a day. Considering the time spent in this work, the results shown are remarkably good.

In view of the desirability of having frequent checks on the stadia work, particularly where there are so many new observers, I would suggest that the topographical parties be required to locate points at intervals of not more than a mile, by means of a tertiary system of triangulation. This system should begin and end on lines of known length, so that it can be checked.

TOPOGRAPHY.

The general scope of the topographical work was the same as last season, a description of which is given in Appendix G, Progress Report of the Mississippi River Commission, 1882. The compass was used in running lines through the woods, as suggested in above report. This method was found to be quite satisfactory, and much more rapid than the transit lines used in former work.

Beyond the prescribed topographical limits there were located the outlines of bluffs, old river lakes and bayous, and the Red River from Cut-off Bayou to the Mississippi River.

HYDROGRAPHY.

Many more soundings were taken than heretofore. Besides the sections normal to the channel, soundings were taken along the line of deepest water. The latter work

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

was preferably done during calm weather, when the sounding boat was allowed to drift along the thread of the current. The deepest water found during the season was 156 feet, the stage of river being about 27 feet below the high water of 1872. This depth was found at two points, one near New Texas, and the other about five miles above Bayou Sara.

ORDINARY LEVELS.

The levels were based on the primary elevations of the United States Coast and Geodetic Survey. Very few of the Coast Survey stone lines were connected with the stones could not be found. Many of them were buried below, or even with the surface of the ground, and no mark was left above the surface to indicate the location of the bench mark.

A new form of bench mark was used for points situated in the woods, some distance from the river, the object being to increase the stability and make them more conspicuous, so they can be easily found.

This bench mark consisted of a flat stone, 12 inches square and 4 inches thick. The upper surface was dressed smooth, and a hole was drilled in the center, into which a copper bolt was inserted, the end projecting a quarter of an inch above the face of the stone.

The stone was marked thus $\begin{matrix} U\ S \\ B\ M \end{matrix}$ This was placed three feet below the surface of the ground, with the marked surface up, care being taken to have it horizontal and firm.

On this stone, and centered over the copper bolt, a cast iron pipe, 4 inches in diameter, and 3 feet long, was placed, and the dirt tamped in around it. The pipe is large enough to admit a leveling rod. The top is closed with a cap, which is fastened to the pipe by means of a bolt.

The cap is marked as follows:



The elevation of both the top of the pipe and the stone were determined. The amount of work done is given in a table below.

TOPOGRAPHY.

Number of miles of river surveyed (above Greenville, 36; Natchez to Bayou Sara, 100)	
Average miles of river surveyed per month	
Number of square miles of topography (above Greenville, 704; Natchez to Bayou Sara, 250)	32
Average number of square miles per month	
Number of elevations determined	34
Average number of elevations per square mile	
Number of triangulation stations occupied	
Number of base lines measured with steel tape	
Number of stone bench-marks set	

HYDROGRAPHY.

Total number of soundings	23,
Number of sextant angles read	15,
Average distance between sections	3
Number of square miles of hydrography	
Total number of square miles surveyed	

Plate 1 shows the portion of the river covered by the survey.

CAVING BANKS.

The rate of caving in the bends between Arkansas City and Greenville during years 1880 to 1882, as determined by comparing the present position of the alignment with its position when the triangulation was done, is given in a table below.

There being no reliable data for determining the rate of caving below Natchez, this much has been omitted.

Locality.	Character of banks.	Annual rate of caving.
		<i>Meters.</i>
Yellow Bend $2\frac{1}{2}$ miles below Arkansas City.....	Clay and sand	57
Yellow Bend $3\frac{1}{4}$ miles below Arkansas City.....	do	14
Yellow Bend opposite Port Anderson	Sand and silt	22
Georgetown Bend $\frac{1}{2}$ mile below Offutt's	Clay and sand	39
Georgetown Bend at Eutopia	do	39
Georgetown Bend at Ashbrook Point.....	Sand and silt	29
Rowdy Bend $\frac{2}{3}$ of a mile below Gaines Landing	Clay and sand	35
Rowdy Bend $\frac{2}{3}$ miles below Gaines Landing	do	14
Rowdy Bend at Scott's Landing	do	22
Miller's Bend at Morris Landing	do	40
Miller's Bend at Tarpley place	do	28

SAND WAVES.

A minute survey was made of a sand bar near Fairview, La., for the purpose of showing the sand waves which are characteristic of all bars. The bar selected is not an extreme case. There are many which have larger and higher waves, and others which are comparatively smooth. In the latter case the waves have the appearance of a pond whose surface is ruffled by a gentle breeze.

It is evident that these waves are mainly due to the action of the water, as they are frequently found on the lower part of bars composed of silt, which is not movable by the wind. The particles on the above bar are about the size of common building sand. The crests of the waves are smooth curves, which are frequently parallel for several waves in succession.

The bluff part of the wave is on the down-stream side, and is frequently nearly vertical. The slope on the up-stream side is generally very gentle.

A plat of the Fairview Bar, which shows the waves by means of contours one foot apart, and two sections of the bar, is appended herewith. A model, showing the bar in relief, has also been prepared.

LEVEES.

ARKANSAS CITY TO GREENVILLE.

Right bank.—From Arkansas City down $\frac{1}{2}$ mile the embankment of the L. R. and M. R. R. serves the purpose of a levee. Here the railroad turns back, and the embankment of an old abandoned railroad continues along the river for $1\frac{1}{2}$ miles, when it disappears. One and a half miles lower down it again appears and follows along the bank of what was at one time the chute of Island 80, to Gaines Landing, the only break being a small one through which Boggy Bayou passes. At this break the levee is now about 2 miles from the river. A private levee incloses the plantation at Gaines Landing. After following along near the river for $\frac{1}{2}$ mile below Gaines the levee ends abruptly on the caving bank of Rowdy Bend. This break is about 3 miles long, reaching to a point near Scott Landing. Here the levee divides, and one portion of it runs south about half way across the point, then turns west and runs to Yellow Bayou, forming a back levee for the plantations fronting on Spanish Moss Bend, and turning the water which overflows the banks in Rowdy Bend into Bayou Maçon.

The other part of the levee follows along near the river down to the chute of Island 82, thence down the chute to river on the lower side of the point, thence along river bank again down to near Bellevue Landing. Here it turns and joins the back levee mentioned above. This line is broken in many places, one of the breaks, near Linwood, being about $\frac{1}{2}$ mile long.

The levee begins again $\frac{1}{2}$ mile below Bellevue and 600 meters from the river, and runs down till it joins the old levee about $\frac{1}{2}$ mile above Luna. The old levee extends above this juncture about a mile. From Luna the levee is continuous for about $4\frac{1}{2}$ miles, when it is again out off by a caving bank. At Point Chicot Landing it appears again and runs directly back from the river for a distance of 600 meters, where it is again broken, and does not appear till beyond the limits of this survey.

Left bank.—From Offutt's Landing the levee runs almost directly across to a point $1\frac{1}{2}$ miles above Argyle Landing, leaving Ashbrook and Woodstock Points outside. It is 550 meters from the river at the lower part of Miller's Bend. From the point where it strikes the river above Argyle it turns and runs down at a distance of $\frac{1}{2}$ mile from the river in the deepest part of the bend, and continues down behind Island 83 to Greenville.

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

NATCHEZ TO BAYOU SARA.

Right bank.— From Vidalia the levee runs down near river bank to Whitehall. Here it turns back and runs around Natchez Island, coming near the river again near Crocker's Plantation. From latter point it runs about 400 meters from the river till it reaches the head of Sails. Catherine's Bend, where it turns and runs directly across Esplanade Point to the Pecan plantation, about $\frac{1}{2}$ mile above Green's Landing. A small levee then follows along near the river for a distance of a mile and there ends. From the latter point to Ashley Landing there is no levee. Then comes a piece, badly broken, aggregating $1\frac{1}{2}$ miles long. Below this there is no levee till we reach Fairview, where there are several patches, with a total length of about $1\frac{1}{2}$ miles. At Home Place we again find a small levee 1 mile long, and small patches may be found down as far as Bongere. Then there is no levee till we reach Union Point, where it starts back at the old river bank behind the batture, and continues for about 3 miles. Then comes a break extending to Black Hawk. From this point the levee follows along behind cypress swamp for about 3 miles, and finally, after numerous breaks, is lost entirely and no more levee is found till Red River Landing is reached. From latter point it runs along near river to Smithland, where it turns back along bank of Old River, touching the river again at Fleets above New Texas. There is an old levee about 1 mile long lying along bank of Old River, but opposite Tunica Island and 1 mile from the main river.

From Fleets the levee "Grand Levee" is broken continuous down to the end which was nearly closed.

Left bank.— There is Tunica Island. From this section was known. It remains. There are small patches it disappears entirely, and Morganza. From the Island Stuart's Landing. It is half a mile of the mouth of the river.

There are private levees about $1\frac{1}{2}$ miles long, which are

Behind the Corena plantation, which serves to keep out the back water.

Allaway plantation has a small front and back levee $1\frac{1}{2}$ miles long. Artonish plantation above Stamp's Landing, has about 1 mile of levee. Langside plantation has a levee along lower side of Clark's Lake, which is about 1 mile long. On the Angola plantation a levee starts in about opposite Smithland and follows along about a mile from the river for a distance of about 4 miles, when it runs into the batture. The locations of the above-described levees may be seen on Plate 1, accompanying this report.

STONE LINE SECTIONS.

In the Report of Mississippi River Commission, Appendix G, page 162, a discussion of river bank profiles is given. A continuation of the same study has been made to embrace that part of the river lying between Arkansas City and Donaldsonville.

The sections of the banks do not differ materially from those heretofore published until we reach a point near Baton Rouge (Stone line No. 11). From this point down the levees are very close to the edge of the bank, and the land outside of the levee is very often three or four feet higher than that on the inside. This indicates a deposit of that amount since levees were built. Sometimes this deposit reaches nearly to the top of the levee.

The sections of the river bed grow gradually narrower and deeper as we approach Donaldsonville.

Respectfully submitted,

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission

J. A. OCKERSON,
Assistant United States Engineer.

REPORT OF ASSISTANT ENGINEER C. M. WINCHELL, LAKE PROVIDENCE TO WARRENTON AND BAYOU SARA TO DONALDSONVILLE.

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., June 22, 1883.

I have the honor to make the following report concerning the work done by hydrographic and topographic party under my charge during the field season of 1883:

Obedience to written instructions from you, I left Saint Louis on September 26, for Lake Providence, La., to assume charge of the party which had been organized and taken the field under the direction of Assistant G. Y. Wisner. I arrived at Providence October 3.

From this date the party had been engaged in filling up gaps in the last year's work which had been skipped on account of the high water of 1882.

Survey was continued with the assistants assigned as follows: Hydrography, Russell and C. N. Roberts; topography, left bank, G. W. Wood and F. B. ; topography, right bank, J. A. Paige and H. W. Kerr; levels, J. C. Cammack and Moses Greenwood. Recorder J. T. Desmond plotted most of the topographic field-notes, the field-plats being completed by the topographers on rainy days or other times when they could not work to advantage in the field.

Assistant S. L. Beaumont did some topography and assisted in the plotting until he began work at Bayou Sara, January 8, when he was made hydrographer, after having resigned December 28.

Assistant J. C. Cammack died in New Orleans December 31, and Recorder C. N. Roberts carried the levels on the left bank from Port Hudson to Donaldsonville, La. Assistant A. L. Arner reported for duty January 12, and was assigned to assist the hydrographic party.

Cammack was an enthusiast in his profession, a conscientious worker, and excellently well informed in the various branches of engineering. By his untimely death the Commission lost a valuable assistant, and his messmates a beloved friend. He was highly esteemed by all who knew him.

Rate of progress of the work was materially lessened during October and November by sickness, nearly every member of the party suffering from fever or chills. B. R. Morgan, steward, died October 13 and was buried on land of Judge Hays' Landing, Miss. There were very few new cases of sickness after the cold frosts, but 26 men, out of a party of sixty, were discharged on account of sickness before November 15.

Survey was based on a system of secondary triangulation previously executed by the United States Coast and Geodetic Survey, all intermediate points for delineating topographic features being located by transit and stadia, the stadia courses being checked by connecting with triangulation stations. A continuous line of levels was run down each bank of the river and numerous points determined to aid the topographers in developing the five-foot contours. The levels are referred to the datum plane of the Mississippi River Commission, and are checked by comparison with precise bench-marks established under direction of the United States Coast and Geodetic Survey.

Line bench-marks were established once in about three miles of river, consisting of four stones (two on each side of the river), set in line at right angles to channel of the river, the stones furthest back being usually 1,000 to 1,200 meters from the river bank. These lines were so arranged as to pass through a triangulation station on one or both banks of the river, the distance back being determined by the triangulation.

The elevations of the bench-marks were checked by duplicate levels. Two kinds of bench-marks were used, the ones nearest the river being granite posts three feet long and six inches square, set in the ground with their tops projecting about six inches above the surface. The bench-marks set farther from the river consisted of stones 15" x 18" x 4", with copper bolt leaded into hole in center of upper surface. One was set 2½ feet below the surface of the ground, and an iron pipe five feet in diameter was carefully centered over the copper bolt and held in position until the hole was filled and ground tamped around the pipe. The top of the pipe is covered with a cap which can be removed to admit the leveling rod so that the stone can be reached without disturbing the earth around or over it. The elevations of the top of the copper bolt in the stone, and of the top of the cap on the pipe, were both determined in the same manner.

This style of bench-mark is preferable to the stone post, because, having a much larger base and being lighter, its value will not change so much by settling; the one being entirely beneath the surface, will not be in so much danger of accidental disturbance as the stone post which projects above the surface; and, lastly, it is more easily found, the iron pipe projecting 2½ feet above the ground.

In wooded country the compass and stadia were used for locating points of elevation and for developing the five-foot contours. By using the compass, woods and swamps were examined more rapidly and with less cutting than by the usual method of

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

10 20

thus considerably reducing the expense of the survey. When the work was connected with the regular stadia courses, or with triangulation, it was found that the work closed with an error of less than

the survey was completed to Big Bayou, about eight miles below Vicksburg, where Lieutenant L. L. Wheeler's party began work, December 22. The tug Mignon, which had become disabled, was laid up, and the party was detained at Vicksburg until January 1, 1883, waiting for a boat to move us to Bayou Sara, La.

In obedience to your instructions the party started for Bayou Sara as soon as the iron launch which had been assigned to the party was repaired sufficiently to make the trip.

Work was begun at Bayou Sara January 8, six days having been consumed in getting there from Vicksburg. We were delayed on the way by fog and by the wheel of the launch getting loose, which made it necessary to hoist her out of the water for repair. A new hub was cast for the wheel at Baton Rouge, but the boiler leaked so badly that the tug was of very little use the rest of the season. The tug Frolic was assigned to the party a short time, which enabled us to get good soundings of the channel below Plaquemine, where they could not well have been obtained by the six-oared cutter, at the then existing high stage of river, on account of the deep bays and strong currents.

Below Bayou Sara the river, because the bank river being much less than

The survey was completed on Survey topography March 17. The party were retained and returned to the Pioneer, the tug Frolic, and the tow-boat Baker, and his regular

A full description of the work required for each party, and of the Report of the Mississippi River Survey

The season's work may be summarized

Miles of river surveyed
Square miles of topography
Square miles of hydrography

Total area surveyed square miles.

Discrepancies between precise and ordinary levels.

Between P. B. M's.	Distance.	Discrepancies.	Observer.
	Miles.	Feet.	
No. 112 and 1128	23	+0.194	J. C. Cammack.
No. 128 and 137	54	-0.017	Do.
No. 137 and 140	14	-0.195	Do.
No. 140 and 150	54	-0.042	Do.
No. 150 and 162	15	-0.144	J. C. Cammack and M. Greenwood.
No. 162 and 171	5	-0.043	Do.
No. 171 and 179	4	-0.042	Do.
No. 179 and 184	24	-0.064	Do.
No. 184 and 188	2	-0.077	Do.
No. 188 and 197	5	-0.100	Do.
No. 197 and 207	44	-0.007	Do.
No. 207 and 211	44	-0.084	Do.
No. 211 and 215	74	-0.039	Do.
No. 215 and 217	5	+0.071	Do.
No. 217 and 236	84	+0.051	Do.
No. 236 and 25	6	-0.078	Do.
No. 25 and 34	9	+0.064	Do.
No. 34 and 33	5	-0.078	Do.
No. 33 and 32	64	+0.043	Do.
No. 32 and 39	14	-0.074	C. N. Roberts.
No. 39 and 28	1	+0.090	Do.
No. 28 and 27	34	-0.030	Do.
No. 27 and 26	44	-0.116	Do.
No. 26 and 25	7	-0.014	Do.
No. 25 and 24	5	+0.023	Do.
No. 24 and 23	64	+0.138	Do.
No. 23 and 22	24	-0.163	Do.
No. 22 and 21	64	-0.136	Do.
No. 21 and 20	44	+0.010	Do.
No. 20 and 19	34	-0.062	Do.
No. 19 and 17	64	+0.030	Do.

The sum of these discrepancies is -0.869 feet for a distance of 159 miles.

Discrepancies between right and left bank ordinary levels.

Locality where compared.	Distance.	Discrep- ancy.
	Miles.	Feet.
.....	7	0.221
.....	3½	0.018
.....	6	0.190
.....	11	0.167
.....	4½	0.19
.....	6	0.130
.....	6	0.111
.....	10½	0.219
.....	4½	0.160
.....	4½	0.100
.....	12	0.028
.....	2½	0.278
.....	8	0.180
.....	3	0.130
.....	3½	0.004
.....	5	0.113
.....	3½	0.100
.....	7½	0.122
.....	4½	0.036
.....	4	0.014
.....	2½	0.064
.....	7	0.092
.....	5	0.005
.....	4	0.194
.....	8	0.046

HIGH-WATER MARKS.

Providence	Well-defined mark on tree opposite Lake Providence, La	1882	114.98
.....	Nail in large oak tree	1882	111.53
.....	do	1880	109.49
No. 97	Well defined mark on Mr. Zach. Leatherman's house, about one mile below Arcadia Landing.	1882	110.45
n's Bend	On steps of Morancy's house, back of levee	1882	102.25
.....	Mark cut on corner of gin-house in front of levee	1882	105.05
.....	On steps of dwelling three miles below Young's Point Landing	1882	90.62
.....	On United States gauge	1882	47.60
.....	Mark on tree two miles above Plaquemine	1882	30.60
.....	Nail in cottonwood tree at landing	1882	30.00
Do	do	1880	35.40
.....	1882	37.65
.....	Well-defined mark on warehouse	1882	37.35
.....	Mark on warehouse established by Gen. J. Thompson	1874	36.12
.....	Marks cut on northwest corner of market-house by Gen. Jeff. Thompson.	1862	35.21
Do	1869	33.73
Do	1874	35.18

Table showing surface slope of river as determined by this survey.

	Distance.	Slope per mile.	Vicksburg gauge- reading.	Rising or falling.
	Miles.	Feet.		
Providence to head of Island 95	6.7	0.70	11.50	Falling.
of Island 95 to Hays' Landing	3.5	0.49	9.2	Stationary.
Landing to Wilton	6.8	0.40	8.9	Do.
..... to Chotard	10.8	0.54	9.0	Falling.
..... to Omega	8.3	0.26	8.8	Stationary.
..... to Helpino Landing	7.0	0.55	11.2	Rising.
..... to Nebraska Landing	4.5	0.36	13.5	Do.
..... Landing to King's Point	5	0.19	12.6	Falling.
Point to head of Warrenton T. H	5.5	0.16	11.2	Do.
Sara to Kelson Landing	12.8	0.14	*15.2	Rising.
Landing to Lobdell's Landing	12.5	0.13	*14.5	Stationary.
..... Landing to Baton Rouge	10	0.12	*18.7	Rising.
Rouge to Manchac	10	0.12	*24.1	Do.
..... to Forlorn Hope	14	0.12	*27.5	Do.
..... Hope to Bayou Goula	7.6	0.14	*26.6	Stationary.
Goula to Donaldsonville	19.5	0.12	*30.4	Rising.

* Baton Rouge gauge.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Equality of the work accomplished is due in a great measure to the industry of my assistants, to whom I desire to express my thanks for the skillful manner in which they performed their duties.

Faithfully, your obedient servant,

C. M. WINCHELL,
United States Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

3.—REPORT OF ASSISTANT ENGINEER L. L. WHEELER, WARRENTON TO NATCHEZ.

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., July 5, 1883.

SIR: I have the honor to submit the following report upon the operations of the party in my charge during the season of 1882-'83.

The work assigned to the party was to make a topographical and hydrographic survey of that portion of the Mississippi River lying between Warrenton and Natchez, or at least three-quarters of a mile on each side, and in all of the lakes, sloughs, bayous, and other topographical features within a distance of ten miles of the river.

The party left Saint Louis the 10th of October, on the quarter-boat Illinois and Kentucky, and was taken in tow by the steamer Osage the 20th. Two days were spent in getting the boats towed down to Natchez.

Assistant Engineer E. E. Hastings was sick and was obliged to return to Saint Louis. E. Kastl were detailed for the party about the middle of October. Recorder E. K. Woodward was promoted from rodman to assistant engineer. The party consisted of Assistant Engineers Wheeler, J. W. Dorst, O. A. Kastl, and Fred Morley, E. K. Woodward, Jr., and a complement of men.

The field-work commenced November 1 on the triangle side "Last-Big Bayou," about seven miles below Vicksburg, and continued until February 22, 1883, when the work was completed to Natchez.

The following day instruments, charts, note-books, &c., were packed and sent by express to Saint Louis, and the party disbanded, the assistants returning to the office.

The party was therefore engaged in field-work 114 days, 16 of which were Sundays, one an observed holiday, and on 14 the weather was such that no field-work could be done. Field-work was therefore done on 83 days, on many of which, however, only part of the day was suitable for work.

The length of main river surveyed was 93 miles, embracing 217.2 square miles of topography, and 63.3 square miles of hydrography, or a total area of 280.5 square miles surveyed.

The survey was based upon a system of triangulation and a line of precise levels executed by the United States Coast and Geodetic Survey, the results of which were furnished from that office. The survey was made in the following manner:

1st. A line of levels was run on each bank, which determined the elevations of triangulation stations, sounding stakes, stadia-stakes, stone line bench-marks, water gauges, high water marks, water surfaces, &c. The levels on the right bank were checked by the precise levels, and those on the left bank by reciprocal leveling across the river. The two lines also mutually checked each other by frequent determinations of water surfaces on opposite sides of the river. All elevations were referred to the Memphis datum plane, which is a plane 225 feet below the reading 34.16 on the Memphis gauge. The leveling was performed by Assistants Dorst and Kastl.

2d. A stadia line was run on each bank, checking frequently as to azimuth and distance upon triangulation stations and intersections on distant signals, and as to elevations upon the line of levels run on each bank.

The principal topographical features along the river bank, including landings, gauges, lights, sounding-stations, &c., were located when the shore line was run. The topography back from the river was taken by lines run back for that purpose. Where the country was wooded lines were cut back from the river three-fourths of a mile in such a direction as would best determine the topography. The locating of

rees, lakes, bluffs, bayous, &c., when beyond the limit of topography, was done by stadia lines connecting with the main lines. The topographical work was done by Assistants Darrow, Ferguson, Weber, Milner, and Recorder Woodward.

3d. The hydrography consisted of lines of soundings taken normal to the stream every 400 meters, and a line of soundings taken longitudinal to the stream. The soundings were taken with a 22-pound tallowed lead, about every third sounding being located by sextant angles between signals on the banks. A sounding line of Italian hemp was first used, but was discarded and a cotton line used instead.

Assistant Wood and Recorder Morley performed the hydrographical work, and also materially aided in the other work of the survey.

4th. The points located by the topographical parties were plotted on protractor sheets to the scale 1:10000, the sketching, contours, &c., being put in by the observers when field-work could not be done. The plotting was done by Assistant Orrman.

5th. All notes were reduced in the field, and all note-books indexed.

6th. The points of the survey were marked on the ground by the usual lines of marking-stones, the positions and elevations of which were determined, and descriptions of which were made in a book kept for that purpose.

My thanks are due to the assistants and recorders for their hearty co-operation and interest in the work. Assistants Darrow, Ferguson, and Wood gave me valuable assistance aside from their regular duties, and deserve special mention for the interest shown in the general progress of the party.

Very respectfully, your obedient servant,

L. L. WHEELER,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

4—REPORT OF ASSISTANT ENGINEER H. B. WOOD, UPON RESURVEYS IN FRONT OF CREVASSES.

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, September 15, 1883.

SIR: I have the honor of submitting to you the following report on hydrographic work above Arkansas City, completed during the months of October and November, 1882.

The special object being to ascertain the effect of large breaks in levees upon the river bed during the great spring flood of 1882, four reaches in the immediate vicinity of said breaks were selected for hydrographic observations, all of which were located in that portion of the river surveyed by the party in charge of Mr. J. A. Ockerson, assistant engineer, during the winter season of 1881-82, just before the flood. The first reach extended from Malone's Landing, near the foot of Island No. 66, to Australia; the second, from Riverton to the head of Ozark Island; the third, from Bolivar to Cypress Creek; and the last, from Mound Place to Arkansas City.

The party consisted of two assistant engineers, pilot, steam engineer, fireman, cook, boatman, and two rodmen, and was provided with the tug Eva, of Helena, two skiffs, and camping outfit.

To re-sound the sections as located by the previous party required that the stone lines should be found, and where no Δ stations or other landmarks of prominence served to identify the other sections, a stadia line was run, and the positions of former sections marked. Accordingly, with some few exceptions, the re-sounded sections were identical with those previously established.

The water surface was connected at frequent intervals with established benches referred to the Memphis datum, and a constant gauge record kept during the progress of the work.

In the first reach, from Malone's Landing, thirty-two sections were re-sounded, covering a distance of about sixteen miles. These cross-sections have been plotted, together with the corresponding ones of the previous year, and their areas approximately measured with the planimeter, the results being tabulated herewith. A very small amount of filling-in below the breaks occurred here. By the annexed table of compared areas of cross-sections, it will be seen that an average fill has taken place, making each section about 2,200 square feet less in area than before the flood, not counting sections that were above or below their former position.

In the second reach, from Riverton, seventeen sections were re-sounded, covering about nine miles. Here each section averaged about 11,000 square feet less in area than formerly.

In the third reach, from Bolivar, where eighteen sections were re-sounded in a distance of ten miles, each section averaged 8,400 square feet less in area than when sounded the previous year.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

on Mound Place, where nine sections were re-sounded in a distance of one hundred and forty five miles to Arkansas City. At the conclusion of the work, the party proceeded to Vicksburg, and joined the party in charge of Mr. L. L. Wheeler, Assistant Engineer, then located at Moore's Landing, according to your orders.

The following are the approximate crevasse discharges for the several reaches were measured by Assistant Engineer J. B. Johnson:

	Cubic feet per second.
First reach, Lake Charles and Pushmataha Breaks,.....	15,000
Second reach, River on Break.....	107,480
Third reach, Bolivar Breaks.....	123,250
Fourth reach, Mound Place Break.....	20,600

The above survey occupied from October 10, 1882, to November 10, 1882, during which time seventy-six sections were resounded, covering forty miles of the total distance of one hundred and forty five miles to Arkansas City. At the conclusion of the work, the party proceeded to Vicksburg, and joined the party in charge of Mr. L. L. Wheeler, Assistant Engineer, then located at Moore's Landing, according to your orders.

Very respectfully, yr

HENRY B. WOOD,
Assistant Engineer.

FIRST LIEUT. SMITH S. LEACH,
Secretary Mississippi River Comm.

Table showing approximate areas of sections of

FROM MALON

to a common water-level both before and after

to AUSTRALIA.

Section.	Area before flood.		Difference.	Remarks.
	Square feet.	Square feet.	Square feet.	
Stone line No. 28.....	62,850	97,550	Cut out by chute 68.
16.....	64,200	64,100	- 100	
17.....	77,100	68,100	- 9,000	
18.....	81,000	64,000	- 17,000	
19.....	71,550	69,100	- 2,450	
20.....	87,150	60,900	- 26,250	
Stone line No. 39.....	60,000	78,400	+18,400	
25.....	66,800	67,800	+ 1,000	
26.....	56,450	63,250	+ 6,800	
27.....	52,000	50,350	- 1,650	410' below old sect.
28.....	61,550	66,500	+ 4,950	
29.....	48,700	38,500	-10,200	
30.....	52,750	57,000	+ 4,250	
31.....	45,200	41,900	- 3,300	
32.....	49,100	44,400	- 4,700	
29 (chute 68).....	14,850	13,850	- 1,000	
Ft. chute.....	15,250	19,000	+ 3,750	
33.....	54,950	49,100	- 5,850	
34.....	84,400	77,050	- 7,350	
35.....	78,050	75,550	- 2,500	
36.....	71,500	78,650	+ 7,150	
37.....	74,850	72,850	- 2,000	
38.....	61,650	58,550	- 3,100	
39.....	61,800	55,550	- 6,250	
40.....	62,350	56,800	- 5,550	
41.....	61,000	51,000	-10,000	
42.....	49,100	60,000	+ 10,900	
Δ Id. 60.....	55,400	64,000	Below old sect.
44.....	66,000	73,000	Do.

howing approximate areas of cross-sections below a common water-level both before and after the flood of 1882—Continued.

FROM RIVERTON TO HEAD OF OZARK ISLAND.

Section.	Area before flood.	Area after flood.	Difference.	Remarks.
	<i>Square feet.</i>	<i>Square feet.</i>	<i>Square feet.</i>	
.....	65,300	69,800	+ 4,500	
.....	74,050	64,850	— 9,200	
.....	70,550	43,100	—27,450	
.....	87,100	66,400	—20,700	
River.....	109,400	91,900	—17,500	
.....	71,800	90,100	+18,800	
.....	50,000	63,150	+13,150	
.....	92,000	65,600	—26,400	
.....	92,550	74,150	—18,400	
.....	68,200	65,750	— 2,450	
.....	75,350	57,400	— 7,950	
.....	65,250	56,450	— 8,800	
.....	92,200	69,100	—23,100	
to Angle 22.....	12,000	84,600	In pocket below old sect.
to © L118.....	109,000	79,700	—29,300	
Pt.....	160,050	158,450	—10,600	

FROM BOLIVAR TO CYPRESS CREEK.

.....	52,500	46,800	Below old sect.
er.....	12,150	11,000	— 1,150	
.....	82,650	48,800	300 ^m below.
.....	75,850	51,350	—23,500	
.....	92,150	63,000	—29,150	
.....	79,800	70,150	— 9,650	
.....	74,250	68,100	— 6,150	
.....	70,100	59,750	—10,350	
.....	58,200	62,100	+ 3,900	Midstream.
y Pt.....	57,950	45,650	—12,300	
.....	4,100	2,700	— 1,400	Old River, Catfish T. H.
.....	85,250	82,900	— 2,350	
.....	53,550	45,650	— 7,900	
.....	87,650	60,400	—27,250	
.....	66,700	56,000	—10,700	
me No. 58.....	75,950	73,600	— 2,350	
.....	81,850	87,100	+ 5,250	
l Luck.....	62,550	68,500	+ 5,950	
.....	68,450	64,250	— 4,200	
.....	72,500	53,900	—18,600	

FROM MOUND PLACE TO ARKANSAS CITY.

.....	60,600	71,200	+10,600	
.....	94,500	66,150	—28,350	
.....	100,700	67,150	—33,550	
.....	106,700	56,550	—50,150	
.....	79,600	64,550	200 ^m above old sect.
.....	102,000	88,800	—13,200	
.....	122,850	90,000	—32,350	
line No. 63.....	103,550	83,600	—19,950	

APPENDIX F.

REPORT OF ASSISTANT ENGINEER E. S. DAVIS UPON THE FIELD-WORK AND RESULTS OF TRANSALLUVIAL LEVELS.

SAINT LOUIS, MO., June 21, 1883.

SIR: I have the honor to submit the following report on the work of trans-alluvial leveling.

The scheme for this work contemplated nine sections, located at the following-named places, all of which have been run, except No. 3:

1. From the Mississippi River, at Island No. 13, east and west to land above overflow.
2. From the Mississippi River, at Hickasaw Bluff west to land above overflow.
3. From Memphis east to uplands beyond the Saint Francis River, on line of Memphis and Little Rock Railroad.

4. From Helena.
5. Up Cypress Creek.
6. From Grand Gulf west to land above overflow.

7. From Lake Providence.

8. From Grand Gulf west to land above overflow.

9. From Fort Adams west to land above overflow.

10. From Bayou Boeuf, and one across the Mississippi River.

11. From the Mississippi River, at Island No. 13, east and west to land above overflow.

The location of No. 8 was determined by the location of No. 7. The line contemplated from Helena to Lake Providence was expected to run after the precipitation of running it after the presence of water in the stream had been submerged when work was to be done.

The work has occupied the time from the first of June to the first of August; also the time from the first of August to the first of September. The time from the first of September to the first of October is included in the time from the first of August to the first of September.

Bayou Maçon Hills across the cut-off

Island.

; thence two branches, one across

half to Saint Joseph.

season been omitted, with the exception of the time had been made impracticable by the opening, however, that this line has been abandoned, and it yet remains

following table gives the amount of progress. The time given each season is the date of disbanding the party:

Season.	Distance.	Time.	Average daily rate.
	Miles.	Days.	Miles.
1880-'81	62	150	.41
1881-'82	62	104	.50
1882-'83	164	174	.97

About 20 per cent. of the time spent in the field has been occupied in traveling from Saint Louis and between lines.

Over each line levels in duplicate and a traverse have been run. All streams crossed have been gauged roughly; elevations of high-water marks have been taken where they could be found. An azimuth has been observed at the inland end of each line except No. 5.

During the first season (1880-'81), Mr. Hunter Stewart assisted me, he running the traverse and I the levels. A transit and stadia were used in running the traverse, the stadia being used to measure all distances. An ordinary level and target-rod were used in running the levels.

During the first part of this season the levels were checked by running between benches a second time. During the latter part of the season the levels and check levels were run at the same time, the following method being employed: After the rod had been read in the usual position, it was inverted and held on the same point as before, and another set of readings taken. This method of checking levels will be discussed later. During the second and third seasons a combined level and transit was used.

The combination was made by fastening the essential parts of a Stackpole level to the limb of a Würdemann transit.

The device for making the combination is very simple and inexpensive, as shown by the following sketch:




Fig. 1 is a vertical projection of a part of the instrument.

L is the bar of the level.

T is the bar of the transit.

A is the transit axis.

C and C are the collars used to hold the two instruments together.

Fig. 2 is a horizontal projection of the same parts.

Fig. 3 is a right section through the collars and shows how the parts are fastened together. When a transit was needed for azimuth observations, the screws shown in Fig. 3 were taken out, the collars and level bar removed, and the transit wyes fastened on the transit bar by the same screws. It took only a few minutes to make this change.

By the use of the combined instrument one observer was enabled to run the levels, check levels, and traverse at the same time.

As a level the combination worked admirably, and the results of azimuth observations indicate that it worked well as a transit, although the vernier plate was a little below the plane of the limb, caused by the weight of the level attachment.

When the vernier plate was brought up to the plane of the limb the spindle had a little play in its socket, which was not desirable in the level; therefore the spindle was allowed to sink far enough into its socket to prevent the play.

There was no means of causing the telescope to revolve in a vertical plane, at the same time keeping the plane of the limb horizontal. However, the necessity for reading angles with the telescope inclined did not occur very often; when it was necessary, it was accomplished by setting the instrument up so that one of the foot or supporting screws would be in the plane in which it was desirable to revolve the telescope, then the foot screw was used for inclining the telescope. By exercising due care only a small error is introduced in this way.

The telescope used contained three horizontal cross-wires, all of which were read when practicable. It frequently happened, however, that one or the other of the outside wires could not be read. The middle wire and one of the outside wires were always read. Distance tables were computed for all of the intervals, so that distance from the instrument to the rod could always be determined. Self-reading metric rods were used.

Angle or transit stations were taken as far apart as the rods could be seen. The rods used on these stations were straight poles covered with strips of black and white cloth.

The distance between transit stations was obtained by taking the sum of the distances measured between them.

The turning points and level stations between transit stations were as nearly on line as practicable.

THE METHOD OF THE CHIEF OF ENGINEERS, U. S. ARMY.

The following sketch and explanation will show the method:



P and P' are two consecutive transit stations.

Suppose the instrument is at P then P' is moved as to direction by the angle $\angle P' P L$. The transit being set up at P' the instrument is then moved to P and the angle $\angle P P' L$ is measured. The transit being set up at P and the turning point P'' put on the line. The angle $\angle P P' L$ is then measured. The instrument is moved to T , and the angle $\angle T P' P$ is measured. The angles $\angle P P' L$, $\angle P' P L$, and $\angle P' T P$ are known and the distance $P P'$ is known.

For the purpose of the work done, so that at every instrument station the back and fore sights are taken in different lines. Referring to sketch above, when instrument was at P the back sight was L and the fore sight was P' . After comparing readings, instrument was moved to P' and the back sight was P and the fore sight was L' . By having the two stations P and P' at the same time a check was taken. By the time the instrument was at T the distance $P P'$ was known and the time to walk from P to P' and is ready to be put on the

NOTES AND REDUCTIONS.

The instrument being set up at two consecutive turning points, the rods were first held with their ends at the bottom and the readings recorded. Then the rods were inverted and the other end of the rod was at bottom and another set of readings recorded in the same order as the first set.

The rods were held vertically and were in a line of check level. Wooden pegs were driven into the ground and the rods were placed nearly flush with the surface of the ground. The points where the rods were placed are practically elevations of the ground.

A sketch of a page of the field notes is given to illustrate the method of keeping the notes and reducing the observations.

An inspection of the notes will show that the method employed gives two independent checks of the work. The readings are for one rod for the two positions being compared. The distance between the middle wire rods at the middle of the rod.

No.	1	2	3	4	5	6	7	8	9	10	11	12	13	Remarks
1	100	100	100	100	100	100	100	100	100	100	100	100	100	
2	100	100	100	100	100	100	100	100	100	100	100	100	100	
3	100	100	100	100	100	100	100	100	100	100	100	100	100	
4	100	100	100	100	100	100	100	100	100	100	100	100	100	
5	100	100	100	100	100	100	100	100	100	100	100	100	100	
6	100	100	100	100	100	100	100	100	100	100	100	100	100	
7	100	100	100	100	100	100	100	100	100	100	100	100	100	
8	100	100	100	100	100	100	100	100	100	100	100	100	100	
9	100	100	100	100	100	100	100	100	100	100	100	100	100	
10	100	100	100	100	100	100	100	100	100	100	100	100	100	
11	100	100	100	100	100	100	100	100	100	100	100	100	100	
12	100	100	100	100	100	100	100	100	100	100	100	100	100	
13	100	100	100	100	100	100	100	100	100	100	100	100	100	
14	100	100	100	100	100	100	100	100	100	100	100	100	100	
15	100	100	100	100	100	100	100	100	100	100	100	100	100	
16	100	100	100	100	100	100	100	100	100	100	100	100	100	
17	100	100	100	100	100	100	100	100	100	100	100	100	100	
18	100	100	100	100	100	100	100	100	100	100	100	100	100	
19	100	100	100	100	100	100	100	100	100	100	100	100	100	
20	100	100	100	100	100	100	100	100	100	100	100	100	100	

The figures in columns 1, 2, 3, 4, 7, 10, 11, 12 and 13 are the original notes, except the intervals written under each set of readings in columns 4 and 7; the other figures are reductions.

NOTES AND REDUCTIONS.

An inspection of the notes will show the manner of keeping the field records.

Only the mid-wire readings are used in reducing the heights of instrument and elevations, the reductions for rod inverted being marked (i).

Rod in first position, back sights are plus.

Rod in first position, fore sights are minus.

Rod inverted, back sights are minus.

Rod inverted, fore sights are plus.

readings of the outside wires are used for determining distances. The intervals are taken out and placed beneath the sets of readings to which they refer. In the eighth column the mean intervals are placed opposite readings for inside rod, the back-sight interval being placed first. In the ninth column the distances are placed opposite the proper interval.

Of course objections may be raised to this method of checking levels. It might be said that any lack of adjustment of the instrument and local disturbances would affect both lines alike, or in the same direction, and it is granted that this is the case. However, errors arising from these sources would not be likely to vitiate the results beyond the errors of discrepancy allowable in this class of work, especially when care is taken to keep the instrument in good adjustment, and to keep the fore and back sights equal. I feel perfectly confident in saying that this mode of checking levels would detect any error caused by a blunder in reading the rod. Again, it might be said that the observer, knowing the length of the rod, would know what the second set of readings should be, the sum of the readings of any wire in the two positions of the rod being equal to the length of the rod, and that the second set of readings might be vitiated by any error that might have been made in the first set. I think, however, that an error from this source would hardly occur, unless the observer intentionally computed what the second set of readings should be, and recorded them as observed readings.

It will of course be admitted that this method saves a great deal of time, the only additional time required for checking a line of levels being that necessary to take a second set of readings at each instrument station.

There is still another advantage of the system, to which I desire to call attention. There is sufficient data given when all the wires are read, to enable one to correct any error that might have been made in any reading.

MAPS.

The traverse of line No. 1 was plotted on Manilla paper, scale 1:10000; the profile plotted on cross-section paper, scale 1:60, and the whole transferred to tracing cloth; the traverse and profile of lines 2 and 4 were plotted on protractor sheets, horizontal scale 1:10000, vertical scale 1:60, and the whole transferred to tracing cloth. The traverse of lines 5, 6, 7, 8, and 9 was plotted on protractor sheets, scale 1:10000, their profiles plotted on tracing cloth, scale 1:60. The profiles of surface of high water of 1882 have been plotted on lines 2, 5, 6, 7, 8, and 9; the profile of high water of 1867 has been plotted on line No. 4. All the lines, traverse and profile, have been reduced on paper; horizontal scale, 1:100000; vertical scale, 1:120.

On the reduced maps, except that of line No. 1, show the profile of surface of high water of 1867. The map of line 1 shows the surface of high water of 1882 at several points, obtained from the answers to a set of questions sent to persons residing along the section.

The high-water profile for 1882, plotted on line No. 4, was reduced from the higher profile of 1867, plotted on the large-scale map by taking the difference of the high waters of 1867 and 1882 at Helena, and making the profiles parallel. The higher profiles for the other lines were plotted from high-water marks taken while running the sections.

The above-named maps and profiles are herewith respectfully submitted as a part of this report.

The time occupied in completing this work has been much greater than was at first anticipated. However, the nature of the country through which the sections were taken in connection with the fact that the first two seasons were very unfavorable will account, in some measure, for the slow rate of progress.

The country through which the sections were run is mainly uninhabited, and is heavily timbered. This made a great deal of clearing of lines necessary, which greatly retarded the progress of the work.

The almost entire absence of roads made the transportation of camp equipage a serious difficulty even when the swamps were dry; when the swamps were wet the difficulty was very much increased; several bridges and rafts have been built in order to cross streams. It has been necessary on several occasions to abandon all camp equipage except what could be carried by my men, on account of the impossibility of getting pack animals through the swamps.

Very little time has been lost on account of sickness; in fact, the health of my party has been better than could reasonably have been expected.

Very respectfully, your obedient servant,

E. S. DAVIS,
United States Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

APPENDIX F.

REPORTS UPON, AND RESULTS OF, RIVER GAUGINGS AT VARIOUS POINTS ON THE MISSISSIPPI AND OHIO RIVERS.

1.—AT CLAYTON, IOWA, AND PADUCAH, KY.—W. G. PRICE, ASSISTANT IN CHARGE.

CARROLLTON, LA., May 10, 1880.

LIEUTENANT: In accordance with your order of April 26, 1883, I have the honor to submit the following report on the work of observing discharge at Clayton, Iowa, and Paducah, Ky., and on methods of measuring the discharge of rivers.

OBSERVATIONS AT CLAYTON, IOWA.

In accordance with orders received from you, I arrived at Clayton, Iowa, on October 12, 1880, and proceeded to make a reconnaissance of the Mississippi River in the vicinity of the mouth of the Wisconsin, for the purpose of finding the most favorable location for a discharge section. There was some delay in making the selection, but the party got well started by the 25th of October, and the work was carried on without serious interruption till October 25, 1881. Until the breaking up of the ice on March 29, 1881, all the velocity observations were measured with the meter. After the ice stopped running, April 12, 1880, observations were taken with rod-floats, used in connection with the plant.

During the entire season 222 velocity observations were made, of which 85 were with the meter and 137 with rod-floats. Besides the regular velocity observations for discharge, there were taken 36 sets of vertical observations.

The balance of the work comprised:

53 sets slope observations.

28 sets longitudinal soundings.

40 sets sediment observations.

10 sets dredgings.

The results of this work were published in the Report of the Commission for 1882, page 133.

OBSERVATIONS AT PADUCAH, KY.

Arrived at Paducah November 29, 1881, and made observations of discharge from this time till November 26, 1882. During this time 215 discharges were measured, of which 27 were with rod-floats and 188 with the meter and plant. In addition to these velocity observations there were 208 verticals taken. A few of the observations were taken partly with rods and partly with the meter, but this was only an occasional occurrence.

The results of this work, as computed in the office of the commission, are appended to this report.

METHODS OF MEASURING THE DISCHARGE OF RIVERS.

Method with double floats.

I think these floats do not give the mid-depth velocity, owing to the effect the current has on the upper float and connecting wire. The upper float is also affected by the wind. Observers are supposed to use a very fine wire to connect the floats, but as this causes much trouble by breaking, a strong string is usually put in, and this catches too much water. For this reason the measurement would be too great except where there is a strong up-stream wind, when it might be too small. Measurements of vertical curves of velocity with double floats in an up-stream wind show a much greater decrease of velocity near the surface than the same measurements with the current meter.

The mid-depth velocity is not always a mean velocity. I think it varies with different sections and with different stages of water, being from 1 to 4 per cent. greater than the mean. At Paducah, Ky., during the year 1882, it was about 4 per cent. most of the time, being a little less at low water. At Carrollton during this year's observations it has been 4 per cent.

For timing floats a stop-watch is used, and I think they cannot be depended upon

unless in the hands of a careful engineer who has the mechanical skill to keep them in order.

There is no check on any of the observers, one of whom being a careless man will spoil the accuracy of the work. The shore observers may work with their instruments out of adjustment; they may miss the float but, give the signal as though all was right; or the floats, to save labor, may not be adjusted to mid-depth, and the chief of the party may not know it.


Method with rod-floats.

When these floats are observed from the shore, as with double floats, there is no check on any one of the observers. Careless observers will let the float project too much out of water so that it is affected by the wind. It is impossible to run floats nearer than one or two feet of the bottom, and where the sand waves are three feet high they are liable to be over three feet from the bottom most of the time. In deep places they often do not reach to mid-depth.

As the vertical curve of velocity varies very much with different sections, and also at different points on the same section, it is impossible to make a formula which will reduce the observed velocity to a true mean. For this reason when the floats do not reach nearly to the bottom they may not be as accurate as the double floats. At Carrollton, La., where the water is over 100 feet deep, it would not be easy to run floats reaching to mid-depth, and as the velocity at three-fourths of the depth is frequently found to be as great as it is at mid-depth or the surface, the observed velocity of a float reduced by Francis' formula would be far from correct.

At Paducah, Ky., the discharge was measured once a week during a part of the year by both rod-floats and the meter. The floats were run at the same stations and at the same time that the meter was running. The apparatus for running the floats was attached to the stern of the catamaran, which was anchored. The floats were timed by a good stop-watch, which was kept in good order, and it was stopped and started automatically by electricity. During the time these measurements were taken the river fell from about a medium stage to low water. At first the rod-float discharges were the greatest, but when the river had fallen much lower they were less than those taken with the meter. When the rod-float discharges were the greatest the vertical curves of velocity taken with the meter were like Fig. 1, and when they were less they were like Fig. 2.

Fig. 1. Surface. Fig. 2.



Bottom.

This showed that the observed velocity of the floats had not been reduced enough at first, and afterwards too much, though the same formula (Francis') was used all the time.

The method of running rod-floats from an anchorage with an automatic electrical apparatus for timing them is far more accurate than that with observers on shore, and the only part not checked is the reading of the stop-watch, and this should be tested at least twice a day by comparison with an ordinary watch.

Method with current meter.

In this method the man who has charge of the field-work can see that every part is done correctly. An ordinary watch can be used for timing the meter, so there is no error from this source.

It has been supposed that the meter measurements are too great, as it takes in all the oscillations of the current. Observations at Paducah, Ky., a report of which was forwarded on October 10, 1882, show that the horizontal oscillations of the cur-

rent are so small they hardly increase the registrations at all, while another observation at Carrollton, La., the result of which was given in my report of April 1883, shows that the vertical oscillations do not increase the measurements by meter.

If the meter is a good machine and in the hands of a careful observer, I think cannot fail to give correct results, while the methods with floats have been in use a long time, and have been carried to as great perfection as possible, and yet do give perfect results.

The method with the meter has been greatly improved during the last three years and it was not till this year, after I had made a good many changes, that I became satisfied with the apparatus in use.

Experience shows that the only meter which will work in water which contains leaves and grass, is one with a wheel which turns like the Ellis. But the Ellis meter was not constructed with a knowledge of the difficulties it would have to contend with in the Mississippi. Owing to the particles of sand in the water the current would not always work, and the bearings of the wheel were ruined in a short time. Small pieces of drift striking the light wheel bent or broke it, and sometimes carried it away. Repairs and new ratings were required very often. The apparatus for using it was not perfect. The insulated wire would break; the electric connection would fail, and it would be almost impossible to find where the trouble was. But the apparatus has been greatly improved, so that it is now no trouble for an ordinary boatman to manage it. A meter has been constructed which overcomes the old difficulties, and which requires no more attention than simply to be oiled occasionally.

The meter at Carrollton, La., has not been taken apart, or received any attention except to oil it, in nearly three months, and it cannot be seen that it is worn in the least, or is not just as perfect a machine as when it was constructed. The current has never failed, and the register has never stopped except when the insulated wire was worn out.

The ratings of this meter do not vary more than one-tenth of 1 per cent., and I think that this variation is the fault of the observers. It is my experience that it requires a great change in the amount of friction with which the wheel turns, to make 1 per cent. variation in the rating.

Comparison of methods.

On the Lower Mississippi, at high water, a float will pass over the 200-foot section in less than 30 seconds. If 26 floats are run (and I believe that is about the usual number), the velocity will be measured just 13 minutes during each survey, which would require about four hours. Now, if the meter was used to take a discharge, in four hours it would have been measuring all the pulsations of the current during about 200 minutes.

A float passing over the 200 foot section in 30 seconds measures the velocity of the water only in its immediate vicinity, while the meter running only 30 seconds would measure the velocity of a line running through a 200-foot block of water.

Suppose that the observed velocity of a float could always be reduced to a true mean, and that the meter always measures the velocity correctly, it would require more than 20 floats to equal the accuracy of a 10-minute run of the meter; and at two stations at Carrollton it is necessary to run the meter 20 minutes in order to gain an average velocity.

Cost of different methods per month for large rivers:

Method with double-floats or rod-floats:	
One assistant engineer	\$13
One recorder	9
Two leadsmen, at \$55	110
Four boatmen, at \$45	180
Total	312

Method with current meter:	
One assistant engineer	\$13
One engineer of launch	9
One steersman	5
Two boatmen, at \$45	90
One steam launch	10
Total	127

For small rivers where a wire anchorage can be used:

Method with double-floats:

One assistant engineer	\$130
One recorder	90
One leadman	55
Two boatmen, at \$45	90
Total	365

Method with rod-floats or the meter:

One assistant engineer	\$ 130
Two boatmen, at \$45	90
Total	220

The above is the force required to measure the discharge. If the work is to be computed in the field, one recorder will be required in addition to the force given for each method, though the work could be partly computed without him. Data taken with the meter are much the easiest to compute.

CONCLUSION.

I think the method with the current meter is the most accurate and reliable, and for large rivers it is the cheapest. For small rivers the method with rod-floats is nearly as cheap as the method with the meter.

For small rivers where a wire anchorage can be used, the method with rod-floats is much more accurate than the method with double-floats observed from the shore; but in a large, deep river I doubt if the rod-floats are as accurate as the double-floats.

I recommend the following method for measuring the discharge of rivers:

Location of section.

The section should be located in a straight reach if possible and not very near a tributary.

The section at Paducah, Ky., was located just below the mouth of the Tennessee, and the Tennessee water being warmest, and therefore lightest, spread over the Ohio water; and as the Tennessee current was much the slowest, there was a slow surface current and a swift undercurrent; and these currents were not parallel, but ran at an angle of about 20° ; this caused a great deal of trouble. When the section was laid out in November the currents were all right; the trouble did not begin till the next June.

Method of locating section.

The section line should be made at right angles to the average direction taken by at least twenty rod-floats. The floats should be started from points not over 150 feet apart and about 100 feet above a preliminary section line taken at right angles to the shore line. The floats must be started from an anchored skiff; and with a sextant set at 90° , a line at right angles to the direction taken by the float should be staked off on shore. A mean of all these right-angle lines will be the best section line.

If the section is not a very good one the current on one side of the river may not be parallel with the current on the other side; in this case it might be best to make an angle in the section line.

Method of locating soundings and meter stations on section line.

Erect a line of signals on shore at right angles to the section line and up the river from it; make the length of the signal line one-fourth the width of the river. The signals must all be 25 feet apart, except the first six, which must be only 5 feet apart; make the width of the signal cloth 1 foot, and the height about 3 feet. Every fifth signal of these 25 feet apart should be double in height, so as to distinguish it from the others.

An ordinary sextant, or a cheap one made after the plan accompanying this report, must then be set at an angle of $14^\circ 02'$. This is an angle in a right-angled triangle, such that the base is four times the perpendicular; then every 25 foot space covered by the sextant will equal 100 feet out on the section line, and every fraction of 25 feet will equal such a fraction of 100 feet out. It is easy to read the distance in this way to within 1 or 2 feet. The sextant should be tested every morning by measuring with it the known distance across the river.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Location of velocity stations.

ould be measured at at least 18 stations; that is the number of
La. The velocity stations should be near together where the current
is, and farther apart at other places. In order to save labor in calculations
should be located at the same distance from the base line every
two figures of the distance should be 00, 20, 40, 60, or 80.
In a river where the wire anchorage cannot be used, the velocity stations
should be fixed by diagonal range lines on shore and above the section.
These range lines should be run at a sharper angle than 60°, and the nearer to
it is the better.

Method of holding catamaran at the station.

Where the wire anchorage cannot be used, the catamaran should be lashed to the
side of a launch and kept steady at the station by the pilot and engineer; great care
being taken that the run of the meter begins and ends just on the section line.

The wire anchorage.

In a river which does not
tion by a wire anchor

The cross-wire should be
feet 2 inches long; the
ter; this makes the
the sag of the wire;

The cross-wire must be
stream to a rock weighing
five times the depth

A machete for piling
placed on a platform near the
skiffs; this platform must

The direction in which the
versed every time. If the
same direction without
last a long time. When
the cross-wire; during
wire every day to prevent

the catamaran should be held in position
ve the section line.

wire, and should be made in links of
wrought iron rings 2 inches in diameter
ation 80 feet, and allows 4 inches of
this is about the right amount.

ation by an anchor wire running
the length of the anchor wire must

the wire should be used; it should
project 4 feet ahead of the catamaran

ken across the anchorage must be
t the wire cannot be run twice in the
direction is always reversed, it will
be used some time, it is best to doubt-
ably be necessary to raise the cross-wire
under the sand waves.

Method of using the meter.

The meter should be lowered from the stern of the catamaran by two No. 10 iron
wires, one of which should be graduated to feet, and marked at every 10 feet by a red
or white piece of cloth tied round it; the wire must be graduated by soldering to it a
close winding of iron-thread wire, which should not be over $\frac{1}{16}$ of an inch in diameter.
It requires about one hour for a party to graduate a wire in this way, and if
properly done it will last three months. The other wire is the safety wire, and it has
the insulated wire wound around it; it is necessary that the insulated wire be wound
around the other, as if it is only tied to it, it will vibrate in the water and break in a
short time where it is tied. The safety wire should be renewed occasionally to insure
against losing the meter. These wires should run over large wooden pulleys 18 inches
in diameter; small iron pulleys will break the wire in a short time.

The electric current is formed by two wires, one of which is the iron graduated wire;
the electricity passes from this to the iron reel on the catamaran, and is taken from
the shaft of the reel by three brass springs which press against a copper band which
is soldered around the shaft; the other wire is insulated, and is wound around the
iron safety wire which runs off the other reel; the insulated wire passes down to the
shaft of the reel, and out through a groove under the bearing to another copper band
which is insulated from the shaft by pine wedges driven under it; three springs
press against this band the same as on the other reel; two or more springs are necessary,
as one will fail to carry the current occasionally.


The meter frame is allowed to turn both horizontally and vertically. It is fastened
to the iron rod one foot above the weight; the rod should be three-fourths of an inch
in diameter. The weight is linked to the rod so that the vane keeps it parallel with
the current.

Integrations with the meter.

If integrations are to be taken with this apparatus, they must be taken in both directions,
top to bottom and bottom to top, and a mean of the two used.

In the right-angled triangle A B C, let A B equal the distance the water runs while

meter is moving from the top to the bottom, and B C equal the depth of the water; the line measured by the meter will be A C.



the meter must be lowered at such a slow rate that the line A B will be very long in proportion to B C, so that it will nearly equal A C.

Mid-depth velocities.

In taking the velocity at mid-depth, the meter must first be lowered to the bottom, the sounding read on the wire; divide this sounding by 2 for the mid-depth. On account of the sag of the wire down stream, this sounding is greater than that taken by the lead-line, and must not be used in calculating the discharge.

Sounding the section.

The section should be sounded just before or just after the measurement of velocity, except where a wire anchorage is used; in that case the section can be sounded at the same time with the measurement of velocity.

The soundings should not average over 45 feet apart. The soundings should be read both leadsman and recorder.

If an ordinary lead-line is used, it should be tested as follows: Just as soon as the soundings are finished, fasten the lead on the ground and tie a spring balance to the end of the line; give the line one quick pull and fasten it; make the pull just equal to the pull which the leadsman gives the line when he raises it to take the sounding; then measure the line and correct the soundings accordingly; remember that if the line is too short, the soundings are too great. With a 16-pound lead and 100 feet of line, the pull is about 26 pounds.

Method of reading gauge.

When the river is rough the gauge should be read with an instrument, a plan of which is inclosed. The instrument is clamped at an even tenth of a foot on the gauge; then the distance from the clamp to the water is read on the graduated plate which is up in the center. A small hole near the bottom of the pipe lets in the water which lifts the air-tight float and graduated plate. When the waves are 6 inches high the gauge can be read with this instrument to within one or two-thousandths of a foot.

Method of measuring discharge when the river is frozen over.

When the river is covered with ice the meter must be put down through holes, and an apparatus, a plan of which is inclosed, should be constructed for the purpose.

It is a house on a sled and contains a stove, which is fed from the outside, a fuel tank, a battery box, and two reels for lifting the meter, the handles to the reels being worked from the outside. It is large enough for one man only, and should be made as light as possible. The meter is lowered through a trap-door; one reel carries a standing wire with heavy weight, and the other carries a smaller wire with the insulated wire wound around it, which is fastened to the top of a piece of gas-pipe; the meter fastened to the gas-pipe slides up and down on the standing wire.

The electric current is carried by the insulated wire and the wire around which it is wound. It is taken from the hub of the reel by copper bands and springs, the same are used on the catamaran; the standing wire should be graduated to feet.

Method of reading the gauge through the ice.

Put a hole where the water is not over 4 or 5 feet deep, and drive in a stake with a round top; let the top of the stake be about 8 inches above the bed of the river; determine the elevation of the stake by leveling to a bench-mark; read the elevation of the water by measuring from the top of the stake to the surface of the water, using a graduated rod with a piece of board on the end, as shown in the plan accompanying this report. It will be necessary to melt the ice from the rod after each reading.

Rating of meter.

The meter should be rated in a lake of still water, which should not be less than feet deep; put the meter on an iron rod so that it is free to swing in any direction; fasten the rod in front of a skiff so that the meter will be some distance under water; if the meter is too near to the surface or to the skiff, a good rating will not be obtained. Draw the skiff by means of a rope at different velocities over a base of 200 feet. Examine the meter occasionally to see if the connecting wires have not become twisted around the iron rod, so as to hold the meter out of line with the current.

All the ratings of a meter should be the same, unless the wheel has been bent.

All the methods, instruments, and every part of the apparatus given in this report have been used by me for a long time, and are known to work well. The drawings accompanying this report were made by Mr. M. K. Bowen, recorder.

Respectfully submitted.

W. G. PRICE,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

Discharge observations, Paducah, Ky.

This section, of which a sketch and profile are given below, was located 2½ miles below the mouth of the Tennessee River. Parallel base lines, one on each shore, were fixed, and the observations taken on a line at right angles to these; the distance between bases was 4,100 feet. Velocity was taken at sixteen or seventeen stations on this line, and soundings for section were made at intervals varying from 50 to 100 feet.

Above the stage of 41 feet the Illinois bank was overflowed for a limited width. At this bank was covered with a dense growth, the shore-line at high stages was placed where the current became imperceptible.

At a stage of 43 feet, on the Kentucky side, the water reached the top of an old earthwork behind which was a depression, the bottom of which was at the 34-foot level. The water width and area of this depression were neglected in the field computations but were included in the revision made in the office.

A peculiar feature of this section is that at this point the waters of the two rivers are still but imperfectly mingled, the flow of the Tennessee overlying that of the Ohio for some distance out from the Kentucky side. In consequence, the velocities taken by the meter at mid-depth, in this part of the section, being those of the underlying current (Ohio), which is here swifter than that of the Tennessee, are higher than the mean velocities indicated by integration measurements, while the corresponding rod-float velocities are regularly less than the mean. In the field computations this anomaly was disregarded, but in the office computations, these mid-depth velocities were corrected by the use of coefficients deduced from the velocity curves.

In the tables the mean gauge reading is given for noon, while the computations are based upon the gauge height at the mean time of observation.

Scour and fill is the difference between the change of area as observed and that computed from the change of gauge; scour is recorded as plus, fill as minus.

The datum stage was taken at 50 feet, and an area below this datum assumed. "Area below datum" for each discharge was obtained by combining the scour or fill with the preceding datum area.

The direction of the wind is recorded by the "clock-face" method, XII being upstream. Force is estimated on a scale of 1 to 10.

The computations from the beginning of observations to August 12 were made in the field; after that date in the office.

E. H. TWining.

NOTE.—The discharge at this point is subject to the control of such varying conditions, that the plotted sheet shows frequent departures from a normal curve.

The conditions of control are—the stage of water at the mouth of the Ohio, that of the Upper Ohio, and that of the Tennessee.

[illegible][illegible]

6	31.28	+0.27	144,341	227,677	33.9	40.6	53.6	3,814	+	147	2,465	510,943	XI Calm	3-5	69	M.
7	31.35	+0.07	148,720	227,747	32.0	40.7	53.1	3,814	+	70	{ 2,444 2,490 }	517,690	{ IX IX }	3	69	M.
8	31.10	-0.25	148,103	227,953	33.8	40.7	52.0	3,815	+	206	{ 2,498 2,447 }	519,476	{ IX IX }	1	74	M.
9	30.70	-0.40	145,854	227,205	33.4	40.5	51.8	3,800	-	748	2,269	510,470	VII	1	78	M.
10	30.03	-0.67	143,821	227,140	37.9	40.5	50.0	3,783	-	65	2,188	489,983	VIII	1	80	M.
11	29.00	-1.03	456,843	80	M.
12	27.80	-1.11	134,945	227,180	35.9	40.5	49.1	3,758	+	40	2,003	405,311	XI	3	74	M.
13	26.13	-1.76	127,625	226,445	34.2	40.4	46.0	3,729	-	735	{ 2,823 2,899 }	300,800	{ VIII VIII-IX }	4	79	M.
14	24.11	-2.02	120,625	226,081	32.4	40.4	45.1	3,719	+	236	2,022	316,300	IX	5	83	M.
15	22.30	-1.81	113,554	226,318	30.5	40.8	42.0	3,718	-	363	2,560	290,673	3-4	80	M.
16	21.08	-1.22	75	M.
17	20.87	-0.71	105,838	226,342	28.5	40.3	40.9	3,710	+	24	2,418	253,905	VI-VII	5	75	M.
18	21.32	+0.85	75	M.
19	23.36	+2.08	63	M.
20	25.20	+1.90	125,262	227,404	33.6	40.6	40.1	3,730	+	1,062	3,365	421,563	VI	3	69	M.
21	25.72	+0.52	80	M.
22	20.14	+0.42	128,010	226,703	31.3	40.4	46.7	3,736	-	701	{ 3,304 3,292 }	430,030	V	1	82	M.
23	26.36	+0.22	120,060	226,924	34.5	40.5	46.6	3,730	+	221	3,336	421,243	XI	1	83	M.
24	26.47	+0.11	120,467	226,898	34.7	40.5	46.8	3,736	-	26	3,267	430,565	IX	3	87	M.
25	26.23	-0.21	423,008	88	M.
26	25.73	-0.50	126,834	227,047	34.0	40.5	46.3	3,733	+	140	2,973	377,085	IX	5	80	M.
27	24.95	-0.78	124,136	227,119	33.3	40.5	45.1	3,724	+	72	2,859	354,876	X	1	81	M.
28	23.87	-1.03	119,379	227,118	32.2	40.5	44.3	3,724	-	1	{ 2,708 2,568 }	332,107	X	5	83	M.
29	22.85	-1.02	308,979	82	M.
30	21.95	-0.90	113,480	227,561	30.5	40.6	42.2	3,724	+	443	2,460	279,200	X	7	82	M.
1	22.25	+0.30	114,678	227,824	30.8	40.7	42.7	3,724	+	263	2,531	200,239	IX-X	6	82	M.
2	22.16	-0.09	79	M.
3	22.23	+0.07	113,527	226,863	30.5	40.5	42.6	3,724	-	961	2,326	264,121	VIII	3	72	M.
4	22.90	+0.67	07	M.
5	23.47	+0.57	118,495	227,349	31.8	40.6	43.9	3,723	+	486	2,364	280,169	I	6	67	M.
6	24.27	+0.80	121,357	226,973	32.5	40.5	44.7	3,732	-	376	{ 2,369 2,300 }	287,549	V	3	70	M.
7	24.87	+0.60	279,105	69	M.
8	25.25	+0.38	124,790	226,795	33.4	40.4	45.7	3,736	-	178	2,495	311,323	VIII-IX	4-5	73	M.
9	25.25	0	78	M.
10	24.88	-0.37	123,109	226,358	33.0	40.3	45.2	3,736	-	437	2,314	284,910	VIII	4-5	79	M.
11	24.47	-0.41	121,097	226,060	32.4	40.3	44.8	3,736	-	398	2,367	236,600	IV	2	79	M.
12	23.80	-0.67	81	M.
13	22.78	-1.02	72	M.
14	21.68	-1.10	110,817	226,091	29.7	40.3	41.3	3,736	+	31	2,205	254,337	Var.	3	69	M.
15	20.83	-0.85	108,322	226,713	29.1	40.4	41.0	3,720	+	622	{ 2,369 2,347 }	256,626	{ VI-VII VI-VII }	3	72	M.

July

No.	Date	Time	Lat.	Long.	Wind	Force	Sea	Bar.	Therm.	Wet Bulb	Dry Bulb	Remarks
1	1880	10 15	31 3	131 1	3, 6-3	—	176	2, 069	172, 977	VI	1	
2	1880	10 30	31 3	131 1	3, 6-3	—	176	1, 973	170, 536	VI	2	
3	1880	10 45	31 3	131 1	3, 6-3	—	176	1, 877	148, 957	VI	3	
4	1880	11 00	31 3	131 1	3, 6-3	—	176	1, 877	133, 874	V	1	
5	1880	11 15	31 3	131 1	3, 6-3	—	176	1, 802	127, 331	VIII	3	
6	1880	11 30	31 3	131 1	3, 6-3	—	176	1, 805	124, 834	V-VI	3	
7	1880	11 45	31 3	131 1	3, 6-3	—	176	1, 878	116, 419	IX	3-4	
8	1880	12 00	31 3	131 1	3, 6-3	—	176	1, 834	111, 584	VII	3	
9	1880	12 15	31 3	131 1	3, 6-3	—	176	1, 887	114, 855	IX	6	
10	1880	12 30	31 3	131 1	3, 6-3	—	176	1, 777	108, 165	IX	3	
11	1880	12 45	31 3	131 1	3, 6-3	—	176	1, 898	114, 388	XI	3	
12	1880	13 00	31 3	131 1	3, 6-3	—	176	1, 970	118, 910	III	1	
13	1880	13 15	31 3	131 1	3, 6-3	—	176	2, 161	135, 371	VI	4	
14	1880	13 30	31 3	131 1	3, 6-3	—	176	2, 553	184, 008	IX-X	3	
15	1880	13 45	31 3	131 1	3, 6-3	—	176	2, 027	104, 849	XII	7	
16	1880	14 00	31 3	131 1	3, 6-3	—	176	2, 505	190, 303	XI	4-5	
17	1880	14 15	31 3	131 1	3, 6-3	—	176	2, 514	180, 943	I-II	3	
18	1880	14 30	31 3	131 1	3, 6-3	—	176	2, 415	182, 438	I-II	3	
19	1880	14 45	31 3	131 1	3, 6-3	—	176	2, 544	192, 170	Calcu.	3	
20	1880	15 00	31 3	131 1	3, 6-3	—	176	2, 857	193, 980	IV-V	3	

17	12.81	-0.19	71,005	225,000	18.9	48.9	2,000	-	27	1,200	140,000	IV	0	70	M.
18	11.54	-0.11	70,000	224,000	18.9	48.1	2,007	-	28	1,200	140,000	IV	0	71	M.
19	11.12	-0.24	69,000	223,000	18.9	48.1	2,000	-	29	1,200	140,000	V-VI	0	72	M.
20	10.43	-0.46	68,000	222,000	18.9	48.1	2,000	-	30	1,200	140,000	V-VI	0	73	M.
21	10.43	-0.60	67,000	221,000	18.9	48.1	2,000	-	31	1,200	140,000	V-VI	0	74	M.
22	9.83	-0.70	66,011	220,197	17.4	48.9	2,002	-	32	1,200	140,000	VI	0-4	75	M.
23	9.18	-0.80	65,495	224,490	16.9	48.9	2,040	+	33	1,200	140,000	IX	0	76	M.
24	8.44	-0.50	64,184	224,055	16.8	49.0	2,000	+	34	1,200	140,000	VII	0	77	M.
25	7.88	-0.51	63,055	224,980	16.9	49.0	2,002	+	35	1,200	140,000	XI-XII	0	78	M.
26	7.37	-0.37	62,008	225,846	15.7	49.1	2,000	+	36	1,200	140,000	I-II	0	79	M.
27	7.01	-0.21	61,953	225,085	16.2	49.1	2,000	-	37	1,200	140,000	III	0	80	M.
28	6.79	-0.22	61,408	224,729	15.3	49.0	2,000	-	38	1,200	140,000	VI	0	81	M.
29	6.57	+0.15	60,145	224,777	15.5	49.0	2,000	+	39	1,200	140,000	XII	0-4	82	M.
30	6.72	+0.20	59,818	224,688	15.7	49.0	2,000	-	40	1,200	140,000	VI	0	83	M.
31	7.15	-0.17	58,020	224,340	16.2	48.9	2,000	-	41	1,200	140,000	II	0	84	M.
1	7.42	-0.27	57,272	224,234	16.3	48.9	2,000	-	42	1,200	140,000	II-III	0	85	M.
2	7.67	-0.25	56,027	224,204	10.7	48.9	2,000	-	43	1,200	140,000	III	0	86	M.
3	7.80	-0.19	55,557	224,093	17.1	48.9	2,000	-	44	1,200	140,000	IX-X	0	87	M.
4	7.08	-0.40	54,735	223,958	17.5	48.8	2,000	-	45	1,200	140,000	Var.	0	88	M.
5	8.38	+0.52	53,845	223,959	17.5	48.8	2,000	+	46	1,200	140,000	III-IV	0	89	M.
6	8.90	+0.35	52,805	224,401	16.4	48.9	2,000	+	47	1,200	140,000	VI	0	90	M.
7	9.25	+0.05	51,640	224,618	16.1	49.0	2,000	+	48	1,200	140,000	IX	0	91	M.
8	9.30	-0.29	50,805	224,809	15.8	49.0	2,000	+	49	1,200	140,000	IX	0	92	M.
9	9.01	-0.37	50,640	225,298	15.7	49.1	2,000	+	50	1,200	140,000	IX	0	93	M.
10	8.64	-0.50	49,093	225,310	16.0	49.1	2,000	+	51	1,200	140,000	VI	0	94	M.
11	8.14	-0.45	48,000	225,133	19.0	49.1	2,000	-	52	1,200	140,000	IX	0	95	M.
12	7.69	-0.82	47,513	225,041	20.3	49.1	2,000	-	53	1,200	140,000	IX	0	96	M.
13	7.37	-0.29	46,010	224,831	20.9	49.0	2,000	-	54	1,200	140,000	XII	0	97	M.
14	7.08	-0.36	45,000	224,913	19.7	49.0	2,000	+	55	1,200	140,000	XII-I	0	98	M.
15	7.44	-1.04	44,000	224,828	18.6	49.0	2,000	-	56	1,200	140,000	I	0	99	M.
16	9.23	-0.77	43,000	224,959	16.7	49.0	2,000	+	57	1,200	140,000	III	0	100	M.
17	10.60	-0.68	42,000	224,809	16.4	49.0	2,000	-	58	1,200	140,000	III	0	101	M.
18	11.03	-0.84	41,000	225,009	15.1	49.1	2,000	+	59	1,200	140,000	VI	0	102	M.
19	12.65	-0.71	40,000	225,163	14.8	49.1	2,000	+	60	1,200	140,000	IX	0	103	M.
20	12.27	-0.63	39,000	225,120	14.5	49.1	2,000	-	61	1,200	140,000	VII	0	104	M.
21	11.23	-0.39	38,000	225,427	14.5	49.1	2,000	-	62	1,200	140,000		0	105	M.
22	10.15	-0.31	37,000	225,427	14.5	49.1	2,000	-	63	1,200	140,000		0	106	M.
23	9.38	-0.77	36,000	225,427	14.5	49.1	2,000	-	64	1,200	140,000		0	107	M.
24	8.70	-0.84	35,000	225,427	14.5	49.1	2,000	-	65	1,200	140,000		0	108	M.
25	7.86	-0.71	34,000	225,427	14.5	49.1	2,000	-	66	1,200	140,000		0	109	M.
26	7.15	-0.63	33,000	225,427	14.5	49.1	2,000	-	67	1,200	140,000		0	110	M.
27	6.52	-0.39	32,000	225,427	14.5	49.1	2,000	-	68	1,200	140,000		0	111	M.
28	6.13	-0.31	31,000	225,427	14.5	49.1	2,000	-	69	1,200	140,000		0	112	M.
29	5.82	-0.31	30,000	225,427	14.5	49.1	2,000	-	70	1,200	140,000		0	113	M.

CHIEF OF ENGINEERS. U. S. ARMY.

[illegible]

..—AT COLUMBUS, KY., J. H. DAVIS, ASSISTANT IN CHARGE.

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., July 7, 1883.

517. I directed the doctor to submit the following report on the observations made at
the station from September 17, 1881, to November 25, 1882. The work consisted of:

- 1. **Surface velocity curves.**
- 2. **Subsurface velocity curves.**
- 3. **Surface currents.**

The party, consisting, at first of assistant, recorder, and three men, left Columbus on the 20th of November. After locating, operations were begun by taking a reconnaissance of the river in front of town for the purpose of determining a ranging section. This being completed, several days were spent in making the necessary preparations for the work in view. These were somewhat retarded on account of having shipped most of the material to Natchez, the nearest place for the observations. It was not returned to Columbus till some time after the arrival of the party. Meanwhile the party were engaged in building a lazaretto and making such utensils as were needed in manipulating the gas. Large fires were also laid off, and signals made and erected upon the river. A stage was put up, and tri-daily observations upon the stage of the river were made. The preliminaries having been completed, the first discharge of gas was made on the 17th of December.

Large observations were made daily, Sundays excepted. From July 1 to November 25, 1882, there were made in all 243 sets of discharge measurements. 100 sets were made with double floats, 83 sets with rod-floats, and 60 sets with the current meter. Frequent omissions occurred in the early part of the season on account of bad weather and accidents to instruments and machinery. Observations for a vertical curve were made upon each day that the water was high enough for the large measurements. There were frequent omissions, however, on account of lack of time. During the year there were 101 curves determined. The sections of the river so as to include all depths and velocities.

Observations were made monthly. Owing to high water
to the launch, they were not begun till the last of March.
The work - curves were determined. They extend
all the stages of the river from high to low.

... were made weekly when the time was not fully occu-
... 31 sets made during the year, a set con-
... reach of 500 feet.

... the purpose of determining the amount of water passing in the stage of the river. They were placed at a distance of about 3 feet on the gauge. From the water made.

...the currents were unsuccessful. The
...which it was designed. The results

divided into three classes: 1st, observations made with red-floats; 2d, observations made with white-floats; 3d, observations made with black-floats. Each class is subdivided into three sub-classes, as will be

... seats were used in discharge meas-
... at the time. They were of the
... W. H. Davis, at Pelton, Tenn., a small cord
... parts.

For the purpose of determining whether single rods were substituted for double rods, the following apparatus was used. A rod, 15 feet in length, connected and buoyed by a wire, was suspended from a platform, the ends of the rods were perforated so as to admit the water, and the platform was raised about 37 feet in deep water. The water was raised to the surface of the river depth on the gauging section. Readings were taken at low water on March 18, and at intervals of about two weeks, until the end of the observations. In all observations previous to March 18, the rods were located by depth only, and by means of the platform was located only. After that date, they were located in two points, by the platform and by the rods. On the 12th of September, a goniometer was substituted for the

The instructions were to use the current meter in discharge measurements, but it was not practicable to do so in the early part of the work. It could not be used without the bunch, which did not arrive till the 20th of December, and was not serv-

usable for more than a month following, except for very short periods. The meter was first used on January 24, but with only partial success. It was also used on the 27th and 28th, and a few times in February. From the middle of February to the middle of March, the high water and heavy drift rendered it very difficult to get a complete discharge measurement with the meter at all, and at best the work was very unsatisfactory. During a week of the time, also, the launch was at Cairo for repairs.

It being very desirable to have a complete set of observations over this the highest stage of the river, not only of that year, but then on record, it was thought advisable to use rod-floats exclusively, that being a surer method of obtaining complete results. After March 18, the meter came into constant use, the water having fallen sufficiently to handle it with safety and comparative ease. The rod-floats were still used at intervals of about two weeks, in accordance with instructions, and sometimes oftener, when the meter needed repairing. After and including March 18, with few exceptions, the boat was anchored during the observations with the meter. Previous to that time, the observations were made without anchoring. Both methods are described below.

METHODS.

Double floats.—Two ranges were laid off, 100 feet apart, and as nearly parallel as was practicable, with no better instrument than a cloth tape-line. They were also practically at right angles to the thread of the current.

On these ranges front and back signals were erected on both shores, and also intermediate ones for use in measuring distances with the telemeter. The floats were manipulated by an observer in a skiff. The connecting cord was made of sufficient length to allow the subfloat to run practically at mid-depth, the limit being between four-tenths and six-tenths of the depth. The float was put out far enough above the upper range to assume a uniform rate before reaching it. The skiff was kept in line with the float and at a convenient distance behind it, while passing the ranges. The distance from shore was measured by the observer in the skiff, when he reached a point about midway between the two ranges, the telemeter being used for this purpose. Soundings were taken on each range by a leadman in the bow of the skiff. After passing the lower range, the float was picked up, the skiff rowed above line, and the operation repeated for each successive observation. The float was timed by an observer on shore, who watched its crossing of the ranges, and at the same time manipulated a stop-watch. To aid him in determining when the float crossed the ranges, a fine vertical wire was employed at each of the range stations. By standing just behind it, and keeping it in line with himself and the signal across the river, the time of the floats crossing could be determined with tolerable exactness. A field-glass was also used, through which the wire, the signal across the river, and the float, could be distinctly seen at the same time.

The actual float-path could not be measured by this method. In the computations it was considered 100 feet. In most cases it was greater, and where great accuracy is desired, the length of path should be corrected by those determined afterwards at corresponding stages, by use of the transit.

Rod-floats.—(1). Previous to the use of the transit, March 1, the method of using rod-floats was the same as that for double floats, except that they were not run at mid-depth. With few exceptions 37 feet was the immersion used in deep-water observations. That for shallow water was regulated by the sounding, the float being run as near the bottom as practicable without touching.

Rod-floats.—(2). A B. & B. transit (No. 237) was received the latter part of February, and brought into immediate use in the discharge observations with floats. The range lines were tested and found but slightly out. A base line of 515 feet was laid off at right angles to the ranges, and a transit station established at its extremity. A telegraph line was erected for the purpose of signalling from the station on the ranges to the transit station. A key was placed in the circuit at each of the range stations and a sounder at the transit station. The circuit was left open and could be closed by touching either key. The floats were handled from a skiff, the launch being used for towing it above the ranges. The boatmen were necessarily relied upon for correct manipulation of the float as well as the taking and recording of the soundings. The transit being in position and properly set with the lower plate clamped, the battery and all being in perfect working order, the following programme was carried out for each observation:

The float was spliced and lowered some distance above the upper range, so as to assume an erect position and uniform movement before reaching it. An observer on the upper range watched the float until it came within a few feet of line, when he touched his key twice, for a ready signal to the observer at the transit. When the float reached the range the observer touched his key once and immediately went to the lower range. Here the same signals was given as on the upper range.

The observer at the transit having brought the float into his field of view, followed

rate, not exceeding one-half foot per second, the man at the bottom. At the instant of giving signal the observer noted the electrical register, by turning on the switch.

At a point within a few turns of the bottom, the man at the bottom, and upon feeling the weight touch, he called "time" and hauled his reel. When the time signal was called, the observer noted and read the register without stopping it.

At the time and the register reading were very required some skill, especially in high water. It can be done by the observer keeping in mind the reading of the dial only, from the sound of the register, counting the ticks one-half.

As the time is called, the seconds of the watch time, and the reading of the last dial of the register, can be jotted down hastily, while the hours and minutes of the time readings of the remaining dials of the register can be obtained at leisure. By practice the nearest second of time and the nearest half revolution of the wheel can be accurately obtained by the same observer. The meter was hauled to the surface at the same rate as that of the descent, the man at the reel calling "time" when the starting point was reached. The observer again read the register and stopped the register, recording the readings of both.

The results of integration were satisfactory. The meter was now lowered for mid-depth observations. This was done by giving the main reel one-half the number of turns required to send the meter to the bottom. The meter was run at mid-depth for five minutes, the register being read at the end of each minute. When it was possible to hold the boats in one position the meter was run a whole number of turns at mid-depth; otherwise it was run as described in the method without anchoring.

Great care was exercised by the engineer and steersman to hold the boats in one position during the observation, using the engine when necessary to assist the anchor. When not needed the engine was kept moving slowly, except in extreme low water, in order to prevent the wheel of the launch from retarding the current near the boat. In extreme low water the engine could not be run without changing position of the boat.

Without anchoring.—(2.) Without anchoring.—Only mid-depth observations were made this way, and at times when anchoring was not practicable. The method was slightly from that given above. After drifting into position, the sounding was taken, the launch was held as nearly in one position as was possible by the watchfulness of the steersman and engineer. The meter being lowered to the bottom, as estimated from the sounding, the catamaran was brought to the gauging section, when the time was noted and the register started. The engineer, standing with his hand on the throttle-valve, was able to keep the boat almost on the same position during the observation. If, however, at the end of five minutes, the catamaran was a little above or below the gauging section it was brought into position. The time was again noted and the register stopped. The readings of the latter were noted and recorded at the end of each minute, and also at the close of the observation.

The effects of starting and stopping the meter register on the same range practically compensated the effects of any movement up and down stream during the observation. The errors due to lateral movement are not so easily compensated, as the rate of the current is accelerated by a movement in either direction. Such errors were comparatively small, however, except in cases of very high wind, when the boat was liable to drift to a considerable extent in a lateral direction.

The discharge observations with the meter, consisted of velocities at mid-depth at each integration, when anchored, and at mid-depth when not anchored, at from 12 to 20 stations across the river on the gauging section. A sounding was taken at each station as the bottom was very even, this was thought sufficient to give a correct cross-section.

METERS AND METER-RATING.

The same meter was employed exclusively. During the year Nos. 3, 6, and 23 were used in different periods. At times the meter in use was not in the best of order, due to the exceeding delicacy of the instrument and the want of a person capable of repairing it. The errors that might arise from this source were reduced as much as possible by frequent ratings. The same meter was seldom used longer than two weeks without receiving a thorough rating, and when thought advisable it was sent to Saint Louis for repairs. With the greatest precaution it was impossible to keep the meter in perfect order at all times, and consequently the frictional quantity will be found to be variable in some of the equations.

Rating the meter.—The rating was made in the still water of a pond about 100 feet long. The meter was attached to an iron rod secured in a vertical position at one end.

THE CHIEF OF ENGINEERS, U. S. ARMY.

immersed to a depth of about 12 feet. The skiff, with the meter, was drawn through the water at a uniform velocity by a man on the shore, holding a rope attached to the bow. The time taken for the meter to pass over a distance of 150 feet in most of the runs varied from twelve to twenty such observations, the error being not more than one-quarter of a foot per second.

The method was as follows: When practicable, two ranges were marked on the shore of the skiff and the meter was placed at a distance of 100 feet from the shore. When the meter had passed the first range, the observer in the skiff called "time," and when it had passed the second range, he called "back." In many of the ratings this method was not practicable, and the meter was placed at a distance of 100 feet from the shore. In this case the signals were given by the observer in the skiff, the meter being called as they passed.

The method was as the former, as great care was taken to keep the meter at a constant depth.

The results of rating by the method of least squares are as follows:

The results for the vertical velocity curves were obtained by the method of least squares in connection with that work.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The results for the horizontal velocity curves were obtained by the method of least squares at a station, when it was desired to obtain a series of observations at different depths and at different distances from the shore.

The skiff was located by a transitman on shore, at 4 points in its path: on the upper and lower ranges, and on two ranges 200 and 300 feet respectively from the upper range. By means of back and front signals on each of the ranges, the flagman signalled to the observer at the transit when the skiff was on line. The angle was taken by the flagman, who sat near the leadman. From 50 to 150 soundings were taken on each line of 500 feet; sometimes the number was even greater in very low water. Previous to receiving the transit, March 1, the boat was located in only one point of its path, midway between the second and third ranges, by means of the telemeter. From and including September 8 the angles were taken with a goniometer, from the position previously occupied by the transit.

Cross-section soundings.—Frequent soundings were made of a section, located in Smith's Bend, 12 miles below Columbus, for the purpose of determining the amount of scour or fill in sharp bends, corresponding to certain changes in the gauge. The soundings were all taken while drifting, either from the launch or a skiff. From 75 soundings were made at a time, distributed at equal intervals across the river. They were located by a transitman on shore, stationed at the end of a 600-foot base. The angles were taken on a flagman, stationed near the leadman. There was also a man on shore to give range. After the transit was taken away in August, the telemeter was used for taking the angles. It was stationed on a new base line of 600 feet in length. In order to ascertain the character of the fill, specimens of the bottom were taken at each sounding by means of a soaped lead.

INSTRUMENTS CONSTRUCTED.

Telemeter.—Previous to March 1 no transit, sextant, or level had been furnished to the party. It was therefore necessary to contrive some means by which observation points could be located. This necessity gave rise to the construction and use of an instrument has been denominated the telemeter. It consisted of a wooden box, having two of its faces parallel trapezoids, two of them inclined rectangles, the remaining two, the ends, being parallel rectangles. The inside dimensions were about as follows: length, 2 feet; cross-section at the smaller end, 2 by 3 inches; cross-section at the larger end, 2 by 10 inches. At the smaller end of the box was an eye-piece, which consisted of a cylindrical block of wood with a small aperture or peep-hole.

At the larger end was a longitudinal opening the full width of the box and about 1 inch in width. It occupied the middle line of the end of the box, and through it distant objects could be seen by looking through the eye-piece. Inside the box was a sliding reticule that contained a pair of fine parallel wires. It was arranged to move along the central line of the inclosed space and from one end to the other. On top of the reticule was an upright post that moved in an opening in the upper face of the box, and terminated in a rectangular block of wood that moved along on top of the box. This was used as a vernier piece. The top of the box was graduated so that by means of the vernier the instrument could be read to single feet. The graduation was made in the following manner: Two signals were erected at a distance of 1,200 feet apart. The distance was arbitrarily chosen as the most convenient. From the middle point of the line joining the signals a perpendicular was laid off. On this line two points were located, one 400 feet and the other 1,200 feet distant. At each of these points there was made a series of observations to determine the exact location of the 400 and 1,200 foot marks of the graduation on top of the box. In each of these observations the box was held so that the signals could be seen when looking through the peep-hole with the eye conveniently near it. The reticule was then moved, if necessary, by taking hold of the vernier piece on top, until the wires were brought, respectively, in line with the signals. The position of the zero of the vernier was then marked on the box.

The mean of all the observations made in this way was taken as the mark of graduation sought. Having found the 400 and the 1,200-foot marks, the remaining hundred-foot marks were obtained by dividing the space into 8 equal parts. Each of these spaces was subdivided into 10 equal parts for the 10-foot marks.

The graduation for distances less than 400 feet, and greater than 1,200 feet, was made by actual measurement with a scale, the spaces being proportional to the distances. In order to use the telemeter in measuring distances on the river, signals were put up on both shores, at a distance of 50 feet apart. Back signals were erected so that the observer could tell when he was midway between the ranges, that being necessary to perfect accuracy. A slight deviation either way made no appreciable error in long distances. To measure a distance, the observer brought the box to a horizontal position, the wires then being vertical. Placing his eye at the peep-hole, he swung the box, if necessary, until the signals came into the field of view. He then moved the sliding vernier on top of the box, until the wires were brought in line respectively with the signals. Being careful not to move the vernier, he lowered the box sufficiently to read the distance. The instrument was not capable of measuring distances greater than about 1,000 feet with accuracy. For this reason, signals were placed on both shores and measurements made each way. The accuracy with which distances could be measured with the telemeter, depended upon the stability

of the observer's position, and the consequent nicety with which the wires could be brought into line with the signals. In windy weather this was somewhat difficult, but great skill was acquired by practice, and a very close approximation could be obtained at all times. Much greater accuracy could be obtained on land, when a steady rest could be had, and it was possible to measure distances accurately to within 3 feet.

Goniometer.—This was a plane table with a revolving alidade, and was arranged for centering by means of a plumb-bob attached beneath the point of revolution. The point was taken as the center of an arc described on the table with a radius of 10 inches. Angles were taken with the goniometer by measuring the chords of the included arcs. The angle corresponding to a measured chord was taken from Gillespie's tables. Any point in the arc could be taken for the zero point, and the chords measured from it. This was a matter of great convenience in setting up the instrument. To measure an angle on a moving object, the eye was brought to the peep-sight, the alidade revolved so as to keep the vertical wire in line with the object. When the signal was given, the motion was stopped, and the intersection of the line of sight with the arc marked with a well sharpened pencil. The chord was then measured with a triangular scale. If the chord was too long for the scale, the included arc was divided into two or more parts, and the sum of the corresponding angles taken. This prevented the use of a ruler being necessary. Under favorable conditions a tolerably close degree of approximation could be attained with the goniometer.

Remarks.—On the 11th of October instructions were received to turn over to recorder, J. H. Field, all instructions and engineering property, and report at St. Louis at the earliest convenience for other duties. The remainder of the observations which were continued till November 25th, were in charge of Mr. Field, who for some time previous had conducted the field-work of the discharge observations.

After the meter came into constant use in March the field-work did not require full attention of both assistant and recorder. After that date a large part of the assistant's time was occupied in computing discharges and doing other office work. At the time of leaving the work the discharges had been computed up to date, with the exception of about 8 weeks. The remainder of the computations were made in the office under your immediate supervision. At the time of leaving the work most of the notes in connection with velocity curves and cross-section and longitudinal soundings had been reduced, excepting one set of longitudinal soundings, which had been plotted and a tracing made.

The success of the work depended largely upon the ability to make the best use of the means at hand for accomplishing a particular purpose. The more inadequate the means, the greater the dexterity of judgment required.

The most perplexing problems often presented themselves, inasmuch as the magnitude of the work was probably underestimated in the outset. The greatest exertion was made to obtain the best results possible with the methods employed. Much depended upon the individual members of the party, who, with few exceptions, were always prompt and true to duty. They were J. H. Field, recorder; H. A. Wilson, steersman; W. J. Wilder, engineer; John V. Bandy, A. J. Wilder, and John Q. Hamilton, boatmen.

Respectfully submitted,

J. H. DAVIS,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

Discharge Observations, Columbus, Ky.

The discharge computations for this station were made in the field, and by the following method, viz: The cross-sections and positions of velocity observations were plotted on cross-section paper, the cross sections divided into partial sections and the areas determined by counting the squares.

The meter velocities were determined by ratings frequently taken.

Rod float velocities were reduced by Francis' formula. Many of the abrupt changes in area are probably due to change in method of taking observations; a change of method usually resulting in a marked change in the number and position of the cross-section soundings, and often in the values of the soundings themselves. The large number of soundings were taken in rod-float observations.

The gauge readings on "discharge days" are mean readings for the time occupied in taking observations. On "no discharge days" the noon reading is recorded; noon being about the mean time of field observations.

Datum plane was taken at a gauge reading of 102.627 feet.

Datum width, 2,694 feet.

Datum area 191,880 square feet, as observed on February 28.

Datum areas for other days were determined by successively adding and subtracting scours and fills.

Mean depth was determined by dividing water area by water width, and datum depth by a similar process.

35	102.591	+0.290	191,880	71.2	71.2	101.0	2,604	-8,709	8,121	1,552,828.3	VI	8-6	R.F.
36	102.595	+0.295	182,196	64.4	07.9	100.5	2,049	-8,990	8,241	1,501,527.0	XII	2	R.F.
37	102.601	+0.186	189,500	71.4	70.9	94.0	2,649	+8,233	8,025	1,521,139.6	XII	2	R.F.
38	102.627	-0.110	186,880	71.3	70.8	98.0	2,619	-	8,039	1,518,454.4	Calm		R.F.
1	102.657	-0.004	180,510	70.0	70.2	98.0	2,649	-1,848	7,845	1,463,149.5	X	2-4	R.F.
2	102.677	-0.226	186,110	70.1	70.6	95.5	2,054	+1,093	7,525	1,430,047.8	VI	3-5	R.F.
3	102.699	-0.337	184,020	69.3	70.1	89.5	2,053	-1,324	7,625	1,403,204.8	VI	4-6	R.F.
4	101.878	-0.290	180,650	68.4	69.1	89.5	2,641	-2,634	7,694	1,339,912.2	Calm		R.F.
5	101.681	-0.278	181,830	64.8	69.9	90.5	2,641	+2,054	7,225	1,323,720.1	VI	3-5	R.F.
6	101.455	-0.149	178,620	67.7	68.8	88.5	2,639	-2,769	7,351	1,313,074.9	I	3-4	R.F.
7	101.118	-0.182	185,595	70.0	71.1	92.5	2,644	+6,151	7,350	1,360,649.6	V	3-5	R.F.
8	100.828	+0.095	185,825	70.2	71.2	92.5	2,646	+2,290	7,089	1,317,275.1	XI	2-6	R.F.
9	100.550	+0.153	185,970	70.3	71.2	89.0	2,646	+74	7,425	1,385,773.7	II	3	R.F.
10	100.401	+0.027	185,790	70.2	71.3	92.0	2,646	+130	7,354	1,366,285.7	VI	2	R.F.
11	100.219	-0.117	192,089	70.9	72.1	88.5	2,645	+2,279	7,136	1,338,925.8	X	3-5	R.F.
12	100.089	-0.162	194,368										
13	99.821	-0.268											
14	99.601	-0.220											
15	99.267	-0.334											
16	98.805	-0.462	182,902	68.7	71.6	84.0	2,635	-1,348	6,387	1,168,218.0	II	5-10	M.
17	98.242	-0.583	187,465	71.2	73.9	90.0	2,634	+6,046	6,091	1,141,828.0	IV-I	4-6	M.
18	97.456	-0.786	182,450	69.3	72.8	88.0	2,632	-2,946	5,773	1,053,340.3	XI-XII	6-8	M.
19	96.789	-0.667	183,225	69.1	73.7	87.0	2,630	+2,530	5,810	1,064,509.2	VI	3-4	M.
20	96.271	-0.518	176,835	67.3	71.9	82.0	2,627	-5,029	5,462	965,913.3	XI	3-6	M.
21	95.938	-0.333											
22	95.938	-0.000	178,860	68.1	72.9	82.0	2,625	+2,899	5,596	1,000,966.7	XI-V	5-10	M.
23	95.756	-0.182	178,865	68.1	73.1	82.0	2,624	+483	5,433	971,713.0	Calm		M.
24	95.796	+0.040	179,800	68.5	73.4	82.0	2,624	+830	5,510	990,702.4	XI	4-10	M.
25	95.913	+0.137	180,525	68.7	73.6	84.0	2,628	+365	6,051	1,092,383.0	V-VI	4-7	M.
26	96.060	+0.127											
27	96.152	+0.092	181,430	69.0	73.7	86.0	2,630	+329	5,900	1,070,398.7	XII-XI	3-4	M.
28	96.076	-0.076											
29	95.889	-0.187	180,895	68.7	73.7	86.0	2,631	+157	5,941	1,074,721.6	XII	2	M.
30	95.342	-0.547	178,565	68.0	73.4	86.0	2,628	-892	5,753	1,027,339.3		2	M.
31	94.386	-0.956	177,690	67.7	74.0	85.0	2,625	+1,636	5,491	975,641.7	XI	2	M.
32	92.940	-1.446	172,260	65.8	73.4	84.0	2,619	-1,639	5,220	899,116.8	XII	3-4	M.
33	91.076	-1.864											
34	89.636	-1.440	162,480	62.7	73.0	79.0	2,589	-1,176	4,756	772,834.2	XII	2	M.
35	89.382	-0.254											

Mar.

Apr.

Mississippi River—Discharge observations at Columbus, Ky.—Continued.

Date	Gauge.		Dimensions of cross section of discharge.						Width	Error of gage	Mean velocity per second.	Discharge per second.	Direction and force of wind	Method.	Remarks
	Reading	Rise or fall in the preceding 24 hours.	Water	Area	Depth.	Mean diameter	Mean	Max.							
	Feet.	Feet.	Feet	Sq. feet	Feet	Feet	Feet	Feet							
1882.															
Apr 10	80.831	+0.440	104.76	197.048	6.5	3.6	81.0	2.600						M.	1-8
11	80.918	+0.097	104.76	197.417	6.1	3.3	80.0	2.600						M.	4-8
12	80.041	+0.15	104.74	198.084	6.1	3.5	81.0	2.600						M.	7-10
13	80.661	-0.280	104.880	198.048	6.1	3.6	80.0	2.600						M.	1-8
14	80.411	-0.60	104.800	197.411	6.1	3.4	80.0	2.600						M.	2-8
15	80.386	-0.155	104.910	197.690	6.1	3.4	80.0	2.600						M.	1-8
16	80.618	+0.43	104.755	197.405	6.1	3.6	80.0	2.600						M.	1-8
17	80.846	+0.32	104.780	197.417	6.1	3.6	80.0	2.600						M.	1-8
18	80.891	-0.15	104.780	197.417	6.1	3.6	80.0	2.600						M.	1-8
19	80.407	-0.484	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
20	80.541	-0.280	104.880	198.048	6.1	3.6	80.0	2.600						M.	1-8
21	80.545	-0.13	104.880	198.048	6.1	3.6	80.0	2.600						M.	1-8
22	80.777	+0.783	104.880	198.048	6.1	3.6	80.0	2.600						M.	1-8
23	80.841	-0.136	104.880	198.048	6.1	3.6	80.0	2.600						M.	1-8
24	80.311	-0.726	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
25	80.201	-0.40	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
26	80.753	+0.452	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
27	80.301	+0.158	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
28	80.601	+0.500	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
29	80.906	+0.335	104.880	198.048	6.1	3.6	80.0	2.600						M.	1-8
30	80.186	+0.280	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
May 1	80.411	+0.225	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
2	80.008	+0.197	104.840	198.048	6.1	3.6	80.0	2.600						M.	1-8
3	80.676	+0.008	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
4	80.710	+0.034	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
5	80.505	-0.205	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
6	80.211	-0.294	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
7	80.708	-0.445	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
8	80.310	-0.430	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
9	80.473	+0.163	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
10	80.518	+0.045	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
11	80.498	+0.070	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8
12	80.114	+0.628	104.760	197.417	6.1	3.6	80.0	2.600						M.	1-8
13	80.481	+0.367	104.800	198.048	6.1	3.6	80.0	2.600						M.	1-8

Mid-depth only.

1994, 1995, 1996, 1997, 1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 26

Date.	Gauge.	Dimensions of various quadrants of other basins					Method
		Reading.	Area.		Mean.	Depth.	
			Water.	Below station.			
1862.	Feet.	Feet.	Sq. feet.	Sq. feet.	Depth.	Depth.	
July 8	10 33.7	104 431	104 431	104 431	104 431	104 431	
9	10 33.7	104 431	104 431	104 431	104 431	104 431	
10	10 33.7	104 431	104 431	104 431	104 431	104 431	
11	10 33.7	104 431	104 431	104 431	104 431	104 431	
12	10 33.7	104 431	104 431	104 431	104 431	104 431	
13	10 33.7	104 431	104 431	104 431	104 431	104 431	
14	10 33.7	104 431	104 431	104 431	104 431	104 431	
15	10 33.7	104 431	104 431	104 431	104 431	104 431	
16	10 33.7	104 431	104 431	104 431	104 431	104 431	
17	10 33.7	104 431	104 431	104 431	104 431	104 431	
18	10 33.7	104 431	104 431	104 431	104 431	104 431	
19	10 33.7	104 431	104 431	104 431	104 431	104 431	
20	10 33.7	104 431	104 431	104 431	104 431	104 431	
21	10 33.7	104 431	104 431	104 431	104 431	104 431	
22	10 33.7	104 431	104 431	104 431	104 431	104 431	
23	10 33.7	104 431	104 431	104 431	104 431	104 431	
24	10 33.7	104 431	104 431	104 431	104 431	104 431	
25	10 33.7	104 431	104 431	104 431	104 431	104 431	
26	10 33.7	104 431	104 431	104 431	104 431	104 431	
27	10 33.7	104 431	104 431	104 431	104 431	104 431	
28	10 33.7	104 431	104 431	104 431	104 431	104 431	
29	10 33.7	104 431	104 431	104 431	104 431	104 431	
30	10 33.7	104 431	104 431	104 431	104 431	104 431	
31	10 33.7	104 431	104 431	104 431	104 431	104 431	
Aug. 1	10 33.7	104 431	104 431	104 431	104 431	104 431	
2	10 33.7	104 431	104 431	104 431	104 431	104 431	
3	10 33.7	104 431	104 431	104 431	104 431	104 431	
4	10 33.7	104 431	104 431	104 431	104 431	104 431	
5	10 33.7	104 431	104 431	104 431	104 431	104 431	
6	10 33.7	104 431	104 431	104 431	104 431	104 431	
7	10 33.7	104 431	104 431	104 431	104 431	104 431	
8	10 33.7	104 431	104 431	104 431	104 431	104 431	

	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	1	2	3	4																																																																																																																																																																																																																																										
Time	77.363	77.174	76.921	76.551	76.249	75.993	75.768	75.549	75.345	75.146	74.952	74.763	74.579	74.399	74.224	74.054	73.889	73.729	73.574	73.424	73.278	73.136	72.998	72.864	72.734	72.608	72.486	72.368	72.254	72.144	72.038	71.936	71.838	71.744	71.654	71.568	71.486	71.408	71.334	71.264	71.198	71.136	71.074	71.016	70.962	70.902	70.846	70.794	70.746	70.692	70.642	70.596																																																																																																																																																																																																																																							
Lat.	194.719	194.176	193.250	191.939	190.225	188.032	185.337	182.040	178.140	173.638	168.534	162.928	156.819	150.206	143.089	135.468	127.343	118.714	109.580	99.941	89.794	79.049	67.704	55.760	43.217	30.074	16.332	2.090	-12.651	-27.909	-42.667	-56.824	-70.380	-83.336	-95.692	-107.448	-118.604	-129.160	-139.116	-148.472	-157.228	-165.384	-172.940	-180.006	-186.582	-192.668	-198.264	-203.370	-208.006	-212.172	-215.868	-219.094	-221.850																																																																																																																																																																																																																																						
Long.	81.1	81.1	81.1	80.9	80.7	80.1	79.1	77.6	75.5	72.8	69.4	65.1	60.0	54.0	47.0	39.0	30.0	20.0	9.0	-2.0	-11.0	-19.0	-26.0	-32.0	-37.0	-41.0	-44.0	-46.0	-47.0	-48.0	-48.0	-47.0	-44.0	-40.0	-35.0	-29.0	-22.0	-15.0	-7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0	32.0	37.0	41.0	44.0	46.0	47.0	48.0	48.0	47.0	44.0	40.0	35.0	29.0	22.0	15.0	7.0	2.0	11.0	19.0	26.0

17	70 840	+0.284	108, 143	192, 863	44.3	71.5	60.0	2, 440	+1, 510	2, 266	344, 037.5	IV	3-4	M.
18	70 841	+0.104	107, 193	191, 490	43.9	71.1	61.5	2, 440	-1, 204	2, 273	344, 104.3	IV-V	4-5	M.
19	70 830	-0.114												
20	70 836	-0.234	104, 336	191, 473	43.6	71.1	61.0	2, 438	-18	2, 255	329, 811.0	VI	5-6	M.
21	70 840	-0.250	107, 740	193, 495	43.9	71.4	60.0	2, 453	+3, 023	1, 759	189, 637.3	Calm		R.F.
22	70 121	-0.325	104, 240	190, 647	42.8	70.7	60.0	2, 455	-2, 919	1, 800	188, 250.8	X	2-3	R.F.
23	70 039	-0.082	107, 610	194, 144	43.9	72.1	59.9	2, 452	+3, 001	1, 807	300, 090.4	III-IV	6	R.F.
24	69 891	-0.148	105, 250	192, 120	43.1	71.8	59.8	2, 442	-2, 025	1, 883	196, 215.9	VI	2-3	R.F.
25	69 838	-0.053	105, 365	192, 314	43.3	71.4	59.5	2, 432	+1, 224	1, 873	190, 594.1	IX-X	3	R.F.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., July 16, 1883.

SIR: In accordance with your letter of April 26 inclosing a copy of a letter from the president of the River Commission, I have the honor to submit the following report as an appendix to my report on the Columbus observations:

The information requested was an opinion as to the relative accuracy, reliability and economy of the methods of gauging by double floats, by a vertical rod, and by meter, with suggestions as to improvements in the methods used.

Relative accuracy.—This part of the subject will be considered by first pointing out some of the sources of inaccuracy in the different methods, and then drawing some conclusions as to the adaptability of each to certain conditions.

I. Method by double floats. There are two probable sources of error in this method, first, the necessity of assuming the mean velocity in a vertical plane at some fixed depth, corrected, perhaps, by some given formula; and, second, the possible inability to measure the velocity correctly at the assumed depth.

(1) By an examination of observations made on velocities in a vertical plane, it is found that there is no fixed relation between the velocities at different depths. This is especially the case in silt-bearing streams, such as the Lower Mississippi, where the conditions are so numerous and unstable. Any method of determining a mean velocity in a vertical plane must therefore be based on a great number of points. The double-float method, which provides for measuring the velocity in a vertical plane, can lay little claim to accuracy, when viewed from this point. It is believed that the results, if viewed from a practical standpoint, terminating vertical curves, will, when subjected to a close examination, show that they are not reliable. It is believed that they are not reliable for determining relative velocities in a vertical plane. If so, no method can be relied on for measuring a velocity at any point in a vertical section.

(2) There is also some doubt as to whether a velocity at any point in a vertical section can be measured accurately with the double-float method. During the observations made at Fulton, Tenn., by Assistant Engineer J. H. ... it was my duty for several months to give personal attention to the operation of the floats. It gave an excellent opportunity for observing the surface and sub-surface currents. At times the surface float would be considerably inclined backward or forward. In each of these cases the surface float had a powerful influence in retarding or accelerating the sub-float, the velocity of the former not representing the correct velocity of the water in the vicinity of the latter. The above indications were frequently noticeable in high water. Sometimes also in high water the subfloat was apparently held up, the assumed immersion not being reached. This was shown by the fact that several feet of wire were sometimes taken in before there was any appreciable weight of the subfloat. By an examination of the vertical velocity observations at Fulton, Tenn., it will be found that in the sets in which two or more floats were run at the same depth the velocities differ from 1 to 15 per cent.

In these observations the boat was anchored, and the floats all started from the same point, their paths varying but slightly across the ranges. The Fulton observations have been selected, inasmuch as they are probably the best that have been made with double floats on the Mississippi River.

II. Method by rod floats. Within certain limits of depth the vertical rod is well adapted to measuring the mean velocity accurately, being acted upon by the whole body of water in a vertical plane. Where the float can be run of sufficient length to nearly touch bottom, there is but a small source of error due to the corrections to be made. Where due care is taken in the manipulation, allowing full time for the float to acquire a uniform movement and erect position before entering upon its measured path, little variation should be expected from a series of observations in the same plane. A very small per cent. of variation was found in the observations made with the plant at Grafton, Ill., where six rods of the same length were run from each station. As to the two methods of locating instrumentally, and obtaining the length of path by the plant, used on the Upper Mississippi, the latter is preferable where the depth does not exceed about 25 feet; beyond that depth there is difficulty in putting out the float so as to acquire its equilibrium before entering upon the measured path. A rod-float of more than 35 or 40 feet in length can not be handled successfully. Hence for river depths greater than about 40 feet, the method loses in accuracy. The same objection then comes in that has been presented in connection with double floats, viz., that only a part of the vertical velocity section is measured.

III. Method by the current meter. There is a good deal of room for improvement in the current meter for effective work on the Lower Mississippi. Some improvement has no doubt been made recently in this direction. My experience is confined to the

meter. The chief objection to the method as used by me rests with the instrument itself. The objection presented to the rod-float and the double-float methods does not find a place in the method with the meter. It is possible to obtain results at depths in a vertical plane within reasonable limits. The only question that arises is the accuracy with which a velocity can be measured at any particular point. Under certain conditions great accuracy may be attained with the Ellis meter. In clear stream, of not too great velocity or depth, the meter, having been carefully tested and rated, will do accurate work, and will continue to so long as the friction remains constant. It is easily handled, with suitable plant, and can be relied upon. But in such a stream as the Mississippi, at high water, with its great depth and velocity, its silt and floating material, the instrument is entirely unsuited to the work. A constant friction cannot be maintained under such conditions can hardly admit of doubt to any one who has had an extended experience. There is nothing to prevent the journal-box from catching fine particles of sand, that not only increase the friction at the time, but produce a constant wearing effect that results in a permanent increase of friction. The mercury contact, as used at Columbus, is another source of variable friction, on account of certain parts of it that catch the sediment, a binding effect being the result. This change of friction can be detected by turning the instrument in the wind at frequent intervals during a set of observations. The velocity of wind required to turn the wheel will be found to vary materially. A high cleansing will often remove the difficulty temporarily. These differences of friction are not to be found in the equations, as the meter was always rated in clear water. The Ellis meter is very delicate, and is subject to be entirely destroyed by catching logs. From my experience I think it possible to construct a meter that will be free from most of the imperfections mentioned.

There is a considerable source of error in using any meter without anchoring. This is especially the case in windy weather, when it is impossible to avoid lateral movement.

The rate of the meter is increased by a movement in either direction; hence there is no way of compensation. This error is likely to be considerable with a strong wind and slow current. For instance, a movement of a hundred feet would be unreasonable, with a brisk wind, during a five-minute observation. That would correspond to about twenty-five revolutions of the meter-wheel, an average of five revolutions per minute. If the meter should make but thirty revolutions per minute, not an unreasonable supposition, the error would be 20 per cent. Such errors can be practically avoided by locating the position of the boat as frequently as possible, and correcting the velocities accordingly. The error from this source diminishes as the velocity increases.

Conclusions.—Of the three methods, the double float is considered the least accurate, incapable of producing fair results in a stream of even banks and bed. In a clear stream of limited depth, the methods by rod-floats and meter are, perhaps, equally accurate; when sediment is contained in any considerable quantity, the former of the two is preferable. At high-water stages on the Lower Mississippi none of the methods can be relied on for perfect accuracy. In extreme high water rod-floats are considered preferable to the Ellis meter. I have no doubt but that a meter may be constructed and manipulated as to do comparatively accurate work at all stages on the Lower Mississippi.

Reliability.—As to the reliability, the method by rod-floats seems to have the advantage, although that with the meter may be equally good within limits. From the results already presented, the double-float method is considered very unreliable at high-water stages, and reliable only in a limited degree at all stages.

Economy.—When an anchorage, similar to that employed on the Upper Mississippi, is used, the methods by rod-float and current-meter are equally expensive, either being less so than that by double floats. Free rod-floats and double floats, located permanently, are equally expensive. In high water, when the use of a launch is necessary, the method by meter is the cheapest method of all.

Suggestions as to improvements will be offered.
Respectfully submitted.

J. H. DAVIS,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

3.—AT HELENA, ARK., F. A. YEAGER, ASSISTANT IN CHARGE.

HOTCHKISS, TENN., June 12, 1883.

SIR: In reply to your letter containing instructions from president of Commission concerning reports, &c., of different methods of gauging, I have to say that I did not pick up my notes at Helena, so know nothing of the results. During the latter part of my stay there I ran rod-floats and the meter at the same time.

Six: In
president
an apper

The 11
and sec

meter, is

Relate

some

cancel

I. M.

first,

depth

to be

(1)

from

last

con

to

in

for

or

it

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

?

... accuracy of the method
... at launch. This can be done, w
... are being recorded. The plant is
... The launch I had at Helena
... and I found it perfectly safe at all tim
... correct,

F. A. YEAGER,
Assistant Engineer

Conclusions.

Large observations, Helena, Ark.

Large observations at Helena, Ark., was as follows:

... on cross-section paper, and their areas found
... horizontal, 20 feet vertical, per square or inch.
... were plotted on the cross-sections, and the area diff
... being placed so as to give, as nearly as poss
... area, or so that the depth at the velocity post
... of the partial areas.
... usually found at a depth considerably less than the

... and red-foots were corrected and reduced by Francis's

$$v = r \left[1 - .116 \left(\sqrt{\frac{s-1}{s}} - 0.1 \right) \right]$$

... velocity, v = observed velocity, s = sounding, and I =

... applied as directed in the field-notes.

... at the highest gauge reading, 47.10 feet, on March
... as datum area, and all others obtained by success
... and this.

... of readings taken at 6 a. m., 12 m., and 6 p. m.

... Major Henryson.

... dividing water area by water width.

... by dividing datum areas by datum width (= 49.10 ft)
... from cross-section soundings in note-books.

... which no measurements were made, were derived from
... the measured widths to gauge.

... by dividing discharge by water area.

... "incomplete" are nearly all computed on cross-sections
... corrected for gauge.

... were also substituted from other dates; especially for part
... sections or "end areas"

... the width accurately, the lack of soundings near the riv
... and the lack of velocity observations near the banks, a
... of inaccuracy in the results.

Discharge observations at Helena, Ark.

Date.	Gauge.		Dimensions of cross-section of discharge.						Width.	Scour or fill.	Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature, Fahr.		Method.	Remarks.	
	Read- ing.	Rise or fall in the preced- ing 24 hours.	Area.		Depth.		Mean datum.	Maxi- mum.										
			Water.	Below datum.	Feet.	Sq. feet.								Feet.	Sq. feet.			
1892.	Feet.	Feet.	Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Feet.	Sq. feet.	Sq. feet.	Feet.	Cubic feet.			o	o		
Jan.																		
1	38.12	+0.36																
2	38.48	+0.36																
3	38.80	+0.32																
4	39.07	+0.27																
5	39.27	+0.20																
6	39.33	+0.06																
7	39.43	+0.08																
8	39.48	+0.05																
9	39.48	0.00																
10	39.49	-0.08																
11	39.35	-0.05																
12	39.33	-0.02																
13	39.43	+0.10																
14	39.53	+0.10																
15	39.05	-0.12																
16	39.92	+0.27																
17	40.30	+0.38	200,777	242,534	43.5	49.5	74.5											
18	40.70	+0.40																
19	41.08	+0.38																
20	41.38	+0.30																
21	41.70	+0.32	214,487	240,767	44.3	49.0	72.0											
22	41.95	+0.25																
23	42.20	+0.25	217,725	241,501	44.8	49.2	73.0											
24	42.45	+0.25	214,403	237,050	44.0	48.3	71.2											
25	42.65	+0.20	219,282	240,866	45.0	49.1	68.5											
26	42.85	+0.20																
27	43.10	+0.25																
28	43.33	+0.23	210,401	237,763	45.0	48.4	74.8											
29	43.45	+0.12																
30	43.65	+0.20																
31	43.81	+0.16	230,187	246,200	47.3	50.2	78.5											
1	43.90	+0.09	232,474	248,080	47.7	50.5	77.8											
2	43.99	+0.09	229,005	244,764	47.1	49.9	78.5											
3	44.15	-0.16																
Feb																		

No observations taken.

No observations taken.

*No discharge taken.

*No discharge taken.

R. F.

R. F.

R. F.

R. F.

M.

Feb

MISSISSIPPI RIVER - Discharge observations at Helena, Ark.—Continued.

Date.	Time.	Gauge.			Dimensions of cross-section of discharge.			Width.	Area.	Depth.		Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature, $^{\circ}$ Fahr.		Method.	Remarks.
		Read- ing.	Rise or fall in the prev- ing 24 hours.	Water.	Below datum.	Mean.	Maxi- mum.								Air.	Water.		
1882 Feb.	4	44 35	+0 29	Sq. feet. 234, 118	Sq. feet. 217 542	Feet. 48 1	Feet. 50 4	Feet. 41 3	Feet. 41 3	Feet. 41 3	Feet. 41 3	Feet. 4 982	Cubic feet. 1, 100, 476		0	0	M.	
	5	44 47	+0 12														M.	
	6	44 65	+0 18	228, 528	240 401	46 0	46 0	46 0	46 0	46 0	46 0	4 897	1, 119, 100				M.	
	7	44 80	+1 15	231, 834	245, 037	48 0	48 0	48 0	48 0	48 0	48 0	5 230	1, 231, 870				M.	
	8	45 15	+0 35														M.	
	9	45 40	+0 25	241, 531	240, 711	49 1	49 1	49 1	49 1	49 1	49 1	5 515	1, 330, 880				M.	
	10	45 65	+0 25														M.	
	11	46 15	+0 49	237, 726	242, 841	48 8	49 5	49 5	49 5	49 5	49 5	5 541	1, 317, 240				M.	
	12	46 29	+0 24														M.	
	13	46 58	+0 30														M.	
	14	46 00	+0 02	240 730	241 234	49 4	49 5	49 5	49 5	49 5	49 5	5 807	1, 419, 000				M.	
	15	46 50	00	241 361	245, 771	47 0	48 0	48 0	48 0	48 0	48 0	5 776	1, 344, 215				M.	
	16	46 57	+0 07														M.	
	17	46 28	+0 31	235, 703	239, 557	48 4	48 8	48 0	48 0	48 0	48 0	5 703	1, 343, 415				M.	
	18	46 04	-0 01	233, 463	236 451	47 0	48 0	48 4	48 4	48 4	48 4	5 596	1, 300, 845				M.	
	19	46 05	-0 03															
	20	46 10	-1 05															
	21	45 85	-0 15															
	22	45 72	-0 13															
	23	45 60	-0 06															
	24	45 54	-0 12	221 370	228 977	45 5	46 6	46 6	46 6	46 6	46 6	5 812	1, 294, 555				M.	
	25	45 48	-0 06	224, 921	232, 831	46 2	47 4	46 2	46 2	46 2	46 2	5 504	1, 257, 965				M.	
	26	45 42	-0 06															
	27	45 41	-1 01	247, 977	245, 672	46 8	48 0	48 4	48 4	48 4	48 4	5 470	1, 247, 035				M.	
	28	45 52	+0 11															
	1	45 51	-0 01															
Mar.	2	45 58	+0 07	228, 715	240 118	47 0	48 1	48 3	48 3	48 3	48 3	5 457	1, 341, 225				M.	
	3	45 74	+0 16	230, 338	235, 902	47 1	48 1	48 2	48 2	48 2	48 2	5 003	1, 284, 980				M.	
	4	46 06	+0 32															
	5	46 57	+0 51															
	6	47 00	+0 43	233, 616(1)	240, 103	49 2	48 0	48 5	48 5	48 5	48 5	(*)						
	7	47 02	+0 22	231, 109	234, 580	48 1	47 8	48 0	48 0	48 0	48 0	5 432	1, 506, 875					
	8	47 10	+0 08	235, 411	233, 411	47 0	47 5	48 8	48 8	48 8	48 8	5 677	1, 504, 480					
																		* No discharge taken.

No observations taken.

No observations taken.

No observations taken.

[illegible]

Mississippi River—Discharge observations at Helena, Ark.—Continued.

Date.	Gauge.	Dimensions of cross-section of discharge.						Discharge per second.	Direction and force of wind.	Temperature, Faha.		Method.	Remarks.	
		Area		Depth		Width.	Scour or fill.			Mean velocity per second.	Air.			Water.
		Water.	Below datum	Mean.	Mean datum.									
Read- ing.	Rise or fall in the preced- ing 24 hours.	Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Sq. feet.	Feet.	Outlet feet.					
1882.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Feet.					
May 4	+0.02	181,064.7	237,448	37.5	48.4	75.9	+ 034	4.371	791,409.9	VI	4	M.		
5	+0.10	182,581.2	239,463	38.1	48.6	76.8	+2,015	4.302	800,544.5	VI	5	M.		
6	+0.03													
7	+0.07													
8	+0.13	183,426.0	238,213	38.0	48.5	76.2	-1,250	4.321	792,485.2	VI	4	M.		
9	+0.12	181,647.0	236,061	37.7	48.1	78.5	-2,152	4.705	855,516.8	III	5	M.		
10	+0.80	184,503.4	234,920	38.2	47.6	77.0	-1,141	4.324	798,030.0		1	M.		
11	+0.67	186,202.5	243,352	38.6	47.5	78.5	-1,538	4.820	800,005.6			M.		
12	+1.08	191,952.0	243,858	30.8	47.6	78.9	+ 476	4.485	802,978.6	X	80-5	M.		
13	+0.95	195,793.2	233,112	40.5	47.5	80.2	- 746	4.528	806,065.2	X	80-3	M.		
14	+0.65													
15	+0.50													
16	+0.44	201,803.0	231,413	41.6	47.1	81.7	-1,609	5.034	1,015,898.1	X	80-1	M.		
17	+0.34	211,638.6	239,036	43.8	48.8	80.9	+8,193	5.083	1,077,877.1			M.		
18	+0.27	210,231.1	238,823	43.5	48.3	80.5	-2,712	5.125	1,077,486.9			M.		
19	+0.18													
20	+0.12	210,918.0	236,161	42.0	48.1	81.8	- 763	5.271	1,111,696.1			M.		
21	+0.10													
22	+0.05	214,515.7	236,604	44.3	48.0	83.1	+2,838	5.145	1,103,561.1	XII	4	M.		
23	+0.04	210,677.7	234,614	42.6	47.6	83.2	-4,080	5.8.8	1,128,097.1			M.		
24	+0.02	212,967.5	236,741	44.0	48.2	83.1	+2,127	5.070	1,080,092.3		0	M.		
25	+0.03	210,570.7	234,217	48.5	47.7	81.2	-2,624	5.230	1,101,009.2		0	M.		
26	+0.03	215,819.0	239,110	44.5	48.7	82.5	+4,893	5.040	1,086,246.2		0	M.		
27	+0.05	213,592.5	237,623	44.2	48.4	82.3	-1,485	5.810	1,145,092.1					
28	+0.01													
29	+0.03	216,899.4	240,020	44.6	48.9	83.1	+2,494	5.048	1,089,962.9	XII	1	M.		
30	+0.13	210,565.5	235,343	43.6	47.9	82.5	-4,886	5.800	1,116,826.2					
31	+0.16													
June 1	+0.17	215,515.4	241,005	44.6	48.1	83.1	+5,792	5.083	1,095,271.7		0	M.		
2	+0.14	212,431.2	238,688	44.0	48.6	83.1	-2,467	5.010	1,085,217.1			M.		
3	+0.08	211,369.1	238,033	43.7	48.4	82.0	- 656	4.980	1,044,282.0	XII	3	M.		
4	+0.00													
5	+0.09	210,562.5	236,809	43.5	48.3	81.7	-1,334	5.056	1,058,616.5			M.		
6	+0.07													
7	+0.06													
8	+0.03	210,000.6	236,560	43.4	47.9	83.2	-1,339	4.968	1,037,061.3		0	M.		
9														
10														

No observations taken.

10	41.20	-0.10	500, 872.5	735, 850	43.4	47.9	82.5	4, 834	-	80	A. 189	1, 070, 750.1	M.
11	41.22	+0.02	211, 072.3	235, 510	43.7	44.1	81.1	4, 834	+	800	A. 090	1, 074, 572.7	M.
12	41.25	+0.03											
13	41.27	+0.02											
14	41.29	-0.04											
15	41.20	-0.09											
16	41.00	-0.20	212, 483.0	239, 600	43.9	44.8	74.0	4, 833	+	3, 000	A. 843	1, 029, 015.7	R. F.
17	40.05	-0.35											
18	40.20	-0.45											
19	39.75	-0.45											
20	39.20	-0.55	202, 358.0	238, 609	41.9	44.5	78.1	4, 828	-	1, 431	4, 520	938, 257.3	M.
21	38.85	-0.35	194, 781.2	232, 282	40.8	45.2	74.5	4, 828	-	5, 897	4, 845	943, 799.4	M.
22	38.77	-0.08	197, 942.5	235, 809	41.0	48.0	78.5	4, 827	+	3, 547	4, 717	933, 803.0	M.
23	38.85	+0.08	194, 610.0	232, 120	40.3	45.2	78.6	4, 828	-	3, 749	4, 727	920, 000.4	M.
24	39.15	+0.30											
25	39.25	+0.13											
26	39.45	+0.17											
27	39.59	+0.14	199, 201.0	233, 129	41.3	47.4	76.1	4, 828	+	1, 009	4, 900	977, 850.0	M.
28	39.70	+0.11	196, 868.0	230, 265	40.8	46.8	77.1	4, 828	-	2, 864	4, 908	972, 318.6	M.
29	39.72	+0.02	202, 367.0	235, 068	41.9	48.0	75.5	4, 828	+	5, 403	4, 657	942, 482.4	M.
30	39.66	-0.06	204, 015.0	237, 600	43.2	48.4	74.7	4, 828	+	1, 932	5, 102	1, 040, 945.0	M.
1	39.52	-0.14	197, 936.5	232, 556	41.0	47.4	77.2	4, 828	-	5, 044	4, 809	951, 573.6	M.
2	39.45	-0.07											
3	39.25	-0.20	197, 391.0	233, 314	40.9	47.5	77.7	4, 828	+	758	4, 957	978, 522.2	M.
4	39.05	-0.20											
5	38.82	-0.23	193, 848.0	231, 847	40.2	47.2	70.5	4, 828	-	1, 467	4, 993	967, 966.7	M.
6	38.75	-0.07											
7	38.77	+0.02	196, 272.0	234, 512	40.7	47.8	76.3	4, 828	+	2, 665	4, 886	949, 349.6	M.
8	38.87	+0.10											
9	39.15	+0.28											
10	39.35	+0.20											
11	39.55	+0.20											
12	39.70	+0.15	201, 314.5	235, 064	41.7	47.9	74.9	4, 828	+	552	5, 000	1, 018, 668.3	M.
13	39.77	+0.07	202, 123.0	235, 535	41.9	48.0	70.5	4, 828	+	471	4, 901	900, 596.6	M.
14	39.77	0.00	198, 284.4	231, 606	41.1	47.2	78.7	4, 828	-	3, 839	5, 083	1, 007, 821.2	M.
15	39.65	-0.12	199, 182.0	233, 173	41.2	47.3	77.3	4, 828	+	1, 477	5, 164	1, 028, 504.0	M.
16	39.44	-0.21											
17	39.10	-0.34	196, 062.9	232, 709	40.6	47.2	78.0	4, 828	-	464	4, 645	910, 792.6	M.
18	38.63	-0.47	193, 743.9	232, 658	40.4	47.2	78.5	4, 827	-	51	4, 681	906, 905.5	M.
19	38.02	-0.61	193, 015.8	234, 874	40.0	47.7	77.5	4, 827	+	2, 216	4, 650	897, 617.9	M.
20	37.28	-0.74	188, 892.9	234, 323	39.1	47.5	76.4	4, 827	-	551	4, 551	859, 615.6	M.
21	36.40	-0.88											
22	35.35	-1.05	182, 628.0	232, 547	37.8	47.2	72.5	4, 827	-	1, 776	4, 379	799, 762.0	M.
23	34.46	-0.92											
24	33.63	-0.80	170, 750.2	228, 971	35.4	46.4	69.9	4, 825	-	3, 570	4, 254	728, 155.8	M.
25	32.80	-0.83	168, 338.9	230, 555	35.0	46.8	70.3	4, 805	+	1, 584	4, 301	724, 029.7	M.
26	31.96	-0.84	162, 940.9	229, 183	34.1	46.5	69.6	4, 782	-	1, 372	4, 218	687, 350.5	M.
27	31.00	-0.96	160, 341.8	231, 162	33.7	46.9	68.8	4, 756	+	1, 979	4, 115	659, 771.7	M.
28	29.95	-1.05											
29	28.72	-1.23	146, 562.8	228, 213	30.9	46.3	67.2	4, 745	-	2, 949	4, 069	595, 494.3	M.
30	27.35	-1.37											
31	26.25	-1.10	135, 537.3	228, 806	28.8	40.4	64.5	4, 710	+	653	3, 987	540, 376.8	M.

No observations taken.

Observation incomplete.

July

Mississippi River — Discharge observations at Helena, Ark. — Continued.

Date.	Gauge.	Dimensions of cross section of discharge					Scour or fill.	Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature, Fahr.		Method.	Remarks.
		Read- ing	Rise or fall in the preceding 24 hours.	Area.	Depth.	Width.					Air.	Water.		
				Water.	Below datum.	Mean.	Maxi- mum.							
				Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Sq.					
1882.														
Aug.														
1		23.15	+0.10	130,007	237.535	27.7	62.3	4.089	—	—	—	—	M.	
2		24.25	+0.90	121,583	224.375	26.1	63.7	4.007	—	—	—	—	M.	
3		23.62	+0.73	110,071	202.182	24.9	62.5	4.654	—	—	—	—	M.	
4		23.08	+0.46	111,135	201.014	24.0	62.1	4.039	—	—	—	—	M.	
5		22.58	+0.48	111,047	200.910	24.2	65.3	4.032	—	—	—	—	M.	
6		22.15	+0.43	111,542	204.700	24.1	61.8	4.034	—	—	—	—	M.	
7		21.85	+0.30	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
8		22.00	+0.15	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
9		22.70	+0.70	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
10		21.50	+0.85	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
11		21.17	+0.61	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
12		21.47	+0.30	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
13		21.45	+0.10	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
14		21.45	+0.10	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
15		21.45	+0.10	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
16		21.45	+0.10	111,796	206.714	24.2	61.1	4.037	—	—	—	—	M.	
17		23.09	+0.33	123,820	242.070	26.0	61.5	4.059	—	—	—	—	M.	
18		22.58	+0.48	121,876	240.171	26.2	61.9	4.854	—	—	—	—	M.	
19		22.13	+0.48	111,921	232.650	25.8	60.3	4.053	—	—	—	—	M.	
20		21.65	+0.47	111,796	227.674	24.0	61.8	4.048	—	—	—	—	M.	
21		21.35	+0.30	111,955	229.241	24.1	60.8	4.048	—	—	—	—	M.	
22		21.12	+0.23	111,955	229.241	24.1	60.8	4.048	—	—	—	—	M.	
23		20.75	+0.37	111,796	232.778	24.2	62.5	4.036	—	—	—	—	M.	
24		20.92	+0.41	103,987	217.177	22.5	62.6	4.016	—	—	—	—	M.	
25		19.85	+0.47	87,387	223.343	21.2	60.3	4.003	—	—	—	—	M.	
26		19.25	+0.60	80,487	221.540	19.0	64.8	4.574	—	—	—	—	M.	
27		18.63	+0.63	92,060	220.844	20.2	68.2	4.602	—	—	—	—	M.	
28		17.92	+0.70	80,487	221.540	19.0	64.8	4.574	—	—	—	—	M.	
29		17.33	+0.59	80,487	221.540	19.0	64.8	4.574	—	—	—	—	M.	
30		16.80	+0.53	80,487	221.540	19.0	64.8	4.574	—	—	—	—	M.	
31		16.40	+0.40	82,281	221.208	18.1	64.0	4.540	—	—	—	—	M.	
Sept.														
1		16.10	+0.30	82,281	221.208	18.1	64.0	4.540	—	—	—	—	M.	
2		15.25	+0.25	82,281	221.208	18.1	64.0	4.540	—	—	—	—	M.	
3		15.74	+0.11	82,281	221.208	18.1	64.0	4.540	—	—	—	—	M.	

No observations kept.

Observation incomplete.

MISSISSIPPI RIVER.—Discharge observations at Helena, Ark.—Continued.

Date.	Gauge.		Dimensions of cross-section of discharge.							Width.	Scour or fill.	Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature, Fahr.		Method.	Remarks.
	Read- ing	Rise or fall in the preceding 24 hours.	Area.			Depth.		Mean datum.	Maxi- mum.									
			Water.	Below datum.	Feet.	Mean.	Feet.											
1882.	Feet.	Feet.	Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Feet.	Sq.									
Oct. 20	10.06	-0.32	60,738.8	213,403	20.4	43.3	51.3	2,970	-							M.	* Gauge record for week ending October 23 missing. Taken from Reynolds' report. Observation incomplete. Do.	
20	10.08	+0.32	60,738.8	213,403	20.4	43.3	51.3	2,970	-							R. F.		
21	9.85	-0.23	59,538.0	212,801	20.0	43.2	49.5	2,970	-							M.		
21	9.85	-0.23	59,538.0	212,801	20.0	43.2	49.5	2,970	-							R. F.		
22	9.90	+0.05																
23	9.85	-0.05	59,075.0	212,428	19.9	43.1	49.5	2,970	-									
23	9.85	-0.05	59,075.0	212,428	19.9	43.1	49.5	2,970	-									
24	9.80	-0.05	59,139.5	212,640	19.9	43.1	49.5	2,970	-									
24	9.80	-0.05	59,139.5	212,640	19.9	43.1	49.5	2,970	-									
25	9.85	+0.05	59,280.0	212,633	19.9	43.1	49.5	2,970	-									
25	9.85	+0.05	59,280.0	212,633	19.9	43.1	49.5	2,970	-									
26	10.05	+0.20	60,362.8	212,615	20.3	43.1	50.0	2,970	-									
27	10.20	+0.15	60,360.7	212,615	20.3	43.1	50.0	2,970	-									
28	10.22	+0.02	60,360.7	212,615	20.3	43.1	50.0	2,970	-									
28	10.22	+0.02	60,360.7	212,615	20.3	43.1	50.0	2,970	-									
29	10.40	+0.18																
30	10.35	-0.05	60,560.0	212,610	20.4	43.2	50.1	2,970	-									
31	10.30	-0.05																
Nov. 1	10.37	+0.07																
2	10.48	+0.11																
3	10.55	+0.07																
4	10.58	+0.03																
5	10.67	+0.09																
6	10.78	+0.11																
7	10.88	+0.10																
8	10.90	+0.02	61,020.9	212,155	22.4	43.0	51.9	2,761	-	456	3.829	306,068.5				M.	The small area east of sand-bar not included in the November observation. Observation incomplete. Do.	
9	10.92	+0.03																
10	11.03	+0.11	62,803.8	212,652	22.7	43.1	52.0	2,761	+	407	3.310	308,329.6	VI			M.		
11	11.12	+0.09	62,748.0	212,380	32.7	42.0	52.1	2,765	-	523	3.363	311,178.4	VI			M.		
12	11.25	+0.13																
13	11.65	+0.40																
14	11.75	+0.20																
15	11.99	+0.24																

* Gauge record for week ending October 23 missing. Taken from Reynolds' report. Observation incomplete. Do.

The small area east of sand-bar not included in the November observation. Observation incomplete. Do.

-AT HAYS' LANDING, MISS., HOMER P. RITTER, ASSISTANT IN CHARGE.

—Assistant Ritter has a report in course of preparation, but the necessity for
ices in other branches of work has delayed its completion.—S. S. L.

Discharge observations Hays' Landing, Miss.

ling out the accompanying blanks for this station, the mean gauge, water
our and fill, mean velocity, discharge, direction of wind and method were
from MS. $\frac{792}{a.f.}$, Assistant H. P. Ritter.

erature of the air is the mean of three readings taken each day at 6 a. m., 12
6 p. m. Copied from note-book 890.

a was taken at a gauge reading of 38 feet and a surface width of 2,770 feet.
a area for this gauge and width was obtained from the water area of March 15
lying the increase of area due to the difference in gauge readings. This gives
um area 169,015 square feet.

a area for January 2 was next obtained by adding to the water area of this
e area obtained by multiplying the mean of datum surface width and surface
f January 2, by the difference between the gauge reading on January 2 and
on of datum plane, i. e., 38 feet.

m area, as thus obtained, for January 2=158781.

quent datum areas were obtained by the successive addition or subtraction of
urs and fills.

depth was obtained by dividing the water area by the water width.

datum depth was obtained by dividing the datum area by datum width.

um depth was copied from field notes No. 888, and is the deepest actual sound-
en.

for January 2 was obtained by taking the difference between the gauge read-
January 1 at 12 m. and the mean gauge for January 2.

x fall between any other two consecutive days is obtained by taking the differ-
the mean guage readings for those days.

In column headed "method".....
M=Meter.
R=Rod floats.
D. F=Double floats.


manner of computing partial areas, the manner of dividing the section into
areas, and of distributing velocities, is as follows:

mencing at the shore line, the notes read thus—

Station....
1
+50
2
+50
3
&c.

stations marked 1, 2, 3, &c., are meter stations, while at the other stations
ngs only were taken. The first partial area is from 1 to 2+50, the velocity for
rtial area being observed at 2.

second partial area is from 2+50 to 3+50, the velocity for this partial area being
ed at 3; and so on.



partial areas were computed from the recorded soundings.

of partial area = total area. Partial area multiplied by its velocity = partial
rge.

of partial discharges = total discharge.

l discharge divided by total area = mean velocity.

r or fall is the difference between the water area as observed, and that as com-
from the change of gauge.

MISSISSIPPI RIVER.

Discharge observations at Hays' Landing, Miss.

Date.	Gauge.		Dimensions of cross-section of discharge.						Width.	Scour or fill.	Mean velocity per second.	Discharge in cu ft.	Temperature, Fahr.	Method.	Remarks.
	Read- ing.	Rise or fall in the preced- ing 24 hours.	Area.			Depth.									
			Water.	Sq feet.	Below datum.	Mean datum.	Mean datum.	Maxi- mum							
1882.															
Jan.															
1	28.22														
2	29.89	+0.67	138,742	158,781	51.3	49.4	91.8								
3	30.80	+0.41													
4	30.70	+0.40													
5	31.05	+0.35													
6	31.39	+0.34													
7	31.54	+0.10													
8	31.74	+0.20													
9	32.00	+0.26													
10	32.14	+0.14													
11	32.25	+0.11													
12	32.40	+0.15													
13	32.63	+0.23													
14	32.70	+0.07													
15	32.80	+0.10													
16	33.08	+0.28													
17	33.25	+0.17													
18	33.48	+0.23													
19	33.70	+0.22													
20	34.98	+0.28													
21	34.24	+0.26	161,534	171,788	59.6	62.9	99.0								
22	34.45	+0.17													
23	34.60	+0.15	154,328	163,609	56.0	58.1	94.7								
24	35.00	+0.40	155,041	163,944	57.4	59.2	96.7								
25	35.20	+0.20													
26	35.40	+0.20													
27	35.45	+0.05													
28	35.45	+0.00													
29	35.45	+0.00													
30	35.45	+0.00													
31	35.45	+0.00													
32	35.45	+0.00													
33	35.45	+0.00													
34	35.45	+0.00													
35	35.45	+0.00													
36	35.45	+0.00													
37	35.45	+0.00													
38	35.45	+0.00													
39	35.45	+0.00													
40	35.45	+0.00													
41	35.45	+0.00													
42	35.45	+0.00													
43	35.45	+0.00													
44	35.45	+0.00													
45	35.45	+0.00													
46	35.45	+0.00													
47	35.45	+0.00													
48	35.45	+0.00													
49	35.45	+0.00													
50	35.45	+0.00													
51	35.45	+0.00													
52	35.45	+0.00													
53	35.45	+0.00													
54	35.45	+0.00													
55	35.45	+0.00													
56	35.45	+0.00													
57	35.45	+0.00													
58	35.45	+0.00													
59	35.45	+0.00													
60	35.45	+0.00													
61	35.45	+0.00													
62	35.45	+0.00													
63	35.45	+0.00													
64	35.45	+0.00													
65	35.45	+0.00													
66	35.45	+0.00													
67	35.45	+0.00													
68	35.45	+0.00													
69	35.45	+0.00													
70	35.45	+0.00													
71	35.45	+0.00													
72	35.45	+0.00													
73	35.45	+0.00													
74	35.45	+0.00													
75	35.45	+0.00													
76	35.45	+0.00													
77	35.45	+0.00													
78	35.45	+0.00													
79	35.45	+0.00													
80	35.45	+0.00													
81	35.45	+0.00													
82	35.45	+0.00													
83	35.45	+0.00													
84	35.45	+0.00													
85	35.45	+0.00													
86	35.45	+0.00													
87	35.45	+0.00													
88	35.45	+0.00													
89	35.45	+0.00													
90	35.45	+0.00													
91	35.45	+0.00													
92	35.45	+0.00													
93	35.45	+0.00													
94	35.45	+0.00													
95	35.45	+0.00													
96	35.45	+0.00													
97	35.45	+0.00													
98	35.45	+0.00													
99	35.45	+0.00													
100	35.45	+0.00													

Checked twice.

Year	1900	1901	1902	1903	1904	1905	1906	1907	1908	1909	1910	1911	1912	1913	1914	1915	1916	1917	1918	1919	1920	1921	1922	1923	1924	1925	1926	1927	1928	1929	1930	1931	1932	1933	1934	1935	1936	1937	1938	1939	1940	1941	1942	1943	1944	1945	1946	1947	1948	1949	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352
------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------

MISSISSIPPI RIVER.—Discharge observations at Hays' Landing, Miss.—Continued.

Date.	Gauge.		Dimensions of cross-section of discharge.						Width.	Scour or fill.	Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature, Fahr.		Method.	Remarks.	
	Reading.	Rise or fall in the preceding 24 hours.	Area.		Depth.		Mean datum.	Max. min.										
			Water.	Below datum.	Feet.	Sq. feet.								Feet.	Sq. feet.			
1882.	Feet.	Feet.	Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Sq. feet.	Feet.	Sq. feet.	Feet.	Cubic feet.			°	°		
Mar. 28	35.17	-0.14	167,224	172,331	60.7	62.2	100.4	-1,216	2,756	-1,216	5,557	914,773	0				R.	
29	36.06	-0.11	164,614	170,010	59.7	61.4	101.7	-2,321	2,756				VI					
30	35.95	-0.11																
31	35.84	-0.11																
1	35.71	-0.13																
2	35.04	0.07																
3	35.53	-0.11																
4	35.46	-0.07	164,760	171,815	60.4	62.0	96.5	+1	2,730								R.	
5	35.39	-0.07	164,067	171,299	60.1	61.8	99.5	-	2,730								M.	
6	35.74	-0.09	163,855	171,346	60.1	61.9	98.7	+	2,725								M.	
7	35.24	-0.06	163,372	171,026	60.0	61.7	98.6	-	2,725								M.	
8	35.15	0.09																
9	37.09	0.06																
10	35.04	0.05	161,182	169,800	59.5	61.2	99.5	-1,636	2,707		5,404	871,011	0				M.	
11	34.04	0.10																
12	34.90	-0.04	161,783	170,336	59.7	61.5	99.0	+	2,708				XII heavy					
13	34.84	0.02	165,540	174,158	61.1	62.9	101.0	+3,832	2,708		5,506	921,430	XII heavy				R.	
14	34.23	0.05	160,424	169,177	59.2	61.1	98.9	-4,941	2,708		5,430	871,112	XII heavy				R.	
15	34.77	-0.06																
16	34.09	-0.08																
17	34.62	-0.07																
18	34.60	-0.02	164,385	173,773	60.8	62.7	99.2	+4,596	2,704		5,328	877,457	0				R.	
19	34.59	0.01	160,650	170,072	59.4	61.4	99.0	-3,701	2,704		6,037	909,806	VI				M.	
20	34.47	-0.12	166,432	176,159	61.5	63.5	99.5	+0,087	2,704		5,651	925,534	0				M.	
21	34.44	0.03	163,064	173,733	60.5	62.6	98.5	-2,426	2,704		5,490	900,024					M.	
22	34.40	+0.03																
23	34.46	-0.03																
24	34.33	-0.13																
25	34.25	-0.08																
26	34.15	-0.10	159,935	170,788	59.8	61.6	98.5	-2,945	2,699		5,309	854,640	VI heavy				M. & R.	
27	34.04	-0.11	161,403	172,013	60.8	62.3	98.0	+1,826	2,700		5,187	925,491	XII heavy				M. & R.	
28	33.80	-0.12	160,000	171,424	59.2	61.8	99.1	-1,199	2,700		5,321	871,112	0				M. & R.	

6	21.61	-0.57	122,818	172,234	47.4	62.1	78.5	2,001	-1,905	3,846	474,844	VI	heavy.	81	M.
7	20.62	-1.09	121,505	172,240	46.8	62.1	78.0	2,599	+	3,846	474,844	VI	light.	81	M.
8	19.76	-0.76	119,589	170,873	46.0	61.6	78.5	2,599	-1,207	4,116	492,048	XII	heavy.	77	M.
9	18.53	-0.37	119,586	170,995	46.0	61.6	77.7	2,599	+	4,207	510,837	XII	light.	78	M.
10	18.81	-0.03													
11	19.10	+0.29													
12	19.46	+0.36													
13	19.06	+0.20													
14	19.70	+0.04	124,152	173,234	47.7	62.4	80.0	2,601	+2,229	3,995	493,043	VI		85	R.
15	19.68	-0.07	124,049	173,303	47.7	62.5	88.5	2,601	+	3,916	485,826	VI	heavy.	84	R.
16	19.47	-0.16	123,542	173,225	47.5	62.4	80.0	2,599	-	4,015	495,977	VI	light.	84	R.
17	19.45	-0.02	122,903	172,638	47.8	62.2	78.9	2,599	-	3,860	474,445	XII	heavy.	81	R.
18	18.86	-0.59													
19	18.40	-0.46													
20	18.08	-0.87	119,083	172,502	46.0	62.2	78.9	2,589	-	3,860		XII	light.	78	
21	17.60	-0.43	117,282	171,800	45.4	61.9	77.7	2,586	-	4,181	490,380	XII	light.	84	M.
22	17.18	-0.42													
23	16.91	-0.27	113,680	169,982	44.0	61.3	76.9	2,582	-1,818			VI	light.	79	
24	16.46	-0.45													
25	16.06	-0.40	113,603	172,111	44.0	62.0	75.4	2,579	+2,129	3,677	417,741	VI	light.	80	R.
26	15.77	-0.29													
27	15.27	-0.50													
28	14.60	-0.67	109,434	171,672	42.9	61.9	74.0	2,548	-	3,472	379,981			81	R.
29	13.90	-0.70	106,725	170,745	42.0	61.6	73.9	2,541	-	3,836	356,006	VI	light.	79	R.
30	13.33	-0.57	105,497	170,961	41.7	61.6	72.4	2,529	+	3,283	346,835	0		85	R.
31	12.57	-0.76	103,149	170,533	40.9	61.5	71.0	2,522	-	3,173	327,229	VI	heavy.	82	R.
1	12.20	-0.37													
2	11.75	-0.45													
3	11.41	-0.34													
4	11.11	-0.30													
5	10.93	-0.18	97,374	168,872	39.0	60.0	69.2	2,495	-1,661	3,188	310,440	XII	light.	82	R.
6	10.79	-0.14	97,104	169,001	39.0	60.9	68.5	2,493	+	3,104	301,411	XII	light.	83	R.
7	10.69	-0.10	96,896	169,042	38.9	60.9	69.2	2,490	+	3,171	307,288	XII	heavy.	79	R.
8	10.63	-0.06	97,459	169,707	39.2	61.2	68.2	2,489	+	3,202	312,069	XII	heavy.	76	R.
9	10.67	+0.04													
10	10.73	+0.06	98,277	170,324	39.5	61.4	71.0	2,489	+	3,557		0		74	
11	10.85	+0.12	97,864	169,125	39.1	61.0	69.5	2,490	-1,199	3,817	322,995	0		79	M.
12	11.00	+0.15	98,772	170,147	39.6	61.3	69.0	2,496	+1,022	3,564	352,016	VI	light.	78	M.
13	11.13	+0.13	98,085	170,015	39.6	61.3	70.9	2,497	-	3,403	336,748	0		82	M.
14	11.19	+0.06	101,374	172,273	40.6	62.1	71.2	2,497	+2,253	3,602	365,182	0		78	M.
15	11.12	-0.07	100,458	171,545	40.2	61.8	70.0	2,497	-	3,590	360,643	0		80	M.
16	10.95	-0.17													
17	10.74	-0.21	97,954	169,989	39.3	61.3	69.5	2,491	-1,556	3,510	346,726	VI		81	M.
18	10.41	-0.33	97,609	170,452	39.3	61.4	69.0	2,483	+	3,496	341,255	VI	light.	83	M.
19	10.12	-0.29	96,881	170,456	39.1	61.4	68.9	2,477	+	3,446	333,835	VI	light.	82	M.
20	9.91	-0.21	94,829	168,912	38.3	60.9	68.4	2,476	-1,544	3,280	311,026	XII	light.	77	M.

Sept.

4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
6.09	6.11	6.19	6.23	6.24	6.31	6.36	6.40	6.45	6.68	6.78	7.04	7.82	7.85	8.01	8.43	8.80	8.95	9.21	9.34	9.46	9.54
+0.04	+0.07	+0.08	+0.08	+0.05	+0.07	+0.05	+0.04	+0.05	+0.23	+0.30	+0.26	+0.28	+0.33	+0.36	+0.43	+0.23	+0.20	+0.16	+0.23	+0.12	+0.06
86,411	86,865	86,625	86,970	86,970	86,580	86,211	87,270		89,911	89,076	89,635	87,837	89,353	90,191		91,219	92,904	93,556	94,808	98,748	
109,773	109,484	109,070	109,973	109,973	171,402	103,015	109,890		168,808	170,780	170,715	168,276	168,064	168,931		168,387	169,362	169,623	169,797	168,952	
36.2	36.3	36.3	36.4	36.4	37.1	36.0	36.5		36.3	37.2	37.3	36.5	37.0	37.2		37.3	37.9	38.1	38.8	38.0	
61.2	61.1	61.2	61.3	61.3	61.8	60.9	61.2		61.0	61.6	61.6	60.7	61.0	61.0		60.8	61.1	61.3	61.8	61.0	
65.2	65.8	65.4	65.0	65.2	65.2	64.1	65.1		66.1	66.2	67.1	66.9	67.0	67.5		68.1	68.5	68.8	68.8	69.5	
2,548	2,380	2,369	2,369	2,391	2,392	2,392	2,592		2,365	2,368	2,402	2,407	2,416	2,425		2,448	2,450	2,453	2,462	2,465	
-	285	186	207	1,429	2,487	+	975		-1,034	+1,914	-	2,480	+	33		644	974	261	174	845	
2,332	2,009	2,000	2,006	2,009	2,006	2,032			2,750	2,735	2,808	2,801	2,918			3,014	3,067	3,091	3,108		
226,542	225,368	223,912	223,143	231,001	234,700	220,735			239,025	243,692	251,272	251,379	260,730			274,945	284,909	289,149	293,665		
XII	0	0	VI	VI	VI	VI			XII	VI	0	0	XII	XII		XII	XII	VI	XII	XII	
light.			light.	heavy.	very h'vy.				very h'vy.	light.			heavy.			heavy.	light.	heavy.	light.	light.	
01	00	71	71	71	78	00			47	48	55	55	55	46		41	44	47	50	49	
M.	M.	M.	M.	M.	M.				M.	M.	M.	M.	M.			M.	M.	M.	M.		

reach simply the same stations and you know nothing of the changes that are taking place between them. For sounding at this station, light leads and lines were used in preference to the usually heavy ones employed.

The velocity work with floats was performed in the following manner: The floats were timed over a 100-foot path; the transit of float over the ranges inclosing this path was located with transit, the bases of location being 1,000 and 1,100 feet for upper and lower ranges respectively. At the section lines a very satisfactory substitute for transits to line the floats was used. It consisted of fine silk threads, weighted with lead plumb bobs and suspended from the apex of tripods erected over the lining hubs at the sections. These threads gave a line I consider practically as good as that given by the cross hairs of a transit. These stations were established on both banks, all of the river being observed from each bank; there were days, however, when the atmosphere was clear enough to take all the observations from one bank. At each of the lining-in stations, a rude stand was erected for holding the electric key and repeating. The floats were all started from points located on a section 500 feet above the upper extremity of the float path. This section was divided into a sufficient number of stations to cover all the velocities between the banks; the angles corresponding to these stations were calculated, so that to start the float, it was necessary simply to run out this section line until the line indicated by signal from the transit-man was reached. At this point the float starter would launch the float; the depth of immersion of float was always determined from soundings taken previously. Double floats were always run at mid depth. Rods were run as close to the bottom as possible. After the float was launched, the boat party followed the float over the path and noted very closely its action; if anything unnatural was visible, the float was always repeated until a visibly satisfactory observation was obtained. To avoid confusion, a system of signals for repeating floats was adopted. When a float was to be repeated for reasons discovered by the boat party, the float starter indicated the fact by waving a flag. When a float was to be repeated for reasons discovered by the transit party, the transit-man waved a flag. The transit of the float over the sections at extremity of path was signaled to the transit-man by telegraph, by the observer at the lining stations, the observer also acting as time-keeper. For a brief time when the flood was at its height, the locations at path extremities were omitted, and a float path of 100 feet was assumed. The washing away of the telegraph supports necessitated this change.

When rods were used, a special form of rod had to be devised, as at the deeper portions of the sections, the weight attached to rod has to be so great that it is necessary to arrange the attachments in such manner that the weight may be detached before withdrawing the rod. If such an arrangement is not made, you will, in a majority of cases, break your rod. If you attempt to make your rod heavy enough to prevent bending, you will find it will be too cumbersome to handle in a boat. The form of rod devised for this work was the same as that shown in sketch "A." The lower extremity of this rod is made T-shaped, as at "R." To the weight "w" two pan-shaped metallic wrists are attached at *vv*. These strips fit closely to the T portion of the rod, as shown in the figure. The terminal ends spring outward at *cc'* for reasons that will presently be given. A string passes from the weight at "h" to the top of the rod. This string is the one used in raising the weight. The small ring at *zz'* is held by two ring strings that pass from this ring to the top of the rod. The method of launching and withdrawing the rod is as follows: The rod is taken in tow by the skiff. The launching station having been reached, the weight is attached by simply fitting the weight into the groove at "u" and turning the wrists down on the T portion of the rod, making them fast by springing the ring over the spring ends as at *gg'*. This being done, the rod is lowered gradually into the water until the desired immersion is reached. After the observation is complete, to withdraw the rod, it will be simply necessary to give a brisk jerk on the ring strings, which will set the rod free. As the rod is held by party in the boat the weight pressing downward will throw back the wrists which are hinged at *bb'*. The weight having been detached, you will find that the rod will shoot rapidly upward and lie flat on the water surface, before the load weight can be drawn to the surface. While one of the boat crew is raising this weight, the other members of the crew will have taken the float in tow and reached the next station, without loss of time, breakage, or any inconvenience whatever. So it is seen the launching of this type of float is reduced simply to a minimum as to time.

The work with the meter was all conducted from the catamaran. The location was done by intersecting signals established on the bank. This system of location was necessitated by reason of the entire force having duties on the river. The plan of working was as follows: The catamaran was lashed to the launch in such a manner that, the suspending wire holding the meter, the throttle valve of engine and the engineer would all be in plane of the section when on line; the pilot taking such a position with reference to the intersecting signals as to bring the meter exactly on the station. This plan enabled the pilot and engineer to keep the plant in perfect position without any appreciable variation. The greater number of the discharge

velocity observations were taken by holding the plant up against the current. It was found by making a large number of experiments with plant anchored, that the results taken with the plant free or anchored did not differ. Experiments were made frequently at the various stations in order to fully satisfy myself that the plans did not differ appreciably. In doing the work by holding up, care was always taken to commence and end the observations on exact line. The vast amount of time it would take to withdraw and cast large anchors, the continued presence of passing boats and the vast fields of drift that are present in the river continually at flood stages necessitated the adoption of this plan.

In taking vertical velocity-curve observations, the plant was always anchored. The meter was worked from the stern of the catamaran. The connection and general arrangement of the apparatus was as follows: The suspending and guy-wires were attached to two model cog-reels which were attached to the platform, in the bow and stern respectively. The suspending wire passed from the stern-reel over to an iron sheave held by a pulley stanchion that projected about 4 feet upwards from end of the stern; this stanchion leaned outward far enough to let the meter weight clear the platform. The wire passed from this sheave to the loop-clasp of the meter-weight pipe. The guy-wire passed from the stern-reel to a wooden sheave held by a pulley block in the long beam that projected from the center of the platform outward between the bows of the catamaran. This beam was about 20 feet long, and was made adjustable, as its length depends on depth of immersion of the meter. Its length with reference to the hypotenuse and altitude of the triangle, of which it forms the base, may be such as will keep the suspending wire vertical. The guy-wire passes from the sheave to a small clamp that is attached to a cylinder of brass 1 inch long, which works up and down on the pipe of meter weight. This little cylinder has a clamp screw for adjusting it to the pipe at any desired height. The arrangements described above will without doubt keep apparatus perpendicular to the section. In this connection I would say that were it possible to use a rigidly fixed pipe for holding the meter it would, I think, be preferable. But we know on the Lower Mississippi at certain stages this would be impossible, on account of immense quantities of submerged drift that will be met with continually.

In *Annales des Ponts et Chaussées*, by M. De La Greve, a very good form of pipe attachment is described. I give a sketch of this in figure "B." It consists of a piece of gas-pipe of desired length with a small longitudinal section removed, as shown in the horizontal section, figure "a." The meter slides down this pipe and is kept from turning by the projection at c. Though the device is a good one, yet the guy plan, when worked carefully, is the more satisfactory and is always practicable. The battery connections were first made through the reels direct; but it was found advisable afterwards to use two small insulated wires for conducting the electric current. These wires served also as safety wires, as the suspending wire often broke. In some cases the conducting wires would hold the meter. The guy would prevent loss when these wires missing, but it would not prevent the injury that would be done by withdrawing it with the guy-wire. The battery connections were centralized in such manner that but two simple connections on the meter completed the circuit. The battery and register-cases were combined and attached by angle-wires to the catamaran in such manner as to prevent loss. The stern reel was graduated and connected with an index pointer in such manner that depths of less than one-tenth of foot could be read off.

The meter weight consisted of a lead cylinder weighing about 60 pounds. The cylinder was about 10 inches long and about $4\frac{1}{4}$ inches in diameter. A piece of $\frac{1}{2}$ -inch gas-pipe passed through the cylinder. This pipe was about 16 inches long. The meter was attached to this pipe. The top of the pipe terminated in a screw-tap containing the suspending wire clamp. A small brass cylinder containing the guy-wire clamp was attached to this pipe also.

The furniture of the catamaran consisted of a small skiff, a large sweep oar, a long pike pole, an ax, and set of signal flags. Life preservers for the party were also aboard. This outfit, and careful training of the party, prevented losses or accidents of any kind during the year, which was one of the most trying ones that in all probability will ever be encountered by parties on work of this character.

The velocity work done with double floats, rod-floats, and the meter was refined to every detail possible, as the necessity of employing three methods made it absolutely necessary to secure as nearly perfect results as possible, in order to make a comparison of the methods, and to make the discharge work in general satisfactory. The reductions and the curves of velocity, area, and discharge deduced attest fully the accuracy of the work in detail.

The cause of not using the meter exclusively was due to the non-arrival of the launch and the loss of one of the connecting parts of the meter. Work with the meter was a perfect success from the start. After the equipment for making register was received from Saint Louis, not a single observation was taken by any other method. Aside from this, I think the partial use of floats fortunate, as it will admit of a comparison of the methods and under favorable circumstances.

Besides the regular serial work done by the party, an exhaustive examination of the grand cut-off near Black Hawk was made during the flood. No flow through the cut-off was manifest. In Red River, from the mouth of the bayou cut-off down to Spanish Fort, the current was very feeble during the flood. An examination was made of the Bayou des Glaisses from the mouth to Hamburg, La. A discharge was also taken through a section about $\frac{1}{2}$ mile above the mouth of this bayou.

The notes were kept written up daily. The calculations were kept up daily, and a discharge sheet transmitted weekly up to August 17, 1882. After that date no computation could be made, as my assistant, Mr. John C. Cammack, left the party, he having received official orders to report in Saint Louis.

A daily log was kept, also a daily summary. The latter book contained the gauge readings, temperatures of the air and water, direction and force of the wind, dates of rain, frosts, fogs, and other marked features of the weather; also a complete record of the kind and amount of work done daily, the condition of the data, &c.

When work on the river was impossible, the boat party were engaged in the shop, fabricating such articles as were required on the work, making repairs on the apparatus, &c.

The launch was kept in complete repair and improved considerably by the party. The stability of the launch and its excellent running power were fully established by the excellent condition it was in at the close of the work, after having been used seasonably for over a year. For work of this character launches of this type have no equal. The results of the daily discharge observations are given so fully in the tables of calculations and curve charts appended to this report, that a discussion of them here is unnecessary.

The work was inspected by you in person on January 25 and 26, 1882, and again on November 23, 1882. The meter work in actual operation on the river, the plant, and all the auxiliary apparatus were inspected on November 23, 1882, by General H. G. Wright, Chief of Engineers, United States Army, General C. B. Comstock, president Mississippi River Commission, Maj. Amos Stickney, Maj. Chas. R. Suter, United States Army, Maj. B. M. Harrod, Prof. Henry Mitchell, and Judge R. C. Taylor.

The work of the party at Red River Landing closed on November 26, 1882, orders having been received on that date to close the work and proceed with party to the Point Carré crevasse. The note-books and field supplies no longer required were transferred to the steamer Mississippi on November 26, 1882. All the calculations of discharge work for both the Mississippi and Atchafalaya; charts showing deduced curves of velocity, discharge, and area; a map showing relative position of cross-sections; a map of transverse velocity curves taken in bend; a map showing contour of river bed at all of the sections, are all appended to this report.

Before closing this part of my report I desire to acknowledge the valuable assistance rendered by my assistant, Mr. John C. Cammack; the cheerful, prompt, and accurate manner in which he performed his arduous duties during the most trying times of the great flood, and at all times while with my party, is worthy of praise which words are but meager to express.

The changes and action of the river in the vicinity of Red River Landing, and some facts regarding the flood height of 1882 and previous years, and other personal observations made during the year, will doubtless be of interest in connection with the above report.

The weather during the year was variable. It rained on 143 days; fogs prevailed periodically from January 5 to June 13. The minimum temperature of the air for the year was 35° (on January 30). The maximum temperature of the air was 98° (on August 17). The minimum temperature of the water was 44° (on January 30); the maximum temperature of the water was 84° (on June 30, July 1 to 6, August 17 to 31).

The temperatures of the water were taken at points of the section from bank to bank, and as near mid-depth as possible. These temperatures were valuable during the flood. The arrival of flood water from the Texas region was shown by the temperature of the Atchafalaya during the flood. On the day preceding the arrival on the Atchafalaya of the flood water referred to, the temperatures of the Mississippi and Atchafalaya were the same, which might be expected, as the Mississippi was discharging a portion of its waters into the Atchafalaya via Old River. On the day of the arrival of additional flood water on the Atchafalaya the temperature of the Atchafalaya rose several degrees, thus indicating the source of the additional volume of water present in the river.

The river was rising on December 3, 1881, the day of the arrival of party at Red River Landing, and continued rising until December 6, when it began falling. It fell until December 27, on which date it began rising, and continued until March 27, 1882, on which date it reached its maximum stage not only for the year, but the highest ever known. The gauge at 12.30 o'clock on that day read 48.53 feet above the low-water mark of 1872, which is the zero of the gauge. This zero is 2.4 feet above sea level. This remarkable stage of the river was 1.53 feet above high-water mark of 1874, and 2.35 feet above high-water mark of 1867. The high-water marks of the years 1867,

1874, and 1882 are 46.27, 47.05, and 43.53 respectively. It will be seen from these figures that the flood intervals from 1867 to 1882 are 7 and 8 years, respectively; the rise of the flood surface for these periods, 0.78 and 1.48 feet.

The general character of the Old River water-way, and the effects of the periodic flow inward and outward, will doubtless be of interest here. The period of change of flow is generally 3 days. The first sign manifest is a marked checking of the current in Old River, and a more marked degree of clearness in the water. These changes are very easily noticed on the first day. On the second day the current nearly ceases. On the third, the change of flow is found to have taken place; the current will be found as swift as usual, and the water will have the usual mud color. The direction of flow is, of course, governed by the relative stages of the Mississippi and the Atchafalaya, the Red River, of course, governing the Atchafalaya. The current is swifter when the flow is outward. The general effects of an inward flow are more injurious to the Old River water-way than an outward flow is, and for this reason, that when the flow is inward, the current is greatly diminished and the percentage of sediment in the water is visibly greater.

These two ruling elements, which under the circumstances act in unison, cause a more rapid fill, while the checking of the current diminishes the scouring that characterizes an outward flow.

Turnbull Island is also an obstacle to the flow through Old River, and at flood stages it forms the basis of marked fills all the way around the island. It is in fact the nucleus of all the sand-bars in the vicinity. The effects of an outward flow are more beneficial to navigation than an inward flow, though at certain points, which will be described presently, it has a damaging effect. It is in general more beneficial, as the current is more rapid, and the percentage of sediment in the water is much smaller, as Red River water has, I think, a smaller percentage of sediment than Mississippi water. The deep-red color of the former is due to matter held in solution rather than that held in suspension. These are the things which make an outward flow favorable to navigation. The shoal places in Old River are three in number, and are situated as follows: At Barbre's crossing, in vicinity of Ash Cabin Bend, and at the Mississippi mouth of Old River. The causes that have produced this shoaling I consider to have been as follows: At the Barbre crossing the shoaling is due to the checking of the current of Red River as it sweeps around the bend where it enters Old River. In turning this bend, it loses a great part of its velocity, which it cannot possibly recover until it gets some distance beyond Barbre's crossing. The effect of this is the piling up of the sediment which the river has pushed to this point, and which the loss of velocity prevents from being carried farther. The deposit from the water itself is also augmented, owing to the slackening up of the current. The flow either way from Old River causes a fill at this crossing, and for this reason, that when the flow is outward the current is checked in the Red River bend as before; when the flow is inward the current is checked near the turn at the Ash Cabin; and when it gets to Barbre's crossing, it encounters Red River, which is moving nearly at right angles to it. So it is seen both streams meet at this point in a somewhat exhausted condition. Their forces are so nearly equal that equilibrium is nearly produced, which action, as is obvious, causes the fill or shoaling referred to.

The equalization of the forces of the water at this point is verified by the well-defined color line that is always seen at this point. The shoaling near the Ash Cabin is due to the decrease of velocity caused by Old River encountering the bends it meets before it reaches this point. The fill is greater at this point when the current is inward, as the arm of the bend with reference to an inward flow is more abrupt. The shoaling at the mouth is due wholly to an inward flow. The large volume of Mississippi water that sweeps around the turn at Carr's Point carries with it a vast volume of sediment, which it leaves at the shoal section referred to for want of sufficient velocity to carry it farther. The loss of velocity in this case is much greater than in any of the others mentioned; the fill is in consequence much greater. The steamboat channel at entrance of Old River attests the great force and action of the water as it sweeps around this point. This channel, just before you enter Old River, is nearly at right angles to the Old River Channel. On both sides of it, immense sand reefs exist. This channel resembles a canal more than it does a natural passage.

This channel is due to the action of the maximum thread of the current, which sweeps around the point at the mouth with a tremendous force and passes the mouth without entering. It is this portion of the current that produces the channel at the entrance of Old River. This point of Old River is benefited materially by an outward flow, as the volume of water coming out scours more rapidly. The outward volume pushes the Mississippi water as it rounds Carr's Point farther toward the left bank; i. e., it has that tendency. This action causes the bar at the point of Old River (the nucleus of which is Carr's Point) to make rapidly down stream. Its make is due wholly to the meeting of the two rivers at this point when the flow is outward. By meeting they lose a large percentage of their velocity, and thus increase the sedimentary deposit at this point. This bar made about 300 feet down stream last year.

Should the flow continue outward from Old River without changing, and low stages of the river predominate for any great length of time, this bar would eventually work away down stream and connect with the main bank of the Mississippi below Turnbull's, and thus close up Old River at low water entirely. This section of the country, and more especially that within a radius of 10 miles from the center of Turnbull's land, is a very interesting one, and is a wide field for investigation at the present time, as it no doubt contains the unknown quantities that make the problem of the change of the Mississippi channel at the present time a vague uncertainty.

Respectfully submitted.

JOHN EWENS,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

Discharge observations, Red River Landing, La.

In this tabulation the gauge readings, water area, maximum depth, width, mean velocity, discharge, direction and force of wind, temperature of air and water, and much were copied from note-books Nos. 831-835, 839-844, 854.

Rise or fall between any two days was obtained by taking the difference between the gauge readings on those days.

Scour or fill between any two days was obtained thus: Take the difference between the water area on the first day, counted for rise or fall for the time considered, and the water area of the second day. If the area of the second day is the larger, the difference is scour; and if the smaller, this difference is fill.

Datum was taken at a gauge reading of 48.5 feet, and surface width of 3,918 feet, on March 27.

Datum area is the water area of March 27 and = 234,480 square feet.

Subsequent datum areas were obtained by successively adding and subtracting the scours and fills.

Datum areas between December 14 and March 27, 1882, were obtained by working backward from March 27.

Mean depth was obtained by dividing the water area by the water width.

Mean datum depth was obtained by dividing datum area by datum width.

MISSISSIPPI RIVER.

Discharge observations at Red River Landing, La.

Date.	Gauge.		Dimensions of cross section of discharge.							Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature.		Method.
	Reading.	Rise or fall in the preceding 24 hours.	Area.		Depth.		Width.	Mean or full.	Air.				Water.		
			Water.	Below datum.	Mean.	Mean station.									
1881	Feet.	Feet.	Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Feet.	Sq. feet.	Feet.					
Dec 14	30.20	-0.61	140,000	210,147	46.62	66.91	6,747		8,417						
15	29.66	-0.67	147,120	201,010	50.10	60.2	5,790	+ 8,772	4,870						D. P.
16	28.70	-0.94	144,040	220,147	50.65	60.10	5,728	- 1,772	6,207						D. P.
17	27.65	-0.94	141,120	210,447	50.6	60.70	5,704	- 1,000	4,967						D. P.
18	26.91	-0.90													
19	24.17	-0.80	123,000	217,021	55.61	63.1	5,801	- 508	8,001						D. P.
20	23.55	-0.40	110,520	215,171	12.47	65.12	5,001	- 1,048	4,001						D. P.
21	23.15	-0.20													
22	23.05	-0.16	125,700	216,000	34.02	65.10	7,007	+ 110	4,148	591,874	XI				D.
23	23.61	-0.04													
24	25.11	+0.50	141,040	210,040	37.00	61.06	1,774	+ 8,200	4,614						D. P.
25	26.07	+0.50	140,243	220,241	30.20	60.21	3,791	+ 808	4,909	640,837	V				D. P.
26	27.61	+0.94								630,104	III				D. P.
27	28.80	+1.00													
28	29.40	+1.10	160,000	223,014	42.67	67.15	3,740	+ 8,070	4,610	780,800	XII				D. P.
29	30.06	+1.02													
30	30.06	+1.02	100,720	220,000	43.78	64.16	3,757	- 8,004	4,601	740,080	XII				D. P.
31	30.06	+1.02													
1882															
Jan 1	30.10	+1.10													
2	30.04	+0.06													
3	31.70	+1.75													
4	32.10	+0.40													
5	32.09	+0.30													
6	33.32	+0.34													
7	33.50	+0.48													
8	34.17	+0.67													
9	34.58	+0.41													
10	34.78	+0.20													
11	35.11	+0.33													
12	35.28	+0.17													
13	35.70	+0.22													
14	35.00	+0.19													
15	35.67	+0.16													

M = Mean.
H = Red Apple.
D. P. = Double Bottom.

M - Meter.
B - Red Apple.
D. P. - Double Beam.

	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679
--	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

Mississippi River. — Discharge observations at Red River Landing, La. — Continued.

Date.	Gauge.		Dimensions of cross-section of discharge.										Width.	Scour or fill.	Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature, Fahr.		Method.	Remarks.
	Read- ing.	Rise or fall in the preceding 24 hours.	Area.			Depth.												Air.	Water.		
			Water.	Below datum.	Mean datum.	Mean datum.	Max. min.														
1882.	Feet.	Feet.	Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Feet.	Sq.	L. v. sec.	L. v. sec.	L. v. sec.	°	°	D. F.						
Mar. 9	46.52	+0.26	230,080	237,829	58.78	60.70	75.3	3,914	-				80	63	D. F.						
10	46.78	+0.26	230,160	236,891	58.80	60.46	76.6	3,914	-				57	62	D. F.						
11	46.87	+0.09	231,040	237,419	59.18	60.00	77.2	3,904	+				63	63	D. F.						
12	47.03	+0.16																			
13	47.24	+0.21	233,240	238,175	59.74	60.79	77.5	3,904	+				67	61	D. F.						
14	47.30	+0.06	233,280	237,981	59.75	60.74	78.5	3,904	-				72	63	D. F.						
15	47.38	+0.08	233,000	237,988	59.02	60.74	78.6	3,916	+				75	60	D. F.						
16	47.50	+0.12	237,000	241,518	60.64	61.04	79.0	3,916	+				76	57	D. F.						
17	47.56	+0.06	237,760	241,443	60.68	61.62	79.0	3,916	-				78	57	D. F.						
18	47.63	+0.07	234,060	237,489	59.74	60.61	79.0	3,916	- 8,954				74	57	D. F.						
19	47.70	+0.07																			
20	47.77	+0.07	234,560	237,420	59.67	60.60	79.0	3,916	- 69				74	63	D. F.						
21	47.98	+0.21																			
22	48.02	+0.04																			
23	48.12	+0.10	231,760	233,249	59.15	59.53	77.0	3,916	- 4,171	0.087	1,410,763	V	66	70	D. F.						
24	48.25	+0.13	234,320	235,300	59.81	60.05	78.0	3,918	+ 2,051	0.290	1,478,808	VI	68	70	D. F.						
25	48.30	+0.05	231,040	231,834	58.97	59.17	77.5	3,916	- 3,476	0.200	1,409,116	XII	65	67	D. F.						
26	48.46	+0.16																			
27	48.50	+0.04	234,480	234,480	59.85	60.85	79.0	3,918	+ 2,650	0.222	1,458,902	V	74	76	D. F.						
28	48.43	0.07	237,520	237,794	60.92	60.69	80.5	3,899	+ 3,314	0.459	1,638,959	VII	62	64	D. F.						
29	48.39	-0.04	237,360	237,700	60.88	60.69	80.2	3,899	- 4	0.484	1,589,145	VI	66	63	D. F.						
30	48.36	-0.03	234,160	234,707	60.66	60.77	80.0	3,899	- 3,063	0.437	1,504,922	VI	74	60	D. F.						
31	48.32	-0.04	235,360	236,063	60.36	60.07	80.5	3,899	+ 1,856	0.778	1,585,310	VII	74	66	D. F.						
Apr. 1	48.25	-0.07																			
2	48.23	-0.02																			
3	48.09	-0.14	236,240	237,849	60.59	60.70	78.0	3,899	+ 1,777	0.449	1,528,198	0	74	66	D. F.						
4	47.95	-0.14	235,440	237,586	60.58	60.64	77.0	3,899	- 254	0.063	1,437,409	X	67	66	D. F.						
5	47.83	-0.12	232,680	236,294	59.63	60.31	77.0	3,898	- 1,262	0.061	1,416,842	X	69	64	D. F.						
6	47.70	-0.13	234,400	237,521	60.12	60.62	77.5	3,899	+ 1,227	0.336	1,485,810	X	70	64	D. F.						
7	47.66	-0.14	233,440	237,107	59.87	60.52	78.0	3,899	- 414	0.260	1,466,459	X	70	66	D. F.						
8	47.80	-0.17	236,240	240,570	60.59	61.40	78.5	3,899	+ 3,469	0.878	1,412,243	X	72	67	D. F.						
9	47.23	-0.16																			
10	47.62	-0.20	977,190	942,860	61.18	61.68	79.5	3,876	+ 0,000	0.000	0										

May	33	45.77	-0.04	239,000	258,752	63.94	66.04	78.7	3,871	-	261	5.515	1,805,451	X	2	73	66	D.F.
	34	45.69	-0.08	247,520	268,752	63.94	66.04	78.7	3,871	-	261	5.515	1,805,451	X	2	71	66	D.F.
	35	45.61	-0.08	251,800	262,940	64.93	67.11	79.5	3,871	+4,188	+	5.206	1,808,145	X	2	70	67	D.F.
	36	45.52	-0.09	250,160	262,398	64.62	66.97	78.6	3,871	-	542	5.266	1,817,874	XI	2	72	67	D.F.
	37	45.85	-0.17	240,000	258,509	63.55	65.98	79.4	3,871	-3,889	-	5.353	1,816,928	XI	30-1	70	68	D.F.
	38	45.28	-0.07	245,440	258,568	63.40	65.99	79.3	3,871	+	59	5.356	1,814,506	X	1	70	68	D.F.
	39	45.12	-0.16	244,560	258,153	63.18	65.89	78.7	3,871	-	415	5.171	1,804,554	VII	30-5	75	67	D.F.
	40	44.85	-0.12															
	1	44.71	-0.15															
	2	44.59	-0.14	239,600	254,816	61.90	64.91	79.0	3,871	-3,837	-	5.203	1,246,719	XII	2	67	67	M.&D.F.
	3	44.34	-0.12	239,200	254,381	61.79	64.83	79.0	3,871	+	65	5.121	1,235,013	XII	1	68	69	D.F.
	4	44.24	-0.25	237,600	253,749	61.88	64.76	79.0	3,871	-	632	5.082	1,207,592	II	30-2	73	69	D.F.
	5	44.09	-0.10	238,720	255,258	61.67	65.15	77.0	3,871	+	1,507	5.402	1,289,490	II	1	76	65	D.F.
	6	44.09	-0.15	238,400	255,517	61.59	65.22	77.2	3,871	+	261	5.161	1,280,309	XI	2	74	67	D.F.
	7	43.95	-0.14	238,160	255,819	61.52	65.29	78.0	3,871	+	302	5.217	1,242,592	VII	5	76	65	D.F.
	8	43.77	-0.18															
	9	43.88	-0.11	238,240	256,170	61.54	65.38	78.0	3,871	+	351	5.045	1,201,889	XII	6	74	66	D.F.
	10	43.64	-0.24															
	11	43.59	-0.05	237,360	256,413	61.32	65.44	77.5	3,871	+	248	4.903	1,163,865	XII	4	73	65	D.F.
	12	43.28	-0.31	236,480	256,718	62.66	65.52	76.3	3,774	+	305	4.843	1,145,333	IV	3	69	67	D.F.
	13	43.07	-0.21	235,600	256,630	62.56	65.50	76.8	3,766	-	88	5.312	1,251,457	IV	2	68	67	M.
	14	42.92	-0.15	234,240	255,835	62.20	65.30	76.3	3,766	-	795	4.989	1,163,882	IV	5	66	67	M.
	15	42.78	-0.14															
	16	42.64	-0.14	236,480	259,129	62.84	66.14	77.5	3,763	+	294	5.157	1,219,465	VI	2	65	66	M.
	17	42.49	-0.15	235,760	258,973	62.65	66.10	78.0	3,763	-	156	5.008	1,180,768	VII	1	74	67	M.
	18	42.37	-0.12	235,600	259,284	62.64	66.17	77.0	3,761	+	291	5.059	1,191,881	VII	1	66	69	M.
	19	42.25	-0.12	236,560	260,675	62.90	66.53	76.5	3,761	+	1,411	5.117	1,210,493	XI	2	73	65	M.
	20	42.10	-0.15	235,480	260,159	62.59	66.40	77.0	3,762	-	516	5.114	1,204,132	XI	5	72	65	M.
	21	41.91	-0.19	234,240	259,634	62.26	66.27	76.7	3,762	-	525	5.018	1,175,341	XI	4	70	65	M.
	22	41.86	-0.01															
	23	41.77	-0.06	233,040	258,622	61.95	66.01	75.7	3,762	-1,012	-	4.778	1,113,540	VI	3	66	65	D.F.
	24	41.61	-0.09	232,160	258,081	61.73	65.87	75.4	3,761	-	541	5.014	1,164,070	VII	30-4	67	68	M.
	25	41.50	-0.16	231,600	258,123	61.61	65.88	75.0	3,759	+	42	4.950	1,146,364	XI	3	71	65	M.
	26	41.43	-0.11	231,280	258,216	61.53	65.91	75.2	3,759	+	93	4.939	1,142,104	VII	3	75	66	M.
	27	41.38	-0.07	229,120	256,319	60.95	65.42	75.3	3,759	-1,897	-	4.984	1,142,017	XI	3	77	67	M.
	28	41.36	-0.05	230,800	258,187	61.42	65.90	75.0	3,758	+	1,868	5.004	1,155,019	XII	3	71	69	M.
	29	41.34	-0.02															
	30	41.31	-0.02	229,360	256,897	61.02	65.57	75.2	3,759	-1,290	-	4.937	1,132,356	VIII	1	76	68	M.
June	31	41.42	-0.03															
	1	41.42	-0.11	231,360	258,596	61.55	66.00	75.2	3,759	+	699	4.918	1,137,809	XI	5	69	67	M.
	2	41.44	-0.02	232,240	259,401	61.78	66.21	76.0	3,759	+	805	4.900	1,138,053	VI	4	75	68	M.
	3	41.45	-0.01	233,760	260,883	62.19	66.59	76.1	3,759	+	1,482	4.998	1,168,341	X	30-2	75	69	M.
	4	41.41	-0.04	233,120	260,393	62.02	66.46	75.5	3,759	-	490	4.827	1,125,364	I	30-2	79	71	M.
	5	41.40	-0.01															
		41.42	-0.02	232,240	259,475	61.68	66.23	76.0	3,765	-	918	4.725	1,097,303	VIII	30-4	75	69	M.

Barometer observations at Fort Mifflin Landing, Pa. Continued

	Time	Barometer reading	Temperature of air	Direction and force of wind	Remarks	Method	Temperature of air, Fahr.	Air. Water.
1	41.45	29.99	61.4	61.4				
2	41.45	29.99	61.4	61.4				
3	41.45	29.99	61.4	61.4				
4	41.45	29.99	61.4	61.4				
5	41.45	29.99	61.4	61.4				
6	41.45	29.99	61.4	61.4				
7	41.45	29.99	61.4	61.4				
8	41.45	29.99	61.4	61.4				
9	41.45	29.99	61.4	61.4				
10	41.45	29.99	61.4	61.4				
11	41.45	29.99	61.4	61.4				
12	41.45	29.99	61.4	61.4				
13	41.45	29.99	61.4	61.4				
14	41.45	29.99	61.4	61.4				
15	41.45	29.99	61.4	61.4				
16	41.45	29.99	61.4	61.4				
17	41.45	29.99	61.4	61.4				
18	41.45	29.99	61.4	61.4				
19	41.45	29.99	61.4	61.4				
20	41.45	29.99	61.4	61.4				
21	41.45	29.99	61.4	61.4				
22	41.45	29.99	61.4	61.4				
23	41.45	29.99	61.4	61.4				
24	41.45	29.99	61.4	61.4				
25	41.45	29.99	61.4	61.4				
26	41.45	29.99	61.4	61.4				
27	41.45	29.99	61.4	61.4				
28	41.45	29.99	61.4	61.4				
29	41.45	29.99	61.4	61.4				
30	41.45	29.99	61.4	61.4				
31	41.45	29.99	61.4	61.4				
32	41.45	29.99	61.4	61.4				
33	41.45	29.99	61.4	61.4				
34	41.45	29.99	61.4	61.4				
35	41.45	29.99	61.4	61.4				
36	41.45	29.99	61.4	61.4				
37	41.45	29.99	61.4	61.4				
38	41.45	29.99	61.4	61.4				
39	41.45	29.99	61.4	61.4				
40	41.45	29.99	61.4	61.4				
41	41.45	29.99	61.4	61.4				
42	41.45	29.99	61.4	61.4				
43	41.45	29.99	61.4	61.4				
44	41.45	29.99	61.4	61.4				
45	41.45	29.99	61.4	61.4				
46	41.45	29.99	61.4	61.4				
47	41.45	29.99	61.4	61.4				
48	41.45	29.99	61.4	61.4				
49	41.45	29.99	61.4	61.4				
50	41.45	29.99	61.4	61.4				
51	41.45	29.99	61.4	61.4				
52	41.45	29.99	61.4	61.4				
53	41.45	29.99	61.4	61.4				
54	41.45	29.99	61.4	61.4				
55	41.45	29.99	61.4	61.4				
56	41.45	29.99	61.4	61.4				
57	41.45	29.99	61.4	61.4				
58	41.45	29.99	61.4	61.4				
59	41.45	29.99	61.4	61.4				
60	41.45	29.99	61.4	61.4				
61	41.45	29.99	61.4	61.4				
62	41.45	29.99	61.4	61.4				
63	41.45	29.99	61.4	61.4				
64	41.45	29.99	61.4	61.4				
65	41.45	29.99	61.4	61.4				
66	41.45	29.99	61.4	61.4				
67	41.45	29.99	61.4	61.4				
68	41.45	29.99	61.4	61.4				
69	41.45	29.99	61.4	61.4				
70	41.45	29.99	61.4	61.4				
71	41.45	29.99	61.4	61.4				
72	41.45	29.99	61.4	61.4				
73	41.45	29.99	61.4	61.4				
74	41.45	29.99	61.4	61.4				
75	41.45	29.99	61.4	61.4				
76	41.45	29.99	61.4	61.4				
77	41.45	29.99	61.4	61.4				
78	41.45	29.99	61.4	61.4				
79	41.45	29.99	61.4	61.4				
80	41.45	29.99	61.4	61.4				
81	41.45	29.99	61.4	61.4				
82	41.45	29.99	61.4	61.4				
83	41.45	29.99	61.4	61.4				
84	41.45	29.99	61.4	61.4				
85	41.45	29.99	61.4	61.4				
86	41.45	29.99	61.4	61.4				
87	41.45	29.99	61.4	61.4				
88	41.45	29.99	61.4	61.4				
89	41.45	29.99	61.4	61.4				
90	41.45	29.99	61.4	61.4				
91	41.45	29.99	61.4	61.4				
92	41.45	29.99	61.4	61.4				
93	41.45	29.99	61.4	61.4				
94	41.45	29.99	61.4	61.4				
95	41.45	29.99	61.4	61.4				
96	41.45	29.99	61.4	61.4				
97	41.45	29.99	61.4	61.4				
98	41.45	29.99	61.4	61.4				
99	41.45	29.99	61.4	61.4				
100	41.45	29.99	61.4	61.4				

14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69																															

MISSISSIPPI RIVER.—Discharge observations at Red River Landing, La.—Continued.

Date.	Gauge.	Dimensions of cross section of discharge.							Scour or fill.	Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature, Fahr.		Method.	Remarks.
		Area.			Depth.		Width.	Mean datum.					Max. min.			
		Water.	Below datum.	Sq. feet.	Feet.	Feet.								Feet.		
1882.		Feet.	Sq. feet.	Sq. feet.	Feet.	Feet.	Feet.	Feet.	Sq. feet.	Feet.	Cu. ft.		°	°		
Sept.																
2		16.35	140, 273	253, 585	38.08	64.72	47.5		—	787	8, 684	VI	83	80	M.	
3		17.73														
4		17.18	136, 310	253, 909	37.08	64.81	45.9	+	+		8, 678			84	M.	
5		16.17	134, 862	255, 675	34.55	65.26	40.0	+	+		8, 676			84	M.	
6		16.11														
7		15.56	129, 173	252, 726	35.22	64.50	45.0	—	—		8, 666			83	M.	
8		15.32	128, 207	252, 643	34.95	64.48	44.6	—	—		8, 668			80	M.	
9		15.00														
10		14.64														
11		14.50	123, 973	251, 409	33.90	64.17	43.5	—	—		8, 657			81	M.	
12		14.23	122, 186	250, 609	33.42	63.96	43.0	—	—		8, 656			80	M.	
13		14.04	121, 761	250, 879	33.30	64.03	42.0	+	+		8, 657			81	M.	
14		13.98														
15		13.98	122, 029	251, 368	33.37	64.16	42.7	+	487		8, 657	X	83	79	M.	
16		14.00	121, 112	250, 376	33.13	63.90	43.0	—	990		8, 657	VII	80	79	M.	
17		13.92														
18		13.83	118, 949	249, 834	32.08	63.77	42.6	—	543		8, 653	XII	84	80	M.	
19		13.71	120, 274	250, 597	32.99	63.96	41.0	+	708		8, 649	X	87	80	M.	
20		13.51	119, 587	250, 640	32.76	63.97	42.3	+	43		8, 651	X	85	80	M.	
21		13.34														
22		11.02														
23		12.70	114, 874	248, 882	31.51	63.52	42.0	—	1, 758		8, 646	VII	86	78	M.	
24		12.62														
25		12.62	115, 206	248, 809	31.63	63.52	42.0	—	13		8, 645	VIII	77	77	M.	
26		13.20	117, 335	249, 521	32.18	63.69	42.0	+	653		8, 646	VII	78	76	M.	
27		13.70														
28		14.11	122, 109	251, 032	33.40	64.07	43.0	+	1, 511		8, 658	XII	78	76	M.	
29		14.38														
30		14.41	122, 236	250, 061	32.40	63.81	43.8	—	1, 081		8, 650	XI	79	77	M.	
Oct.																
1		14.23														
2		13.90														
3		13.43	119, 637	250, 884	32.74	64.03	43.8	+	883		8, 651	VII	80	78	M.	
4		12.88	117, 550	250, 978	32.21	64.06	42.0	+	61		8, 650	VIII	79	78	M.	

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Discharge observations, Atchafalaya River.

Measurements for the discharge of the Atchafalaya River were made in the following manner:

Sections were obtained by plotting the sections on cross-section paper, locating the position of velocity observations, then dividing the section into partial areas, counting the small squares in each area; thus giving to each velocity an area, and two or more velocities were taken very close together, in which case an area was given to the mean of this group of velocities.

The sum of these partial areas being the total area of section.

The discharge for partial areas was obtained by multiplying the area by its velocity.

The total discharge being the sum of the partial discharges thus obtained.

The mean velocity was obtained by dividing the total discharge by the total area.

The mean depth is obtained by dividing the area by the water width.

The maximum depth is the deepest actual sounding taken.

Scour or fill is the difference in sectional area obtained by actual area difference compared with difference due to change of gauge; 51 feet was taken as datum gauge reading, being .13 foot above highest gauge-reading when observations were made. The difference in area due to this difference in gauge was added to the water area of March 24; the area then obtained was the datum area.

The other datum is obtained by successively adding or subtracting the difference in area due to change of gauge.

Mean datum depth was obtained by dividing the datum area by the datum width.

Owing to the records of the gauge being very unsatisfactory, they were discarded and a new gauge was interpolated from the Barbres Lake gauge, about 1,500 feet above the discharge point from this gauge, and readings were taken at the same time.

The gauge is at the same section. A curve was interpolated for 4 p.m. readings.

The difference between the readings at section and Barbres gauge was applied to readings on Barbres gauge.

The result was made in the field; after that date the readings were made in the office.

A discharge curve was computed; the line was recomputed; a

all of the observations farthest from the datum were in error, others checking closely.

A. H. W.

Discharge observations at Atkasutaya River—Continued.

[illegible]

Date	Place	Description	Remarks
1850	New York	Born	
1851	New York	Attended school	
1852	New York	Completed school	
1853	New York	Entered service	
1854	New York	Promoted	
1855	New York	Discharged	
1856	New York	Resided at home	
1857	New York	Died	

[illegible]

1911-12-13-14-15-16-17-18-19-20-21-22-23-24-25-26-27-28-29-30-31-32-33-34-35-36-37-38-39-40-41-42-43-44-45-46-47-48-49-50-51-52-53-54-55-56-57-58-59-60-61-62-63-64-65-66-67-68-69-70-71-72-73-74-75-76-77-78-79-80-81-82-83-84-85-86-87-88-89-90-91-92-93-94-95-96-97-98-99-100-101-102-103-104-105-106-107-108-109-110-111-112-113-114-115-116-117-118-119-120-121-122-123-124-125-126-127-128-129-130-131-132-133-134-135-136-137-138-139-140-141-142-143-144-145-146-147-148-149-150-151-152-153-154-155-156-157-158-159-160-161-162-163-164-165-166-167-168-169-170-171-172-173-174-175-176-177-178-179-180-181-182-183-184-185-186-187-188-189-190-191-192-193-194-195-196-197-198-199-200-201-202-203-204-205-206-207-208-209-210-211-212-213-214-215-216-217-218-219-220-221-222-223-224-225-226-227-228-229-230-231-232-233-234-235-236-237-238-239-240-241-242-243-244-245-246-247-248-249-250-251-252-253-254-255-256-257-258-259-260-261-262-263-264-265-266-267-268-269-270-271-272-273-274-275-276-277-278-279-280-281-282-283-284-285-286-287-288-289-290-291-292-293-294-295-296-297-298-299-300-301-302-303-304-305-306-307-308-309-310-311-312-313-314-315-316-317-318-319-320-321-322-323-324-325-326-327-328-329-330-331-332-333-334-335-336-337-338-339-340-341-342-343-344-345-346-347-348-349-350-351-352-353-354-355-356-357-358-359-360-361-362-363-364-365-366-367-368-369-370-371-372-373-374-375-376-377-378-379-380-381-382-383-384-385-386-387-388-389-390-391-392-393-394-395-396-397-398-399-400-401-402-403-404-405-406-407-408-409-410-411-412-413-414-415-416-417-418-419-420-421-422-423-424-425-426-427-428-429-430-431-432-433-434-435-436-437-438-439-440-441-442-443-444-445-446-447-448-449-450-451-452-453-454-455-456-457-458-459-460-461-462-463-464-465-466-467-468-469-470-471-472-473-474-475-476-477-478-479-480-481-482-483-484-485-486-487-488-489-490-491-492-493-494-495-496-497-498-499-500-501-502-503-504-505-506-507-508-509-510-511-512-513-514-515-516-517-518-519-520-521-522-523-524-525-526-527-528-529-530-531-532-533-534-535-536-537-538-539-540-541-542-543-544-545-546-547-548-549-550-551-552-553-554-555-556-557-558-559-560-561-562-563-564-565-566-567-568-569-570-571-572-573-574-575-576-577-578-579-580-581-582-583-584-585-586-587-588-589-590-591-592-593-594-595-596-597-598-599-600-601-602-603-604-605-606-607-608-609-610-611-612-613-614-615-616-617-618-619-620-621-622-623-624-625-626-627-628-629-630-631-632-633-634-635-636-637-638-639-640-641-642-643-644-645-646-647-648-649-650-651-652-653-654-655-656-657-658-659-660-661-662-663-664-665-666-667-668-669-670-671-672-673-674-675-676-677-678-679-680-681-682-683-684-685-686-687-688-689-690-691-692-693-694-695-696-697-698-699-700-701-702-703-704-705-706-707-708-709-710-711-712-713-714-715-716-717-718-719-720-721-722-723-724-725-726-727-728-729-730-731-732-733-734-735-736-737-738-739-740-741-742-743-744-745-746-747-748-749-750-751-752-753-754-755-756-757-758-759-760-761-762-763-764-765-766-767-768-769-770-771-772-773-774-775-776-777-778-779-780-781-782-783-784-785-786-787-788-789-790-791-792-793-794-795-796-797-798-799-800-801-802-803-804-805-806-807-808-809-810-811-812-813-814-815-816-817-818-819-820-821-822-823-824-825-826-827-828-829-830-831-832-833-834-835-836-837-838-839-840-841-842-843-844-845-846-847-848-849-850-851-852-853-854-855-856-857-858-859-860-861-862-863-864-865-866-867-868-869-870-871-872-873-874-875-876-877-878-879-880-881-882-883-884-885-886-887-888-889-890-891-892-893-894-895-896-897-898-899-900-901-902-903-904-905-906-907-908-909-910-911-912-913-914-915-916-917-918-919-920-921-922-923-924-925-926-927-928-929-930-931-932-933-934-935-936-937-938-939-940-941-942-943-944-945-946-947-948-949-950-951-952-953-954-955-956-957-958-959-960-961-962-963-964-965-966-967-968-969-970-971-972-973-974-975-976-977-978-979-980-981-982-983-984-985-986-987-988-989-990-991-992-993-994-995-996-997-998-999-1000-1001-1002-1003-1004-1005-1006-1007-1008-1009-1010-1011-1012-1013-1014-1015-1016-1017-1018-1019-1020-1021-1022-1023-1024-1025-1026-1027-1028-1029-1030-1031-1032-1033-1034-1035-1036-1037-1038-1039-1040-1041-1042-1043-1044-

Date	Time	Air		Height	Pressure	W. ind.	Range or dir.	Mean velocity per second.	Discharge per second.	Direction and force of wind.	Temperature		Method	
		Surf.	Atmos.								Air	Water		
1911	644	64.4	64.4	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	645	64.5	64.5	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	646	64.6	64.6	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	647	64.7	64.7	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	648	64.8	64.8	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	649	64.9	64.9	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	650	65.0	65.0	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	651	65.1	65.1	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	652	65.2	65.2	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	653	65.3	65.3	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	654	65.4	65.4	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	655	65.5	65.5	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	656	65.6	65.6	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	657	65.7	65.7	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	658	65.8	65.8	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	659	65.9	65.9	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	660	66.0	66.0	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	661	66.1	66.1	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	662	66.2	66.2	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	663	66.3	66.3	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	664	66.4	66.4	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	665	66.5	66.5	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	666	66.6	66.6	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	667	66.7	66.7	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	668	66.8	66.8	17.8	30.1	47.1	551.5	— 300	2,808	19,800.0	WS	30	30	M
1911	669	66.9	66.9	17.8	30.1	47.1	551.5	— 300	2,808</					



2660 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

6.—AT WINONA. MINN., JOHN EWING, ASSISTANT IN CHARGE.

(NOTE.—Reverts in Report of Commission for 1882, page 127.)

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., June 1, 1881.

SIR: I have the honor to inform you that in accordance with your instructions received in September, 1880, I proceeded to Wabasha, Minn., where I completed organization of party and made immediate preparations to carry out your instructions.

After a careful examination of the topography of the country in the vicinity of Wabasha, I found that a formidable outlet known as "Beef Slough," situated at a distance back from the left bank, would make the locality a very undesirable one for the work of gauging, which first of all for its success requires the absence of obstructions. Surveys and sectional soundings of the river at this point were sent to Saint Louis for examination. In a very brief time afterward orders were received for the party to remove to Winona, 47 miles below. Examinations similar to those made at Wabasha were made at Winona, and at the town of Homer, about 4 miles below. A large number of sections were sounded at both of the places mentioned, and a section for discharge measurement selected at both. The Winona section was situated about 1½ miles below the Chicago and Northwestern Railroad bridge. This section was selected on account of the banks being higher than elsewhere in the vicinity and owing to the absence of eddies and other disturbing elements that detract from the accuracy of discharge work. The Winona section, though the best to be found in the vicinity, presented many disadvantages which no doubt have their influence on the work of this character, where refinement is so desirable. The most prominent drawback was the presence of large numbers of immense rafts which skirted the right bank five miles above and below the discharge section, extending for some distance out in the river. The effect of such obstructions on the velocity and character of the flow is obvious that a description here of their effect is unnecessary. In consequence of the constant presence of these rafts I thought for a time that the Homer section might be preferable, but found that at high water the discharge would be entirely cut off at a small outlet fed by the river above this section. So, in view of these facts Winona was finally decided on.

The success of the advance of supplies, work with the electric plant designed for the purpose, and the measurement until the spring of 1881. Rod-floats were employed for velocity measurements until the closing of the river, which took place on November 24, 1880. After the closing of the river preparations were begun immediately for the winter work through the ice with the water-meter. The severity of the winter in this State suggested to me the propriety of devising some plan by which the work could be continued without interruption from the cold. To meet this difficulty, a small house was constructed. It consisted of an oblong structure large enough to accommodate the members of the party to conduct the work in. This house was built of logs, the ends being clad with steel; a window on the front side of the house was provided with the light required. A trap-door with a portable frame was made in the roof of the house for lowering and raising the meter. The interior of the house was provided with a desk for recording and holding the register, a stove, and a number of other conveniences for lowering and raising the meter and into the river. The house was built as a house. The stations having been previously marked, the work was done at the ice at each station, the center of the hole being marked by a stake in the station. A path, the center of which was the section line, was then run to the gauge of the runners of the sled, was then carried to the house. With these arrangements to perform the work, it was simply necessary to go to the house over the river, raise the trap-door, and insert the trap-door into the hole in the ice. The trap-door proved to be an excellent device for the purpose. It excluded the air completely, and formed a wooden chamber in the ice. To illustrate how admirably the house plan worked, I will state that the party continued the work successfully during the winter, the thermometer indicated a temperature within the house of 40° F.

The work was continued with all the care and refinement possible, and the results were no doubt detracted from by the fact that the work was done in the winter. The work was continued until the breaking up of the ice on the 14th of April, 1881. Though the river was not yet open, the party had made arrangements to begin discharge work with the electric plant on the morning of April 15, six hours after the breaking up of the ice. The question of water anchorage used, and the general character of the work, was also discussed.

of plant and method of working, have been described so fully by you in the report of the Commission for 1881, that a description here is unnecessary. open-river work was continued successfully until October 23, 1881, orders have been received to leave Winona with the party on October 25, 1881. In connection with the regular discharge work, the following work was done: slope observations taken daily, sediment and dredge specimens were taken at regular periods, and longitudinal soundings were taken as often as time would permit. The dredge-work made of more than passing interest on account of the refinements introduced in sizing. The system of sieves used enabled the party to do this work perfectly. work was inspected by you in person on July 15, 1881. The computed discharges, other calculations, with maps of reach, chart showing deduced curves of discharge, velocity, and areas; also sketches showing portable sled-house and dredge; photograph of electric plant in actual working position, are all appended to this report. The discharge data, with map of reach and curve chart, appeared in the report of the Commission for 1881. The necessity of beginning the work on lower Mississippi as soon as possible after closing the work at Winona prevented report from accompanying the data mentioned at that time.

In conclusion, I desire to acknowledge the valuable assistance rendered by my order, Mr. Hiram Phillips, who performed all his duties in a manner worthy of the best commendation I can give him.

Very respectfully, your obedient servant,

JOHN EWENS,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

7.—AT HANNIBAL, MO., HOMER P. RITTER, ASSISTANT, IN CHARGE.

(NOTE.—Results in Report of Commission for 1882, page 138.)

OFFICE MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., October 8, 1883.

SIR: I have the honor to submit herewith a report on the observations of the gauging party stationed at Hannibal, Mo., from October, 1880, to October, 1881. In accordance with instructions received from you, I left Saint Louis October 9, 1880, and proceeded to the mouth of the Des Moines River to make a reconnaissance for a favorable location for obtaining the discharge of the Mississippi River below the mouth of the Des Moines River.

I arrived at Warsaw, Ill., October 11, and proceeded at once to make a reconnaissance of the river in this vicinity. On October 15 I received your communication informing me that the Commission had examined the following location, i. e., 500 feet above the Hannibal bridge and connecting with the Snv Levee, and found it well adapted for a gauging station, and that it should be occupied unless a decidedly better one be discovered.

I started immediately for Hannibal, Mo., and after examining the location indicated, decided to locate there, finding it well adapted for gauging purposes.

A preliminary survey of the locality was then made; the discharge section established; range polls and targets erected; slope gauges established and put up; the necessary plant collected; the wire anchorage laid and the electrical float apparatus set together. Everything being ready, observations were commenced November 12, 1880, and continued until October 24, 1881, when orders were received to discontinue observations. The party consisted of one recorder and two boatmen, with an additional boatman during high water.

Location of the section.—The section was located 500 feet above the Hannibal bridge and parallel to the same. The Mississippi River at this point is very narrow, being only 1,200 feet wide at low water; 1,500 feet at a bank-full stage, and 2,550 feet at extreme high water, 1,000 feet of the latter width being the distance from the left bank to the Snv Levee, this distance being covered only a few feet in depth during high water. On the right bank the bluffs run close to the river. The deepest water in the section was about 30 feet, at low water, distant about 400 feet from the right bank. The bottom of the river was uniform, sloping from each bank towards the deepest part. The path of the current was normal to section.

Season of the observations.—The observations made during the season consisted of: (1) A measurement of the river's discharge, taken every available day. (2) Slope of the river surface for a distance of 2,000 feet above and 2,000 feet below the discharge-section. (3) Sediment samples of the water taken at different points in the section at various stages, to determine the amount of sediment carried in suspension.

(4) Dredging, obtaining specimens of the bottom of the river, to determine material and changes in material. (5) Tri-daily readings of the water-gauge.

Discharge.—Discharge observations with the rod-float plant were commenced November 11, and were continued November 12, 13, and 15. These observations had to be discontinued, with the exception of December 13 and 14, on account of running ice, until the river froze over, which occurred on December 29. From January 3 to March 10, inclusive, discharge observations were taken by cutting holes in the ice and using a current-meter. After the ice had broken up and ceased running (April 7), the wire anchorage was again put in, and the discharge observations with rod-float plant resumed, and continued to October 12, when observations at the station were discontinued. During the season 94 discharges were obtained, 29 of which were meter discharges. The discharge observations were reduced and computed during the season, and the results forwarded to the office at Saint Louis, Mo. Taking a discharge consisted in obtaining a cross-section of the river by means of soundings, and determining the velocity of the current at various points in the section. The soundings were taken either with a pole or a lead-line, and were 25 feet apart. A 20-pound lead was used. Velocities were taken every 100 feet by means of rod-floats or current-meter.

In determining velocities by means of rod-floats 6 rods were run to each station, and a mean taken for the observed velocity at that point. When the current-meter was used a mid-depth and an integrated velocity were taken at each station.

In reducing and computing rod discharges, the observed velocities of the rods were reduced to the mean velocity in the vertical section by Francis' formula, *i. e.*:

in which
$$v' = v \left(1 - 0.116 \left[\sqrt{\frac{D-D'}{D}} - 0.1 \right] \right)$$

v' = mean velocity.

v = observed velocity.

D = depth of water.

D' = immersion of rod.

The cross-section was divided into partial areas by ordinates midway between the observing stations. The mean of the result of rods run at any station was multiplied into the corresponding partial area, and the partial discharges thus obtained were added together for the total discharge. The latter quantity was divided by the total cross-section for the mean velocity of the river. The meter discharges were computed in the same manner, with the exception that a mean of the mid-depth and integrated velocity at each station was multiplied into its corresponding partial cross-section.

In taking discharges with rod floats, the following plant was used, the principal features being the wire anchorage, the electrical float apparatus, and the rod floats.

The wire anchorage consisted of a No. 9 steel wire running across the river and fastened at each shore. From this cross-wire anchor wires ran up stream every 100 feet. The anchor wires were 200 feet long, one end being fastened to the cross-wire and the other to a large stone weighing from two to three hundred pounds. When not in use, this wire system lay at the bottom of the river.

The electrical-float apparatus used was rigged in the following manner: Across the stern of a 22 foot skiff is bolted an outrigger 20 feet long and five inches wide, which is graduated to feet. From the extremities of this outrigger two wires, each 100 feet long, supported on battens, trail down stream, and to their lower ends is attached another similar strip supported on three buoys; the upper and lower strips, together with the two side wires, forming a parallelogram 20 by 100 feet. On the up-stream face of the lower outrigger is fastened a strip of sheet copper one inch wide extending the whole length of the board. In front of the above copper strip is stretched a similar copper band, supported at each end on wooden bridges.

The strip of copper which is fastened to the face of the lower outrigger is connected with an insulated wire running along one of the wires forming the parallelogram, and the copper band in front of the strip is connected with a similar insulated wire running along the other wire of the parallelogram. The two insulated wires lead into the upper skiff, where they are connected with a battery and electric bell. At the middle of the lower outrigger is attached a skiff used in catching the floats. The rods used were cylindrical in shape, $1\frac{1}{4}$ inches in diameter and from 3 to 25 feet in length. To the bottom of the rods were attached tin cans of the same diameter as the rods and from 12 to 30 inches long. These cans were filled with shot, thus enabling the rods to float in an upright position. A discharge with the float apparatus was taken in the following manner: The apparatus having been gotten ready, the shore-end of the cross-wire was raised and put over the bow of the upper skiff, where

(4) Dredging, obtaining specimens of the bed and changes in material. (5) Tri-daily re-

Discharge.—Discharge observations were continued until November 11, and were continued November 12, but discontinued, with the exception of December 10, until the river froze over, which occurred December 10, and discharge observations were discontinued. After the ice had broken, anchorage was again put in, and the discharge resumed, and continued to October 12, when it terminated. During the season 94 discharge observations were made, and the results forwarded to the office. It consisted in obtaining a cross-section of the river, by taking the velocity of the current at various points, taken either with a pole or a lead-line, and used. Velocities were taken every 10 feet.

In determining velocities by means of a float, a mean taken for the observed velocity was used, and an integrated

In reducing and computing rod discharges, the mean velocity in the

in which

$$v = \frac{Q}{A}$$

$$v = \frac{Q}{A}$$

$$v = \frac{Q}{A}$$

$$D = \frac{Q}{A}$$

$$D = \frac{Q}{A}$$

The cross-section was divided into corresponding parts, and the mean velocity for the total discharge was found for the mean velocity in each part, and the total discharge was found for each station.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The discharge was found by multiplying the mean velocity by the area of the cross-section.

The section were taken

through holes cut in the

ice, the dredging was

done frame, to which

were above, were the

each dredging was kept

and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

form, were forwarded to

the office, and the results, in tabular

HOMER P. RITTER,
Assistant Engineer.

STATE ASSISTANT IN CHARGE.

Chief of Commission for 1892, page 142.)

MISSISSIPPI RIVER COMMISSION,
Saint Louis, Mo., July 13, 1891.

In following report, on the observations at O'Fallon, Mo., October 25, 1891.

On the morning of the 25th of October, the assistant about the middle of October, at O'Fallon, Mo., so that little more than local

work was done, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

work, and the arrival of two boatsmen, a record was made, for the purpose of local

ENT.

ly, when practicable, during the period. They were discontinued in March.

.....	4
.....	11
.....	6
.....	3
.....	2
.....	1
.....	14

very irregular in the early part of the season. It stopped running on account of ice and did not period there was no way of forwarding specimens. The boats commenced running again and continued until August, when it was taken back. Between the shipping-boats not being properly repaired, they were taken and forwarded to the office.

Only, after and including March. The measurements continued till late in December, and it was impossible to continue January and February. Ten sets of specimens were made.

made daily when more important work did not prevent. Some of the observations were rendered worthless by the ice level was obtained with which to compare such observations were made.

Observations were made with the meter during the last period. Only 119 curves were determined at 13 different stations.

As already stated, the first discharge was taken on November 10th, both being by the plant method. For the first time commenced to flow in large quantities and from that date till clear of it.

During the river blocked, but did not freeze over. For immense fields of ice that covered more than half the river, it was impossible to work upon. This continued through January, during which it was impossible to measure discharges. As soon as the river became open, the meter was brought into immediate use. The ice remained until March, and the meter was employed up to that time. There were a number of repairs needed on the instrument. Although the work was done upon it early in February, it did not break away until the middle of March. During this time no discharges could be measured. As soon as the ice was cleared, discharges were taken by timing ice chunks, a few of which could be handled. The distances were all estimated by guess. During the running, the use of double floats was continued until a new set of floats in and arrangements made for using the plant. During March six sets of observations were made in this way. On the 5th of April the work was completed and the original method by plant resumed. The river was becoming very high. After five sets of observations were taken the anchorage was swept away by the swelling volume of water. Several wires were made to replace it. Several wires were stretched across the river, broken before being used; some of the breaks were occasioned by the ice, others by the force of the current alone, all efforts to keep it in were abandoned. At request a transit was furnished the party, and on April 16 the first discharge was made with double floats located from shore. This method was continued till the middle of July, ninety-one discharges having been taken in this

middle of July, free rods were substituted for double floats, the river then being high enough to handle them conveniently. This was not practicable in high water. A skiff party of only two boatmen, who had to manage the skiff, handle the rods, and record the soundings. Free rods were used and located with the plant. 25 discharges being taken. On the 19th of August the plant was removed from the river having become sufficiently low to make it practicable. This method was kept up till the 4th of October, 10 discharges having been taken. By the 1st of October the river had again

DET OF THE CHIEF OF ENGINEERS, U. S. A.

24 to October 14 nine different points in the section were being added on the Illinois side of the river.

described below. From March 24 to October 14, the dredging was done by means of a canvas bag surrounding an iron frame, attached

stations used, with the addition of the two mentioned above,
Dredgings.

A specimen of the bottom of the river obtained by each dredge, and analyzed.

The specimens, 324 in number, put in tin boxes and labeled, were from St. Louis, Mo. The specimens were analyzed in the field, and the results comprising 39 sheets, forwarded. When dredging through holes in the described dredge was found to answer the purpose. It consisted of sheet-iron 18 inches long and 6 inches in diameter, open at one end. A strip of wrought iron 1 by $\frac{1}{2}$ by 20 inches was riveted to the inside (wise) of the cylinder, and allowed to project a few inches beyond the end. This strip was screwed a rod made of half-inch gas-pipe. The dredge was divided into sections, each 7 feet long, with gas-pipe couplings for screwing together, permitting the rod to be lengthened or shortened, as the depth required.

The section nearest the cylinder was bent upwards at an angle the cylinder to be pulled along the bottom, scooping up the was let into the water-cylinder—end down stream. In pulling the cylinder assumed a perpendicular position, thereby enabling bottom to be brought up without undergoing any change by tides washed out. The dredge was found to work without depths in the section.

Very respectfully, your obedient servant,

E03

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

B.—AT GRAFTON, ILL., J. H. DAVIS, ASSISTANT.

(NOTE.—Results in Report of Commission for

OFFICE MISSISSIPPI
Se

SIR: I have the honor to submit the following report on, Illinois, made from October 15, 1880, to October 21,

The scene of operations was reached by the assistant. There was neither material nor assistance at hand, so could be done during the first week. Upon the arrival of the most favorable portion of the river was a gauging section. Upon the arrival of C. L. Harris, complete, consisting of assistant, recorder, and two boys, preliminary work to be done in putting up gauges, anchorage, laying off ranges and putting up sign instruments were furnished, and the material and was lost unnecessarily in this work. Most of the utensils. Finally, on the 13th of November, the agent to measure a discharge by the method of p

The serial work consisted of—

- 1st. Discharge observations.
- 2d. Sediment observations.
- 3d. Dredging observations.
- 4th. Slope observations.
- 5th. Determining vertical velocity curves.

REPORT OF THE CHIEF

ENGINEERS, U. S. ARMY.

Prescott, Minn., January

be done except to attend to the slope and recorder was occupied in. In this way much time was saved. Mr. C. L. Harrison, recorder, leave of absence, extending from the charge of the observations, and ex- sistant labored under great disad- was frequently impracticable to carry was pursued that seemed, in the j- cumstances.

Respectfully submitted.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Com-

on discharge observations at

Large
000
feet
second.

Date. Gauge.

1882.		
May	29	442.7
	30	442.6
	31	442.6
June	1	442.5
	2	442.4
	3	442.3
	4	442.3
	5	442.2
	6	442.1
	7	442.0
	8	442.0
	9	441.9
	10	441.8
	11	441.7
	12	441.5
	13	441.3
	14	441.2
	15	441.0
	16	440.8
	17	440.5
	18	440.3
	19	440.1
	20	439.9
	21	439.6
	22	439.4
	23	439.3
	24	440.2
	25	440.3
	26	440.4
	27	441.2
	28	442.1
	29	442.3
July	1	442.3
	2	442.3
	3	442.6
	4	442.3
	5	442.1
	6	442.1
	7	442.1
	8	442.1
	9	442.1
	10	441.9
	11	441.8
	12	441.7
	13	441.7
	14	441.7
	15	441.7
	16	441.7
	17	441.7
	18	441.5
	19	441.2
	20	441.2
	21	441.6
	22	441.2
	23	441.4
	24	441.5
	25	441.6
	26	441.9
	27	442.0
	28	442.0
	29	442.3
	30	442.3
	31	442.6

9.—PROBABLE DISCHARGES OF THE

Table showing daily discharges

[Computed from the gauge re-

NOTE.—As the Prescott ga-
above Prescott), were taken,

Date.	Gauge.	Dis- in cub. feet
1882.		
Jan. 1	441.5	
2	441.9	
3	442.0	
4	442.2	
5	442.4	
6	442.3	
7	442.1	
8	442.0	
9	441.9	
10	441.8	
11	441.7	
12	441.5	
13	441.3	
14	441.2	
15	441.0	
16	440.8	
17	440.5	
18	440.3	
19	440.1	
20	439.9	
21	439.6	
22	439.4	
23	439.3	
24	440.2	
25	440.3	
26	440.4	
27	441.2	
28	442.1	
29	442.3	
30	442.3	
31	442.6	

T OF THE CHIEF OF ENGINEERS, U. S. ARMY.

be done except to attend to the slope gauges. The remainder of the time of the assistant and recorder was occupied in computing some tables for reducing velocities. In this way much time was saved in the computations made during the working season. Mr. C. L. Harrison, recorder, was an able and reliable assistant. During my leave of absence, extending from the 12th to the 29th of September, he was in full charge of the observations, and executed the work with entire satisfaction. The assistant labored under great disadvantages, owing to the location of the station. It was frequently impracticable to carry out the instructions. In this case, the method was pursued that seemed, in the judgment of the assistant, best adapted to the circumstances.

Respectfully submitted.

J. H. DAVIS,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

9.—PROBABLE DISCHARGES OF THE MISSISSIPPI RIVER AT VARIOUS POINTS, DURING THE YEARS 1881 AND 1882.

Table showing daily discharge of the Mississippi River at Prescott, Wis., January 1, 1881, to January 1, 1883.

[Computed from the gauge readings by a formula deduced from discharge observations at the same point in 1881.]

NOTE. As the Prescott gauge was not read in 1882, the gauge readings at Hastings, Minn. (3 miles above Prescott), were taken, after corrections for slope and changes of slope.

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
1882.			1882.			1882.		
Jan. 1	180.8	18	Feb. 15	180.4	17	Apr. 1	184.2	24
2	180.9	18	16	180.4	17	2	184.7	24
3	181.0	19	17	180.4	17	3	185.2	25
4	181.2	19	18	180.5	17	4	185.7	25
5	181.4	20	19	180.5	17	5	186.2	26
6	181.5	20	20	180.5	17	6	186.7	26
7	181.6	21	21	180.6	17	7	187.2	27
8	181.7	21	22	180.6	17	8	187.7	27
9	181.9	22	23	180.7	18	9	188.2	28
10	181.8	22	24	180.7	18	10	188.7	28
11	181.8	22	25	180.6	17	11	189.2	29
12	181.7	21	26	180.5	17	12	189.7	29
13	181.6	21	27	180.4	17	13	190.2	30
14	181.7	21	28	180.5	17	14	190.7	30
15	181.7	21	Mar 1	180.5	17	15	190.1	29
16	181.7	21	2	180.9	18	16	190.9	30
17	181.7	21	3	181.3	20	17	189.8	28
18	181.6	21	4	181.8	22	18	189.7	28
19	181.6	21	5	182.2	24	19	189.6	28
20	181.6	21	6	182.7	26	20	189.1	27
21	181.6	21	7	183.2	28	21	189.5	28
22	181.6	21	8	183.2	28	22	189.4	28
23	181.5	20	9	183.2	28	23	189.2	28
24	181.4	20	10	183.1	27	24	189.2	28
25	181.3	20	11	183.0	27	25	189.1	28
26	181.4	20	12	182.8	26	26	189.1	28
27	181.5	20	13	182.7	25	27	189.0	28
28	181.4	20	14	182.6	25	28	189.0	28
29	181.3	20	15	182.4	24	29	189.0	28
30	181.3	20	16	182.2	24	30	188.9	28
31	181.2	19	17	182.1	23	May 1	188.6	28
Feb. 1	181.2	19	18	182.1	23	2	188.5	28
2	181.2	19	19	182.1	23	3	188.3	28
3	181.1	19	20	182.1	23	4	188.1	28
4	181.0	19	21	182.2	24	5	188.1	28
5	180.9	18	22	182.2	24	6	187.7	28
6	180.9	18	23	182.1	23	7	187.6	28
7	180.8	18	24	182.2	24	8	187.4	28
8	180.8	18	25	182.3	24	9	187.2	28
9	180.7	18	26	182.3	24	10	187.4	28
10	180.7	18	27	182.4	24	11	187.6	28
11	180.6	17	28	182.7	25	12	188.1	29
12	180.6	17	29	183.1	27	13	188.6	29
13	180.5	17	30	183.4	28	14	189.2	30
14	180.5	17	31	183.8	30	15	189.8	30

bed
not
In
low
char
not
wa
wa
cup
b

at Winona, Minn., January 1, 1882.
(1883.)

obtained from discharge observations at the
(1882.)

		Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
1882.					
Apr.	20	38	May 20	442.7	
	21	35	20	442.6	
	22	35	31	442.6	
	23	35	June 1	442.5	
	24	35	2	442.4	
	25	36	3	442.3	
	26	37	4	442.2	
	27	37	5	442.1	
	28	36	6	442.1	
	29	35	7	442.0	
	30	35	8	442.0	
	1	36	9	441.9	
	2	38	10	441.8	
	3	39	11	441.7	
	4	44	12	441.5	
	5	48	13	441.3	
	6	50	14	441.2	
	7	51	15	441.0	
	8	52	16	440.8	
	9	53	17	440.5	
	10	56	18	440.3	
	11	53	19	440.1	
	12	64	20	439.9	
	13	75	21	439.8	
	14	84	22	439.6	
	15	90	23	439.8	
	16	98	24	440.2	
	17	100	25	440.3	
	18	104	26	440.4	
	19	104	27	441.0	
	20	101	28	441.7	
	21	98	29	442.1	
	22	97	30	442.3	
	23	95	July 1	442.3	
	24	91	2	442.3	
	25	88	3	442.3	
	26	86	4	442.4	
	27	86	5	442.4	
	28	86	6	442.1	
	29	86	7	442.1	
	30	86	8	442.1	
	1	84	9	442.1	
	2	84	10	441.8	
	3	84	11	441.8	
	4	84	12	441.8	
	5	82	13	441.7	
	6	82	14	441.7	
	7	80	15	441.7	
	8	79	16	441.7	
	9	78	17	441.7	
	10	78	18	441.7	
	11	76	19	441.5	
	12	74	20	441.1	
	13	72	21	440.8	
	14	71	22	440.8	
	15	71	23	440.8	
	16	71	24	440.8	
	17	71	25	439.8	
	18	72	26	439.6	
	19	73	27	439.6	
	20	86	28	439.3	
	21	95	29	439.1	
	22	97	30	439.0	
	23	96	31	439.0	
	24	95	Aug 1	438.9	
	25	95	2	438.9	
	26	90	3	438.9	
	27	88	4	438.8	
	28	87	5	438.8	
	29	87	6	438.8	
	30	87	7	438.8	
	31	87	8	438.8	
	1	87	9	438.8	
	2	87	10	438.8	

St. Lawrence River at Hannibal, Mo., &c.—Contd.

No.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	No.
1882					
July					
1	86.5	247	10	84.6	10
2	87.2	253	11	84.2	11
3	87.9	260	12	84.0	12
4	88.2	267	13	83.7	13
5	88.2	267	14	83.4	14
6	87.8	278	15	83.1	15
7	87.5	271	16	82.9	16
8	87.1	261	17	82.6	17
9	86.7	251	18	82.2	18
10	86.2	240	19	82.0	19
11	86.0	236	20	81.6	20
12	85.7	229	21	81.2	21
13	85.3	220	22	80.7	22
14	85.4	244	23	80.4	23
15	85.3	260	24	80.1	24
16	85.3	273	25	79.9	25
17	85.6	273	26	79.6	26
18	85.6	273	27	79.4	27
19	85.3	265	28	79.2	28
20	85.0	258	29	79.1	29
21	85.6	253	30	79.0	30
22	85.5	267	31	79.1	31
Aug.					
1	85.6	256	1	79.2	1
2	85.6	256	2	79.2	2
3	85.6	256	3	79.0	3
4	85.9	251	4	78.8	4
5	85.3	250	5	78.9	5
6	85.1	250	6	78.2	6
7	85.1	250	7	78.9	7
8	85.5	250	8	79.0	8
9	85.3	250	9	78.5	9
10	85.3	250	10	78.3	10
11	85.3	250	11	78.3	11
12	85.3	250	12	77.9	12
13	85.3	250	13	77.8	13
14	85.3	250	14	77.3	14
15	85.3	250	15	77.2	15
16	85.3	250	16	77.2	16
17	85.3	250	17	76.9	17
18	85.3	250	18	76.7	18
19	85.3	250	19	76.6	19
20	85.3	250	20	76.4	20
21	85.3	250	21	76.4	21
22	85.3	250	22	76.3	22
23	85.3	250	23	76.2	23
24	85.3	250	24	76.1	24
25	85.3	250	25	76.0	25
26	85.3	250	26	75.8	26
27	85.3	250	27	75.8	27
28	85.3	250	28	75.8	28
29	85.3	250	29	75.8	29
30	85.3	250	30	75.6	30
31	85.3	250	31	75.6	31
Sept.					
1	85.3	250	1	75.5	1
2	85.3	250	2	75.5	2
3	85.3	250	3	75.5	3
4	85.3	250	4	75.6	4
5	85.3	250	5	75.7	5
6	85.3	250	6	75.8	6
7	85.3	250	7	76.1	7
8	85.3	250	8	76.3	8
9	85.3	250	9	76.5	9
10	85.3	250	10	76.4	10
11	85.3	250	11	76.3	11
12	85.3	250	12	76.2	12
13	85.3	250	13	76.2	13
14	85.3	250	14	76.0	14
15	85.3	250	15	75.9	15
16	85.3	250	16	75.8	16
17	85.3	250	17	75.6	17
18	85.3	250	18	75.5	18
19	85.3	250	19	75.5	19
20	85.3	250	20	75.3	20
21	85.3	250	21	75.2	21
22	85.3	250	22	75.0	22
23	85.3	250	23	74.8	23
24	85.3	250	24	74.7	24

ving daily discharge of the Mississippi River at Hannibal, Mo., &c.—Continued.

Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
		1882.			1882.		
74.6	47	Oct. 28	77.2	77	Nov. 30	77.0	74
74.5	46	29	77.2	77	Dec. 1	76.7	70.
74.4	45	30	77.2	77	2	76.5	68.
74.3	44	31	77.2	77	3	76.3	65.
74.3	44	Nov. 1	77.2	77	4	76.2	64.
74.2	43	2	77.1	75	5	75.9	60.
74.2	43	3	77.1	75	6	75.8	59.
74.2	43	4	76.9	72	7	75.1	52
74.2	43	5	76.7	70	8	74.6	47.
74.2	43	6	76.5	68	9	74.0	41.
74.1	42	7	76.3	65	10	73.6	37.
74.1	42	8	76.2	64	11	72.6	27.
74.1	42	9	76.0	62	12	71.6	17.
74.1	42	10	76.0	62	13	71.7	18.
74.1	42	11	76.0	62	14	72.2	23.
74.2	43	12	76.0	62	15	72.1	22.
74.2	43	13	75.9	60	16	73.0	31
74.4	45	14	75.8	59	17	71.9	20.
74.7	48	15	75.7	58	18	72.0	21
74.7	48	16	75.6	57	19	71.7	18.
74.7	48	17	76.2	64	20	72.4	25.
75.1	52	18	76.4	66	21	73.2	33
75.6	57	19	76.5	68	22	74.0	41
76.0	62	20	76.6	69	23	74.8	49
76.2	64	21	76.7	70	24	75.1	52.
76.2	64	22	76.7	70	25	75.2	53.
76.2	64	23	76.8	71	26	75.5	56.
76.3	65	24	76.9	72	27	75.6	57.
76.6	69	25	77.1	75	28	75.9	60.
76.7	70	26	77.1	75	29	76.0	62.
76.9	72	27	77.2	77	30	76.0	62.
77.0	74	28	77.2	77	31	75.8	59.
77.2	77	29	77.2	77			

ing daily discharge of the Mississippi River at Grafton, Ill., January 1, 1882,
to January 1, 1883.

from the gauge readings by a formula deduced from discharge observations at the same
point in 1881.]

Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
		1882.			1882.		
22.7	153	Jan. 27	18.3	75	Feb. 22	29.7	270
22.0	142	28	18.3	75	23	29.2	259
22.3	135	29	18.1	73	24	26.2	197
21.7	131	30	17.9	70	25	24.7	170
21.3	126	31	18.2	74	26	22.9	141
20.0	121	Feb. 1	18.3	75	27	21.8	122
19.0	115	2	18.5	77	28	21.3	115
18.0	110	3	18.3	75	Mar. 1	21.7	121
17.0	112	4	18.2	74	2	22.1	127
16.0	110	5	18.7	79	3	21.9	124
15.0	109	6	18.7	79	4	22.0	126
14.0	103	7	18.7	79	5	22.2	129
13.0	105	8	18.7	79	6	22.5	134
12.0	105	9	18.8	80	7	22.7	137
11.0	96	10	18.0	81	8	23.0	142
10.0	86	11	18.7	79	9	23.3	147
9.0	81	12	18.5	77	10	24.2	161
8.0	79	13	18.6	78	11	25.1	177
7.0	75	14	18.6	78	12	25.6	186
6.0	72	15	18.6	78	13	25.4	183
5.0	70	16	18.5	77	14	25.0	176
4.0	72	17	18.9	81	15	24.7	170
3.0	75	18	19.1	84	16	24.4	165
2.0	75	19	19.3	86	17	24.3	163
1.0	75	20	24.5	167	18	24.2	161
0.0	163	21	28.7	247	19	24.2	161

2674 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Table showing daily discharge of the Mississippi River at Grafton, Ill., &c.—Contir

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Dis in cub per
1882.			1882.			1882.		
Mar. 20	24.4	165	June 5	32.0	324	Aug. 21	18.8	
21	24.6	168	6	32.0	324	22	18.6	
22	25.1	177	7	32.1	326	23	18.5	
23	25.2	179	8	32.1	326	24	18.4	
24	25.2	179	9	31.9	321	25	18.4	
25	25.2	179	10	31.5	312	26	18.4	
26	25.1	177	11	31.2	305	27	18.3	
27	25.1	177	12	30.6	290	28	18.1	
28	25.0	176	13	30.4	285	29	17.9	
29	25.0	176	14	30.4	285	30	17.7	
30	25.1	177	15	30.6	290	31	17.5	
31	25.1	177	16	30.8	295	Sept. 1	17.7	
Apr. 1	25.1	177	17	31.8	307	2	17.9	
2	25.2	179	18	31.7	317	3	17.7	
3	25.3	181	19	31.6	314	4	17.7	
4	25.5	185	20	31.2	305	5	17.7	
5	25.6	186	21	30.9	297	6	17.9	
6	25.5	185	22	30.7	292	7	17.9	
7	25.5	185	23	30.8	283	8	18.1	
8	25.3	181	24	30.1	279	9	18.3	
9	25.6	186	25	29.7	270	10	18.4	
10	25.5	185	26	29.4	263	11	18.4	
11	25.8	190	27	29.7	270	12	18.4	
12	26.1	195	28	30.1	279	13	18.2	
13	26.4	201	29	30.7	292	14	18.1	
14	26.8	209	30	31.5	312	15	18.0	
15	27.1	215	July 1	32.5	336	16	17.8	
16	27.4	221	2	33.1	350	17	17.8	
17	27.5	223	3	34.0	374	18	17.5	
18	27.9	231	4	34.5	387	19	17.3	
19	27.8	239	5	34.7	392	20	17.2	
20	27.2	217	6	34.7	392	21	17.1	
21	27.1	215	7	34.5	387	22	16.9	
22	27.8	219	8	34.2	379	23	16.7	
23	28.3	239	9	33.7	366	24	16.6	
24	29.1	257	10	33.0	348	25	16.5	
25	29.6	268	11	32.3	331	26	16.4	
26	30.2	281	12	31.7	317	27	16.3	
27	30.6	290	13	30.9	297	28	16.1	
28	30.8	295	14	30.2	281	29	16.1	
29	31.1	302	15	29.5	266	30	16.0	
30	31.2	305	16	28.9	252	Oct. 1	15.9	
May 1	31.2	305	17	28.3	239	2	15.9	
2	31.1	302	18	27.9	231	3	15.8	
3	30.9	297	19	27.4	221	4	15.7	
4	30.6	290	20	27.0	218	5	15.7	
5	30.2	281	21	26.5	203	6	15.7	
6	29.6	268	22	25.2	179	7	15.6	
7	28.5	243	23	24.8	172	8	15.6	
8	28.5	243	24	24.6	168	9	15.6	
9	30.3	283	25	24.4	165	10	15.6	
10	30.4	285	26	24.0	158	11	15.7	
11	31.1	302	27	23.5	150	12	15.7	
12	31.3	307	28	23.1	143	13	15.7	
13	31.3	307	29	22.8	139	14	15.9	
14	31.3	307	30	22.6	135	15	16.2	
15	31.2	305	31	22.3	131	16	16.3	
16	31.1	302	Aug. 1	22.1	127	17	16.4	
17	31.0	300	2	22.0	126	18	16.9	
18	30.6	290	3	22.0	126	19	17.5	
19	30.7	292	4	21.9	124	20	17.7	
20	30.4	285	5	21.7	121	21	17.8	
21	30.0	277	6	21.7	121	22	17.9	
22	28.5	243	7	21.9	124	23	18.0	
23	28.9	252	8	21.9	124	24	18.0	
24	28.1	235	9	21.8	123	25	18.1	
25	27.9	231	10	21.5	118	26	18.1	
26	27.0	213	11	21.2	113	27	18.2	
27	27.1	215	12	20.8	108	28	18.4	
28	28.2	237	13	20.4	102	29	18.6	
29	29.3	261	14	20.1	97	30	18.7	
30	29.9	274	15	19.9	94	31	18.8	
31	30.6	290	16	19.8	93	Nov. 1	18.9	
June 1	31.3	307	17	19.7	92	2	18.9	
2	31.5	312	18	19.5	89	3	18.8	
3	31.8	319	19	19.2	85	4	18.7	
4	32.0	324	20	19.0	83	5	18.6	

ing daily discharge of the Mississippi River at Grafton, Ill., &c.—Continued.

Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
12.6	77	1882 Nov. 25	12.8	80	Dec. 14	12.8	31
12.2	79	26	12.9	81	15	12.8	31
12.1	79	27	12.9	81	16	14.0	33
12.0	72	28	12.0	83	17	14.2	34
17.8	69	29	12.1	84	18	14.2	34
17.7	68	30	12.2	85	19	14.4	36
17.6	67	Dec. 1	12.3	86	20	14.7	38
17.7	68	2	12.2	86	21	14.7	39
17.9	70	3	12.5	77	22	15.1	42
17.8	69	4	12.3	74	23	15.2	50
17.7	68	5	17.9	70	24	16.4	55
17.8	69	6	17.5	64	25	16.9	60
17.8	69	7	17.2	63	26	17.3	64
12.1	73	8	16.7	58	27	17.5	66
12.2	74	9	16.2	53	28	17.5	66
12.4	76	10	15.2	43	29	17.6	67
12.4	76	11	14.8	40	30	17.7	68
12.6	78	12	14.2	34	31	17.7	68
12.6	78	13	14.0	33			

ing daily discharge of Mississippi River at Fulton, Tenn., January 1, 1881, to January 1, 1883.

from the gauge readings by a formula deduced from discharge observations at the same point extending from November, 1879, to November, 1880.]

NOTE.—I in the column of remarks means that gauge-readings were interpolated.

Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.
187.86	109		Feb. 17	182.58	876	
187.80	109		18	183.03	895	
188.10	114	I	19	183.37	910	
188.24	119	I	20	183.76	929	
188.69	126		21	184.15	947	
188.64	142		22	184.53	963	
189.26	170		23	184.89	982	
189.13	215		24	185.18	996	
189.58	232		25	185.45	1,010	
189.86	272	I	26	185.61	1,018	
189.10	285	I	27	185.83	1,027	
189.69	318	I	28	185.94	1,032	
187.71	337		Mar. 1	185.92	1,031	
189.09	377		2	185.83	1,027	
171.10	442		3	185.61	1,016	I
172.14	507		4	185.39	1,007	
174.69	608		5	184.90	982	
176.15	616		6	184.07	944	
171.65	648		7	182.69	889	
171.65	672		8	181.42	827	
173.62	687		9	180.01	767	
176.14	691		10	178.75	719	
177.34	690		11	178.10	692	
177.69	648		12	177.27	657	
178.61	610		13	176.09	637	
174.37	598		14	176.29	621	
172.69	496		15	176.10	614	
170.69	430		16	176.08	612	
169.52	395		17	177.22	655	
168.44	359		18	178.09	690	
167.96	305		19	178.68	713	
167.86	327		20	179.28	738	
167.87	363		21	180.20	775	
171.65	404	I	22	181.26	818	
174.69	538	I	23	182.27	863	
177.69	647	I	24	182.65	879	
179.69	749		25	183.06	899	
181.20	820		26	183.38	911	
181.96	847		27	183.54	919	

2070 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Table showing daily discharge of the Mississippi River at Fulton, Tenn., &c.—Con

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.
1881.				1881.			
Mar. 28	183.71	936		June 14	170.26	413	
29	183.84	932		15	170.76	424	
30	184.83	979		16	171.58	438	
31	183.75	928		17	172.33	478	
Apr. 1	183.45	914		18	172.96	498	
2	183.20	908		19	173.96	523	
3	182.95	891		20	174.96	570	
4	182.87	887		21	175.37	529	
5	182.76	883		22	175.86	543	I
6	182.53	874		23	177.45	554	
7	182.30	868		24	177.54	568	
8	181.99	850		25	177.35	580	
9	181.66	835		26	176.89	533	
10	181.67	835		27	176.34	523	
11	181.92	846		28	175.77	501	
12	182.41	888		29	175.19	509	
13	182.95	891		30	174.64	500	
14	183.49	917		July 1	174.18	543	
15	184.10	945		2	172.71	534	
16	184.68	971		3	173.29	516	
17	185.12	1,000		4	173.08	503	
18	185.68	1,030		5	173.25	506	
19	186.11	1,040		6	173.43	514	
20	186.46	1,058		7	173.61	520	I.
21	186.78	1,074		8	173.68	523	I.
22	187.12	1,090		9	173.57	519	
23	187.28	1,099		10	173.15	506	
24	187.79	1,121		11	172.52	485	
25	187.99	1,131		12	171.67	452	
26	188.09	1,136	High water.	13	170.71	427	
27	188.07	1,135		14	169.78	400	
28	187.98	1,130		15	168.69	374	
29	187.96	1,129		16	168.23	358	
30	187.85	1,122		17	167.96	345	
May 1	187.67	1,114		18	168.02	346	
2	187.35	1,100		19	168.31	355	
3	187.18	1,096		20	168.69	371	
4	187.05	1,087		21	168.84	371	
5	186.90	1,085		22	169.00	377	
6	186.94	1,082		23	169.22	384	
7	186.93	1,082		24	169.41	390	
8	186.95	1,083		25	169.49	392	
9	186.97	1,083		26	169.52	393	
10	187.05	1,087		27	169.44	390	
11	187.07	1,086		28	169.20	383	
12	187.00	1,085		29	168.97	378	
13	186.87	1,078		30	168.49	361	
14	186.53	1,067		31	167.74	338	
15	185.90	1,030		Aug. 1	167.04	331	
16	185.07	990		2	166.87	308	
17	184.08	944		3	166.88	289	
18	183.05	896		4	166.50	279	
19	181.68	836		5	165.29	273	
20	180.73	796		6	165.08	267	
21	179.59	750		7	164.89	263	
22	178.69	714		8	164.71	257	
23	177.92	683		9	164.49	253	
24	177.18	651		10	164.20	244	
25	176.35	623		11	163.84	236	
26	175.73	600		12	163.42	224	
27	175.31	582		13	163.06	217	
28	175.07	575		14	162.63	207	
29	174.86	566		15	162.27	199	
30	174.55	554		16	161.90	191	
31	174.02	537		17	161.73	188	
June 1	173.96	511		18	161.63	183	
2	172.62	491		19	161.41	181	
3	171.96	471		20	161.10	175	
4	171.37	450		21	162.53	205	
5	170.97	438		22	161.90	192	
6	170.58	423		23	161.81	189	
7	170.50	420		24	161.68	186	
8	170.64	424		25	161.53	183	
9	170.76	430	I	26	161.41	181	
10	170.73	428		27	161.31	179	
11	170.48	419		28	160.02	151	
12	170.26	413		29	158.82	128	
13	170.18	410		30	159.68	121	

1861

1861

1861

1861

1861

(12) = zero of gauge established December, 1861.

2678 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Table showing daily discharge of Mississippi River at Fulton, Tenn., &c.—Contd

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.
1883.				1883.			
Jan. 29	35.82	1,224		Apr. 17	27.81	845	
30	35.87	1,228		18	27.88	848	
31	35.78	1,224		19	27.92	851	
Feb. 1	35.74	1,221		20	27.51	837	
2	35.71	1,220		21	27.68	846	
3	35.74	1,221		22	26.34	782	
4	35.74	1,221		23	26.61	785	
5	35.65	1,226		24	24.70	718	
6	35.65	1,226		25	24.65	715	
7	35.64	1,226		26	22.99	687	
8	35.66	1,226		27	22.82	688	
9	35.69	1,228		28	22.82	688	
10	35.67	1,226		29	22.81	686	
11	35.59	1,222		30	24.46	708	
12	35.50	1,217		May 1	24.79	719	
13	35.51	1,217		2	24.87	724	
14	35.37	1,211		3	24.96	729	
15	35.23	1,201		4	25.11	735	
16		1,199		5	25.22	740	
17	35.11	1,194		6	25.25	741	
18	35.05	1,191		7	25.05	738	
19	35.08	1,190		8		734	
20	35.12	1,194		9	24.53	715	
21	35.17	1,199		10	25.25	745	
22	35.23	1,201		11		748	
23	35.32	1,207		12	26.53	839	
24	35.59	1,222		13	26.68	850	
25	35.69	1,230		14	26.85	864	
26	35.19	1,255		15	31.63	1,022	
27	35.43	1,268		16	32.16	1,047	
28	35.63	1,278		17	32.52	1,065	
Mar. 1	35.69	1,282		18	32.67	1,073	
2	35.66	1,279		19		1,075	
3	35.60	1,277		20	32.60	1,075	
4	35.51	1,272		21	32.85	1,083	
5	35.44	1,269		22		1,081	
6	35.44	1,269		23	32.79	1,080	
7	35.38	1,266		24	32.81	1,080	
8	35.28	1,260		25	32.80	1,080	
9	35.26	1,259		26	32.68	1,074	
10	35.18	1,255		27	32.51	1,065	
11	35.11	1,250		28	32.14	1,047	
12	35.04	1,247		29	31.69	1,021	
13	35.04	1,247		30	31.04	994	
14	35.13	1,251		31	30.66	975	
15	35.13	1,251		June 1	30.66	975	
16	35.00	1,245		2	30.61	969	
17	35.08	1,237		3	31.00	993	
18	35.76	1,232		4	31.27	1,006	
19	35.68	1,226		5	31.55	1,018	
20	35.62	1,224		6	31.71	1,026	
21	35.52	1,218		7	31.85	1,032	
22	35.44	1,214		8	31.97	1,039	
23	35.17	1,197		9	32.04	1,042	
24	34.97	1,187		10	32.07	1,044	
25	34.73	1,172		11	32.07	1,044	
26	34.49	1,160		12	31.96	1,039	
27	34.25	1,148		13	31.69	1,021	
28	33.96	1,133		14	31.25	1,005	
29	33.68	1,120		15	30.50	967	
30	33.42	1,108		16	29.49	921	
31	33.25	1,100		17	28.45	874	
Apr. 1	32.11	1,064		18	27.45	830	
2	32.96	1,087		19	27.90	850	
3	32.84	1,082		20	27.21	820	
4	32.70	1,075		21	27.86	847	
5	32.68	1,069		22	28.59		
6	32.30	1,055		23	29.01	869	
7	31.79	1,030		24	29.35	914	
8	31.10	997		25	29.51	926	
9	30.16	950		26	29.79	935	
10	29.32	913		27	29.81	935	
11	29.05	901		28	29.09	930	
12	28.79	889		29	29.39	917	
13	28.62	882		30	29.09	902	
14	28.41	872		July 1	28.56	879	
15	28.06	856		2	28.57	870	
16	27.87	848		3	28.26	865	

Table showing daily discharge of Mississippi River at Fulton, Tenn., &c.—Continued.

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.
1882.				1882.			
July 4	26.29	868		Sept. 20	12.47	309	
5	26.62	882		21	13.02	322	
6	26.89	894		22	13.60	337	
7	26.20	908		23	13.52	334	
8	26.58	921		24	13.01	322	
9	26.82	936		25	12.33	305	
10	26.08	946		26	11.84	291	
11	26.13	950		27	11.30	276	
12	26.12	950		28	10.76	261	
13	25.89	940		29	10.30	248	
14	26.74	887		30	9.85	238	
15	26.41	872	L	Oct. 1	9.53	230	
16	26.04	856		2	9.31	224	
17	27.30	824		3	9.02	218	
18	26.61	795		4	8.84	214	
19	25.82	764		5	8.75	212	
20	25.02	732		6	8.79	213	
21	24.31	702		7	8.79	213	
22	23.69	678		8	8.77	212	
23	23.17	657		9	8.70	211	
24	22.70	641		10	8.63	210	
25	22.15	619		11	8.60	209	
26	21.49	590		12	8.58	208	
27	20.52	557		13	8.57	208	
28	19.50	520		14	8.48	207	
29	18.64	492		15	8.40	205	
30	18.87	500		16	8.30	202	
Aug. 1	18.22	478		17	8.20	200	
2	17.52	457		18	8.01	196	
3	17.31	451		19	7.92	195	
4	17.00	442		20	7.82	192	
5	16.74	433		21	7.73	190	
6	16.43	421		22	7.70	189	
7	16.41	420		23	7.76	190	
8	16.76	433		24	7.87	193	
9	17.62	460		25	7.98	196	
10	18.34	482		26	8.05	197	
11	18.58	490		27	8.08	198	
12	18.54	488		28	8.06	198	
13	18.39	484		29	8.10	198	
14	18.15	476		30	8.13	198	
15	17.78	465		31	8.18	199	
16	17.63	461		Nov. 1	8.30	202	
17	17.15	446		2	8.30	202	
18	16.49	420		3	8.33	203	
19	15.84	404		4	8.38	204	
20	15.60	398		5	8.47	206	
21	15.36	390		6	8.51	207	
22	15.11	383		7	8.50	207	
23	14.83	374		8	8.51	207	
24	14.44	362		9	8.54	208	
25	13.97	348		10	8.54	208	
26	13.55	335		11	8.77	212	
27	13.06	323		12	9.11	220	
28	12.62	314		13	9.18	222	
29	12.21	301		14	9.39	227	
30	11.91	292		15	9.59	232	
Sept. 1	11.74	288		16	9.70	235	
2	11.54	282		17	9.68	234	
3	11.42	279		18	9.74	236	
4	11.42	279		19	9.86	238	
5	11.42	279		20	9.90	240	
6	11.41	279		21	9.78	236	
7	11.41	279		22	9.62	233	
8	11.48	280		23	9.54	230	
9	11.61	284		24	9.41	227	
10	11.75	288		25	9.22	222	
11	11.95	293		26	9.18	222	
12	12.10	298		27	9.12	220	
13	12.13	299		28	9.08	219	
14	12.01	295		29	9.03	218	
15	11.85	291		30	9.08	219	
16	11.65	286		Dec. 1	9.09	219	
17	11.47	280		2	9.10	220	
18	11.19	273		3	9.11	220	
19	11.00	268		4	9.12	220	
	11.62	268		5	9.11	220	
	11.57	268		6	9.11	220	

OF THE CHIEF OF ENGINEERS

Discharge of Mississippi River at Fulton

	Discharge in 1,000 cubic feet per second.	Remarks.	Date.	Gauge
	1,234		1882	
	1,226		Apr. 17	21.
	1,234		18	22.
	1,231		19	23.
	1,231		20	24.
	1,229		21	25.
	1,231		22	26.
	1,231		23	27.
	1,236		24	28.
	1,236		25	29.
	1,236		26	30.
	1,236		27	31.
	1,236		28	32.
	1,236		29	33.
	1,236		30	34.
	1,217		May 1	35.
	1,217		2	36.
	1,211		3	37.
	1,201		4	38.
	1,199		5	39.
	1,194		6	40.
	1,191		7	41.
	1,190		8	42.
	1,194		9	43.
	1,199		10	44.
	1,201		11	45.
	1,207		12	46.
	1,222		13	47.
	1,239		14	48.
	1,255		15	49.
	1,268		16	50.
	1,276		17	51.
	1,282		18	52.
	1,279		19	53.
	1,277		20	54.
	1,272		21	55.
	1,269		22	56.
	1,269		23	57.
	1,266		24	58.
	1,260		25	59.
	1,259		26	60.
	1,255		27	61.
	1,250		28	62.
	1,247		29	63.
	1,247		30	64.
	1,251		June 1	65.
	1,251		2	66.
	1,245		3	67.
	1,237		4	68.
	1,232		5	69.
	1,226		6	70.
	1,224		7	71.
	1,218		8	72.
	1,214		9	73.
	1,197		10	74.
	1,187		11	75.
	1,172		12	76.
	1,160		13	77.
	1,148		14	78.
	1,133		15	79.
	1,120		16	80.
	1,108		17	81.
	1,100		18	82.
	1,094		19	83.
	1,087		20	84.
	1,082		21	85.
	1,075		22	86.
	1,069		23	87.
	1,055		24	88.
	1,030		25	89.
	997		26	90.
	950		27	91.
	913		28	92.
	901		29	93.
	889		30	94.
	882		1	95.
	872		2	96.
	856		3	97.
	848		4	98.

Table showing daily discharge of Mississippi

Memphis, Tenn., Ga.—C

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Remarks.
1882 Dec. 7	8.28	222	
8	8.40	225	
9	8.50	229	
10	8.54	235	
11	8.55	219	
12	8.74	212	
13	8.47	206	
14	8.17	200	
15	7.86	198	
16	7.47	184	
17	7.29	179	
18	7.04	174	
19	6.78	169	

Table showing daily discharge of the Mississippi
to the Gulf of Mexico[Computed from the gauge readings, by a /
Landing, Ark., 1879-1880 (12 miles below
gauge readings.)]

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date
1881 Jan. 1			1881 Feb.
2	4.43	211	
3	4.36	209	
4	4.35	209	
5	4.30	206	
6	4.25	202	
7	4.20	198	
8	4.15	194	
9	4.10	190	
10	4.05	186	
11	4.00	182	
12	3.95	178	
13	3.90	174	
14	3.85	170	
15	3.80	166	
16	3.75	162	
17	3.70	158	
18	3.65	154	
19	3.60	150	
20	3.55	146	
21	3.50	142	
22	3.45	138	
23	3.40	134	
24	3.35	130	
25	3.30	126	
26	3.25	122	
27	3.20	118	
28	3.15	114	
29	3.10	110	
30	3.05	106	
31	3.00	102	
1	2.95	98	
2	2.90	94	
3	2.85	90	
4	2.80	86	
5	2.75	82	
6	2.70	78	
7	2.65	74	
8	2.60	70	
9	2.55	66	
10	2.50	62	
11	2.45	58	
12	2.40	54	
13	2.35	50	
14	2.30	46	
15	2.25	42	
16	2.20	38	
17	2.15	34	
18	2.10	30	
19	2.05	26	
20	2.00	22	
21	1.95	18	
22	1.90	14	
23	1.85	10	
24	1.80	6	
25	1.75	2	
26	1.70		
27	1.65		
28	1.60		
29	1.55		
30	1.50		
31	1.45		

Date.	Gauge.
1882 June 12	31.5
13	31.4
14	31.9
15	30.9
16	30.1
17	29.2
18	28.4
19	27.6
20	27.2
21	27.2
22	27.0
23	28.5
24	29.0
25	29.2
26	29.3
27	29.4
28	29.5
29	29.5
30	29.1
July 1	28.8
2	28.5
3	28.2
4	28.1
5	28.0
6	28.0
7	28.5
8	28.0
9	29.2
10	29.5
11	29.7
12	30.0
13	29.6
14	29.0
15	28.2
16	28.5
17	27.8
18	27.1
19	26.3
20	25.5
21	24.6
22	23.7
23	22.0
24	21.5
25	21.9
26	21.3
27	20.3
28	19.3
29	18.2
30	17.2
31	16.3
Aug 1	15.5
2	15.0
3	14.5
4	14.3
5	14.0
6	13.7
7	13.7
8	13.4
9	13.2
10	13.0
11	12.8
12	12.6
13	12.4
14	12.2
15	12.0
16	11.8
17	11.6
18	11.4
19	11.2
20	11.0

River at Memphis, Tenn., &c.—Continued.

		Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
			1882.		
		190	Nov. 21	7.25	207
		190	22	7.25	211
		190	23	7.00	212
		190	24	6.75	217
		190	25	6.60	214
		189	26	6.35	213
		166	27	6.50	212
		184	28	6.45	211
		184	29	6.40	210
		179	30	6.35	206
		175	Dec. 1	6.30	205
		173	2	6.25	207
		173	3	6.25	207
		171	4	6.20	208
		171	5	6.40	210
		178	6	6.40	211
		180	7	6.45	211
		181	8	6.60	214
		181	9	6.60	216
		181	10	6.60	214
		181	11	6.50	212
		182	12	6.25	207
		184	13	6.00	202
		185	14	5.70	196
		186	15	5.25	187
		186	16	4.85	179
		188	17	4.45	171
		190	18	4.50	169
		191	19	4.60	169
		192	20	3.75	157
		192	21	3.50	152
		192	22	2.55	123
		193	23	2.75	127
		201	24	4.15	165
		205	25	4.90	180
		207	26	5.07	183
		211	27	6.30	207
		217	28	7.20	220
		220	29	8.20	253
		225	30	9.00	271
		228	31	9.70	289
		230			

Stage of the Mississippi River at Carrollton, La., January 1, 1881,
to January 1, 1883.

Readings by a formula deduced from discharge observations at the same
extending from December, 1879, to October, 1880.]

Stage in feet above second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
	1881.			1881.		
	Jan. 20	2.1	296	Feb. 8	10.4	621
438	21	2.0	292	9	10.4	621
438	22	2.1	296	10	10.0	601
451	23	2.4	308	11	10.1	608
454	24	3.0	333	12	9.9	656
466	25	3.2	342	13	9.6	641
488	26	3.6	361	14	9.3	626
574	27	4.1	383	15	9.3	626
595	28	4.8	415	16	9.3	626
596	29	5.6	451	17	9.4	631
629	30	6.5	492	18	9.8	651
612	31	7.2	530	19	10.3	676
638	Feb. 1	7.9	562	20	10.6	691
656	2	8.3	578	21	10.8	701
682	3	8.6	591	22	11.3	726
682	4	8.9	606	23	11.4	731
698	5	9.3	626	24	11.6	742
704	6	10.0	661	25	11.9	758
704	7	10.6	691	26	12.0	764

Table showing daily discharge of Mississippi River at Carrollton, La., &c.—Contin

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Dis- charge per
1881.			1881.			1881.		
Feb. 27	12.3	780	May 16	12.1	780	Aug. 2		4.8
28	12.1	780	17	12.0	781	3		4.4
Mar. 1	12.2	774	18	12.1	780	4		3.9
2	12.0	764	19	12.1	780	5		3.6
3	12.1	780	20	12.1	780	6		3.3
4	12.2	774	21	12.25	777	7		3.2
5	12.2	774	22	12.3	780	8		2.8
6	12.1	780	23	12.3	780	9		2.5
7	12.2	774	24	12.3	780	10		2.1
8	12.0	764	25	12.3	780	11		1.9
9	12.0	764	26	12.4	785	12		1.7
10	12.2	774	27	12.3	780	13		1.7
11	12.3	780	28	12.3	780	14		1.7
12	12.4	785	29	12.3	780	15		1.6
13	12.3	780	30	12.4	785	16		1.8
14	12.4	785	31	12.3	780	17		2.0
15	12.5	780	June 1	12.3	780	18		2.0
16	12.5	780	2	12.2	774	19		1.7
17	12.4	785	3	12.2	774	20		1.4
18	12.3	780	4	12.2	774	21		1.1
19	12.3	780	5	12.2	774	22		1.0
20	12.2	774	6	12.2	774	23		1.0
21	12.3	780	7	12.2	774	24		0.8
22	11.9	758	8	12.2	774	25		0.8
23	12.1	780	9	12.0	764	26		1.0
24	12.1	780	10	12.0	764	27		1.0
25	12.1	780	11	11.9	758	28		0.7
26	12.2	774	12	11.6	742	29		0.8
27	12.2	774	13	11.3	726	30		0.8
28	12.3	780	14	11.1	716	31		1.3
29	12.4	785	15	10.9	706	Sept. 1		1.4
30	12.25	777	16	10.8	701	2		1.5
31	12.2	774	17	10.7	696	3		1.5
Apr. 1	12.2	774	18	10.5	686	4		1.4
2	12.2	774	19	10.3	676	5		1.3
3	12.2	774	20	10.2	671	6		1.1
4	12.3	780	21	10.1	666	7		0.8
5	12.3	780	22	10.0	661	8		0.7
6	12.3	780	23	9.75	648	9		0.5
7	12.3	760	24	9.6	641	10		0.3
8	12.4	785	25	9.6	641	11		0.4
9	12.4	785	26	9.6	641	12		0.6
10	12.4	785	27	9.6	641	13		0.8
11	12.4	785	28	9.8	651	14		1.15
12	12.55	792	29	9.9	656	15		1.5
13	12.5	790	30	9.95	658	16		1.1
14	12.3	780	July 1	9.9	656	17		1.1
15	12.8	780	2	9.9	656	18		1.3
16	12.2	774	3	10.0	661	19		1.2
17	12.0	764	4	10.0	661	20		1.0
18	12.1	769	5	9.9	656	21		0.9
19	12.1	769	6	9.8	651	22		0.7
20	12.0	764	7	9.6	641	23		0.65
21	12.1	769	8	9.4	631	24		0.7
22	12.1	769	9	9.2	621	25		0.8
23	12.2	774	10	9.1	616	26		1.0
24	12.4	785	11	8.7	596	27		1.2
25	12.2	774	12	8.3	578	28		1.4
26	12.3	780	13	8.1	570	29		1.4
27	12.2	774	14	7.9	562	30		1.8
28	12.1	769	15	7.9	562	Oct. 1		2.0
29	12.0	764	16	7.7	554	2		1.9
30	12.0	764	17	7.4	541	3		1.8
May 1	11.9	758	18	7.1	525	4		1.4
2	11.9	758	19	6.7	503	5		1.1
3	12.0	764	20	6.3	483	6		1.2
4	11.9	758	21	5.6	451	7		2.1
5	11.9	758	22	4.9	420	8		1.8
6	12.1	769	23	4.3	393	9		1.6
7	12.1	769	24	3.9	374	10		1.4
8	12.3	780	25	3.7	365	11		1.7
9	12.2	774	26	3.4	351	12		2.0
10	12.2	774	27	3.3	347	13		2.2
11	12.3	780	28	3.2	342	14		2.2
12	12.2	774	29	3.3	347	15		2.4
13	12.1	769	30	3.4	351	16		2.5
14	12.2	774	31	3.4	351	17		2.7
15	12.2	774	Aug. 1	3.9	374	18		2.75

Table showing daily discharge of Mississippi River at Carrollton, La., &c.—Continued.

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
1881.			1882.			1882.		
ct. 19	2.75	822	Jan. 4	9.9	656	Mar. 23	14.65	904
20	2.75	822	5	10.0	661	24	14.65	904
21	2.85	827	6	10.4	681	25	14.8	912
22	2.9	829	7	10.7	696	26	14.8	912
23	2.9	829	8	10.9	706	27	14.95	921
24	3.0	833	9	11.1	716	28	14.9	918
25	2.9	829	10	11.2	721	29	14.75	909
26	2.9	829	11	11.2	721	30	14.65	904
27	3.0	833	12	11.2	721	31	14.6	901
28	2.5	856	13	11.2	721	Apr. 1	14.6	901
29	4.0	879	14	11.3	726	2	14.65	904
30	4.4	897	15	11.8	726	3	14.6	901
31	4.1	883	16	11.4	731	4	14.6	901
Nov. 1	4.1	883	17	11.7	747	5	14.0	901
2	4.2	888	18	11.6	742	6	14.6	901
3	4.2	888	19	11.7	747	7	14.4	890
4	4.3	893	20	11.8	753	8	14.4	890
5	4.4	897	21	12.1	769	9	14.2	879
6	4.5	402	22	12.2	774	10	14.1	874
7	4.9	420	23	12.3	780	11	14.1	874
8	4.8	415	24	12.3	780	12	14.2	879
9	4.8	415	25	12.5	790	13	14.3	884
10	4.8	415	26	12.4	785	14	14.15	876
11	5.0	424	27	12.3	786	15	14.15	876
12	5.2	433	28	12.5	790	16	14.1	874
13	5.2	433	29	12.6	795	17	14.0	869
14	5.3	438	30	12.7	800	18	14.0	869
15	5.3	438	31	12.7	800	19	13.9	864
16	5.45	444	Feb. 1	12.7	800	20	13.9	864
17	5.7	455	2	12.7	800	21	13.75	855
18	5.8	460	3	12.85	807	22	13.9	864
19	5.8	460	4	12.8	806	23	13.7	853
20	6.2	478	5	12.7	800	24	13.6	848
21	6.2	478	6	12.7	800	25	13.5	842
22	6.7	503	7	12.8	805	26	13.5	842
23	7.2	530	8	12.9	810	27	13.45	839
24	7.4	541	9	13.0	816	28	13.45	839
25	7.6	550	10	12.9	810	29	13.6	848
26	7.8	558	11	13.0	816	30	13.5	842
27	8.1	570	12	13.0	816	May 1	13.45	839
28	8.3	578	13	13.1	821	2	13.4	836
29	8.6	591	14	13.1	821	3	13.3	831
30	8.9	606	15	13.2	826	4	13.2	826
Dec. 1	9.0	611	16	13.2	826	5	13.2	826
2	9.2	621	17	13.2	826	6	13.2	826
3	9.4	631	18	13.3	831	7	13.1	821
4	9.4	631	19	13.4	836	8	13.2	826
5	9.5	636	20	13.4	836	9	13.1	821
6	9.7	646	21	13.5	842	10	13.1	821
7	9.7	646	22	13.4	836	11	13.2	826
8	9.8	651	23	13.4	836	12	13.0	816
9	9.9	656	24	13.4	836	13	12.9	810
10	9.9	656	25	13.6	848	14	12.9	810
11	9.8	651	26	13.7	853	15	12.0	810
12	9.8	651	27	13.8	858	16	12.8	805
13	9.6	641	28	14.0	869	17	12.7	800
14	9.5	636	Mar. 1	14.0	869	18	12.8	805
15	8.9	606	2	14.0	869	19	12.7	800
16	8.7	599	3	14.1	874	20	12.8	805
17	8.4	582	4	14.1	874	21	12.8	805
18	8.2	574	5	14.2	879	22	12.8	805
19	7.8	558	6	14.3	884	23	12.7	800
20	7.5	540	7	14.4	890	24	12.8	805
21	7.2	530	8	14.6	901	25	12.8	805
22	6.8	508	9	14.7	907	26	12.8	805
23	6.5	492	10	14.0	901	27	12.8	805
24	6.2	478	11	14.7	907	28	12.8	805
25	6.3	483	12	14.8	912	29	12.7	800
26	6.5	492	13	14.75	909	30	12.7	800
27	6.5	492	14	14.7	907	31	12.6	795
28	6.9	514	15	14.75	909	June 1	12.6	795
29	7.3	536	16	14.8	912	2	12.5	790
30	7.5	546	17	14.8	912	3	12.5	790
31	8.0	566	18	14.9	918	4	12.4	785
Jan. 1	8.5	586	19	14.8	912	5	12.4	785
2	8.9	606	20	14.9	918	6	12.4	785
3	9.5	636	21	14.9	918	7	12.5	790
			22	14.8	912	8	12.7	800

2684 REPORT OF THE CHIEF OF ENGINEERS

Table showing daily discharge of Mississippi River at Cairo

Date.	Gauge.	Discharge in 1,000 cubic feet per second.	Date.	Gauge.	Discharge in 1,000 cubic feet per second.
1881.			1881.		
Feb. 27	12.3	780	May 16	12.1	760
28	12.1	769	17	12.0	764
Mar. 1	12.2	774	18	12.1	766
2	12.0	764	19	12.1	768
3	12.1	769	20	12.1	768
4	12.2	774	21	12.2	774
5	12.2	774	22	12.3	774
6	12.1	769	23	12.3	774
7	12.2	774	24	12.3	774
8	12.0	764	25	12.3	774
9	12.0	764	26	12.4	774
10	12.2	774	27	12.3	774
11	12.2	780	28	12.3	774
12	12.4	785	29	12.3	774
13	12.3	780	30	12.4	774
14	12.4	785	31	12.3	774
15	12.5	790	June 1	12.3	774
16	12.5	790	2	12.3	774
17	12.4	785	3	12.3	774
18	12.3	780	4	12.2	774
19	12.3	780	5	12.2	774
20	12.3	774	6	12.2	774
21	12.3	780	7	12.3	774
22	11.9	758	8	12.2	774
23	12.1	769	9	12.0	774
24	12.1	769	10	12.0	774
25	12.1	769	11	11.9	774
26	12.2	774	12	11.6	774
27	12.2	774	13	11.3	774
28	12.3	780	14	11.1	774
29	12.4	785	15	10.9	774
30	12.25	777	16	10.8	774
31	12.2	774	17	10.7	774
Apr. 1	12.2	774	18	10.5	774
2	12.2	774	19	10.3	774
3	12.2	774	20	10.2	774
4	12.3	774	21	10.1	774
5	12.3	780	22	10.0	774
6	12.3	780	23	9.75	774
7	12.3	780	24	9.6	774
8	12.4	785	25	9.5	774
9	12.4	785	26	9.4	774
10	12.4	785	27	9.3	774
11	12.4	785	28	9.2	774
12	12.55	792	29	9.1	774
13	12.5	790	30	9.0	774
14	12.3	780	July 1	8.9	774
15	12.2	780	2	8.8	774
16	12.2	774	3	8.7	774
17	12.0	764	4	8.6	774
18	12.1	769	5	8.5	774
19	12.1	769	6	8.4	774
20	12.0	764	7	8.3	774
21	12.1	769	8	8.2	774
22	12.1	769	9	8.1	774
23	12.2	774	10	8.0	774
24	12.4	785	11	7.9	774
25	12.2	774	12	7.8	774
26	12.3	780	13	7.7	774
27	12.2	774	14	7.6	774
28	12.1	769	15	7.5	774
29	12.0	764	16	7.4	774
30	12.0	764	17	7.3	774
May 1	11.9	759	18	7.2	774
2	11.9	759	19	7.1	774
3	12.0	764	20	7.0	774
4	11.9	759	21	6.9	774
5	11.9	759	22	6.8	774
6	12.1	769	23	6.7	774
7	12.1	769	24	6.6	774
8	12.2	774	25	6.5	774
9	12.2	774	26	6.4	774
10	12.2	774	27	6.3	774
11	12.3	780	28	6.2	774
12	12.2	774	29	6.1	774
13	12.1	769	30	6.0	774
14	12.1	769	Aug 1	5.9	774
15	12.1	769			

Widths between high-water banks.

No.	Locality.	M. R. C., 1860.	H. & A., 1861.	Remarks.
		<i>Feet.</i>	<i>Feet.</i>	
....	Cole Creek Point	1,985	*2,350	*Locality uncertain
....	Natches	4,122	*4,540	*Do.
....	Ellis Cliffs	1,985	*2,350	*Do.
....	Routh's Point	3,709	3,800	
....	Mouth of Red River	4,231	3,500	
....	4,000 feet below Red River	4,329	3,800	
....	8,000 feet below Red River	3,575	3,700	
....	12,000 feet below Red River	3,800	3,800	
....	Racconet, upper end	4,602	2,400	
....	Racconet, lower end	3,200	2,400	
....	Tunica Bend	3,476	*2,320	*Ellis's report.
1	Baton Rouge, Arsenal	3,181	3,900	
2	Baton Rouge, State House	2,657	2,850	
3	4,000 feet below State House	2,400	2,300	
4	8,000 feet below State House	2,581	2,650	
5	12,000 feet below State House	3,313	3,035	
6	16,000 feet below State House	3,313	2,400	
7	20,000 feet below State House	3,650	3,100	
8	24,000 feet below State House	3,609	3,400	
9	28,000 feet below State House	3,673	3,000	
10	32,000 feet below State House	3,313	2,800	
11	36,000 feet below State House	3,676	3,250	
12	40,000 feet below State House	3,300	3,400	
13	44,000 feet below State House	3,874	3,300	
14	48,000 feet below State House	3,492	3,350	
15	52,000 feet below State House	3,771	3,475	
16	56,000 feet below State House	3,700	3,350	
17	60,000 feet below State House	3,634	3,300	
18	64,000 feet below State House	3,820	2,450	
19	68,000 feet below State House	3,903	3,700	
20	Mouth of Bayou Manchac	3,606	3,900	
21	4,000 feet below Bayou Manchac	2,556	2,400	
22	8,000 feet below Bayou Manchac	2,377	2,300	
23	12,000 feet below Bayou Manchac	2,400	2,450	
24	16,000 feet below Bayou Manchac	3,543	3,250	
25	20,000 feet below Bayou Manchac	3,346	3,000	
26	24,000 feet below Bayou Manchac	2,706	2,400	
27	Mouth of Plaquemine Bayou	3,132	2,700	
28	4,000 feet below Plaquemine Bayou	2,953	2,750	
29	8,000 feet below Plaquemine Bayou	2,680	2,575	
30	12,000 feet below Plaquemine Bayou	2,344	2,930	
31	16,000 feet below Plaquemine Bayou	2,006	2,030	
32	20,000 feet below Plaquemine Bayou	3,083	2,000	
33	24,000 feet below Plaquemine Bayou	4,290	4,400	
34	28,000 feet below Plaquemine Bayou	3,543	3,500	
35	32,000 feet below Plaquemine Bayou	2,601	2,500	
36	36,000 feet below Plaquemine Bayou	2,400	2,400	
37	40,000 feet below Plaquemine Bayou	3,083	3,350	
38	44,000 feet below Plaquemine Bayou	2,723	2,700	
39	48,000 feet below Plaquemine Bayou	2,755	2,450	
40	52,000 feet below Plaquemine Bayou	2,601	2,450	
41	56,000 feet below Plaquemine Bayou	2,635	2,800	
42	Bayou Goula	4,105	3,750	
43	4,000 feet below Bayou Goula	3,444	3,250	
44	8,000 feet below Bayou Goula	3,314	2,650	
45	12,000 feet below Bayou Goula	2,090	2,650	
46	16,000 feet below Bayou Goula	3,400	2,500	
47	20,000 feet below Bayou Goula	2,478	2,250	
48	24,000 feet below Bayou Goula	2,400	2,400	
49	28,000 feet below Bayou Goula	3,624	2,500	
50	32,000 feet below Bayou Goula	3,304	3,100	
51	36,000 feet below Bayou Goula	3,903	3,500	
52	40,000 feet below Bayou Goula	3,336	3,700	
53	Opposite Claiborne Isle	2,962	3,400	
54	4,000 feet below Claiborne Isle	3,006	2,450	
55	8,000 feet below Claiborne Isle	2,310	2,800	
56	12,000 feet below Claiborne Isle	3,181	3,100	
57	16,000 feet below Claiborne Isle	2,853	3,000	
58	20,000 feet below Claiborne Isle	2,682	2,500	
59	Ashland plantation	2,682	2,550	
60	4,000 feet below plantation	2,640	3,550	
61	8,000 feet below plantation	2,939	3,500	
62	12,000 feet below plantation	3,280	3,000	
63	16,000 feet below plantation	3,627	3,000	
64	20,000 feet below plantation	3,657	3,450	
65	24,000 feet below plantation	2,290	3,000	
66	28,000 feet below plantation	2,705	2,700	
67	32,000 feet below plantation	2,857	3,000	
68	Donaldsonville	2,932	3,300	
	Mean of 68 sections	2,864	2,335	

Comparison of sections between Plaquemine and Donaldsonville.

Section.	Locality.	Area.		Maximum depth.		Difference of areas.	Reading of Baton Rouge gauge.		
		1881.	1882.	1881.	1882.		Date.	Read- ing.	Date.
1881.							1881.		1880.
O"	2½ miles below Plaquemine	183,825	181,000	103	100	- 2,825	Mar. 1	29.7	Mar. 1
J"	Arcadia Landing	108,250	100,250	101	102	- 8,000	Mar. 2	29.4	Mar. 2
J"	Just below Arcadia	120,750	97,500	105	112	- 23,250	Mar. 2	29.4	Mar. 2
H"	1 mile below Arcadia	119,250	118,250	96	96	- 6,000	Mar. 2	29.4	Mar. 2
G"	1½ miles below Arcadia	115,750	108,500	87	89	- 7,250	Mar. 2	29.4	Mar. 2
F"	1 mile above Brown's Landing	124,750	128,125	105	100	+ 3,875	Mar. 9	30.4	Mar. 9
E"	Near Brown's Landing	152,000	130,000	160	177	- 22,000	Mar. 10	30.4	Mar. 10
D"	1 mile below Brown's Landing	152,350	147,500	169	146	- 4,750	Mar. 10	30.4	Mar. 10
C"	1 mile below Brown's Landing	125,000	144,000	125	137	+ 19,000	Mar. 8	30.4	Mar. 8
A"	1 mile above Dunboine Landing	116,825	133,000	105	104	+ 14,175	Mar. 8	30.4	Mar. 8
X'	Ciphetus Landing	126,000	108,325	97	90	- 18,175	Mar. 10	30.4	Mar. 10
V'	1 mile above Bayou Goula	132,000	105,570	133	115	- 26,430	Mar. 10	30.4	Mar. 10
T'	1 mile below Bayou Goula	112,500	112,925	141	131	- 9,575	Mar. 13	30.5	Mar. 13
S'	1 mile below Bayou Goula	112,175	114,250	131	138	+ 2,075	Mar. 13	30.5	Mar. 13
P'	1½ miles above Belle Grove	148,500	163,750	156	159	+ 14,950	Mar. 13	30.5	Mar. 13
O'	1 mile above Belle Grove	112,250	117,625	105	109	+ 5,375	Mar. 14	30.5	Mar. 14
N'	Just above Belle Grove	124,825	130,500	110	116	+ 14,675	Mar. 14	30.5	Mar. 14
M'	Just below Belle Grove	119,250	100,150	97	97	- 10,100	Mar. 14	30.5	Mar. 14
J'	Just above Hard Times	112,675	93,075	74	76	- 20,600	Apr. 9	30.4	Mar. 12
I'	1 mile below Hard Times	108,500	97,575	144	105	- 10,925	Apr. 5	30.4	Mar. 12
F'	1 mile above Southwood	130,250	124,500	97	126	+ 5,250	Mar. 23	29.4	Mar. 12
E'	Just above Southwood	130,250	145,570	128	144	+ 15,320	Mar. 22	29.4	Mar. 14
C'	1 mile below Southwood	116,075	120,150	115	131	+ 4,075	Mar. 10	29.6	Mar. 15
A'	14 miles below Southwood	118,750	127,250	92	103	+ 8,500	Mar. 8	28.8	Mar. 15
X'	1 mile below Southwood	109,750	110,000	90	93	+ 250	Mar. 13	24.5	Mar. 15
V'	Just above Ashland	110,125	108,125	78	79	- 4,000	Feb. 12	24.4	Mar. 15
T'	1 mile below Ashland	124,375	127,750	89	107	+ 3,375	Feb. 10	24.4	Mar. 16
P'	1 mile above Acasnon	120,875	152,125	104	110	+ 31,250	Jan. 21	8.0	Mar. 16
O'	Just above Acasnon	119,625	119,000	90	105	+ 625	Jan. 15	13.5	Mar. 16
M'	1 mile below Acasnon	148,575	161,375	153	151	+ 12,800	Jan. 6	13.5	Mar. 16
							1880.		
S. L. 26	14 miles above Donaldsonville	119,500	120,250	116	115	+ 750	Dec. 28	10.5	Mar. 16
247	1 mile above Donaldsonville	120,500	140,000	103	112	+ 25,500	Dec. 17	20.1	Mar. 16

* Soundings taken in April and May, dates not known. Baton Rouge gauge ranges between 29.9 and 20.2.

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

	Square ft.
Mean area of section in 1881.....	122, 9
Mean area of section in 1883.....	123, 6
Difference of means.....	7

Depths are referred to the plane of 1883.

Thirty-two sections which are identical with or come very near the sections of 1881 have been plotted and are shown on Plates 9, 10, and 11.

The sections of the Coast Survey and Geodetic Survey are copied from tracings (8. 4) on file in this office. The soundings there shown were reduced to the "average low water of the year" during which they were taken. The stage of the river when the soundings were made was but a little below the high water of 1881. A comparison of the sections is given in the above table, the area of the sections being measured below the lowest water surface, or that given by the United States Coast and Geodetic Survey sections. The sections were plotted and the areas measured with a planimeter by Assistant H. B. Wood.

Very respectfully, your obedient servant,

J. A. OCKERSON,
Assistant Engineer.

First Lieut. SMITH S. LEACH,
Secretary Mississippi River Commission.

APPENDIX H.

REPORT OF CAPTAIN CLINTON B. SEARS, CORPS OF ENGINEERS, UNITED STATES ARMY, EXECUTIVE OFFICER, DEPARTMENT OF CONSTRUCTION.

DEPARTMENT OF CONSTRUCTION,
Saint Louis, Mo., November 5, 1883.

COLONEL: In accordance with your circular letter of September 6, 1883, I have the honor to submit the following report of operations performed under my immediate supervision as executive officer, construction department, Mississippi River Commission, since the date of my last annual report, which was brought up to December 1, 1882.

My office has been fully employed during the past eleven months, in the construction of the floating plant, recommended by the Commission, and approved by the honorable the Secretary of War, in its distribution to the various works; in the charter of steamers; in the purchase and supply of stone, wire, coal, subsistence stores, and other material required on the several reaches; in the care of the fleet at Cairo, consisting of coal and floating plant not in use; in the repair of boats and barges, and in the management of the general service steamers.

The general system of purchase and supply was outlined in my last report, and need not be repeated here. This system, as there stated, has been continued. Special freight rates have been secured from commercial steamers and from the railroads, and shipments have been made by one or the other, as happened to be more favorable at the time, whenever the shipment has been so small as not to justify bringing one of our steamers to Saint Louis.

During the winter, when ice has closed the river down to Cairo, supplies have been shipped by rail to Cairo, and hence by our steamers. The steamers Mississippi and Etheridge have been kept in almost constant use towing our barges and other plant. In August the Etheridge, in bringing down a tow from Louisville, got aground at Flint Island bar, in the Ohio River, and was, after some difficulty, pulled off into deeper water above the bar. As there appeared to be no prospect of getting her down for some weeks, owing to low water, she was laid up at Louisville, under charge of watchmen, and her crew transferred to the steamer Jack Frost. Her tow was taken down by the Reindeer, a small light-draught boat, chartered temporarily for the purpose. October 16, the Etheridge reached Cairo in tow of the Minnetonka, and was put in commission immediately. August 7, the steamer John Dippold, a powerful boat belonging to the Mississippi Valley Transportation Company, was chartered for the general service at \$50 per day, for two weeks, or longer, if necessary. She was kept in constant use until October 7, when she was turned in to the owners. Another large steamer, the Jack Frost, was chartered for the general service, September 15, 1883, at \$50 per day, for such time as the Etheridge might be laid up. She was surrendered to her owners October 16, 1883, and the same day the new tow-boat, Minnetonka, was chartered for three months, at \$60 a day, with the privilege of pur-

5,000, less charter money paid. At present, therefore, we have in the general, three steamers, two belonging to the United States and one chartered. In the ten months ending October 31, 1883, the Mississippi has moved 489 pieces over various distances, amounting to one piece moved 113,177 miles at a cost of 33.15 cents per mile. Her average daily expenses while doing this work have been \$212.76, which includes fuel, pay, and subsistence of crew, and supplies and other running expenses, but does not include interest on her cost, nor the cost of repairs. She has made several trips with the Commission or the construction committee, the running expenses of which have been paid by the secretary of the Commission out of the appropriation for Mississippi River Commission.

Meridith during the eleven months has moved 377 pieces over various distances, amounting to one piece moved 104,861 miles, at a cost of 22 cents per mile. Her average daily expenses have been \$68.84.

Polk, while under charter, moved 139 pieces over various distances, amounting to one piece moved 37,930 miles, at a cost of 35.3 cents per mile. Her daily expenses, excluding charter, averaged \$212.76. She was in service 63 days. The Jackdaw, while under charter, moved 69 pieces, amounting to one piece moved 10,359 miles at a cost of 49.4 cents per mile. Her daily expenses, including charter, averaged \$124. She was under charter 31 days. These two steamers would have shown better results, from an economical point of view, had circumstances permitted us to work them up to their full capacities. For reasons to be hereafter explained this was impracticable.

Netonka has not been in service sufficiently long to enable me to report on her as being a fair average as to her daily expenses. She was built for our work, and has been left undone by her owners to make her an acceptable boat for that purpose.

She is fully equipped in every respect for towing. My original arrangement with her owners was to charter her for six months, but owing to their delay in getting her, I cut this down to three months with the privilege of a renewal, if necessary. Summing up the above, I find that our general-service steamers have averaged \$5.75 per day each, as to running expenses, and have moved 1,074 pieces over various distances, or one piece 266,327 miles, at an average cost of 33.15 cents per mile. Estimating each piece at 100 tons (a low estimate) will make the cost per ton one-third cent. Had we had this towing done by commercial steamers it would have cost about two-fifths cent per ton mile, and we would have been subjected to vexatious and expensive delays.

Our captains have had great trouble in keeping efficient crews, especially in the sickly season. Government boats pay no hospital dues, and when men are sick they forfeit their right to treatment and care at the marine hospitals, although the benefit of dues previously paid when on commercial steamers. The summer and fall seasons have been very unhealthy on the lower river, and several of our boats have been disabled for want of effective crews.

I earnestly recommend that the Commission take some action towards securing through the Treasury Department or by Congress, some remedy for this. It seems to me but proper that men employed on United States civil vessels should have the right to hospital treatment. Practically this is at present denied them, whether proper or not, it would certainly add to the efficiency of our service if such medical aid could be given.

Chartered steamer Success, in use on Lake Providence Reach, was returned to us on April 20, 1883, not having proved satisfactory.

On July 1, 1883, I chartered the steamer Graham for six months, at \$15 a day, for use on the Memphis Reach. July 1 this charter was extended three months with the privilege of six months. She is still under charter.

On July 2, 1883, I bought the steamer Charlie De Pauw for \$17,404, she having proved herself a valuable and efficient boat. She was kept in constant use on Lake Providence Reach until August, when she broke her shaft. She was sent to Saint Louis for a new shaft and a general overhauling. After being thoroughly repaired and repainted, her name was changed to the Vidalia, and she was returned to Lake Providence Reach, where she is doing good work.

On August 1, 1883, I chartered the steamer J. C. Fisher, for the Lake Providence Reach, at \$15 a day for six months. Though her charter has expired we still retain her, in order to have use for her until navigation closes.

On August 1, 1883, I chartered the steamer Little Eagle No. 2, for use on the Plum Point Reach, at \$17.50 per day for seven months.

On August 9, 1883, I chartered the steamer Pearl, for use on Lake Providence Reach, at \$17.50 per day for six months.

On September 2, 1883, I chartered the steamer Little Andy Fulton, for use on Lake Providence Reach, at \$30 a day for three months.

Two launches have been purchased for use at New Orleans, and another launch at Plum Point Reach.

ynopsis is herewith submitted, viz:

team tow-boat.....	\$17,404 00
team tug.....	5,000 00
team launch.....	3,000 00
Mattress-boats.....	40,360 00
Screen-boats.....	6,000 00
Quarter-boats.....	34,463 00
Barges.....	275,127 40
Pile-drivers.....	142,661 76
Machine-shop boats (balance).....	9,871 25
Pumping-boat.....	1,500 00
Whitehall boats.....	339 00
skiffs.....	2,126 00
ft of plant.....	17,246 28
ellaneous (anchors, hoisting-engines, boilers, electric-light outfits, pump and derrick).....	9,988 78
pe.....	23,114 50
	<hr/>
	588,201 97

Of this amount \$142,963.68 was for plant now in use for the general service. An
lized statement of my expenditures from December 1, 1882, to October 31, 1883,
companies this report, and is marked B.
The following is a classified statement of said expenditure:

SCHEDULE OF EXPENDITURES BY CAPTAIN CLINTON B. SEARS, EXECUTIVE OFFICER,
CONSTRUCTION DEPARTMENT, MISSISSIPPI RIVER COMMISSION, ON ACCOUNT OF
APPROPRIATION FOR IMPROVING MISSISSIPPI RIVER, FROM NOVEMBER 30, 1882, TO
OCTOBER 31, 1883.

General service.

Office:		
Pay-roll.....	\$8,469 83	
Furniture and office outfit.....	387 45	
Stationery.....	371 12	
Transportation and traveling expenses.....	1,400 85	
Ice and water.....	79 91	
Rent and repairs.....	679 70	
Gas and fuel.....	170 97	
Telegraphing.....	344 75	
Mileage.....	1,289 06	
Fuel for Captain Sears.....	160 48	
	<hr/>	\$13,354 12

COAL FLEET.

Material and supplies.....	\$369 57	
Plant and outfit.....	336 93	
Transportation.....	174 84	
Labor.....	16 00	
Ice.....	7 59	
Use of public property.....	4,074 00	
Repairs.....	30 33	
	<hr/>	5,009 26

STONE DEPOT.

Inspection and administration.....	\$13 50	
Material and supplies.....	338 06	
Plant and outfit.....	1,453 90	
Transportation.....	14 35	
Labor.....	2,681 00	
Subsistence.....	54 00	
	<hr/>	4,554 81

STEAMER MISSISSIPPI.

Office expenses.....	\$46 51	
Material and supplies.....	2,133 99	
Fuel.....	33 21	
Plant and outfit.....	224 17	
Transportation and steamer expenses.....	12,832 85	
Repairs.....	1,517 42	
Labor.....	694 59	
Subsistence.....	5,061 36	
Use of public property.....	221 50	
	<hr/>	22,765 60

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

STEAMER ENOLA KEMMERER.

Office expenses.....	\$65 31
Material and supplies.....	2,172 00
Fuel.....	1,433 50
Transportation and steamer expenses.....	12,952 72
Labor.....	1,003 94
Repairs.....	498 20
Subsistence.....	3,726 74
.....	207 99

\$21,050

STEAMER JACK DUFFOLD.

Office expenses.....	\$8 40
Material and supplies.....	1,129 20
Fuel.....	3,665 00
Repairs.....	14 35
Transportation and steamer expenses.....	6,372 65
Labor.....	40 75
Subsistence.....	1,208 60

12,850

STEAMER JACK FRIZZ.

Office expenses.....	\$12 07
Material and supplies.....	1,739 02
Fuel and outfit.....	19 25
Fuel.....	1,131 19
Transportation and steamer expenses.....	3,340 42
Labor.....	10 00
Subsistence.....	554 01

6,896

STEAMER BENTON.

Material and supplies.....	\$3 92
Fuel.....	153 50
Labor.....	8 00
Transportation and steamer expenses.....	459 98
Subsistence.....	79 05

690

STEAMER MICKENHILL.

Office expenses.....	\$10 21
Material and supplies.....	360 09
Transportation and steamer expenses.....	866 34
Fuel.....	427 60
Labor.....	23 92
Subsistence.....	302 58

1,990

Total amount of general service..... 89,732

FOR NEW MADRID REACH.

Inspection and administration.....	\$461 07
Office expenses.....	3 00
Plant and outfit.....	127,195 63
Transportation.....	1,870 66
Material and supplies.....	686 18
Labor.....	20 00
Repairs to plant.....	9 50
Care of public property.....	18 50

190,264

FOR PLUM POINT REACH.

Inspection and administration.....	\$1,383 42
Office expenses.....	200 25
Material and supplies.....	64,662 67
Fuel.....	1,765 26
Plant and outfit.....	88,596 73
Transportation.....	5,674 28
Repairs to plant.....	6,929 03
Labor.....	401 49
Subsistence.....	32,191 86
Care of public property.....	622 00

202,486

T T—REPORT OF MISSISSIPPI RIVER COMMISSION. 2697

FOR MEMPHIS REACH.

nd administration.....	\$1,250 16	
es.....	2 00	
supplies	12,956 21	
tfitt	121,791 54	
on	5,712 24	
ant	407 45	
.....	115 50	
.....	1,277 92	
ic property.....	260 65	
		\$143,773 67

FOR LAKE PROVIDENCE REACH.

nd administration	\$1,934 49	
ses.....	13 10	
l supplies	35,855 35	
.....	844 00	
ntfitt.....	144,152 84	
ion.....	13,064 08	
lant	2,734 68	
.....	432 54	
.....	27,257 94	
lic property	586 46	
		226,875 48

account on improving Mississippi River..... 853,133 57

OF EXPENDITURES ON ACCOUNT OF APPROPRIATION FOR IMPROVING HAR- NEW ORLEANS, LA., FROM NOVEMBER 30, 1882, TO OCTOBER 31, 1883.

nd administration	\$299 67	
ses.....	10 00	
d supplies.....	3,290 03	
ntfitt.....	24,460 97	
ion	677 50	
lant	159 30	
.....	168 97	
.....	497 45	
olic property.....	6 00	
		29,569 89

OF EXPENDITURES ON ACCOUNT OF APPROPRIATION FOR IMPROVING RED RIVER, LOUISIANA, FROM NOVEMBER 30, 1882, TO OCTOBER 31, 1883.

ses.....	\$10 00	
d supplies.....	277 15	
.....	614 62	
ntfitt.....	4,524 00	
.....	56 37	
.....	910 60	
ion.....	26 00	
lic property.....	10 00	
		6,428 74

CLASSIFIED SUMMARY.

or :		
nd outfit.....	\$574,189 46	
l and supplies	126,043 44	
ence.....	73,122 11	
ortation.....	65,439 76	
to plant	12,866 00	
nd gas.....	8,946 43	
xpenses (including pay-rolls).....	8,848 68	
f public property	6,007 10	
tion and administration.....	5,342 31	
.....	5,167 33	
.....	1,289 06	
nd repairs	679 70	
ture and office outfit.....	387 45	
ery.....	371 12	
raphing	344 75	
nd water.....	87 50	
		889,132 20

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

GENERAL SUMMARY.

Improving harbor at New Orleans, La	\$29,569 89	
For improving mouth of Red River, Louisiana	6,428 74	\$35,998 63
For New Madrid Reach	190,264 54	
For New Madrid Reach, proportion of general service	4,605 84	194,870 38
For Plum Point Reach	202,486 99	
For Plum Point Reach, proportion of general service	38,144 57	240,631 56
For Memphis Reach	143,773 67	
For Memphis Reach, proportion of general service	8,637 91	152,411 58
For Lake Providence Reach	226,875 48	
For Lake Providence Reach, proportion of general service ..	38,144 57	265,020 05
		\$889,982 83

The above amount, \$89,732.89, for the general service, has been divided up among the several allotments, as shown in the general summary. Whenever an expense has been specifically for any particular reach, it has, of course, been charged to that reach. There have been, however, large expenditures which it has been impossible without complicating accounts very seriously, to definitely assign to any particular allotment. These I have divided among the several allotments in proportion to their respective amounts, duly considering the service each reach has received.

When towing for Red River and New Orleans has been done by the general steamers, the necessary expense has been met by assigning sufficient of the vote of said steamers for payment by these appropriations. This method of dividing general service expenses is inaccurate, clumsy, and unsatisfactory, and makes accounts very complicated. I would recommend, therefore, that if another appropriation be given, a special allotment be made for the general service, with authority for me to draw on the several allotments for such amounts as cover specific expenditures for the corresponding reaches. I would further recommend that the officer in charge of the fourth district purchase all his own supplies except such as he may deem convenient to have me buy and ship, as stone and coal. New Orleans is a better market for this district than Saint Louis.

I submit the following financial statement of all funds expended under the commission of the Mississippi River Commission to November 1, 1883.

FINANCIAL STATEMENT.

(July 1, 1882, to October 31, 1883.)

NEW MADRID REACH

	By Captain Sears.	By Captain Knight.	Total
Drawn from Treasury	\$207,000 00	\$5,500 00	\$212,500 00
Expended	204,572 16	4,498 95	209,071 11
Balances in hand, available November 1, 1883 ..	2,427 84	1,001 05	3,428 89

All the allotment, viz, \$212,500, has been drawn.

PLUM POINT REACH.

	By Captain Sears.	By Captain Knight.	Total
Balances on hand from previous appropriation fiscal year ending June 30, 1882	\$10,232 11	\$12,424 90	\$22,657 01
Drawn from Treasury of current appropriation	314,000 00	635,000 00	949,000 00
Total to be accounted for	324,232 11	647,424 90	971,657 01
Expended	298,866 96	561,917 16	860,784 12
Balances in hand	25,365 15	85,507 74	110,872 89

X T T—REPORT OF MISSISSIPPI RIVER COMMISSION. 2699

from current appropriation	\$1,000,000 00
in Treasury	949,000 00
in Treasury	51,000 00
in hands of disbursing officers	110,872 89
on November 1, 1883	160,872 89

MEMPHIS REACH AND HARBOR.

	By Captain Sears.	By Major Miller.	Total.
in Treasury, &c	\$167,000 00	\$125,000 00	\$292,000 00
.....	162,379 64	105,890 00	268,269 64
on hand	4,620 36	19,110 00	23,730 36

ent from current appropriation	\$325,000 00
.....	292,000 00
in Treasury	33,000 00
in hands of disbursing officers	23,730 36
on November 1, 1883	56,730 36

SURVEY OF HELENA REACH.

by Major Miller	\$8,000 00
ed by Major Miller	7,511 29
available November 1, 1883	488 71

the allotment, viz, \$8,000, has been drawn.

LAKE PROVIDENCE REACH.

	By Captain Sears.	By Captain Marshall.	Total.
on hand from appropriation for fiscal year June 30, 1882	\$10,232 11	\$3,341 74	\$13,573 85
in Treasury of current appropriation	354,000 00	459,000 00	813,000 00
to be accounted for	364,232 11	462,341 74	826,573 85
d	359,531 33	447,714 59	807,245 92
ances in hand	4,700 78	14,627 15	19,327 93

ent from current appropriation	\$950,000 00
.....	813,000 00
in Treasury	137,000 00
in hands of disbursing officers	19,327 93
on November 1, 1883	156,327 93

VICKSBURG HARBOR.

by Captain Marshall	\$50,000 00
led by Captain Marshall	44,522 40
in hand	5,477 60
ent from current appropriation	100,000 00
.....	50,000 00
in Treasury	50,000 00
in hand	5,477 60
on November 1, 1883	55,477 60

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

NEW ORLEANS HARBOR.

	By Captain Stann.	By Major Stock- ney.	Total.
July 1, 1902, from previous appor-			204,100
By 1, 1902		25,307 22	25,307 22
Total to be accounted for		25,307 22	25,307 22
From the Treasury	225,000 00	2,307 22	227,307 22
Expended	22,300 00	2,307 22	24,607 22
Balance in hand	2,697 22	-2,307 22	300 00

Available July 1, 1902	\$147,700
Drawn	41,200
Balance in Treasury	106,500
Balance in hands of	2,000
Available November	108,500

SAINT FRANCIS HARBOR, SMOOK DISTRICT.

From the Treasury	\$5,000
Expended by Captain	3,312 00
Balance available for	1,688 00
All the allotment, viz. \$5,000	500

SAINT FRANCIS HARBOR, SMOOK DISTRICT.

From the Treasury	\$4,000 00
Expended by Major Miller	3,212 00
Balance available for	788 00

The amount of \$4 00 has been drawn.

MOUTH OF RED RIVER.

	By Captain Stann.	By Captain Stann.	By Major Stock- ney.	Total.
From the Treasury	\$25,000 00	\$5,000 00	\$25,000 00	\$55,000 00
Expended	7,000 00	1,000 00	27,000 00	35,000 00
Balance in hand	18,000 00	4,000 00	-2,000 00	20,000 00

From the Treasury September 1, 1902

From the Treasury	\$30,812 40
From the Treasury	37,812 40
Balance in Treasury	53,000 00
Balance in hands of	-14,158 96
Available November 1, 1902	38,841 04

NATCHEZ AND VIDALIA.

	By Captain Miller.	By Major Stick- ney.	Total.
able June 30, 1882, from former appropriations..	\$8, 252 04	\$8, 252 04
ded	722 95	\$2, 197 67	2, 920 62
Balance available November 1, 1883	*7, 529 09	—2, 197 67	5, 331 42

* Transferred to Major Stickney, September 9, 1882.

OBSERVATIONS AT CARROLLTON, LA.

he allotment of \$3,000 from the appropriation for improving Mississippi River has
a drawn and expended by Major Stickney. The observations are now being car-
l on with an allotment from the appropriation for Mississippi River Commission.

SURVEY OF UNLEVEED FRONTS IN THIRD DISTRICT.

own by Captain Marshall	\$1, 000 00
ended by Captain Marshall	496 96
Balance available November 1, 1883.....	503 04

If the allotment, viz : \$1,000, has been drawn.

SURVEY OF UNLEVEED FRONTS IN FOURTH DISTRICT.

stment	\$1, 000 00
one of which has been drawn or expended.	

SURVEY OF CUBITT'S GAP.

own by Major Stickney	\$300 00
ended by Major Stickney	137 14
Balance available November 1, 1883.....	162 86

If the allotment, viz : \$300, has been drawn.

DELTA POINT, LOUISIANA.

ance from another appropriation	\$25, 770 13
stment from appropriation for improving Mississippi River	50, 000 00
Available June 30, 1882	75, 770 13
ended by Captain Marshall	75, 762 49
Balance on hand	7 64

This work is finished.

CHOCTAW BEND SURVEY.

own by Captain Marshall	\$2, 700 00
ended by Captain Marshall	2, 679 86
Balance in hand	20 14

stment from current appropriation	4, 000 00
own	2, 700 00

Balance in Treasury	1, 300 00
Balance in hand	20 14

Available for transfer to other works	1, 320 14
---	-----------

This survey has been completed.

27

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

	\$106
	102
	— 2
	110
	100
	10
	— 2
Deo	7
vi	
Key	
	\$426
	251
	174
Avail	
Draw	
Datar	1, 315
Datar	1, 285
Availat	30
	230
	260

SUMMARY.

allotments	\$3,978,800 00
allotted and in Treasury	144,200 00
allotted and in hands of Captain Sears, from sale of fuel to himself.	126 00
Total appropriation	4,123,126 00
from last appropriation	36,230 86
from other appropriations	272,628 38
Total	4,431,985 24
Expended for as follows:	
U. S. Treasury, not drawn	607,025 90
allotted	3,433,716 04
in hands of disbursing officers	391,243 30
Total	4,431,985 24
available November 1, 1883, for works carried on under the Mis- sissippi River Commission	998,269 20

greater portion of this available balance will be exhausted by January 1, 1884. A large amount of public property to be taken care of, and the uncertainty con-
cerning the time when another appropriation will be made, makes it desirable to re-
quire sufficient funds to amply provide for such care of property. I would, therefore,
recommend to the Commission that the work on the several reaches be brought to a
close on an early date, and the forces be reduced to the lowest point compatible with
proper protection of the works, the care of public property, and the settlement
of claims.

which is respectfully submitted.

CLINTON B. SEARS,
Captain, Engineers, U. S. A.,
Executive Officer, Construction Dep't, M. R. C.

Col. C. B. COMSTOCK,
Corps of Engineers, U. S. A.,
President Mississippi River Commission.

that is first presented by Capt. H. Moore, Corps of Engineers, U. S. A., from December 1, 1903 to November 1, 1904.

Date		Average first cost of (c.s.)	Total cost	Allotment or appropriation		Balance	
1892.	Dec. 7						
	1						
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10						
	11						
	12						
	13						
	14						
	15						
	16						
	17						
	18						
	19						
	20						
	21						
	22						
	23						
	24						
	25						
	26						
	27						
	28						
	29						
	30						
	31						
	32						
	33						
	34						
	35						
	36						
	37						
	38						
	39						
	40						
	41						
	42						
	43						
	44						
	45						
	46						
	47						
	48						
	49						
	50						
	51						
	52						
	53						
	54						
	55						
	56						
	57						
	58						
	59						
	60						
	61						
	62						
	63						
	64						
	65						
	66						
	67						
	68						
	69						
	70						
	71						
	72						
	73						
	74						
	75						
	76						
	77						
	78						
	79						
	80						

Itemized statement of expenditures for improving the Mississippi River from December 1, 1882, to October 31, 1883, both inclusive—Continued.

OFFICE—Continued.

Date.	Voucher number.	For what expended.	Pay-roll.	Furniture and outfit.	Stationery.	Transportation and traveling expenses.	Ice and water.	Rent and repairs.	Gas and fuel.	Telegrams.	Mileage.	Fuel for Capt. O. H. Beers.	Total.
1883.													
Oct. 26	86	Pay-roll	\$748 50			\$10 50							
" 1	87	Travelling expenses				11 80							
" 1	88	do				12 85							
" 1	89	do					96 00						
" 24	92	Sprinkling street.											
" 25	102	Telegrams								\$80 64			
" 26	114	Fuel										\$28 80	
		Total	\$1,400 00	\$500 00	\$877 67	1,400 05	78 81	\$600 00	\$170 97	\$44 70	\$1,268 13	160 48	\$28,864 13

Itemized statement of expenditures for improving the Mississippi River from December 1, 1882, to October 31, 1883, both inclusive—Continued.

OFFICE—Continued.

Date	Voucher number.	For what expended.	Pay-roll	Furniture and outfit.	Stationery.	Transportation and traveling expenses.	Ice and water.	Repairs and repairs.	Gas and fuel.	Telegrams.	Mileage.	Fuel for Capt. O. H. Beers.	Total
Dec 27	86	Pay-roll.....	\$748 50										
Dec 27	87	Traveling expenses.....				\$10 80							
Dec 28	88	do.....				11 80							
Dec 28	89	do.....				12 85							
Dec 28	90	Drinking water.....					\$6 00						
Dec 28	91	Telegrams.....								\$80 54			
Dec 28	92	Fuel.....										\$23 60	
Dec 28	93	Total.....	\$3,400 83	\$300 56	\$677 47	1,400 85	79 91	\$620 85	\$170 97	344 75	\$1,260 13	100 48	\$13,364 13

Material and miscellaneous exp.	Fuel.	Cost of plant.	Transportation and steamer expenses.	Repairs.	Labor on plant and construction.	Subsistence.	Care of public prop- erty.	Total.
\$40 00								
13 33							\$150 00	
10 78							106 00	
							639 25	
56 60			\$115 76					
3 81								
77 12							166 00	
10 44								
							406 00	
							50 00	
							341 50	
13 90								
4 53							140 00	
							166 00	
							301 00	
				\$14 68				
		\$22 50						
1 29			1 00				253 90	
				\$ 00				
			100 00					
			14 87					
		\$14 43					301 00	
			6 35					
0							285 00	
5								

RT OF THE CHIEF OF ENGINEERS,

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1892, to October 31, 1893, both inclusive—Continued.

COAL FLEET—Continued.

[illegible]

Mar.	24	Substance																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
------	----	-----------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

MEMBER OF THE CHIEF OF ENGINEERS, U. S. ARMY.

[illegible]

RODRIGUEZ VIKTOR EMIL STERIDGER

[illegible]

[illegible]

DATE	DESCRIPTION	AMOUNT	TOTAL	REMARKS
May 1	Pay-roll (April)	100.00	100.00	
May 1	Rego	1.00	101.00	
May 1	Labor	1.00	102.00	
May 1	Subsistence	1.00	103.00	
May 1	Meat	1.00	104.00	
May 1	Labor	1.00	105.00	
May 1	Oil	1.00	106.00	
May 1	Pump	1.00	107.00	
May 1	Ice	1.00	108.00	
May 1	Labor and material	1.00	109.00	
May 1	Traveling expenses	1.00	110.00	
May 1	Supplies	1.00	111.00	
May 1	Subsistence	1.00	112.00	
May 1	Transportation	1.00	113.00	
May 1	Meat	1.00	114.00	
May 1	Subsistence	1.00	115.00	
May 1	Labor	1.00	116.00	
May 1	Rego	1.00	117.00	
May 1	Meat	1.00	118.00	
May 1	Subsistence	1.00	119.00	
May 1	Supplies	1.00	120.00	
May 1	Clock	1.00	121.00	
May 1	Pay-roll (May)	100.00	221.00	
May 1	Labor	1.00	222.00	
May 1	Rego	1.00	223.00	
May 1	Meat	1.00	224.00	
May 1	Subsistence	1.00	225.00	
May 1	Supplies	1.00	226.00	
May 1	Clock	1.00	227.00	
May 1	Pay-roll (May)	100.00	327.00	
May 1	Labor	1.00	328.00	
May 1	Rego	1.00	329.00	
May 1	Meat	1.00	330.00	
May 1	Subsistence	1.00	331.00	
May 1	Supplies	1.00	332.00	
May 1	Clock	1.00	333.00	
May 1	Pay-roll (May)	100.00	433.00	
May 1	Labor	1.00	434.00	
May 1	Rego	1.00	435.00	
May 1	Meat	1.00	436.00	
May 1	Subsistence	1.00	437.00	
May 1	Supplies	1.00	438.00	
May 1	Clock	1.00	439.00	
May 1	Pay-roll (May)	100.00	539.00	
May 1	Labor	1.00	540.00	
May 1	Rego	1.00	541.00	
May 1	Meat	1.00	542.00	
May 1	Subsistence	1.00	543.00	
May 1	Supplies	1.00	544.00	
May 1	Clock	1.00	545.00	
May 1	Pay-roll (May)	100.00	645.00	
May 1	Labor	1.00	646.00	
May 1	Rego	1.00	647.00	
May 1	Meat	1.00	648.00	
May 1	Subsistence	1.00	649.00	
May 1	Supplies	1.00	650.00	
May 1	Clock	1.00	651.00	
May 1	Pay-roll (May)	100.00	751.00	
May 1	Labor	1.00	752.00	
May 1	Rego	1.00	753.00	
May 1	Meat	1.00	754.00	
May 1	Subsistence	1.00	755.00	
May 1	Supplies	1.00	756.00	
May 1	Clock	1.00	757.00	
May 1	Pay-roll (May)	100.00	857.00	
May 1	Labor	1.00	858.00	
May 1	Rego	1.00	859.00	
May 1	Meat	1.00	860.00	
May 1	Subsistence	1.00	861.00	
May 1	Supplies	1.00	862.00	
May 1	Clock	1.00	863.00	
May 1	Pay-roll (May)	100.00	963.00	
May 1	Labor	1.00	964.00	
May 1	Rego	1.00	965.00	
May 1	Meat	1.00	966.00	
May 1	Subsistence	1.00	967.00	
May 1	Supplies	1.00	968.00	
May 1	Clock	1.00	969.00	
May 1	Pay-roll (May)	100.00	1069.00	
May 1	Labor	1.00	1070.00	
May 1	Rego	1.00	1071.00	
May 1	Meat	1.00	1072.00	
May 1	Subsistence	1.00	1073.00	
May 1	Supplies	1.00	1074.00	
May 1	Clock	1.00	1075.00	
May 1	Pay-roll (May)	100.00	1175.00	
May 1	Labor	1.00	1176.00	
May 1	Rego	1.00	1177.00	
May 1	Meat	1.00	1178.00	

Remitted statement of expenditures for expenses of the 1st Cavalry Division, 1900 to 1901, and for the 1st Cavalry Division, 1902 to 1903.

1900 to 1901, and for the 1st Cavalry Division, 1902 to 1903.

Date.	Voucher number.	For what expended.	Amount.	Balance.	Amount.	Balance.	Amount.	Balance.	Amount.	Balance.	Amount.	Balance.
1900												
May 29	357	Liner boxes										
May 29	360	Labor										
May 29	361	Lumber, repairs										
May 29	362	Labor										
May 29	363	Subsistence										
June 18	365	Meat										
June 18	371	Ice										
June 25	403	Repairs										
June 30	412	Pay-roll (June)										
May 29	413	Labor										
May 29	414	do										
May 29	415	Supplies										
July 3	1	Repairs										
July 2	2	Subsistence										
July 2	3	do										
July 3	9	do										
July 5	16	Supplies										
July 6	24	Repairs										
July 6	29	Supplies										
July 14	49	Repairs										
July 13	52	Subsistence										
July 14	54	Repairs										
July 16	58	Supplies										
July 16	62	Subsistence										
July 17	65	Supplies										
July 17	66	Repairs										
July 19	68	Subsistence										
July 19	69	do										
July 19	71	Repairs										
July 24	73	Supplies										

Amount.

Amount.

Amount.

Amount.

Amount.

Amount.

Amount.

Amount.

Amount.

Amount.

Amount.

Aug.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	
------	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	--

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1892, to October 31, 1893, both inclusive—Continued.

STEAMER EMMA ETHERIDGE—Continued.

Number.	For what expended.	Inspection and maintenance.	Other expenses.	Fuel and oil.	Cost of plant.	Transportation and steamer expenses.	Repairs.	Labor on plant and construction.	Subsistence.	Care of public prop- erty.	Total.
123	Pay roll					518 61			68 68		587 29
123	do					614 00					614 00
229	Totals		65 31	2,310 23	964 00	1,450 60	81,003 94	8564 90	2,911 49	214 46	89,654 44

CHARTERED STEAMER JOHN DIPPOLD.

Month	Item	Quantity	Unit Price	Total
Sept.	Coal	111	60.00	6,660.00
	Subsistence	213	1.00	213.00
	Lumber	235	1.00	235.00
	Labor	237	1.00	237.00
	Labor and material	238	1.00	238.00
	Supplies	242	1.00	242.00
	Subsistence	243	1.00	243.00
	do	244	1.00	244.00
	do	245	1.00	245.00
	do	246	1.00	246.00
Aug.	Charter	247	1.00	247.00
	Coal	248	1.00	248.00
	Subsistence	249	1.00	249.00
	Pay-roll	250	1.00	250.00
	Stores and supplies	251	1.00	251.00
	Subsistence	252	1.00	252.00
	Transportation	253	1.00	253.00
	do	254	1.00	254.00
	Subsistence	255	1.00	255.00
	do	256	1.00	256.00
Sept.	Coal	257	1.00	257.00
	Subsistence	258	1.00	258.00
	do	259	1.00	259.00
	do	260	1.00	260.00
	do	261	1.00	261.00
	do	262	1.00	262.00
	do	263	1.00	263.00
	do	264	1.00	264.00
	do	265	1.00	265.00
	do	266	1.00	266.00
Oct.	Charter	267	1.00	267.00
	Coal	268	1.00	268.00
	Subsistence	269	1.00	269.00
	Pay-roll	270	1.00	270.00
	Stores and supplies	271	1.00	271.00
	Subsistence	272	1.00	272.00
	Transportation	273	1.00	273.00
	do	274	1.00	274.00
	Subsistence (fee)	275	1.00	275.00
	do	276	1.00	276.00

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

from a variance of approximately the Minorities from December 1, 1962, to October 31, 1962, both inclusive--Continued.

THE AMERICAN PEOPLE'S CHOICE

[illegible][illegible][illegible]

Abstract

ITALIANO STEINBERG

Account	Debit	Credit	Balance
1000		100.00	100.00
1010		100.00	200.00
1020		100.00	300.00
1030		100.00	400.00
1040		100.00	500.00
1050		100.00	600.00
1060		100.00	700.00
1070		100.00	800.00
1080		100.00	900.00
1090		100.00	1000.00
1100		100.00	1100.00
1110		100.00	1200.00
1120		100.00	1300.00
1130		100.00	1400.00
1140		100.00	1500.00
1150		100.00	1600.00
1160		100.00	1700.00
1170		100.00	1800.00
1180		100.00	1900.00
1190		100.00	2000.00
1200		100.00	2100.00
1210		100.00	2200.00
1220		100.00	2300.00
1230		100.00	2400.00
1240		100.00	2500.00
1250		100.00	2600.00
1260		100.00	2700.00
1270		100.00	2800.00
1280		100.00	2900.00
1290		100.00	3000.00
1300		100.00	3100.00
1310		100.00	3200.00
1320		100.00	3300.00
1330		100.00	3400.00
1340		100.00	3500.00
1350		100.00	3600.00
1360		100.00	3700.00
1370		100.00	3800.00
1380		100.00	3900.00
1390		100.00	4000.00
1400		100.00	4100.00
1410		100.00	4200.00
1420		100.00	4300.00
1430		100.00	4400.00
1440		100.00	4500.00
1450		100.00	4600.00
1460		100.00	4700.00
1470		100.00	4800.00
1480		100.00	4900.00
1490		100.00	5000.00
1500		100.00	5100.00
1510		100.00	5200.00
1520		100.00	5300.00
1530		100.00	5400.00
1540		100.00	5500.00
1550		100.00	5600.00
1560		100.00	5700.00
1570		100.00	5800.00
1580		100.00	5900.00
1590		100.00	6000.00
1600		100.00	6100.00
1610		100.00	6200.00
1620		100.00	6300.00
1630		100.00	6400.00
1640		100.00	6500.00
1650		100.00	6600.00
1660		100.00	6700.00
1670		100.00	6800.00
1680		100.00	6900.00
1690		100.00	7000.00
1700		100.00	7100.00
1710		100.00	7200.00
1720		100.00	7300.00
1730		100.00	7400.00
1740		100.00	7500.00
1750		100.00	7600.00
1760		100.00	7700.00
1770		100.00	7800.00
1780		100.00	7900.00
1790		100.00	8000.00
1800		100.00	8100.00
1810		100.00	8200.00
1820		100.00	8300.00
1830		100.00	8400.00
1840		100.00	8500.00
1850		100.00	8600.00
1860			

Itemized statement of expenditures for improving the Manistiquet River, from December 1, 1909, to October 31, 1912, both inclusive—Continued.

CHARTRICK) NTEAMER JACK FROST—Continued.

[illegible]

FLUM POINT REACH

Capt. J. G. D. Dwyer.

1892.		1891.		1890.		1889.		1888.		1887.		1886.		1885.		1884.		1883.		1882.		1881.		1880.		1879.		1878.		1877.		1876.		1875.		1874.		1873.		1872.		1871.		1870.		1869.		1868.		1867.		1866.		1865.		1864.		1863.		1862.		1861.		1860.		1859.		1858.		1857.		1856.		1855.		1854.		1853.		1852.		1851.		1850.		1849.		1848.		1847.		1846.		1845.		1844.		1843.		1842.		1841.		1840.		1839.		1838.		1837.		1836.		1835.		1834.		1833.		1832.		1831.		1830.		1829.		1828.		1827.		1826.		1825.		1824.		1823.		1822.		1821.		1820.		1819.		1818.		1817.		1816.		1815.		1814.		1813.		1812.		1811.		1810.		1809.		1808.		1807.		1806.		1805.		1804.		1803.		1802.		1801.		1800.		1799.		1798.		1797.		1796.		1795.		1794.		1793.		1792.		1791.		1790.		1789.		1788.		1787.		1786.		1785.		1784.		1783.		1782.		1781.		1780.		1779.		1778.		1777.		1776.		1775.		1774.		1773.		1772.		1771.		1770.		1769.		1768.		1767.		1766.		1765.		1764.		1763.		1762.		1761.		1760.		1759.		1758.		1757.		1756.		1755.		1754.		1753.		1752.		1751.		1750.		1749.		1748.		1747.		1746.		1745.		1744.		1743.		1742.		1741.		1740.		1739.		1738.		1737.		1736.		1735.		1734.		1733.		1732.		1731.		1730.		1729.		1728.		1727.		1726.		1725.		1724.		1723.		1722.		1721.		1720.		1719.		1718.		1717.		1716.		1715.		1714.		1713.		1712.		1711.		1710.		1709.		1708.		1707.		1706.		1705.		1704.		1703.		1702.		1701.		1700.		1699.		1698.		1697.		1696.		1695.		1694.		1693.		1692.		1691.		1690.		1689.		1688.		1687.		1686.		1685.		1684.		1683.		1682.		1681.		1680.		1679.		1678.		1677.		1676.		1675.		1674.		1673.		1672.		1671.		1670.		1669.		1668.		1667.		1666.		1665.		1664.		1663.		1662.		1661.		1660.		1659.		1658.		1657.		1656.		1655.		1654.		1653.		1652.		1651.		1650.		1649.		1648.		1647.		1646.		1645.		1644.		1643.		1642.		1641.		1640.		1639.		1638.		1637.		1636.		1635.		1634.		1633.		1632.		1631.		1630.		1629.		1628.		1627.		1626.		1625.		1624.		1623.		1622.		1621.		1620.		1619.		1618.		1617.		1616.		1615.		1614.		1613.		1612.		1611.		1610.		1609.		1608.		1607.		1606.		1605.		1604.		1603.		1602.		1601.		1600.		1599.		1598.		1597.		1596.		1595.		1594.		1593.		1592.		1591.		1590.		1589.		1588.		1587.		1586.		1585.		1584.		1583.		1582.		1581.		1580.		1579.	
Dec	1	215	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13 89	13																																																																																																																																																																																										

11	303	Outfit																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									</
----	-----	--------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1892, to October 31, 1893, both inclusive—Continued.

PLUM POINT REACH—Continued.

Date	Voucher number.	For what expended.	Administration and inspection	Office expenses	Material and miscellaneous supplies.	Fuel	Cost of plant	Transportation and steamer expenses.	Repairs.	Labor on plant and construction.	Subsistence.	Care of public property.	Total
1883													
Jan 31	120	Services	\$10 00										
29	122	Supplies			\$157 04						\$13 03		
20	123	anchors					\$155 75						
20	125	Vinegar									24 06		
29	126	Cook's quarters					100 21				79 12		
30	128	Apples											
30	130	Salmon			38 20								
30	142	Transportation						\$48 52					
31	144	Peas		\$31 80									
30	154	Services	108 53					0 00					
31	159	Light (loading stores)					46 40						
Feb 1	160	Cook's quarters											
3	164	Supplies										\$32 00	
3	175	Stores			663 10								
Jan 2	184	Traveling expenses	3 00										
Feb 7	188	Wine			3,064 00			75 56					
6	195	do			7,542 11			164 80					
12	198	Meat outfit					148 45						
20	200	Transportation						65					
15	204	Supplies			3,461 70		380 86						
14	206	Cheese										14 00	
14	208	Services											
16	211	Supplies			60 60						800 65		
16	212	do									104 98		
17	217	Hardware			26 70								
16	219	Red and fire			85 83								
16	217	Canned fruit											
16	218	Sugar									65 50		
17	219	Sugar									197 00		

new	exp.	date	description	quantity	unit	price	total	balance
2	297	Feb.	Tape and rule	1	roll	1.00	1.00	24.44
3	298	Mar.	Hama	11	lb	1.00	11.00	
24	299		Advertising for materials	4	lb	1.00	4.00	
6	300		Knobs	26	pc	1.00	26.00	
7	301		Wire-bare	416	pc	1.00	416.00	
8	302		Supplies	204	pc	1.00	204.00	
9	303		Rope	63	lb	1.00	63.00	
10	304		Towing	11	lb	1.00	11.00	
11	305		Brushes	407	pc	1.00	407.00	
12	306		Advertising for material	408	pc	1.00	408.00	
13	307		Stone					
14	308		Labor					
15	309		Supplies					
16	310		Labor					
17	311		Lumber					
18	312		Iron					
19	313		Supplies					
20	314		Books					
21	315		Potatoes					
22	316		Skins and ears					
23	317		Servives					
24	318		Wire					
25	319		Servives					
26	320		Labor					
27	321		Towage					
28	322		Supplies					
29	323		Reducers					
30	324		Straw					
31	325		Outfit					
32	326		Supplies					
33	327		Ranges					
34	328		Stationery					
35	329		Outfit					
36	330		Supplies					
37	331		Outfit					
38	332		Supplies					
39	333		Outfit					
40	334		Traveling openess					
41	335		Hoisting engine					
42	336		Labor					
43	337		Stone					
44	338		Hardware					

Item and amount of expenditures for improving the Mississippi River, from December 1, 1882, to October 13, 1883, both inclusive—Continued.

PLUM POINT REACH—Continued.

Year.	For what expended.	Administration and inspection			Office expenses	Material and miscel-		Fuel.	Cost of plant.	Transportation and steamer expenses.		Repairs.	Labor on plant and construction.	Subsistence.	Care of public prop-erty.	Total.
		Salaries.	Travel.	Other.		Material and miscel-laneous supplies.	Material and miscel-laneous supplies.			Transportation and steamer expenses.	Transportation and steamer expenses.					
1882.																
Apr 16	For steam					\$24 20			\$33 75	\$1 00						
16	For supplies					151 20				2 31						
16	do								637 50	8 75						
16	For fuel									29 80				\$1,067 06		
16	For construction									24 00				530 00		
17	do									1 00						
17	For repairs					17 01				1 00				67 80		
17	For fuel									1 00						
17	For construction					54 27				1 00						
17	For fuel					46 08				1 00						
17	For construction															
17	For fuel					8 00										
17	For construction					250 50									\$35 10	
17	For fuel															
17	For construction															
17	For fuel					105 24				22 85		\$3 40		360 00		
17	For construction									5 20				240 40		
18	do								430 40	9 02						
18	For fuel									16 85				313 85		
18	For construction															
18	For fuel								10 28							
18	For construction								72 28	1 00						
18	For fuel								65 32							
18	For construction								172 91							
18	For fuel								261 84							
18	For construction															
18	For fuel					125 77										
18	For construction					803 88										
18	For fuel								527 80	22 50						
18	For construction								5 25	1 00						

[illegible]

Continued from December 1, 1902, to October 31, 1903, both inclusive—Continued.

WILLIAM PUNNET REACH—Continued.

Number	For what employed	Administrative and inspection	Office expenses	Material and repair	Fuel	Cost of plant	Transportation and storage expenses	Repairs	Labor on plant and construction	Subsistence	Cost of public property	Total
1	Half											
2	Back to town			\$21 00		\$64 24	\$0 00					
3	Supplies			30 00						\$1,240 53		
4	do			36 17						184 04		
5	do			213 24			4 80					
6	do		\$9 60									
7	Barge					1,250 00						
8	Traveling expenses	\$6 40										
9	Labor and material											
10	Stove			239 65								
11	do					14 08						
12	Barge					5,200 00						
13	do					2,700 00						
14	Towage						10 00					
15	Labor and electric light					108 00						
16	Material and barge					8,400 00						
17	do					1,250 00						
18	Sub						20 00			63 00		
19	do			10 00								
20	do					9,800 00						
21	do						12 00					
22	do											
23	do						119 60			65 20		
24	do			102 00						2,784 19		
25	do			50 06			8 80					
26	do			990 19			16 06					
27	do			8 62			1 00					
28	do					45 28						
29	do			27 10			8 25					
30	do			14 00								

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1882, to October 31, 1883, both inclusive—Continued.

MILUM POINT BLAOK—Continued.

[illegible]

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1882, to October 31, 1883, both inclusive--Continued.

PLUM POINT BEACH—Continued.

Date.	Voucher number.	For what expended.	Administration and inspection.	Office expenses.	Material and miscellaneous supplies.	Fuel.	Cost of plant.	Transportation and steamer expenses.	Repairs.	Labor on plant and construction.	Subsistence.	Care of public property.	Total.
1883													
Sept 30	424	Service	\$60 00										
Sept 12	429	Hose			\$104 28								
July 30	437	do			379 00			\$1 00					
Sept 29	447	Service	50 00										
Sept 30	448	Charter						525 00					
Sept 30	449	Lumber			200 50								
Oct 10	21	Labor										\$5 40	
Oct 10	22	Stone			786 26								
Oct 10	23	Towage						169 00					
Oct 10	24	Service of steamer										84 00	
Oct 22	25	Subsistence						89 04			\$1,455 90		
Oct 22	27	do						8 80			485 25		
Oct 22	34	Towage						6 00					
Oct 24	37	Supplies			29 08			70					
Oct 12	40	do			117 41			2 80					
Oct 22	45	Labor and material							\$349 08				
Oct 22	46	Hardware			180 27								
Oct 22	47	do			8 30								
Oct 22	48	Freight						2 54					
Oct 22	49	Stoves			2 28								
Oct 22	53	Outfit					947 56						
Oct 22	54	do					12 96						
Oct 22	56	Beef						1 42					
Oct 22	58	Subsistence						37 12			726 00		
Oct 20	61	Stationery		\$38 25				44 95			747 78		
Oct 20	63	Lamps											
Oct 20	63	Labor					73 40	4 50					

		1,848 43	207 10	64,654 73	1,765 36	80,897 08	5,968 87	7,000 26	32,169 95	622 96	302,487 19
NEW MADRID REACH.											
Capt. T. G. D. KNIGHT.											
1882.											
	91	Traveling expenses	30 10								
	181	Services	45 00								
	187	Stationery		8 00							
	196	Machinery				4,200 00					
Dec. 3	222	Barges				5,550 00					
	223	do				9,245 00					
	230	Towage					715 00				
Dec. 3	237	Barges				9,750 00					
	243	Pile-driver leads				3,250 00					
Dec. 7	243	Traveling expenses	15 00								
9	253	Services								12 00	
9	257	Pile-driver hulls				27,000 00					
13	261	Repairs					23 16				
11	262	Towage					350 00				
18	272	Barges				3,700 00					
19	273	Towage					60 00				
20	275	Services	37 50								
30	279	do	25 00								
30	280	Traveling expenses	6 75								
23	313										
1883.											
Jan. 2	1	Barges				5,400 00					
3	3	Pile-driver leads, &c.				3,250 00	430 00				
2	4	Towage					25 00				
Feb. 6	17	Traveling expenses	11 75								
8	25	do	21 12								
15	26	Services				15,600 00				6 50	
15	33	Barges									
15	39	Traveling expenses	11 00								
16	40	Salt				76 25					
25	45	do				52 65					
7	115	Rope			\$86 18		1 50				
5	116	Pumps				2,070 00					
31	118	Services	95 00								
2	155	Barges (coal)				550 00					
6	176	Barges				1,850 00					
6	177	do				10,050 00					
6	178	do				2,000 00					
12	182	Pumps				4,960 00					
12	197	anchors				1,630 48					
20	207	Towage					100 00				
19	226	do					10 00				

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1892, to October 31, 1893, both inclusive—Continued.

NEW MADRID BEACH—Continued.

[illegible]

Standard statement of expenditures for Improving the Atlantic City River, from December 1, 1909, to October 31, 1910, both inclusive—Continued.

THE UNIVERSITY OF CHICAGO

Date		Particulars	Debit	Credit	Balance
1943	Jan 25	Bank			
	26	Traveling expenses	100		100
	27	Hotel	100		200
	28	Meals	100		300
	29	do	100		400
	30	do	100		500
	31	do	100		600
	1	do	100		700
	2	do	100		800
	3	do	100		900
	4	do	100		1000
	5	do	100		1100
	6	do	100		1200
	7	do	100		1300
	8	do	100		1400
	9	do	100		1500
	10	do	100		1600
	11	do	100		1700
	12	do	100		1800
	13	do	100		1900
	14	do	100		2000
	15	do	100		2100
	16	do	100		2200
	17	do	100		2300
	18	do	100		2400
	19	do	100		2500
	20	do	100		2600
	21	do	100		2700
	22	do	100		2800
	23	do	100		2900
	24	do	100		3000
	25	do	100		3100
	26	do	100		3200
	27	do	100		3300
	28	do	100		3400
	29	do	100		3500
	30	do	100		3600
	31	do	100		3700
	1	do	100		3800
	2	do	100		3900
	3	do	100		4000
	4	do	100		4100
	5	do	100		4200
	6	do	100		4300
	7	do	100		4400
	8	do	100		4500
	9	do	100		4600
	10	do	100		4700
	11	do	100		4800
	12	do	100		4900
	13	do	100		5000
	14	do	100		5100
	15	do	100		5200
	16	do	100		5300
	17	do	100		5400
	18	do	100		5500
	19	do	100		5600
	20	do	100		5700
	21	do	100		5800
	22	do	100		5900
	23	do	100		6000
	24	do	100		6100
	25	do	100		6200
	26	do	100		6300
	27	do	100		6400
	28	do	100		6500
	29	do	100		6600
	30	do	100		6700
	31	do	100		6800
	1	do	100		6900
	2	do	100		7000
	3	do	100		7100
	4	do	100		7200
	5	do	100		7300
	6	do	100		7400
	7	do	100		7500
	8	do	100		7600
	9	do	100		7700
	10	do	100		7800
	11	do	100		

20	Apr. 6	Towage	50 00																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
----	--------	--------	-------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1882, to October 31, 1883, both inclusive—Continued.

MEMPHIS REACH AND HARBOR—Continued.

Date.	Voucher number.	For what expended.	Administration and inspection.	Office expenses.	Material and miscel- laneous supplies.	Fuel.	Cost of plant.	Transportation and steamer expenses.	Repairs.	Labor on plant and construction.	Subsistence.	Care of public prop- erty.	Total.
1883.													
Aug 1	119	Chartered						\$465 00					
2	124	Lumber					\$5 50						
2	126	Services	\$25 00										
3	131	Stone			\$400 86				\$2 00			\$6 30	
10	156	do			78 30								
16	167	Labor											
15	187	Lumber							4 00				
15	190	Stone			106 71								
27	226	Towage						4 00					
4	256	Travelling expenses	4 16										
30	269	Paper			5 00								
31	274	Services	25 00										
31	276	do	25 00										
3	288	Charter						465 00				4 60	
3	292	Labor and material							6 33				
1	297	Services	25 00										
7	318	Labor and material							178 05				
12	343	Travelling expenses	2 50										
12	343	Stone			102 38								
12	344	Labor											
13	350	Labor and material							9 80			5 45	
17	370	Labor											
18	379	Travelling expenses	1 00									1 40	
5	383	Stone			917 14								
6	384	Labor and material							29 60			10 60	
6	385	Labor											
20	424	Services	25 00					105 00					
30	425	Charter											
			96 60					669 40					

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1892, to October 31, 1893, both inclusive—Continued.

LAKE PROVIDENCE REACH--Continued.

[illegible]

Mon.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	Apr.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	May	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	June	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	July	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	Aug.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	Sept.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	Oct.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	Nov.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	Dec.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
	Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges and rigging.																															Barges																														

Itemized statement of expenditures for improving the Mississippi River, from December 1, 1882, to October 31, 1883, both inclusive—Continued.

LAKE PROVIDENCE REACH—Continued.

Date.	Voucher number.	For what expended.	Adaptation and inspection.	Office expenses.	Material and miscellaneous supplies.	Fuel.	Cost of plant.	Transportation and steamer expenses.	Repairs.	Labor on plant and construction.	Subsistence.	Care of public property.	Total.
1883.													
July 30	117	Services											
Aug. 1	120	Charter	\$75 00					\$527 00					
2	124	Lumber				\$11 76							
2	126	Services	50 00										
3	132	Stone			\$221 71				95 00			\$12 00	
3	123	Traveling expenses											
3	130	Subsistence	17 80					19 90			\$435 00		
3	130	do						34 48			1,050 63		
3	137	do						41 00			1,078 65		
3	138	do											
3	139	Supplies			19 75								
7	141	Labor and material							431 75				
8	142	Skiffs					204 00						
9	154	Belges					9,900 00						
9	156	Labor and material			9 76				12 75				
10	160	Stone			156 78							25 44	
10	167	Labor											
13	170	Labor and material							94 80				
13	178	Traveling expenses	8 00										
15	187	Material							8 16				
15	190	Stone			303 45								
17	203	Labor and material							175 18				
17	204	do							4 65				
17	205	Services											
27	213	Material			10 00							75 00	
27	217	Motor					53 60						
27	218	Labor							25				
27	220	Towing						8 00					
30	229	Skiffs, &c.			17 06								

Month	Item	Quantity	Unit Price	Total	Balance	Carried Forward
Aug.	Substance	10	70	700		
	do	10	60	600		
	Labor, coaling	10	70	700		
	do	10	60	600		
	Substance	10	70	700		
	do	10	60	600		
	do	10	70	700		
	do	10	60	600		
	do	10	70	700		
	do	10	60	600		
Sept.	Substance	10	70	700		
	do	10	60	600		
	Labor, coaling	10	70	700		
	do	10	60	600		
	Substance	10	70	700		
	do	10	60	600		
	do	10	70	700		
	do	10	60	600		
	do	10	70	700		
	do	10	60	600		
Oct.	Substance	10	70	700		
	do	10	60	600		
	Labor, coaling	10	70	700		
	do	10	60	600		
	Substance	10	70	700		
	do	10	60	600		
	do	10	70	700		
	do	10	60	600		
	do	10	70	700		
	do	10	60	600		

MOUTH OF RED RIVER.

MAJ. ALAN STICKNEY.

[illegible]

Itemized statement of expenditures for compensation, 1964, by Defendant H, 100A, such as follows: 4 continued.

Public Health and Safety

Date	Number	For what expended	1902	1903	1904	1905	1906	1907	1908	1909	1910	1911	1912	1913	1914	1915	1916	1917	1918	1919	1920	1921	1922	1923	1924	1925	1926	1927	1928	1929	1930	1931	1932	1933	1934	1935	1936	1937	1938	1939	1940	1941	1942	1943	1944	1945	1946	1947	1948	1949	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	
------	--------	-------------------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	--

APPENDIX I.

TAIN J. G. D. KNIGHT, CORPS OF ENGINEERS UPON OPERATIONS IN THE FIRST DISTRICT.

UNITED STATES ENGINEER OFFICE,
 Cairo, Ill., Norember 27, 1883.

he following report is submitted in compliance with instructions of 383, to send immediately after October 31, 1883, a report of work done ds controlled by the Mississippi River Commission since the date of my ort and up to October 31, 1883.
 levee location along the Saint Francis front; (2) the improvement of d Reach; and (3) the improvement of the Plum Point Reach.

SAINT FRANCIS FRONT.

i, 1882, instructions were issued by the Commission that such surveys e of the Saint Francis front in the first district as would render it pos- to the Commission the cost of closing all gaps in the levee to the old at front; but no allotment out of which to pay the cost of such surveys l November 19, when \$5,000 was allotted for the survey of so much of icis front as lies in the first district. Two days later the Commission ctions for the surveys of new levees.
 vee that could be utilized in the construction of the new amounted, in t, to but 1 per cent. of the volume of the entire work, instead of for i the old levee, the required estimates were for virtually building a new s front; hence, the instructions of the Commission as to surveys for new cidedly applicable to this work.
 r a small party was sent out to commence the location; but as it was at its instructions were not sufficiently comprehensive, and as fuller in- essitated a differently organized party, the first was recalled.
 ys and estimates could not be made in time for the last annual report, s deferred until after the high water. In the spring, propositions were various parties to make the required surveys at prices varying from r mile; and the lowest proposition, that of Civil Engineer H. N. Pharr, ., accepted. His party started out about June 1, 1883, from Bird's Point, ecuted the work with energy until it was stopped, in the bend above y high water. Resuming in July, Engineer Pharr carried on the loca- pletion. The level notes and profiles were received in September; the r passed without the plotted location coming to hand.
 ximate estimate the following figures are given, to be followed by a rt when additional data are at hand:

to be leveed	miles..	228.5
to be cleared	do	114.5
ire levee	cubic yards..	9,000,000
levee available	do	90,000
th to be moved	do	8,910,000

earthwork at 25 cen's per yard, clearing at \$30 per acre—the number estimated as 750—and cost of surveying and inspection at \$50,000, the ost of leveeing so much of the Saint Francis front as is in the first dis- 2,301,000.

: expended under the allotment is as follows:

and draughtsman	\$3,069 36
stationery, and maps	226 05
ops	9 50
.....	8 00
.....	3,312 91

STATEMENT.

.....	\$5,000 00
in above statement	3,312 91
.....	1,687 09

FROM CHIEF OF THE CHIEF OF BUREAU OF THE

Air carrier has a right to be run between Cleveland and
other airports and to make with reference to the
and a carrier between and Northwest Arkansas, this contract
to operate, subject or to be incurred.

NEW MADRID BEACH

The [redacted] was completed, August 18, 1960, that the [redacted] [redacted]
[redacted] made for the New Madison [redacted] [redacted]
[redacted] : a project for the plant however
[redacted] I was informed that the [redacted]
[redacted] inside the river from the [redacted]
[redacted] [redacted]. August 18, 1960

On December 23, 1942, L. J. Smith made the following December, having been
A map of the entire survey was

... for this work was ...
... and approved by the ...
... over and brush, one machine ...
... six one-hundred-five ...

... of plant already existing was ...
... was suspended; and on March 15 ...
... the Point allotment, and ...
... was ordered transferred to the ...

_____ for the executive officer of the _____
_____ the pile-drivers, one machine _____
_____ as follows:

~~_____ is a justice of the peace, Mississippi River County,
_____ is the District Clerk, for use on that ranch.~~

	Item and amount	Total cost.	
	4 4	\$22,154 00	} Of these horses 11 \$32,045 are in use at Point Barrow and 21 at \$42 100 in general service.
	4 4	4 245 00	
	4 4	12 200 00	
	4 4	4 125 00	
	4 4	2 200 00	
	4 4	2 200 00	
	4 4	2 200 00	In use at Point Barrow.
	4 4	2 200 00	} 5 in use at Point Barrow } use at Lake Providence } laid up.
		11 00 00	
		11 00 00	
		\$22,154 00	

2. The net change in the number of employees was 42,308.

[illegible]

Captain Knight		T	
1	1	1	1
2	2	2	2
3	3	3	3
4	4	4	4
5	5	5	5
6	6	6	6
7	7	7	7
8	8	8	8
9	9	9	9
10	10	10	10
11	11	11	11
12	12	12	12
13	13	13	13
14	14	14	14
15	15	15	15
16	16	16	16
17	17	17	17
18	18	18	18
19	19	19	19
20	20	20	20
21	21	21	21
22	22	22	22
23	23	23	23
24	24	24	24
25	25	25	25
26	26	26	26
27	27	27	27
28	28	28	28
29	29	29	29
30	30	30	30
31	31	31	31
32	32	32	32
33	33	33	33
34	34	34	34
35	35	35	35
36	36	36	36
37	37	37	37
38	38	38	38
39	39	39	39
40	40	40	40
41	41	41	41
42	42	42	42
43	43	43	43
44	44	44	44
45	45	45	45
46	46	46	46
47	47	47	47
48	48	48	48
49	49	49	49
50	50	50	50
51	51	51	51
52	52	52	52
53	53	53	53
54	54	54	54
55	55	55	55
56	56	56	56
57	57	57	57
58	58	58	58
59	59	59	59
60	60	60	60
61	61	61	61
62	62	62	62
63	63	63	63
64	64	64	64
65	65	65	65
66	66	66	66
67	67	67	67
68	68	68	68
69	69	69	69
70	70	70	70
71	71	71	71
72	72	72	72
73	73	73	73
74	74	74	74
75	75	75	75
76	76	76	76
77	77	77	77
78	78	78	78
79	79	79	79
80	80	80	80
81	81	81	81
82	82	82	82
83	83	83	83
84	84	84	84
85	85	85	85
86	86	86	86
87	87	87	87
88	88	88	88
89	89	89	89
90	90	90	90
91	91	91	91
92	92	92	92
93	93	93	93
94	94	94	94
95	95	95	95
96	96	96	96
97	97	97	97
98	98	98	98
99	99	99	99
100	100	100	100

STATEMENT.

allotment	\$700,000 00
transferred to Plum Point allotment.....	\$300,000 00
transferred to Lake Providence allotment	187,500 00
expended by Captain Sears	204,572 16
expended by Captain Knight	4,498 95
	<hr/> 696,571 11
Balance	<hr/> 3,428 89
amount in hands of Captain Sears November 1.....	\$2,427 84
amount in hands of Captain Knight November 1.....	1,001 05
	<hr/> 3,428 89

Although apparently it is not contemplated to begin work on the New Madrid Reach on any portion of the appropriations hitherto made, the still existing necessity of improvement of this reach cannot be doubted. During the low-water season just ended it has been marked by three of the most troublesome places between Cairo and Memphis, viz: Phillip's Crossing, Point Pleasant, and Tiptonville. Shoal water and narrow channel have characterized these places, and the latter vicinity has been marked by loss of property, delay of steamboats, and many channel changes. It will continue to be so characterized until the extremely unstable banks from New Madrid to Tiptonville be protected from the assaults of the river, and the channel otherwise improved. The locality is an excellent one for a crucial test of any system of bank protection, much of the river bank being sandy and high. Should the Commission consider the advisability of work of river improvement elsewhere than where already commenced, I would suggest this field as one where improvement is urgently demanded.

PLUM POINT REACH.

From December 19, 1882, to June 6, 1883, First Lieut. T. W. Symons, Corps of Engineers, was in local charge of work on this reach. On his accepting other duty, retired State Assistant Engineer A. J. Frith resumed charge, and has since retained it. Since the date of my last report, additional dikes, shown on the maps of the reach annexed (Plates II-V), and as follows, have been ordered by the Commission: Two between 1a and 1b, between dikes 1 and 2, at Gold Dust; dike 4, in Osceola Chute, and dike 2, in Bullerton Chute.

The dikes in course of construction at that date were those at Gold Dust—the main dike and cross-dikes 1 to 5—the Osceola middle, and Osceola-Bullerton. Later work on the upper Osceola was resumed. Osceola cross No. 1 was commenced March, 1883; Osceola cross No. 2, April, 1883; Osceola cross No. 3, March, 1883; Bullerton cross-dike No 1, June, 1883; Plum Point main dike and No. 1 cross-dike in September, 1883, and No. 2 cross-dike in October.

Of the dikes ordered or approved by the Commission, the following have not been commenced: Osceola cross No. 4, Bullerton cross No. 2, and Plum Point cross Nos. 3, 4, and 5. Osceola cross-dike No. 4 was ordered June 30, 1883, but its construction could not be carried on at low water. Bullerton cross-dike No. 2, ordered at the same time, could not be put in, as the attempt so to do would have interfered with the use of the only navigable channel near Bullerton Tow-head; the Plum Point dikes were deferred, as my project, in which they were incorporated, was approved subject to the proviso that they be not undertaken so long as the plant can be employed elsewhere. While projects submitted from time to time covered bank protection of the Tennessee shore from Ashport to Gold Dust, of the Arkansas shore from Mill Bayou to upper Osceola Chute, and from Bullerton Chute to Craighead Point, of upper and lower Osceola Bars, of Bullerton Tow-head, and Yankee Bar, to attempt to protect more than Bullerton tow-head has been found impracticable. That this should be protected was necessary, as the bar in front continually crowded the water over, thus threatening the cutting in two of the tow-head; also as the river persisted in establishing for this season the main channel in Bullerton Chute, there might have been much wearing away at the head. Two thousand six hundred and ninety-four feet of mattress, with upper bank protection, were built at Ashport, and so far have served to prevent wearing.

The following table shows the amount of work reported at each place and the amount actually standing, as shown by the reports of Assistants Gender, Marx, Nolty, Yeager (Appendices J 2-J 5) and the plates thereto annexed (Plates II-V). The difference between the two items serves as a basis for determining the total amount of work destroyed, not limited to the past year, and the estimated value thereof. These values are based on those given later in a table, showing the amount and cost of all work on this reach:

Estimated value and quantity of damage done to works at Plum Point, Tennessee.

[illegible]

NOTE.—The amount of brush-work reported as lost includes, in the case of like work, such amount of mattress as had to be renewed on account of pile-like giving way. Figures marked * represent work done previous to July 12, 1882, *i. e.*, previous to present appropriation.

age to the pile-work resulted from the weak forms of dike first used, from late condition, and from irresistible scouring action of the river. The work consisted of bents formed by pulling over and fastening at the tops long piles of two parallel rows; 2,400 feet of this was removed by scour in the case of a foot-mat. Later, dikes of piles braced by single inclined piles and lateral stringers were tried and found wanting; the one at Upper Osceola having been almost wholly broken off, though not before it had induced much damage to the head of the chute. Then was tried a form shown in my report of 1882, as was shown by its experience with the high water of last spring. A plan planned by United States Assistant Engineer A. J. Frith, has been adopted recently, and will, it is thought, prove sufficiently strong. From the dikes, even if finished, being too weak to resist the great strains they have been subjected, there was the desire to take advantage of favorable water, which resulted in the pile-work being hurried ahead too far in advance of protecting mat-work; and when rising water came, there came with it drift, which, at the same time, both prevented mat construction and injury. Finally 2,500 of the 3,300 feet of Osceola middle dike were carried away by a sudden scouring out a volume having a cross-section of 1,200 feet by 20 depth. Even the foot-mat along its front failed to stay this scouring

to the bank protection has resulted from three causes: Chiefly, the attack at too high stages of the river, in consequence of which the mattress or protection has, by rising water, been carried to the tops of banks and ended so high as to admit of undermining; secondarily, water seeping from openings in pools and above comparatively impermeable strata has induced decay of high-water protection; and in a very few cases the mattress or its frame have been found too weak to bear the strain brought upon them by rapid

action is naturally suggested, is a repetition of this great damage to be ex-

pected work, the answer is, no. The height of the tops of dikes having been so high, drift will accumulate against the dikes. A careful following up of pile-work and brush-work and mattrassing of openings before closing them will diminish the possibility of scour. The increased strength given to dikes will increase their life, and equally beneficial results may be expected from a reliance on cross-dikes in some cases where longitudinal have been used, as in the case of Osceola middle dike. Damage to this was exceptional in its cause, and how to guard against like damage is not yet known.

For bank protection, loss may be avoided by abstaining from efforts to build a low section during high stages, as then such work could only be done with any success along a bluff shore. Mattresses can also be strengthened to stand up to the water so far experienced. Seepage water is more troublesome. Drainage of the bank can be attempted in favorable cases; but more likely the true remedy is an ex-posed flat slope above the line of exudation.

The following table gives, as nearly as it can be made from data in this office, the estimated cost of all work on this reach. The exceptionally high cost of Buller-like No. 1 is due to deep and rapid water; that of the Plum Point dikes, however, is due to the fact that much work thereon, being incomplete, can only be estimated.

action of—	Labor in construction.	Material for construction.	Subsistence.	Repair and outfit of plant.	Care of property.	Steamer and towage.
dikes.....	\$5,167 26	\$5,416 11	\$1,078 80	\$7,954 00	\$1,106 22	\$3,615 28
kes.....	13,537 38	9,497 35	3,179 70	17,878 00	2,621 44	8,126 46
kes.....	19,859 59	15,876 60	5,371 50	28,036 00	4,110 77	12,743 38
d bank protec-	32,766 69	30,427 86	7,890 80	48,480 00	7,108 54	22,036 42
ar bank protec-						
.....	11,392 93	8,504 86	2,040 00	15,576 00	2,283 84	7,079 82
ar bank protec-						
.....	5,318 27	4,961 00	1,604 10	8,104 00	1,188 34	3,683 85
like.....	9,437 90	9,850 63	2,234 80	14,674 00	2,152 34	6,670 00
like.....	10,260 52	8,955 10	2,406 90	14,740 00	2,162 25	6,703 00
kes.....	17,866 67	14,376 00	4,611 60	25,134 00	3,685 43	11,424 83
likes.....	85,280 05	79,650 53	18,019 50	128,992 94	18,013 65	55,460 46
ak protection ...	5,187 05	5,527 27	1,402 20	8,268 00	1,211 65	3,758 35
.....	216,074 31	193,073 31	50,740 50	317,836 94	45,704 47	141,301 85

DATE	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
TIME	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100

THE FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE ELEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWELFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTEENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FOURTEENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTEENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTEENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTEENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTEENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETEENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTIETH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE TWENTY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTIETH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE THIRTY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FORTY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE FIFTY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SIXTY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE SEVENTY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE EIGHTY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-FIRST OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-SECOND OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-THIRD OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-FOURTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-FIFTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-SIXTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-SEVENTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-EIGHTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE NINETY-NINTH OF THE ABOVE LISTED SUBJECTS IS THE
 THE HUNDRED OF THE ABOVE LISTED SUBJECTS IS THE

obably due to the contraction produced by the upper and lower sections of -Ballerton dike. It is true that an effort was made to join these sections. If it met with success, it is believed that diverting a large portion of so ly of water as that going through Ballerton Chute would not have failed its at this crossing equally good with those obtained. In front of Buller- and there has been rather a redistribution of material than an increase of w-water area; but this redistribution has been such that the deeper water coincide with the desired new channel. When the Plum Point system of re nearly completed, I can see no reason for doubting that there will be a at least ten feet at low water in front of this towhead. tely behind the Gold Dust main dike the bar crest has raised 10 feet, om 12 to 25 feet above the level of the low water of 1879; the latter figure on the first range above Elmot Bar, No. 31. The fill runs out to nothing eet in rear of the dike. ation of the results gained is rather premature. Over the greater portion h the works are in too incomplete a state to be judged by results. Such should be deferred at least until dikes in course of construction are com- l the Arkansas shore from Mill Bayou to Osceola Chute, Osceola Bars, and Towhead are revetted. e given the works so far planned and still unexecuted, and an estimate of their completion:

vetment, 19,600 feet, at \$12.....	\$235,200 00
revetment, 23,520 feet, at \$12.....	282,240 00
urs revetment, 13,720 feet, at \$12	164,640 00
ur revetment, 7,840 feet, at \$12	94,080 00
Point revetment, 15,000 feet, at \$12	180,000 00
dikes, 10,300 feet, at \$12.25.....	126,175 00
it dikes, 19,250 feet, at \$12	231,000 00
o. 3 dike, 1,000 feet, at \$12.25.....	12,250 00
No. 1 dike, 700 feet, \$34.50.....	24,150 00
No. 2 dike, 1,000 feet, at \$25	25,000 00
	<hr/>
	1,374,735 00

roximate first cost of plant now employed at Plum Point is as follows:

.....	\$48,000 00
-boats	58,320 00
s-boats	43,310 00
oat No. 1	5,200 00
oat No. 2	4,700 00
lic graders	60,464 00
ivers	62,300 00
ivers	10,640 00
ivers	9,240 00
hall boats.....	339 00
.....	536 50
.....	580 00
.....	300 00
oat.....	11,740 00
tug	9,500 00
launch (sunk).....	3,200 00
launch	1,500 00
	<hr/>
id from Plum Point allotment.....	329,869 50
ne-shop boat	\$8,200 00
rivers	26,625 00
s	34,045 00
	<hr/>
aid from New Madrid allotment	68,870 00
	<hr/>
	398,739 50

STATEMENT.

ent from appropriation of March 3, 1881	\$500,226 67
ent from appropriation of August 2, 1882	1,000,000 00
	<hr/>
	1,500,226 67

2782 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY

Disbursed by J. M. Smith, Engineer	\$420,153 69
Disbursed by Captain Smith	294,806 96
Disbursed by Captain Knight	619,323 34

Total disbursements to November 1, 1883.....\$1,334,283 99

Balance on hand November 1, 1883.....100

This balance is accounted for as follows:

In the United States Treasury	\$100
In the hands of Captain Smith	99
In the hands of Captain Knight	100
	100

The third of these balances had been reduced by November 26, 1883, to the ing amount, \$51,100.51.

SUMMARY.

The following table shows all expenditures made for the first district Mississippi River up to November 1, and also includes \$12,329.45 of liabilities incurred:

FLUM POINT.

Capt. Knight and Quinn.....	92, 544 76	912, 648 61	944, 999 97	920, 920 70	9110, 665 34	918, 616 59	9134, 828 45	9236, 832 70	9122, 650 54	902, 248 57	917, 758 46	904, 098 49
Capt. C. B. Beare.....	2, 827 97	340 05	734 50	126, 784 16	47, 376 51	90 00	5, 950 54	7, 241 61	70, 512 67	36, 028 79
	11, 372 69	12, 988 66	45, 704 47	395, 772 86	153, 041 85	16, 706 56	134, 829 29	216, 074 81	193, 073 81	32, 248 57	12, 758 46	131, 123 19
NEW MADRID.												
Capt. J. G. D. Knight.....	683 92	21 00	18 50	193, 549 99	9, 496 50	4, 498 95	30 00	3, 833 25
Capt. C. B. Beare.....	632 93	31 00	18 50	193, 549 99	9, 496 50	4, 498 95	30 00	3, 833 25
SAINT FRANCIS.												
Capt. J. G. D. Knight.....	3, 312 91
Capt. C. B. Beare.....	3, 312 91

RECAPITULATION.

Flum Point.....	911, 372 68	912, 968 66	945, 704 47	9095, 772 86	9158, 041 85	915, 736 53	9134, 828 29	9216, 074 31	9189, 073 81	902, 248 57	912, 738 49	9121, 122 19
New Madrid.....	632 92	21 00	18 50	193, 549 99	9, 496 50	4, 498 95	20 00	3, 833 25
Saint Francis.....	3, 312 91
	12, 005 60	13, 009 66	45, 722 97	589, 322 85	164, 538 35	23, 518 42	134, 849 29	916, 074 31	182, 073 81	32, 248 57	17, 571, 73	131, 123 19

Total to October 31, 1889

\$1, 573, 997 26

Very respectfully,

JOHN G. D. KNIGHT,
Captain of Engineers.

Lient. Col. C. B. CONSTOCK,
Corps of Engineers, U. S. A.,
President Mississippi River Commission.

when deep water, varying strata, moving braces, fastening, and other encountered, twelve piles is a fair day's average. Barges are capable of being employed in 45 feet of water and considerable efficient driving is difficult in water over 30 feet in depth and in violent

boats.—At the commencement of the year we had in all six mattress boats: set in length for 200-foot mattresses.

set in length for 100-foot mattresses.

set in length for 150-foot mattresses.

Two are designed for mattresses with a wire base; the others for mattresses on poles. We have since received three boats 160 feet in length, also barge. The design of these boats is not exactly similar but experience that the main requisites for the pole mattress are an ample platform on the barge; ways with a slope of 1 foot in 3½ feet running close to the water, but over the edge of the barge, also capstans at the ends for ready handling, a number of chocks and kevels for fastening lines.

boats.—There are now in service twelve quarter-boats, including that used at headquarters, and one for storing supplies. At the commencement a barge on an ordinary brush barge fulfilled all requirements, but the incon- venient discomforts of this form led to the building of the type now in use, and in an endeavor to combine all that is necessary for the health, comfort, and convenience of the employes. Most of these boats were built upon the works, and consist of a barge, the hull of which is used for kitchen, stores, and dining-room, and a cabin containing rooms for assistant in charge and foreman, and sleeping quarters for the men. These boats are provided with life line and floats, and buckets and ladders to be used in case of fire, and accommodate 124 in all, including barge, and men.

Two hydraulic graders, No. 2 and 4, have been allotted to work on this

ing the fore part of the year, was in use at Memphis, and was later held in place on September 26, when about to be used in Elmot Chute, it was sunk. It has since been raised, and is now in progress of repair.

, except during the high water, been in almost constant use during the season, being highly efficient and satisfactory.

Each are each fitted with three boilers 22 feet long by 40 inches diameter of compound condensing pumps with 18 and 36 inch by 24 inch steam and 16 by 24 inch water cylinders, and deliver 2,000 gallons a minute into the boom, reaching up the bank, and from which lead the hose to the various points. Two 1½ and one 1¼ inch nozzles are ordinarily used, with pump pressure 110 pounds and nozzle pressure of 80 pounds, the efficiency of water cylinder about 80 per cent. The woven cotton hose has proved in use, the most reliable. A grader has removed from 1,800 to 4,000 cubic yards of earth per day, at a cost of 2.98 cents a yard, including wages, coal, subsistence, &c. Each is provided with electric lights for night work.

To supply material to various parties there are used fifty barges, 100 by 25 feet smaller barge, used for coal. Many of these, constructed with a view to light brush, have broken down under the heavy willows generally fur- nished received later in the year and others altered here are better propor- tioned 6-foot gunwales and two 4-inch fore-and-aft bulkheads, heavy head- boards, and carry 150 cords of brush or 200 cubic yards of rock. There are general-service barges some 30 by 120 foot barges carrying 330 cubic yards each, these are, however, difficult to handle in heavy currents when sinking

METHODS OF CONSTRUCTION.

—The dimensions of piling used during the year were increased over those accepted, by increasing the least size at the top to 8 inches from 6, the least at the foot being 18 inches. Cottonwood piles form the bulk of the piling, though considerable cypress has been received. The piling was re- ceived landed at points above the localities where each piece of work was in- tended, when practicable, dropped in small sections to the drivers; if not, sent loaded 100 to 140 of them on barges which were towed to conveni- ent points for sorting and distribution.

Section of dikes used in the early months of the year is shown in Plate VI, showing a spacing of 7½ feet between each truss. As a considerable portion of this work had been done, with your permission I undertook an investigation to determine what should combine an equality of resistance coupled with economy and a liberal factor of safety, and of proportions that could be maintained under water. The difficulty of determining exact data for these calculations was partly due to the difficulty of getting into the whole subject; still it is believed that the form chosen

... in varying depths of water. The tendency
... destruction of each member ...
... by the pressure of the water ...
... traction to replace the wire ...
... easy coupling of the short rods ...

... stable soil in which the dikes are ...
... one of the most difficult obstacles ...
... the dike seems to be alone ...
... matts used during the first months ...
... has passed completely under the ...
... layers of brush at right angles, held together ...
... the whole being sunk between ...
... the dikes, have not lately been ...
... as shown in Fig. 3. A being the grillage, ...
... of the footmat in all but main dikes. ...
... grillage thus arranged at Gold Dust this ...
... part a curtain, has been made from 30 to 150 ...
... the inclined portion being supported on pilings ...
... tendency to throw the current upwards, thus ...
... which will, it is believed, increase in a manner ...
... further advantage of following up a scour with all ...
... while the tipped grillage in the rear prevents a ...

... screwing action of drift, experienced with portions ...
... are now built up to the 15-foot stage, rising to ...
... which are guarded against scour by thorough mat ...
... (Fig. 4). On high dikes, an immense accum ...
... which rendered all work at this stage during ...
... unsatisfactory.

... stage an extra row of piles should be driven ...
... until mattresses, &c., are completed, after ...
... it is not considered as part of the di ...
... so much the actual pressure which is ...
... believed, but that the accumul ...
... and causes a scour below ...
... the structure. If this scour can be g ...
... to the current, and in the ...
... is 600 feet wide by 1,200 feet lo ...
... from resistance to the flow of

Several methods of constructing mattresses have been followed, governed by their utilities and the work they were expected to perform.

They may be classified as follows:

1st. Shore mattress for the protection of the banks.

2d. Revetment, or protection of high-water slopes.

3d. Foot mattress, for protection of dikes.

4th. Tipped mattress.

5th. Grillage mattress.

1st. Shore mattresses for the protection of caving banks have been made in widths varying from 100 to 150 feet and lengths governed by the difficulties in sinking. When particular danger is to be anticipated, this mattress may be continuous to almost any length. Two varieties have been in use: 1st, that used by Major Ernst below Saint Louis, where the willows are woven on poles, preferably of sycamore, 7 to 8 feet apart, Plate VII, Fig. 5, and forming a stiff and strong mattress, of which 170 feet a day have been made with light brush and under favorable circumstances. This mattress is easy of construction and has been mostly used during the year.

2d. There has also been used along the face of Bullerton a 100-foot mattress woven on a wire base, the willows being interlaced, as shown in Plate VII, Fig. 6, forming a mattress which is extremely pliable and hence more easily sunk. It is not so easily constructed as the first, but a slightly greater average length a day has been obtained. The majority of brush furnished lately has, unfortunately, been too large and heavy to obtain the best results.

As the shore mattresses are made they are guyed to the shore by $1\frac{1}{2}$ to 2 inch lines, which are removed as they are sunk.

The mattresses are fastened to the shore by wire cables or wires at frequent intervals and, when necessary, piles have been driven through the mattress to prevent any movement.

When a stretch of mattress 1,000 or more feet in length is to be sunk, great care must be used. In light currents the most rapid and easiest method (Plate VII, Fig. 5) is to commence sinking at the head, keeping the inner side of the mattress sunk a little in advance, and carefully sounding to see that it does not rise after the force of the current is removed. It will be perceived that the weak point is in the corner (A) where the sharp bend tends to break the poles or willows, and where there is nothing to resist the downward pull of the current but the flotation of the mattress.

When the water is very rapid it has been our practice to commence sinking at the lower end (Plate VII, Fig. 8) where the shore side is also kept sunk a little ahead. This necessitates the drawing of stone barges up stream, which even in the slack-water behind the mattress is troublesome and takes much time; still it has proved much the safer method, as there is little chance of sharp bends and broken willows or the loss by collapsing of an entire mattress from a single accident. It is believed that with this method, when the mattress is made sufficiently strong, especially on the outer edge, and has been sufficiently guyed, that a collapse or entire loss is simply impossible. In October, 1883, on Bullerton 1,800 feet of mattress were sunk in 40 feet of water with a five-mile current. This mattress was built on a netting formed of wire cables such as were used on the dikes; still, at first, it proved too light and broke, yet but 75 running feet were lost. It was then strengthened until we had wire cables on the outer edge and extra poles and wire on the outer 50 feet, when it was sunk in place in perfect shape without difficulty.

We have been extremely fortunate in sinking, and except when a mattress was torn away from its fastenings by drift at high water, but very little has been lost. Great care, however, is always necessary to see that the rock is uniformly distributed, and that the mattress is thoroughly down in every part.

Our mattresses have averaged from one-half to three-fourths of a cord of brush to 100 square feet, which is sunk with from three-fourths to one and one-fourth cubic feet of rock, more being necessary with the second method of sinking than with the first.

2d. Revetment for the protection of high-water bank, which should previously be graded to the required slope, is composed of a frame of stout poles with 12 to 15 squares (Fig. 4) well wired at the intersections; over this a heavy layer of brush is placed, then a second frame on top, the whole being sewed and wired through and through. This is to form a base for a covering of rock placed almost in juxtaposition, though frequently we have been obliged to content ourselves with just sufficient rock to keep brush in place. The great enemy of a revetment is the flow of subsoil water from the bank; the drainage of low lands in the rear has greatly lessened this evil.

Foot mattresses placed at the foot of pile dikes have been made from 50 to 100 feet wide, and in construction do not differ from those made for protection of the bank.

are easily sunk even in rapid currents, by starting at the head and keeping the head of the mattress in the general direction of the current.

4th and 5th. Tipped and grillage mattresses have already been thoroughly discussed for the head of dikes. To sink the former in heavy currents, especially when the

direction of the dike is across the flow of the most rapid water, they have been made in short sections thoroughly fastened with lines, and the inner edge sunk until the supporting wires are in tension when the stiffness of the mattress allows the outer edge to go down without much trouble.

QUARTERING AND SUBSISTING OF MEN.

With the large force of laborers employed, it became necessary to attend to the comfort, health, and safety of the men, and it is believed that the form of quarters already mentioned meets all that is required without unnecessary expense.

These boats are used exclusively by the mattress parties, each quartering from 100 to 125 men in all, who are provided with, and held responsible for, mattresses and bedding. Bread, fresh meat, and ice are delivered by the tow-boats each day, and general stores every 15 days on requisitions of the boarding masters in charge, who also furnish each month an account of the amount used, number of meals furnished, &c., from which the cost of a ration is deduced. This has averaged about 29 cents for the raw and 45½ cents for the cooked ration for one man each day.

Each pile-driver has quarters for its foremen and crew, while every fifth driver has extra accommodations for kitchen, dining-room, and fleet foremen, and can furnish meals for fifty men.

A bakery was built at Plum Point to furnish 400 to 500 loaves of fresh bread a day, but will soon be transferred to floating quarters as more convenient during the higher stage of the river.

Very respectfully, your obedient servant,

ARTHUR J. FRITH,
United States Assistant Engineer in charge.

CAPT. JOHN G. D. KNIGHT,
Corps of Engineers.

I 2

REPORT OF GEORGE W. GENDER, ASSISTANT ENGINEER, UPON OPERATIONS AT GOLD DUST, TENNESSEE.

GOLD DUST, TENN., *October 31, 1883.*

CAPTAIN: I have the honor to submit to you the following report of operations at Gold Dust, Tenn., from December 1, 1882, to October 31, 1883:

The present condition of the work at this point is represented on the sketch herewith accompanying this report, Plate III; also the total amount of construction completed, and the cost of which are placed upon the sketch. Stations were established every 100 feet along the work to.

Operations at this locality were in progress on the 1st of December, 1882, and continued up to this writing with such interruptions only as were made necessary by the high stages of water. This year has been remarkable for its protracted period of high water, which divided the year into two distinct working seasons.

The work done at this point previous to December 1, 1882, consisted of a main dike 2,000 feet long, from Station 47 to Station 99.

On December 1, 1882, a force of men, with their quarters and a complete outfit for constructing dikes, was transferred from Ashport to Gold Dust, and the construction of a mat 10 feet wide, placed directly in front of the main dike, was begun.

Two small mattress boats, each 100 feet long, were used; one, commencing at the upstream end of the main dike at Station 97+57, constructing a continuous mat 1,115 feet long, and the other, beginning near the middle at Station 74, constructing a continuous mat 2,461 feet long, which extended to the lower end of the dike.

On the 14th of December a fleet of 10 pile-drivers arrived and commenced driving on Cross Dikes Nos. 1 and 2. During the first ten days of January this fleet was increased to 17 pile-drivers. These dikes were constructed after the improved form introduced by order of Mr. A. J. Frith, assistant engineer in charge, and consisted of two rows of piles 14 feet apart, with piles in each row spaced 7½ feet between centers. Longitudinal riders were placed on the entire length of both rows, secured to the piling by drift-bolts and wire. The two rows were joined by horizontal braces placed in the direction of the current as near as might be, and resting on the riders of both rows. They were drift-bolted and wired to pile and rider. This construction was strengthened by wire cables, consisting of six strands of No. 8 wire, which were fastened to the piles in the front row 16 feet (required penetration) above the lower end of the pile, and around pile, brace, and rider of the rear row.

After Cross Dikes Nos. 1 and 2 had been completed, with the exception of a passage way for barges and material, the river began rising. In order that piles might be driven over that portion of Elmot Bar, which was exposed at low stages, pile-drivers were moved to the bar end of Cross Dikes Nos. 3, 4, and 5. The water continued to

and soon submerged the dikes when operations were necessarily suspended, February 21, with the river at a 30-foot stage. The force was reduced and pile-drivers

ed to Plumb Point to make necessary repairs and alterations for better con- of work.

the time of operations 4,899 linear feet of dike were driven. There were tructed 4,664 linear feet of footmat 100 feet wide at the main dike, 738 linear et wide at Cross Dike No. 1, and 1,270 linear feet of footmat 50 feet wide at ke No. 2. The largest amount of footmat constructed in any one day on one boat was 251 linear feet. Wattling 10 feet wide was placed on the main its entire length.

the water began rising there were 2,420 linear feet of footmat on the surface ater and no stone could be procured.

lower end of the main dike 412 linear feet were still afloat. Quantities of vded beneath the mat, increasing the current under the mat to such an extent used a deep scour at the piles. As soon as this scour was noticed sacks were but before these were filled, loaded, and towed in place, this portion of the s scoured out and the accumulated raft, consisting of dike mat, and drift ag down-stream struck Cross Dike No. 3, which was temporarily able to re-reat pressure, but being unprotected by a footmat, after several days a por- t scoured out.

ass of drift, driven by the swift current, struck Cross Dike No. 4 with irre-orce, demolishing a portion of that dyke.

s Dike No. 1, 738 linear feet of footmat, and at Cross Dike No. 2, 1,270 linear otmat 50 feet wide were still afloat, and the sand bags were used on these with

By this time the dikes were entirely submerged, and the mats were anchored fastened to the piles. Sinking was done from skiffs, as the drift above and below the mat prevented the use of barges. Sinking was very difficult, as nt was at right angles to the line of the dike, and therefore had a tendency : the up-stream edge under or over. The mat being driven down-stream by and current, the lower edge necessarily landed on the front piling, where it . after the up-stream edge was sunk.

onnt of the accumulation of drift in front of the main dike, work on foot- to be suspended before the upper section was completed, leaving the main roTECTED from Station 74 to Station 79+60. The river at this time was at a age, rising at the rate of one foot per day, and carrying heavy masses of its efforts to follow the more direct channel through Elnot Chute the cur- ce through the main dike where it was unprotected by footmat at Station 75, mass of drift took out a portion of Cross Dike No. 2, represented on sketch tters a b.

ster rushing through this gap with a velocity of not less than 5 miles per hour, ing heavy masses of drift which struck the edges of the breach, breaking pile , soon increased the length of the breach, which was again increased during d rise. The gap in Cross Dyke No. 2 was not increased, the dyke being 10 r than the main dike.

empt was made to repair these gaps, as the dikes were submerged.

ing an examination of the works at a low stage of water, it was found that dike had been damaged to a greater or less extent from Station 77+50 to 5+50, and from Station 59+60 to Station 47. That portion of the main dike , upper breach was found uninjured, with the exception of a few riders and hich were crushed by the weight of drift resting on them after the water l.

gh the water was 7 feet above the tops of the piles the drift did not pass over and at some places it is 60 feet wide and solid to the bottom.

the dike was not protected by footmat small channels formed, having suffi- cency to erode the bed.

ike No. 1 remained intact, and has a deposit in its rear as high as the dike places.

t-mat in front of that portion of the main dike which was carried away re- uninjured, and is covered for its entire length with large gravel, although : a scour of several feet on both sides of it. The new dike has since been rough this foot-mat.

ater portion of the damage done to these dikes was due to the sudden rise rer before the work could be completed; nevertheless large deposits were hin the area that would be inclosed by the work when finished.

main dike the deposits formed immediately behind the dike, while at the s the material was deposited some distance below the dikes, and nearly to f the piles.

s Dike No. 2, where the lower edge of the foot-mat rested upon the dike, the rmed immediately under the mat and does not extend for any distance be- like. This deposit consists of large gravel. The success of this accidental ion suggested the building of similar structures in hopes of obtaining like

II 16, with the river at a 28.35-foot stage, work was resumed and was con- 5908 EN—174

which was a force which was increased and decreased as the stage of the water was raised and lowered.

The construction of Elmot Bar being submerged, advantage was taken of the high stage of water to extend the western end of the main dike and northern end of Cross Dike No. 3 and to connect them with the main dike. The construction of the new dike was pushed forward rapidly, employing four pile-drivers on each of the main dikes. The first drivers Nos. 12, 21, and 22, stationed at the main dike were not used but were a valuable improvement on the old ones. The height of the lead was increased to 45 feet, enabled the greater portion of the piles to come under the hammer before reaching the water; while with the old leads, which had been used at a low stage of the river piles had to penetrate for several feet before they could be brought under the hammer. The new drivers were also equipped with large centrifugal compound duplex steam pumps, having two 10-inch and two 8-inch cylinders. The old drivers were equipped with single-acting piston pumps having 12-inch cylinders.

At this point driving has been exceedingly difficult on account of layers of very coarse gravel and blue clay. Pieces of gravel weighing half a pound have frequently been found.

At some places piles had to be pointed and driven, as the 14-inch jet of the drivers was unable to displace the coarse gravel. The new drivers using a two-inch jet were able to work through these hard strata without pointing the piles, but without a liberal use of the hammer. As soon as the piles had passed through the hard layers they would sink to the required depth of 16 feet with little difficulty.

About the 1st of May the construction of a grillage mat between the two rows of piles and extending about 10 feet in front of the dike, was begun at Cross Dike No. 3. Sections of mat 60 by 35 feet were constructed, and consisted of a thick, coarse braided mat lying in the direction of the current, firmly lashed to a grillage of poles which was suspended about 1 foot above the surface of the water by wires fastened to the boom of the dike. As soon as a section was completed the wires were taken off and it was sunk to the bottom with stones. These sections overlap about 7 feet.

A foot mat 100 feet wide placed directly in front of the main dike was commenced at Station 21-25; but work had to be suspended after completing 164 linear feet, on account of the drift accumulating in front of the dike, making it almost impossible to move the mattress boat.

Work on these lines was carried on until about the 1st of June, when they were compelled to desist on account of the high stage of the water.

While the work of extending these lines was thus delayed, eight pile-drivers were moved to Cross Dike No. 5 and its construction pushed forward. Four pile-drivers were transferred to Bullerton.

From April 16 to June 1 there were driven 5,200 linear feet on the main dike, 1,400 linear feet on Cross Dike No. 3, and 2,800 linear feet on Cross Dike No. 4. There were also placed 2,200 linear feet of grillage 40 feet wide on the main dike, 1,600 linear feet 35 feet wide on Cross Dike No. 4, and 850 linear feet 35 feet wide on Cross Dike No. 3. Watling 6 feet high was placed on the main dike for 800 linear feet, on Cross Dike No. 3 for 800 linear feet, and on Cross Dike No. 4 for 1,020 linear feet.

During the unexpected rise considerable damage was done to the main dike above Station 36 and to the south end of Cross Dike No. 3, which was due to the unfinished condition of these lines.

After the water had fallen it was found that the portion of Cross Dike No. 3 lying south of Station 8+50, the end of the grillage, was damaged to a greater or less extent by the piles scouring out and by the inability to secure the diagonal cables before the dike was submerged, the intention being to secure them after the grillage was constructed and sunk. A breach of about 100 feet was discovered above Station 36 on the main dike and one from Station 43+50 to Station 51.

The pieces of dike which had been scoured out floated down to Cross Dikes Nos. 4 and 5, and the piles are there being utilized to support the tip-mat. All of the piles were scoured out, as none were found broken. During the rise large deposits were formed immediately in the rear of the main dike.

A bar whose crest became dry when the river fell to a 26-foot stage extended nearly the whole length of the main dike below the lower breach. The largest deposits were made at the junction of Cross Dikes Nos. 3 and 4 and the main dike.

The point of Elmot Bar, lying to the northward of the main dike, within the space allotted to the channel, was washed away during this rise, and deposited in the rear of the main dike. This point previously caused a large percentage of water to pass through Elmot Chute, thereby increasing the pressure on the dikes during high stage of the river.

At the outer edge of the foot-mat on the main dike a scour has been noticed for the entire length of the concave portion.

It was noticed that where drift had accumulated in front of the cross dikes a scour has taken place equal in volume to that of the drift, and that after the water had fallen the bar the drift would exactly fill the space scoured out.

star having fallen, operations were first resumed upon the gap in the main Station 36, and upon Cross Diike No. 3, at Station 8+50. The main dike strengthened wherever small channels were discovered passing through it, by clusters of two piles in the front row, and also a third row. The piles in the second row were supplied with cables which were fastened around pile, and brace of the third row, to conform to the "Standard Diike," at this time in- by Mr. A. J. Frith.

la-driven were able to complete all dikes before the water left the bar, but some work was delayed by inability to obtain material owing to the flooding Elbow camps. Grillage and wattling is now being completed on dry land, the brush being supplied from the head of Elmot Bar.

the transportation of rock across the dry bar, tarred sacks filled with gravel are being substituted.

section of the main dike which was driven before the 1st of December, 1882, strengthened by driving two rows of piles in front of it and using the old third row. Considerable difficulty was experienced driving through the old , which was covered with coarse gravel.

section of the dike is being protected by a tip-mat from 38 to 60 feet wide, bed in sections of 150 feet. The mattress boat is placed parallel to the dike, some of the ways extending over the gunwale of the barge having been taken as are evenly distributed over the ways and their lower ends firmly secured less of the dike. The brush is wattled upon the poles by passing a rod of it ly above and below them. The mat is strengthened by placing poles above with the wattling pole, firmly lashing them with No. 12 wire. A section of having been completed, the mattress boat is sparred from under the mat, and rear edge sunk to the bottom.

deep channel near the Tennessee shore a tip-mat 75 feet wide is being con- in front of Cross Dikes Nos. 3, 4, and 5. The mattress boat is placed at right to the dike, the ways nearest the dike having been raised to the level of the maintain the mat at that height after it is launched from the mattress boat. making the mat, piles are floated under it. The up-stream ends of these are the poles of the mat, and the down-stream ends raised to the level of the here they are drift-bolted and wired to the piles of the dike. The up-stream e mat is then sunk to the bottom. In swift currents this mat is constructed as 120 feet long, about the length of a rock barge, as the mat has to sink for length simultaneously to prevent the up-stream edge from doubling over or

the main dike and cross dikes strike the Tennessee shore, the bank has been l by a mattress 350 feet long, and varying in width from 50 to 100 feet. The is completed to this mattress, leaving a mattressed opening for navigation 8 feet wide. The bank at these places has been graded, and bank pro- being placed.

g was done with pile-driver No. 19, which is equipped with a Worthington d duple pump, having two 10-inch and two 16-inch cylinders. The dis- about 420 gallons per minute, passes first through a 4-inch pipe, then through hose, and is delivered through a 1½-inch nozzle.

Table giving length of completed work as represented on sketch.

	Number of linear feet of dike.	Number of linear feet of grillage or old foot-mat.	Number of linear feet of wattling.	Number of linear feet of tip-mat.	Number of linear feet of grading.	Number of linear feet of bank protection.	Number of linear feet of mattresses.
No. 1	2,457	8,311	1,000	1,325		410	350
No. 2	700	200					
No. 3	650	225					
No. 4	300						
No. 5	700	350					
No. 6	2,910	2,810	850		330		300
No. 7	4,400		1,020	800	850		240
No. 8	2,400	2,100	450	1,505			
Total	22,397	17,636	3,020	2,130	670	410	690

Respectfully, your obedient servant,

GEO. W. GEUDER,
United States Assistant Engineer.

J. G. D. KNOX,
Engineer, U. S. A., Cairo, Ill.

as built previous to 1900 within the same or less area. It is now before be built some in the direction from a point near Osceola Bar, via the inclined struts, and to close in April. The piles, 14 feet apart, are swift current and are abandoned, and the dike is protected in water. The high water last year is considered as the breaks, which are scouring action in the coming out of the point. The foot-mat, as it is still in place, is in front of the dike, though it stood higher behind those. The part of this fill is all on the dike. If it is further on, it may be a fair one. The construction, a fault in the dike, was a lack of previous

OSCEOLA DIKE, 1900.

It is impossible to connect the end of Osceola Up dike further down the dike was protected and with the dike. During the construction of the dike drift of the foot of the upwater was immediately seen. The dike occurred in order to make the dike had to be changed at that point, the dike was driving. Luckily the material scoured out

piece of wire-united willow matting about 8 feet square was made. The bundle was wrapped up in it, and the center and ends of this bundle firmly wired. In case bailed rock was tied to willow bundles 6 to 8 feet long, and 1 to 1½ feet square. It was found by inspection, after the high water went down, that the use of fascines mentioned had done the better service of the two. They generally remained in place, while the bailed rock of the second kind, catching on the cables, prevented the fascine from going to the bottom.

Secondary No. 1, which stood the high water well, is especially remarkable for the amount of drift gathered in front of it. For a time the whole head of the dike from the dike up, was filled completely. Winds blew some of the drift down, but it had become firmly packed; but even to date about twenty acres of it are still wedged. Of course this mass has not been without its marked effect. The drift first began collecting an increased tendency to scour in front of the dike. The depth of this scour, as might be supposed, was equal to the height of the drift at the point under consideration. Where it has been possible the opening has been closed by sinking the drift, a barge of rock being expended for this purpose in front of Secondary No. 1. Should sinking the drift ever prove impossible, the scouring out of a dike is to be feared, unless it is well protected by foot-mats.


The effect of the drift, cited above, a good one can be opposed. When the construction of the dike was first begun quite a strong current set through the chute. The drift checked it so completely that when the present amount had come the current was almost dead. A marked fill both in front and behind the dike has taken place, so that if the holding of the latter should prove successful the direction of the work would seem to be indicated.

OSCEOLA SECONDARY NO. 2.

The construction of these dikes was pushed at the same time that No. 1 was built. The first section extends from the Arkansas shore to the northern point of the dike. The second section, from the lower end of this same towhead to the foot of Upper Bar. The type adapted is the double-line, rectangular, 14-foot base for the southeastern end of Section 1 and the northeastern end of Section 2. These portions of the dike running up on high ground, it was deemed sufficient to build them of but a single line of piles. In the second section an opening of 100 feet had to be left to enable the boats to reach the parties at work at the time when the water began falling it fell so rapidly that the pile-drivers had to be withdrawn before the gap could be closed. With the exception of this piece, then, the whole length of dike are protected by a grillage foot-mat and by wattling. From April 10 and finished May 20, these dikes have passed safely through one high stage of water; but built under the shelter of No. 1, little strain has come on them from other causes. A slight fill has taken place behind both of the dikes.

OSCEOLA MIDDLE DIKE.

Middle Dike, connecting the foot of Osceola Upper with the head of Osceola Lower was begun November 1, 1882. During December 1,065 linear feet were completed, giving the whole structure a length of 3,309 feet. The form of the dike adopted was the one as shown here. Top of outside pile



stage of 25 feet. Top of inside pile driven to a stage of 14 feet. Front rider fastened 5 feet below top of outside pile, rear rider at top of inside pile. A horizontal brace a b, horizontal a c; width of base, 14 feet. A 100-foot mattress was laid the whole length of the dike and the latter also wattled. As the water rose the lower front fore-and-aft rider it became impossible to push the wattling down. It would have been better had it therefore been left out entirely, for

2752 JOURNAL OF CLIMATE

[illegible]

GENERAL INVESTIGATIVE DIVISION

[illegible]

In the morning the ice 20 feet of low-mud had been sunk and a large amount of driftage for fuel put in. On account of the high water, an attempt was made to lower the level of the gas. Repeated soundings showed that no additional work

1. The first of these is the fact that the system is not a simple one. It is a complex system, and the results of the system are not predictable. The system is a complex system, and the results of the system are not predictable.

[illegible]

OSCEOLA UPPER BAR.

The head of this bar was well protected by a foot-mat 50 feet in width, and by a ot revetment, closely connected with the former. About 800 linear feet of this -graded work were executed, all of which is in good condition to date. That same cannot be said for some of the other work on the bar is easily explained. A foot mattress was put in the whole length of Osceola Upper Bar and sunk. This at low water. Though the grading and revetting were started immediately in of the mattress, it was impossible to finish them before high water set in. Of linear feet of grading put in, 2,100 were rendered entirely worthless, because the covered the banks before they could be revetted. The 1,400 feet that were ed with brush and partially rock also suffered heavily, for the reason that no action between the high and low-water protection could be secured. The banks ing away between the two has left a gap, as shown in sketch, which it will be easy to fill with a second mat.

OSCEOLA LOWER BAR.

During the high water in June and July, while it was found impossible to work at idary No. 3, a 100-foot mattress was started on the inside of the lower bar. y drift running necessitated the building of a drift-boom, in shape of a spur from the head of the bar down the chute for a distance of about 100 feet. Under ction 1,020 linear feet of mattress were built and sunk in place. A small section, y 120 feet, near the head of the bar, was put in when the water fell, and remains ighted to date for lack of stone. The bank protection on the inside begun June abandoned June 8, on account of high water, was continued August 13. By ist of the same month a total of 72,422 square feet had been made, of which 49,931 e feet remain unrocked to date. Of the 4,040 linear feet of grading put in last ary on the outside of this, the lower bar, no traces remain, as the graded bank ntirely unprotected when high water came up. This was to be expected. Eight red feet of a 100-foot mattress, which was also started at that time, were ht afloat by the same rise. Drift collected under the mat, and would have ren- l all attempts to sink it futile, even if rock had been on hand for that purpose. s constantly expected, the increased strain on the head-lines, due to the accum- g drift, caused them to part. Even one of the capstans of the mat barge was out of its fastenings, when the lines snapped, and mat and drift swung down the . Of the new one, 150 feet in width, which was started September 1, 3,583 linear have been completed to date, but only 920 feet of this amount have been sunk ; on the same has been stopped for the present, it not being deemed advisable in of former experiences to carry the mattressing too far ahead of the grading and tting. Another precaution has also been taken. Though the contour of the bar been closely followed by the mat in most places, it has been impossible to adapt tter to any sudden changes in the outline of the bank. The small openings thus ad between mat and shore have been covered with separate pieces of grillage firmly wired to the mattress proper. Four thousand four hundred and sixty e feet of this kind of matting have been called for to date, and more will be put the necessity for so doing arises. By this means a thorough connection between high and low-water protection can be obtained, i. e., if the former be put in at the nt stage of water.

ADAPTATION OF PLANT FOR PURPOSES INTENDED.

In accordance with your request, I submit, in addition, the following opinion, as to adaptation for purposes intended of those articles of plant which I have had oc- e to use.

The 100 foot mat barges, with ways 30 feet long, and a slope of the latter of about ninth, do not fill all the requirements that must be met. Great difficulty in shing the consecutive shifts of a mattress was constantly experienced. This is ly due to the slight slope of the ways and partly to the fact that so little space was between the lower end of the ways and the deck of the mat barge that the r (front) end of the mattress rests on the deck of the barge. In addition the ide butts of the willows do not pay freely over the end kevels, and the want of a tan was severely felt. The 175 and 213 foot mat barges, built with projecting more sloping ways, answer their purpose admirably. The latter barge, on which mattress on the outside of Osceola Bar is now building, can, however, only be to advantage in slackwater. In a strong current the handling of it becomes et an impossibility, as I found when this barge was swung across the break in els Secondary No. 3.

The service barges belonging to the reach answer all requirements.

The new general service barges, 120 by 30, used especially for the transportation ck, are somewhat unwieldy. Even if supplied with capstans, which they are it will always be a matter of some difficulty to handle them with a load of 300 yards of stone.

It was not considered necessary to do any work of a permanent character, as when the dikes are completed the chute will fill up. Mattresses made along the banks of this tow-head, with the exception of 350 of the wire-net pattern. This mattress constructed on specially designed machine has for its foundation a wire netting made of galvanized iron wire of No. 12 gauge, the heavier wires running longitudinally or up and down and smaller transversely. The distance between the longitudinal wires, which is of the length of the mesh, is 4 feet, while the distance between the others is 2 feet. A mesh 4 feet long by 2.5 feet wide has been adopted here. The brush is carried by suitable machinery operated by steam-power from the brush barge to the mattress barge, and deposited upon the netting, where it is received by men upon the mattress and supplied with long hooks, who pack it close together, taking time seeing that it breaks joints properly to give it the requisite transverse stiffness. After brush sufficient for a shift has been thus disposed upon the mattress, the binders are passed over. These are inserted with their butts into and bent through the netting, and then bent over the brush just laid and wired down. These binders are of course placed at right angles to the brush, and the length beyond where they are wired will be under the succeeding mattress. This makes an excellent mattress, being very flexible in a longitudinal direction, giving the necessary transverse stiffness, and is rapidly constructed. One hundred and eighty linear feet have been made in a day of ten hours when the current is moderate, and the party not subject to delays in getting brush. Three hundred and fifty feet of the mattress made here was of the regular pole pattern, and brush is alternately woven over and under the poles.

When the mattress between Ranges 51 and 52 was begun, it was evident that a mattress of great longitudinal strength to withstand the great strain which would be upon it during the operation of sinking would have to be constructed. For this purpose the single No. 8 wires were replaced by wire cables made of six of the same size well twisted together. These cables were placed 7 feet apart. In other respects the mattress is similar to the one just described.

The water bank protection whose lower edge laps over the inner edge of the mattress and which extends to the crest of the bank, consists of a loose brush matting continuous for its entire length.

The mattress is covered with stones, they being placed close together but only one layer thick.

In places where, owing to slight settling of the foot-mat, the high and low water protections do not make a good lap, small sections of mat, 100 feet long and 10 feet wide, enough to cover the gap, were constructed upon an ordinary barge placed parallel with the bank. One end of these mats rests upon the revetment. When finished the barge is pushed from under the mat, allowing it to fall

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

which were allowed to float away. About 500 linear feet of mat were sunk in making that new mattress had to be constructed. This is extra work resulting from high water, and of which mention has already been made.

The work at this place will ultimately be subjected to a very severe test, the utmost care has been taken to do it properly, and to impart to it that permanent character which work requires in order to answer the purpose of its construction.

When a new section of mattress was begun it was made to overlap the preceding one by at least 25 feet, thus practically making a continuous mattress. The mattress was made to follow the indentation of the bank as close as possible, and when this owing to the depth and shortness of the pockets, was not practicable supplementary mattresses were constructed after the principal one had been sunk, these small ones well overlapping the inner edge of the larger ones.

The report accompanying this report shows the condition of the work up to date. By referring to it, it will be seen that the length of bank operated upon is 9,625 feet. Of this 7,000 linear feet have been graded by the hydraulic grader and 1,525 feet with shovels, leaving 1,100 feet still to be graded. Five hundred feet of foot-mat and 2,700 feet of mattress yet remain to be constructed, while of the revetment made a large amount remains to be loaded with stone. That part of foot-mat-mat at the head of the head bounded on each side by Range 50 was constructed prior to December 1st, 1902. All the other work has been done since that date.

Whenever the foot-mat-mat has been sunk the erosion of the banks has entirely ceased, even at those places where the current strikes the bank directly, and while prior to the construction of mattresses were eating rapidly. Some of the finished work has been exposed to the various stages of the river from a complete submergence to very low water and has stood the test without sustaining the slightest damage.

The dikes now, though not yet finished, have done admirable work in deepening and widening the channel along the tow-head. Soundings taken in October, when the river was very low, show nowhere less than 12 feet of water, while at most places the depth is much greater. The least depth is at the upper entrance to the channel. Since our structures have had the slightest difficulty in delivering supplies here, and they have at all times been able to tow the most heavily-loaded barges through.

At the opening of the work last year, nearly all the towing had to be done through the channel on the Arkansas side, and around the foot of the tow-head up as high as they could go.

Attention is respectfully called to the urgent necessity of completing this work before the high-water season sets in. Should the river rise 4 or 5 feet above the present stage, great damage would be done to the unloaded revetment, and a high rise would seriously damage that part of the bank at the middle of the tow-head not yet protected, and endanger the finished work below.

Enclosed is a table showing the amount and kind of work done and giving dimensions of same. No account of the work as it is taken as that will appear in the report of the assistant engineer now in charge of the completion of these works.

A piece of a less width than 100 feet such as has been laid inside of main mattress for the purpose of covering gaps left by the latter. The piece of 150 feet was laid where the indentation of the bottom was exceptionally steep.

A length of mattress and revetment mat will be found to be respectively 100 feet and 150 feet. The excess of the length of bank operated upon. This excess will be reconstructed of damaged work, by the construction of mattresses to fill the gaps between the main one and the shore line or revetment, and by the amount of work done.

Work done at Bullerton Tow-head from December 1, 1902, to November 1, 1903

Kind of work	Dimensions	Totals
1. Mattress and revetment mat	100 by 150 feet	15,000 square feet
2. Mattress and revetment mat	25 by 150 feet	3,750 square feet
3. Mattress and revetment mat	4 by 150 feet	600 square feet
4. Mattress and revetment mat	150 by 4 feet	600 square feet
5. Mattress and revetment mat	150 by 6 feet	900 square feet
6. Mattress and revetment mat	24 by 150 feet	3,600 square feet
7. Mattress and revetment mat	150 by 24 feet	3,600 square feet
8. Mattress and revetment mat	150 by 24 feet	3,600 square feet
9. Mattress and revetment mat	150 by 24 feet	3,600 square feet
10. Mattress and revetment mat	150 by 24 feet	3,600 square feet
11. Mattress and revetment mat	150 by 24 feet	3,600 square feet
12. Mattress and revetment mat	150 by 24 feet	3,600 square feet
13. Mattress and revetment mat	150 by 24 feet	3,600 square feet
14. Mattress and revetment mat	150 by 24 feet	3,600 square feet
15. Mattress and revetment mat	150 by 24 feet	3,600 square feet
16. Mattress and revetment mat	150 by 24 feet	3,600 square feet
17. Mattress and revetment mat	150 by 24 feet	3,600 square feet
18. Mattress and revetment mat	150 by 24 feet	3,600 square feet
19. Mattress and revetment mat	150 by 24 feet	3,600 square feet
20. Mattress and revetment mat	150 by 24 feet	3,600 square feet
21. Mattress and revetment mat	150 by 24 feet	3,600 square feet
22. Mattress and revetment mat	150 by 24 feet	3,600 square feet
23. Mattress and revetment mat	150 by 24 feet	3,600 square feet
24. Mattress and revetment mat	150 by 24 feet	3,600 square feet
25. Mattress and revetment mat	150 by 24 feet	3,600 square feet
26. Mattress and revetment mat	150 by 24 feet	3,600 square feet
27. Mattress and revetment mat	150 by 24 feet	3,600 square feet
28. Mattress and revetment mat	150 by 24 feet	3,600 square feet
29. Mattress and revetment mat	150 by 24 feet	3,600 square feet
30. Mattress and revetment mat	150 by 24 feet	3,600 square feet
31. Mattress and revetment mat	150 by 24 feet	3,600 square feet
32. Mattress and revetment mat	150 by 24 feet	3,600 square feet
33. Mattress and revetment mat	150 by 24 feet	3,600 square feet
34. Mattress and revetment mat	150 by 24 feet	3,600 square feet
35. Mattress and revetment mat	150 by 24 feet	3,600 square feet
36. Mattress and revetment mat	150 by 24 feet	3,600 square feet
37. Mattress and revetment mat	150 by 24 feet	3,600 square feet
38. Mattress and revetment mat	150 by 24 feet	3,600 square feet
39. Mattress and revetment mat	150 by 24 feet	3,600 square feet
40. Mattress and revetment mat	150 by 24 feet	3,600 square feet
41. Mattress and revetment mat	150 by 24 feet	3,600 square feet
42. Mattress and revetment mat	150 by 24 feet	3,600 square feet
43. Mattress and revetment mat	150 by 24 feet	3,600 square feet
44. Mattress and revetment mat	150 by 24 feet	3,600 square feet
45. Mattress and revetment mat	150 by 24 feet	3,600 square feet
46. Mattress and revetment mat	150 by 24 feet	3,600 square feet
47. Mattress and revetment mat	150 by 24 feet	3,600 square feet
48. Mattress and revetment mat	150 by 24 feet	3,600 square feet
49. Mattress and revetment mat	150 by 24 feet	3,600 square feet
50. Mattress and revetment mat	150 by 24 feet	3,600 square feet
51. Mattress and revetment mat	150 by 24 feet	3,600 square feet
52. Mattress and revetment mat	150 by 24 feet	3,600 square feet
53. Mattress and revetment mat	150 by 24 feet	3,600 square feet
54. Mattress and revetment mat	150 by 24 feet	3,600 square feet
55. Mattress and revetment mat	150 by 24 feet	3,600 square feet
56. Mattress and revetment mat	150 by 24 feet	3,600 square feet
57. Mattress and revetment mat	150 by 24 feet	3,600 square feet
58. Mattress and revetment mat	150 by 24 feet	3,600 square feet
59. Mattress and revetment mat	150 by 24 feet	3,600 square feet
60. Mattress and revetment mat	150 by 24 feet	3,600 square feet
61. Mattress and revetment mat	150 by 24 feet	3,600 square feet
62. Mattress and revetment mat	150 by 24 feet	3,600 square feet
63. Mattress and revetment mat	150 by 24 feet	3,600 square feet
64. Mattress and revetment mat	150 by 24 feet	3,600 square feet
65. Mattress and revetment mat	150 by 24 feet	3,600 square feet
66. Mattress and revetment mat	150 by 24 feet	3,600 square feet
67. Mattress and revetment mat	150 by 24 feet	3,600 square feet
68. Mattress and revetment mat	150 by 24 feet	3,600 square feet
69. Mattress and revetment mat	150 by 24 feet	3,600 square feet
70. Mattress and revetment mat	150 by 24 feet	3,600 square feet
71. Mattress and revetment mat	150 by 24 feet	3,600 square feet
72. Mattress and revetment mat	150 by 24 feet	3,600 square feet
73. Mattress and revetment mat	150 by 24 feet	3,600 square feet
74. Mattress and revetment mat	150 by 24 feet	3,600 square feet
75. Mattress and revetment mat	150 by 24 feet	3,600 square feet
76. Mattress and revetment mat	150 by 24 feet	3,600 square feet
77. Mattress and revetment mat	150 by 24 feet	3,600 square feet
78. Mattress and revetment mat	150 by 24 feet	3,600 square feet
79. Mattress and revetment mat	150 by 24 feet	3,600 square feet
80. Mattress and revetment mat	150 by 24 feet	3,600 square feet
81. Mattress and revetment mat	150 by 24 feet	3,600 square feet
82. Mattress and revetment mat	150 by 24 feet	3,600 square feet
83. Mattress and revetment mat	150 by 24 feet	3,600 square feet
84. Mattress and revetment mat	150 by 24 feet	3,600 square feet
85. Mattress and revetment mat	150 by 24 feet	3,600 square feet
86. Mattress and revetment mat	150 by 24 feet	3,600 square feet
87. Mattress and revetment mat	150 by 24 feet	3,600 square feet
88. Mattress and revetment mat	150 by 24 feet	3,600 square feet
89. Mattress and revetment mat	150 by 24 feet	3,600 square feet
90. Mattress and revetment mat	150 by 24 feet	3,600 square feet
91. Mattress and revetment mat	150 by 24 feet	3,600 square feet
92. Mattress and revetment mat	150 by 24 feet	3,600 square feet
93. Mattress and revetment mat	150 by 24 feet	3,600 square feet
94. Mattress and revetment mat	150 by 24 feet	3,600 square feet
95. Mattress and revetment mat	150 by 24 feet	3,600 square feet
96. Mattress and revetment mat	150 by 24 feet	3,600 square feet
97. Mattress and revetment mat	150 by 24 feet	3,600 square feet
98. Mattress and revetment mat	150 by 24 feet	3,600 square feet
99. Mattress and revetment mat	150 by 24 feet	3,600 square feet
100. Mattress and revetment mat	150 by 24 feet	3,600 square feet

Respectfully submitted,

CHAS. D. KNIGHT,
Chief Engineer, U. S. A.

AUG. J. NOLTY,
United States Assistant Engineer.

I 5.

F. F. A. YEAGER, ASSISTANT ENGINEER, UPON OPERATIONS AT OSCEOLA-BULLERTON AND PLUM POINT DIKES.

PLUM POINT DIKE, *November 1, 1883.*

I have the honor to submit herewith a report of progress of the work on Bullerton and Plum Point Dikes from December 1, 1882, to October 31, 1883.

OSCEOLA-BULLERTON MAIN DIKE.

Coming to this dike, that part starting from Osceola Bar will be called North Dike, and the part starting at Bullerton Tow-head, South Dike.

On December 1, 1882, about 1,200 feet of North Dike was standing, and on March 1, 1883, a fleet of eight drivers was put to work, driving until April 13, between which time and the 18th all drivers were moved to Gold Dust. The dike was then completed but two openings, one of 200 feet, 900 feet from south end of South Dike, and another of 250 feet, about 300 feet farther. From April 18 to June 1, 200 feet of dike was added between the two openings, and 500 feet, about 400 feet from south end of South Dike, was added, on account of drift and no foot-mat. June 1 the drivers were again put to work, and on June 22 the mouth of chute was closed, all but a gap of 250 feet, 100 feet from south end of South Dike, and from June 22 to July 10 drivers were again put to work on account of having no piles long enough for depth of water. Between July 10 and 20, 600 feet between Ranges 49 and 49½, having no foot-mat, scoured out, and on the night of the 21st a large raft of logs lodged on the head of remainder of dike, and although this part had been matted, inside and outside, about 200 feet, it was washed away. The washing out of this part may be said to have been caused by the quantities of which had accumulated on dike, extending out farther than this was promoting scouring action under the mat at its outer edge.

On the night of July 23 the steamer J. S. Woods, with tow of empty barges, was put to work on dike where Range 49 crosses, catching pile driver No. 17, and pushing it up and up the front row of piling, about 150 feet. Shortly after this 454 feet of dike at the same place scoured out, caused by collapsing and imperfect sinking of clusters of three piles were then driven about 10 feet apart, and the tops connected by a heavy wire cable. A mat 100 feet wide and 250 feet long was made on each side of these clusters, but collapsed before sinking was commenced; 250 by 40 feet was added good and was sunk. The clusters stood erect for three days, when they were washed out, and about two weeks later washed out or broke loose. At this time, it was almost impossible to drive to any advantage, on account of rapidity and scarcity of long piles. All dike was now matted, and as the water was too high for boats to run outside of tow-head, a gap of 900 feet was left open for navigation, and all force moved down to finish Bullerton Cross-Dike No. 1. Between July 10 and 20, 375 feet of dike was added to south end of North Dike, and about 500 feet to south end of South Dike, making North Dike 3,995 feet in length, and South Dike 1,200 feet, with an opening of 900 feet between them. One thousand three hundred and fifty feet of North Dike is completely covered with sand, and all the South Dike is covered but 500 feet at south end. The general condition of dike is given in accompanying sketch.

BULLERTON CROSS-DIKE NO. 1.

This dike is composed of two parts, one on east side and the other on west side of Chute.

East Dike runs on a line from 49½ Ark to 52 Bullerton Tow-head, and is 570 feet in length. West Dike starts midway between 50 and 50½ Bullerton Tow-head, and runs about 200 feet below 50 Ark. It is 1,200 feet long and makes a curve at 1,130 feet in direction of West Dike. Some difficulty was experienced in the building of this dike, as for a time the piling washed out very fast, but after being matted inside and outside tip-mat, scouring action ceased, and since that time a fill of sand has been taken place, where previous to sinking of mat I reported five piles washed out by 7 feet of water. The shore at end of dike is protected with 200 by 50 feet of piling above and 150 by 50 feet below dike. Also a foot-mat of same material 100 feet wide. Each dike is all matted inside and as far as practicable outside.

East and West Dikes are in good condition, and a noticeable fill is taking place above and below each. From present appearances the chute is slowly filling in, and the channel going on the outside of the tow-head.

PLUM POINT DIKES.

These dikes were started September 20, and as yet little progress has been made owing chiefly to scarcity of material. Up to date work has been done only on Main Dike and Cross-Dikes 1 and 2. The amount of dike completed and incomplete is given on sketch. Five hundred and fifty-six feet of Main Dike has 100 feet foot-mat and 455 feet has inside or grillage mat between the second and third rows. The second row mat is a tip-mat, and was sunk to-day. The foot-mat has not yet been sunk. The foot-mat on Main Dike, according to orders, will be sunk flat, and cross-dikes will have grillage tip-mat and 50 feet tip-mat outside. The shore at head of Main Dike is protected by a revetment 290 feet long and 65 feet wide. The small gap between foot-mat of Main Dike and shore will be closed in a few days and cross-dikes will be finished to shore as soon as possible.

If the material can be had, Main Dike as far as Cross Dike No. 2 and Cross Dike No. 3 can be protected by the latter part of December.

PLANT.

The small, low, 100-foot mat barge used by me in Bulleton Chute is almost perfect for making mat in swift water, as it has but one kevel on each end and no cap. The new large 157-foot mat boat, with capstan on each end, I am now using, which is about that could be desired.

The pile drivers have done very well, but the circular lead drivers are at times awkward to handle, and are the cause of considerable delay. The side lead drivers are much more convenient and in every way preferable to circular leads.

Very respectfully, your obedient servant,

F. A. YRAG

J. G. D. KNIGHT,
Captain of Engineers, U. S. A.

16.

REPORT OF A. P. HATFIELD, ASSISTANT ENGINEER, UPON HYDRAULIC GRADING OPERATIONS.

ELMOT, ARK., November 13, 1892.

SIR: I have the honor to submit the following as my report of the hydraulic grading performed in Plum Point Reach since December 1, 1892.

On that date I was placed in charge of Grader No. 4. This grader has two Dyer pumps, independent action. Plungers 16 inches diameter, driven by two compound engines, the initial or high pressure cylinders being 18 by 24 inches, the low pressure cylinders 34 by 24 inches. Steam is supplied by a battery of three boilers, 22 feet by 44 inches diameter of shell, with five 10-inch flues. Area of grate surface, 50 square inches. The vacuum pumps are also of the Davidson style, steam cylinders 10 inches, water cylinders 12 inches diameter. The water supply came from two tanks directly below the pumps; these are 3 feet square, the water passing through strainers of 2,500 $\frac{1}{8}$ -inch holes. The suction pipe is 14 inches diameter. The discharge is through a boom pipe 10 feet long, having twelve openings fitted with valves; to these the hose is attached. The hose outfit consisted of 4-inch hose sections 50 feet each; two sections 25 feet; two sections 12 feet $2\frac{1}{2}$ inches. A 6-ply hose, four sections, 50 feet, with nozzles of $1\frac{1}{2}$ and 2 inches.

December 2, the grader was taken to the head of Bulleton and began work on west side. Here we graded, up to February 9, 9,432 linear feet, and 98,549 cubic yards. Up to this time the total operating expenses were: for labor, \$1,970.12; and for subsistence, \$548.25; total, \$2,518.37. Cost per yard, 3 cents; per linear foot, 3 mills. The grader had a total crew of 17 men, and used about 80 bushels of coal per week.

March 26 I was transferred to Grader No. 2. This has pumps of the Dyer type, and, except in being duplex action, the same of the same general dimensions and power as Grader No. 4.

We again began work on upper Osceola Bar, where we were at work until April 1, the water again rising obliged us to stop. Here we graded 2,900 cubic feet, and 30,000 cubic yards. The expense of this period was: labor, \$190.00; and for subsistence, \$560.50; total, \$750.50. Cost per yard, 3.8 cents; per linear foot, 11 cents.

We were laid up on account of high water until July 14, when I was directed to take Grader No. 4 and try to wash a channel through the bar forming from the head of Bulleton toward the head of Yankee Bar. We commenced on the lower end of the bar, working up-stream with two $1\frac{1}{2}$ -inch nozzles, which were fastened to

ridson and Deane pumps. The advantage seems to be with the Deane for its simplicity of action and their greater solidity acquired by the iron beds and the metal of its parts.

The arrangement of the wells under the pumps was found to give trouble by the sucking the sand and muddy water running off the banks, wearing the packing ingers. While laid up during May and June this was changed so that the water is now taken from the bow or the point where, as the grader lies to the bank, it is over the deepest water and removed as far as possible from the effect of the suction from the bank. The wells in the bow seem to act as a settling tank and deliver better water to the boilers and pumps, but they require to be frequently cleaned of the mud deposited.

The left pump of Grader No. 4 seemed to have settled out of line, so that during August we could use but one pump. An examination also showed that part of the valve had become so worn that it was probably the cause of the irregularity of stroke and heavy pounding for some time noticed in this pump. The rubber valves seem to wear rapidly. Two sets have been used. The worn valves have been refaced in a lathe after being so faced have proved to be of very little further use.

In making the grade I have generally used one 1½-inch nozzle with two 1¼-inch. The large nozzle proves to be more effective than two small ones, but the small ones make a better grade. There seems to be too much water flowing in one place from the large nozzle. When using all, I have had the small nozzles working together nearer the bank, with the large nozzle about 100 feet ahead in a cut by itself. Occasionally masses of hard blue clay is found which the smaller nozzles cannot cut, and I have obtained all. The general arrangement of strata has been, on the top a brown loam four to twelve feet thick, with underlying strata of sand alternating with strata of clay. These strata occur in great variety of number and thickness. When the bank is of clay but little care need be taken for a smooth grade. Where sand occurs the method I have used has been to keep the top of the cut a little ahead of the sand and always keeping enough of the loose soil back of the cut to form a sluice to prevent the water flowing back over the grade. A gully will be formed at the bank but, if properly managed, this can be filled by the caving of the bluff, and the grade advanced as rapidly as possible. The proper grade should be made at the first; any trimming afterward generally does harm. In some sandy places the only way we could prevent gullies was to throw the water from the top of the grade by a ditch. After cutting does not run down the grade, but glances off into the

countered are logs buried in the bank, stumps, the willow esperrillow brush growing thickly with long roots; these form a mat that will not penetrate, and must be cut and pulled out. When practicable, standing on the grade; otherwise they are pulled out by the hoist-

[Form 2.]

STEAM ENGINEER'S REPORT.

Date: ——— —, —.

Exact time starting.			Exact time stopping.			Reading of counter.	Remarks, cause of del
H ^r	M ^r	S ^r	H ^r	M ^r	S ^r		

[Form 3.]

STEAM ENGINEER'S DAILY REPORT.

Date: ——— —, —.

Time of day.	Pressures.			Strokes per minute.		Reading of counter.	Remarks, time of del cause.
	Steam.	Pump.	Vacuum.	Number.	Length.		

[Form 4.]

NOZZLEMAN'S REPORT.

Date: ——— —, —.

Time of day.	Pressures.			Length of hose.		Remarks, c of hose.
	Nozzle.	Pump.	Vacuum.			
	H ^r	M ^r	S ^r			

I 7.

OF W. H. POWLESS, ASSISTANT ENGINEER, UPON SURVEYS ON THE PLUM
 POINT REACH.

FULTON, TENN., November 5, 1883.

SIR: In accordance with your order of September 14, I have the honor to
 the following report for the eleven months ending October 31, 1883.

and office work.—The following is a statement of the work accomplished by
 ty:

Following additional maps and tracings have been made:

rous progress sheets have been prepared, and several drawings made of
 ery, &c.

Following measurements of discharge have been made:

Following miscellaneous field work has been done:

of the river.—From the hydrograph which accompanies this report it will be
 at three distinct flood-waves passed down during the eleven months. The
 attained by their crests, and the dates of their passage at Plum Point, are as
 :

Date.	Height above low water of 1879.	Height below high water of March 1, 1882.
March 1, 1883.....	Feet. 32.20	Feet. 0.52
April 19, 1883.....	28.80	3.92
June 30, 1883.....	26.75	5.97

First flood caused a general overflow between Cairo and Memphis; but as it
 d very rapidly, its effect was less disastrous than that of March 1, 1882. The
 and third flood-waves only overflowed the banks in a few localities; the latter
 used by the Missouri River, and did much damage above Cairo.
 accordance with your instructions, the mean stage of the river for the years
 November 1, 1882, and November 1, 1883, was computed, a planimeter being
 the purpose. The results obtained were 20.6 and 14.8 feet, respectively.
 owing table gives the mean stage for the months comprising those years.

Mean stage of river.

Months.	1881 and 1882.	1882 and 1883.
	Feet.	Feet.
.....	1881, 17.5	1882, 5.6
.....	1881, 18.2	1882, 5.2
.....	1882, 28.2	1883, 9.7
.....	1882, 31.7	1883, 25.6
.....	1882, 31.8	1883, 24.4
.....	1882, 24.1	1883, 26.0
.....	1882, 25.7	1883, 20.8
.....	1882, 26.1	1883, 24.0
.....	1882, 22.0	1883, 19.4
.....	1882, 11.7	1883, 10.5
.....	1882, 8.0	1883, 8.1
.....	1882, 4.7	1883, 2.4

The following table is also appended.

Number of days on which the stage of the river varies between—	November 1, 1881, to November 1, 1882.	November 1, 1882, to November 1, 1883.
0 and 5 feet....	Days. 12	Days. 75
5 and 10 feet....	45	28
10 and 15 feet....	46	29
15 and 20 feet....	23	61
20 and 25 feet....	73	43
25 and 30 feet....	84	59
30 and 35 feet....	63	26

CHANGES ON THE REACH.

The most striking change noted is the great excess of the fills over the scour feature probably due to the February-March flood, the slackening of the current as the water overflowed its banks causing deposits which subsequent floods have as failed to remove.

Ashport Bend.—In the bend above Daniels Point rapid caving occurs, in medium and high stages, and an unusually swift current existed. (During the February-March flood the surface velocity in this bend, about 300 feet from the cable bank, was 9 feet per second or 6 miles per hour.) The material derived from caving was probably deposited over the bed of the river in Ashport Bend, where current was much more slack. This deposit in turn caused a contraction of section area from which the river, owing to the curvature of its left bank and the nature of its material, sought relief in caving rather than in bed erosion. Approximate values of the volume of scour and fills in this locality were as follows:

	Cubic
Volume of caving bank in bend above Daniels Point	170,000
Volume of caving bank in Ashport Bend	106,700
Volume of bed erosion in Ashport Bend.....	86,000
Volume of fill over bed in Ashport Bend	429,200

Assuming that the volume of caving in the Ashport Bend has been carried by the volume deposited in the bed which has been derived above from sources other than the caving bank in the bend above Daniels Point is 152,500,000 cubic feet.

The values of the mean depths, widths, and sectional area at low water are given in a table accompanying this report, and are also represented graphically on a trac. The following are the mean values in this part of the river.

Mean changes in Ashport Bend, Nos. 20-27, both inclusive.

Decrease in high-water sectional area	square feet.. 10
Decrease in low-water sectional area	do..... 9
Decrease in low-water mean depth	feet..
Increase in low-water width	do.....

Ranges Nos. 27-31—The changes over this portion of the river consist in a fill along the main dike and a fill in the channel. The maximum value of the former is 10 feet and its average about 5 feet. The maximum fill, 23 feet, occurs on No. 30.

Main river, Nos. 32-38. An inspection of Nos. 32 and 33 shows that a very heavy fill has occurred off Elmot Bar, which has been accompanied by marked caving on the Arkansas shore. On No. 33 the area of this fill and caving are nearly equal, on No. 32 the fill is largely in excess. The caving in this locality has formed a point below No. 33, the tendency of which is to throw the water toward the foot of Elmot Bar. This effect is particularly noticeable on No. 36.

Elmot Chute—The changes in this chute are as follows: Over areas behind the dikes a fill has generally resulted; over areas behind the gaps recently closed a scour has occurred; on Nos. 30 and 31, at Keys Point, a caving bank and a marking have shifted the channel to the south, while lower down along Elmot Bar, from No. 27 to 29, similar causes have shifted the channel to the north. Below No. 38 there has been a new low-water mouth along the outside of Island No. 30, causing heavy scours. Owing to this and to the caving banks before mentioned, the result

in the high-water sectional area shows an increase. The increase in the area low-water section is not so marked, owing to the bulk of the erosion occurring low-water mark. Following are the values of these changes:

Mean changes in Elmot Chute.

42, excepting Nos. 23 and 31:

Increase in sectional area, high water.....	square feet..	3,340
Increase in sectional area, low water.....	do.....	420
Increase in mean depth, low water.....	feet..	1.1

Upper mouth of Elmot Chute at the foot of Elmot Bar is about the same as the December-February survey. It filled up completely during the high water but cut out again when the river fell.
No. 30.—The closing of this chute at its head, which was commenced in 1881, continues. It is now entirely cut off at the low stage, and has not been taken account in computing mean values of low-water areas, &c.
Mean changes in its three cross-sections are as follows:

Increase in high-water sectional area	square feet..	2,53.00
Increase in low-water sectional area	do.....	710.0
Increase in low-water mean depth	feet..	0.6

Osceola Chute.—The changes in this chute have been as follows:

Upper Osceola Chute, Nos. 39½, 40, 40½, 41, 41½, 42, and 43.

Increase in high-water sectional area.....	square feet..	4,396.0
Increase in low-water sectional area	do.....	946.0
Increase in low-water mean depth.....	feet..	1.9

Maximum fill 17½ feet, occurs on range 42.

Lower Osceola Chute, Nos. 45-47.

Increase in low-water sectional area.....	square feet..	40
---	---------------	----

Lower, Nos. 37-50.—On this portion of the river the most noticeable change is increased caving along Osceola Bar, extending from Nos. 41-47, and tending to narrow the channel still further toward the Arkansas shore. The closing of chute No. 30 at low stages, and the deepening of the lower mouth of Elmot Chute, have caused a shoaling (maximum value, 44 feet on No. 42) of the old channel, and a scouring of the Tennessee shore, against which the water from Elmot Chute impinges. The water is there deflected and then scours the old channel at No. 44, and thereby creates a fill in the locality where the Government fleet formerly lay. It also appears that a shoaling of 22 feet has occurred at the Plum Point Landing (No. 45). At No. 46, a fill averaging 16.4 feet has occurred for a distance of 2,400 feet, in front of the Osceola-Bullerton Dike, while a marked scour has taken place in the channel. At No. 47, a fill averaging 10 feet in depth has occurred on No. 48 for a distance of 1,200 feet, and on No. 49 a fill averaging 10.6 feet extends to the Arkansas shore.

Main river, No. 50, to head of Yankee Bar.

No. 50 a scour has occurred on the upper side of Bullerton; shoal water still exists along the outside of Bullerton Tow-head off its head, but a channel has been cut out about 1,200 feet from it, giving 10 feet at low water down this passage. At No. 50 a fill has generally occurred over Bullerton Bar, except on range 56, where a scour has taken place, owing to the recession of the bluff sand-bank which is on the right shore of the Tennessee Chute, below No. 55. A marked scour has occurred on the outside of Bullerton Tow-head, at No. 52 and 53, and a deepening has taken place at its foot. This latter change is not shown on the tracings; it occurred between the surveys of August and October, and amounted to 3 feet.

Tennessee Chute.—The following show the mean changes in Nos. 50, 51, 52, and 53, in the last year:

	Square feet.
Increase in high-water sectional area	1,212
Increase in low-water sectional area	1,481

Head of Yankee Bar.—Below Range 58 the changes are not very marked. Owing to the water caving, No. 58, which formerly crossed Yankee Bar, now passes above it, and still continues above Craighead Point.

2788 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Yankee Bar Chute.—No data exists for noting the changes in this locality. Apperances, however, indicate a fill throughout its whole extent.

Changes in Elmot and Island No. 30 chutes between surveys of April, 1882, and September-October, 1883.

The surveys of April, 1882, being made before the dikes were commenced, this comparison gives an idea of the changes caused by them. The caving of the banks at Key's Point and Elmot Bar and the deepening of the chute below No. 38 had begun several years before the dikes were commenced, and their erection has not as yet caused any changes in these localities. The shoaling of the chute of No. 30 at its head is of several years' standing, and still continua.

On a tracing the dikes are shown as they existed about August 1, as the gaps in them which have very lately been closed must have influenced greatly the changes which have occurred. These changes are very similar to those already noted above as occurring between the surveys of December-February, 1882-3, and October, 1883. On No. 31, outside of the dike, a fill is shown, but the former comparison shows that this has since been scoured away.

The mean changes which have occurred in these chutes are as follows:

Increase in high-water sectional area.....	square feet..	1,272
Decrease in low-water sectional area	do	52
Increase in low-water width ..	feet..	10
Decrease in low-water mean depth.....	do ..	0.1

An approximate value of the excess of the volume of scour over that of fill between the high-water sections, from 28 to 42, is 22,426,000 cubic feet.

Gauging observations.—Gauging observations have been made with double floats run at mid-depth and observed from the end of a base-line several hundred feet long. An ordinary watch was used for observing time. The distance over which the passage of floats was observed was 200 feet.

The computed discharges mentioned in the table of results given below (Appendix) have been computed from the equation of the Fulton discharge curve given in my report of July 11, 1881, to the Commission. The observed values of the discharge of the river at Bullerton Tow-head on September 5 and October 26 differ from those computed by 34 and 1 per cent., respectively.

It will be seen that the discharge in Lower Oserola Chute ceases at a stage of about 4 feet; at a stage of 25 feet it passes about 7 per cent. of the volume of the river. The observations taken in Elmot Chute show that in June the upper mouth discharged about one-half more than the lower mouth, but that in October these discharges were about equal. The discharge of Chute 30 ceases at about a 6 foot stage.

The ratio of the discharge of Bullerton Chute to the entire discharge of the river varies inversely as the stage. On September 15 (stage 4.9 feet) its value was 0.62; on October 26 (stage 5.4 feet) this was reduced to 0.50, owing to a scouring, both in the Tennessee and middle channels.

SLOPE OBSERVATIONS.

A table accompanying this report gives a comparison of the profiles of the river on March 1, 1882, on which date it reached the highest level on record, and on October 12, 1883, when the stage at Elmot was 3 feet above low water of 1879. It will be seen that the value of the fall from Ashport to Fulton is 1.36 feet greater at the low than at the high stage. This difference is a maximum at Petty's Landing, the fall between that point and Ashport being 3.28 feet greater at the low stage.

The following values of the fall through Bullerton Chute from Driver's to Petty's Landings, are given:

Date.	Above low water at Driver's Landing.	Fall.
	Feet	Feet.
March 1, 1882	33.	0.6
October 12, 1883	2.1	2.5
November —, 1879	0.2	3.2

From the tracing showing the two profiles, it is seen that the excessively high slope in the vicinity of Bullerton Tow-Lead is accompanied by a low value of the curve of mean depth; also, that a marked scour has occurred in the locality where at the high-water of March 1, 1882, a very heavy slope was found.

During the low-water surveys of August-September, 1883, and October, 1883, great variations were found in the level of the water at the opposite extremities of the cross-sections in the vicinity of Bullerton Tow-head, caused doubtless by a shoal

end of the Tennessee Chute, acting as as a dam and forcing back the water: ber 23 the following differences in elevation were found :

	Feet.
of No. 50 Tennessee above No. 50 Arkansas	0.62
of No. 51 Tennessee above No. 51 Arkansas	1.33
of No. 53 Tennessee above No. 53 Arkansas	1.62
of No. 54 Tennessee above No. 54 Arkansas	1.73
of No. 58 Tennessee above No. 58 Arkansas	1.78

ion is now occurring at this shoal in the chute, the effect of which will be the above differences and increase the discharge.

CAVING BANKS.

Bend.—The length of the caving bank in this bend is about 14,000 feet, from No. 21 to 26, and the greatest annual rate of caving is at present 540 feet; caving since the fall of 1879 has amounted to about 700 feet. As far as caving here occurs wholly at medium and high stages.

Wetcho's.—Caving here extends from the mouth of Mill Bayou to the false bar No. 33, a distance of 8,000 feet; of late, however, but little caving has occurred above No. 32. The maximum caving now occurs at No. 33, where the annual rate is about 300 feet.

Elmot Bar.—Below No. 34 the caving which was in progress in 1879 still continues, and to it is due the erosion of the lower mouth of Elmot Chute and of Chute No. 30 at its head. The length of the caving is about 5,000 feet, present maximum rate is 360 feet per year.

Osceola Bar.—The caving in this locality has been in progress since 1879, at that date the head has receded down-stream 3,000 feet, and the cut now known as the idle entrance formed. The caving since 1879 has been 1,600 feet at No. 41, at No. 44. The maximum caving of late has been at No. 44, where the bank has receded 250 feet in ten months. At present no caving is occurring in the locality, having been revetted.

San Souci.—Caving still continues in this locality and is most marked at the mouth of the chute owing to the swift current in Bullerton Chute. The length of the caving is about 3,700 feet, and its present maximum rate 270 feet per annum.

Shore Craighead Point.—This caving occurs almost entirely at medium and high stages. Its length is about 15,000 feet extending from No. 56 to No. 68. The present rate is about 260 feet per year.

Yankee Bar.—At high stages a very swift current was thrown against the Yankee Bar, due probably to heavy fills in Yankee Bar Chute. The bank composed of sand has receded very rapidly, the amount of recession being 1,200 feet from January to October, 1883.

High-water caving has occurred at Keys Point, left bank of Chute No. 30, and on the shore below Plum Point.

SUMMARY OF CHANGES ON THE REACH.

The following table exhibits the mean values of cross-section areas, &c., from Ashport to Fort Pillow. In all computations relating to low-water dimensions, caving chutes in which no current exists at low water have been disregarded.

Ashport, Osceola, No. 30, and Yankee Bar.
Mean values No. 17 to 71.

(The cross-sections have been measured with a planimeter from curves shown on tracing.)

in high-water sectional area	square feet..	4,438
in low-water sectional area	do	4,728
in low-water mean depth	feet..	0.9
in low-water width	do	109
low-water sections December, 1882, February, 1883	square feet..	49,520
low-water sections October, 1883	do	44,792
low-water mean depth December, 1882, February, 1883	feet..	15.4
low-water mean depth October, 1883	do	14.5
low-water width December, 1882, February, 1883	do	3,308
low-water width October, 1883	do	3,199

The effect of the decrease in high-water sectional area would be probably materially increased if the fills in Ashport and Yankee Bar Chutes had been ascertained. This, however, has not effected the values for the low-water sections.

2790 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

The following is a summary of the volumes of fill and scour over the river between the surveys of December, 1892, February, 1893, and October, 1893.

	Feet
Volume of fill below ordinary high-water mark	726,568,
Volume of fill below low-water mark	655,000,
Volume of fill above low-water mark	70,768,
Volume of scour below ordinary high-water mark	257,908,
Volume of scour below low-water mark	142,500,
Volume of scour above low-water mark	115,400,

My assistants, Messrs. Phillips, Mansur, and Clark have rendered valuable and efficient service.

Respectfully submitted.

W. H. POWLER,
Assistant Engineer

J. G. D. KIMMUR,
Captain of Engineers, U. S. A.

Results of gauging observations.

Locality.	Date.	Elmet gauge.	Area at cross section.	Mean depth.	Mean velocity.	Maximum mid depth velocity.	Observed discharge.	Ratio of observed discharge to area.
	1893.	Feet.	Sq. feet.	Feet.	Ft. per sec.	Ft. per sec.	Cu. Ft. per sec.	
Elmet Chute at Range 28 ...	June 27	26.60	75,781.5	21.9	4.70	5.90	207,651.4	
	July 18	17.00	29,129.0	18.1	4.00	4.50	196,261.0	
	Oct. 11	2.00					22,692.0	
Elmet Chute at foot of Elmet Bay	June 26	26.50					215,281.4	
	July 18	17.00					97,678.0	
	Sept. 20	2.00	2,972.0	8.4	2.71	4.00	11,028.0	
	Oct. 11	2.00	3,570.0	8.6	2.20	2.70	11,592.0	
Elmet Chute lower mouth of range	June 27	26.4	2,144.1	28.4	5.0	5.26	141,670.0	
	July 18	17.55	2,511.1	22.3	4.6	5.55	98,588.0	
	Sept. 20	1.65	5,140.0	6.1	1.76	2.17	8,984.0	
	Oct. 1	2.70	5,440.0	6.5	2.09	2.70	11,240.0	
Small chute opposite lower head on Range 33 ..	June 26	26.60	9,136.0	15.8	3.80	4.20	35,027.0	
	July 18	17.00	3,761.0	7.2	3.80	5.71	14,344.0	
	Sept. 20	1.95					0	
	Oct. 11	2.70					0	
Chute No. 30 ..	June 26	26.60					158,824.7	
	July 18	17.00					57,850.2	
	Sept. 20	1.95					0	
	Oct. 11	2.70					0	
Oscola Chute at Range 41	July 5	25.80	21,449.0	17.3	1.2	1.8	26,545.2	
Oscola Chute, Range 42 Arkansas shore	July 5	25.80	8,562.0	14.9	1.57	2.00	13,552.6	
Oscola Chute, Range 45 ..	May 10	23.30	16,356.8	21.6	3.60	4.20	59,074.5	
	July 5	25.80	16,637.0	21.2	4.00	4.60	65,671.8	
	July 17	16.60	9,000.0	13.2	3.12	3.60	28,148.0	
Oscola Chute, Range 48 ..	Sept. 5	4.95	3,764.0	6.2	0.36	0.45	1,211.0	
Enderton Chute at Range 53 ..	May 10	23.50	42,189.5	41.9	4.60	5.35	194,774.4	
	July 17	16.60	35,924.0	37.0	5.02	5.80	182,235.0	
	Sept. 5	4.95	24,658.0	25.5	5.10	7.00	126,431.0	
	Oct. 26	5.35	24,650.0	23.4	4.48	5.27	107,711.0	
Middle Channel, Range 53 ...	Sept. 5	4.95	18,700.0	9.2	2.80	3.71	52,238.0	
	Oct. 26	5.35	18,600.0	8.6	3.54	4.32	65,875.0	
Tennessee Chute, Range 53	Sept. 5	4.85	10,400.0	7.7	2.50	3.13	25,502.0	
	Oct. 26	5.35	12,050.0	8.5	3.34	4.50	40,255.0	

Discharge of entire river at Range 63.

West gauge.	Above low water at Fulton.	Area.	Width.	Mean depth.	Mean velocity.	Observed discharge.	Computed discharge.	Difference.
Feet.	Feet.	Sq. feet.	Feet.	Feet.	Ft. per sec.	Cu. ft. per sec.	Cu. ft. per sec.	Cu. ft. per sec.
4.45	4.21	53,125	4,345	12.2	2.7	304,100.0	211,700	1,000
4.35	4.34	54,100	4,610	11.0	2.0	323,861.0	211,736	2,127

under 5 the river was falling. On October 26 the river was stationary.

APPENDIX K.

OF MAJOR A. M. MILLER, CORPS OF ENGINEERS, UPON OPERATIONS IN THE SECOND DISTRICT, MISSISSIPPI RIVER.

UNITED STATES ENGINEER OFFICE,
Memphis, Tenn., November 12, 1893.

SIR: In compliance with your letter dated September 6, 1893, I have the honor to submit the following report of work done since December 1, 1892, in the second district, under the supervision of the Mississippi River Commission.

MEMPHIS REACH AND HARBOR.

Bank protection.

Under the act of March 3, 1892, a project was submitted for work on the Memphis Reach, from land No. 40 to Scanlan's Landing, and the revetment of the bank in Hopefield on the west bank, and from Frame's Chute to mouth of Wolf River on the east bank. This project was approved by the Commission, an allotment of \$300,000 having been made for this purpose, and at a subsequent meeting of the Commission, on my urgent recommendation, an additional allotment of \$25,000 was made for the purpose of revetment of the bank on the Memphis front, from the freight elevator to mouth of Wolf River, where caving seriously threatened great damage and the probable destruction of very valuable mills, the cotton compress, and freight elevators.

MEMPHIS FRONT, BELOW WOLF RIVER.

Work of sinking mattresses was nearly completed on December 1, 1892; since that time five mattresses were sunk, three in the vicinity of the cotton compress, and two in front of the city levee, as shown on map. The upper bank was graded by the engineer from the elevator to cotton compress and revetted with willows and broken stone. In connection with the revetment of the bank it was necessary to build wooden culverts to carry the city drainage to low water, in order to prevent its cutting the bank into and thus causing fresh caving.

Amount of work completed here was as follows: Five mattresses 60 by 120 feet = 7,200 cu. yd.; 13,700 cubic yards bank excavation; 362 feet wooden culverts 2 by 2, 273 square yards of upper bank revetment.

Work has apparently accomplished the object for which it was constructed, the prevention of further bank caving. It has stood well the high water of 1893, and quite a growth of willows has made its appearance on the upper bank revetment. Some repairs may be necessary from time to time to keep the culverts in order.

REKETMENT OF HOPEFIELD BEND.

Work consisted in sinking deep-water mattresses, building upper bank protection, and the grading of bank above low water. The object of the work is to hold

the river is to prevent channel, thus preventing a possible cut-off, which would leave the city of Memphis away from the river.

The project contemplated the revetment of the bank from Round Bay Landing above for a distance of 10 miles, to a point in the vicinity of Flowood.

As a special case was taken in December, 1901, in the construction of a bank grade bank in grading the bank and mattress making which was completed on February 15, 1902, when high water put a stop to the work. While in the process of the river during the making of mattress work, rapid rising water came off only, was expected that it was a strong current it was therefore not possible to construct mattress mats. The mattresses were therefore sunk in holes varying from 20 to 30 feet, and having a width of 100 feet.

On February 15, 1902, high water caused a suspension of the work at about 1,125 linear feet of mattress 100 feet wide had been placed in position.

Work was resumed in August, 1901, and is still in progress.

The total amount of work done since December 1, 1901, to October 21, 1902, has been as follows: 4,954 linear feet of mattress 100 feet wide made and sunk; 1,125 linear feet of mattress 100 feet wide made; 6,942 cubic yards of bank-grading; 4,622 cords of willows cut and delivered; 415 cords of poles cut and delivered; 4,922 square yards of upper-bank protection made.

In addition, snagging, bank clearing, and repairs were carried on. For details which reference is made to the report of Mr. W. M. Berra, assistant engineer, made B. forwarded herewith, whose diligence and tact in immediate charge of the work has been of great value.

The portion of the bank revetment 1,125 linear feet, built December, 1901, to February, 1902, and which has experienced the effects of the high water of 1902, when the water was 5 feet over the banks at the point revetted, has shown good stability. After the water fell a small cave occurred, owing to a want of continuity of the mattress, which was rectified by placing a mattress over the vacant spot. The exposed end or head of the mattress work will require some additional work to secure it in its present condition is secure from serious damage. The effect of the next high water upon this work is looked forward to with great interest, as it will probably decide many points in this method of protection. It does not appear to be advised to undertake this kind of work until the water has nearly if not quite reached its lowest stage, although this depends somewhat on the depth of water at the bank to be revetted. At high water it has been found very difficult to place the mats in position, as the tendency is to slide or run up against the bank, thus resulting in upper bank protection, when it is essential that the lower bank should first be held. The principal cause of delay in the work has been difficulty in procuring willows. During low water, when it is absolutely essential to push the work as rapidly as possible, the very worst conditions obtain in reference to procuring willows; that is they cannot be hauled quite a distance together on the barges. This is the principal reason why the work on the reach has been so slow, as it was not possible to haul them to the place where they were needed. It is not possible to haul willows at low water as they must be freely floated down the river for weighing. Delay from lack of timber has not been felt very seriously in this work as the work required has been comparatively small. On the occasion of previous work had sacks filled with black-shot clay to sink a mattress, and the sacks seem to have been 4 or 5 gunny sacks were used at a cost, and loaded on barges, filled of about 50 lbs. the weight was equal to about 214 cubic yards of stone.

Labor has been plentiful, but difficult to keep employed on account of the unhealthful water. White labor has been employed with the exception of one white party, which was composed of Negroes with white overseers. They gave better satisfaction in cutting willows than white labor, but were more difficult to keep as when their wages were spent, they would quite generally leave and lay idle till their wages were spent.

The report of Assistant Engineer Joseph Birney, Appendix K 1, showing all the work done on Memphis Harbor is transmitted herewith.

REPAIR OF LEAVES, YAZOO FRONT

The Board of Engineers, U. S. Army, in Order No. 88, Headquarters Corps, Engineers, Washington, D. C., August 1, 1892, directed the Chief of certain levees in the second district of the Mississippi River, open bids for the construction and repair of levees September 20, 1892, and a further letting was made on October 16, 1892. The following are the abstracts of bids for pairs of levees in the second district of the Mississippi River Improvement.

Abstract of bids opened September 25, 1882.

	Names of bidders.	Locality of levee.	Price per cu- bic yard.	Price of felling timber.	Remarks.
1	R. G. Huston, Cincinnati, Ohio, John B. Neely, Chattanooga, Tenn.	Parker's Enlargement and breaks.	\$0.37		
2	J. W. Eldridge, Lake Charles Landing, Miss.	{ Lake Charles break }	30	\$80 per acre.	{ Excavation. Embankment.
3	McGavock & Tate, Mem- phis, Tenn.		25		
4		Parker's Enlargement and breaks.	32	Cost and 10 per cent.	
5	Wirt Adams, president Mississippi Contract and Improvement Company, Jackson, Miss.	Parker's Enlargement and breaks.	23	(*)	
6		Lake Charles break }	22		

* Heavy clearing, \$48 per acre; light clearing, \$36 per acre.

Notes.—Contracts were awarded to McGavock and Tate for Parker's Enlargement and breaks, and J. W. Eldridge for Lake Charles break, Wirt Adams having declined on account of decision refusing employment of convict labor.

Abstract of bids opened October 16, 1882.

	Names of bidders.	Locality of levee.	Price per cu- bic yard.	Price of fell- ing timber per acre.	Remarks.
1	Patrick F. Lamb, Bolivar County, Mississippi.	Bland's Bayou to Gar- land's.	\$0 25½	\$75 00	Embankment.
2	W. M. Forrest and J. T. Stanton, Memphis, Tenn.	{ Garth's break to Jeffer- son's.	28	75 00	Excavation.
3			22½	50 00	Jefferson break.
4	Arnold & Co., Memphis, Tenn.	{ do.....	27½	50 00	Beard break.
5			24½	50 00	McCloud break.
6		do.....	23½	75 00	
7	McGavock & Tate, Colorado.	Bland's Bayou to Garland's	24½	75 00	
8		Garth's break to Jeffer- son's.	28	40 00	
9	Andrew Bodkin, Memphis, Tenn.	Bland's Bayou to Garland's	28	40 00	
10		Garth's break to Jeffer- son's.	25	40 00	
11	F. Gilcooly and John Clan- cey, Memphis, Tenn.	Bland's Bayou to Garland's	25	40 00	
12		Garth's break to Jeffer- son's.	24½	45 00	
13	Timothy Sullivan, Doni- phan, Mo.	do.....	22	75 00	

Notes.—Contracts were awarded to Timothy Sullivan for levee from Garth's break to Jefferson's, and to Arnold & Co. for levee from Bland's Bayou to Garland's, their bids being the lowest.

Work was pushed on these levee repairs, and the following work was completed and paid for:

Locality of levee.	Amount of work done.			Cost.
	Embank- ment.	Excavation.	Clearing.	
	Cubic yards.	Cubic yards.	Acres.	
Parker's enlargement.....	89,322			\$28,583 04
Lake Charles break.....	38,868	1,061	14.30	11,179 30
Bland's Bayou to Garland.....	44,800		22.83	12,800 25
Garth's break to Jefferson's.....	86,552		45.23	22,554 11
Total	259,542	1,061	82.36	75,116 70

All the contractors completed their work before high water, and final payments were made. Since the completion of the work the levee has broken again at the McCloud break, and should be repaired.

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

MISSISSIPPI.

A survey of the Memphis Reach was completed February 21, 1883, by Asst Engineer F. A. Fisher, whose report (Appendix K 3) is herewith submitted.

A survey of the Wilson Reach from Commerce Cut-off to Friar's Point was placed January 21, 1883, by Assistant Engineer F. A. Fisher, whose report is herewith submitted (Appendix B 4).

A survey, measurement, and estimate for repairs of levees in the second district was completed by Assistant Engineer Richard Klemm, whose report is submitted (Appendix K 5).

A low-water survey of the Memphis Reach was made in September, 1883, by J. S. Smith, draughtsman, on which sheet is plotted the shore lines and position of the work, and which is submitted with this report.

Tables showing detailed statements of expenditure under each allotment from provision for Mississippi River in this district, also table showing amount of purchase for the Memphis Reach, with cost of same, are transmitted herewith.

Very respectfully, your obedient servant,

A. M. MILLER,
Major, Corps of Engineers.

Lieut. Col. C. R. Cresswell.

Corps of Engineers, United States Army,

President Mississippi River Commission.

Table of property bought for use at Memphis Reach and Harbor, with cost of same.

Description.	No.	Unit cost.	Total cost.	Remarks.
Boats	12	\$2,000 00	\$24,000 00	
Do	3	1,000 00	3,000 00	
Total	15		\$27,000 00	
Boats	2	6,000 00	12,000 00	
Do	4	1,500 00	6,000 00	
Total	6		\$18,000 00	
Boats	1	1,000 00	1,000 00	
Do	1	1,000 00	1,000 00	
Do	1	1,000 00	1,000 00	
Do	1	1,000 00	1,000 00	
Total	4		\$4,000 00	
Total	19		\$49,000 00	
Boats	1	1,000 00	1,000 00	
Do	1	1,000 00	1,000 00	
Do	1	1,000 00	1,000 00	
Do	1	1,000 00	1,000 00	
Total	4		\$4,000 00	
Total	23		\$53,000 00	

\$2,500 paid prior to December 31, 1882.

A. M. MILLER,
Major, Corps of Engineers.

STATEMENT OF EXPENDITURES FOR MEMPHIS REACH AND HARBOR.

For purchase of boats	\$27,000 00
For purchase of boats	18,000 00
For purchase of boats	4,000 00
For purchase of boats	4,000 00
Total	\$49,000 00

For 1, 1883. Amount expended for—	
Freight	\$168 85
Traveling expenses	222 83
Office rent	181 00
Fuel	497 80
Telegrams	11 63
Subsistence	16, 121 93
Hire of plant	3, 198 91
Total	105, 890 90

A. M. MILLER,
 Major, Corps of Engineers.

10 STATEMENT OF EXPENDITURES FOR CONSTRUCTION AND REPAIR OF
 LEVERS, YAZOO FRONT.

For 1, 1882. Allotment.....	\$80, 950 00
-----------------------------	--------------

For 1, 1883. Amount expended for—	
Earthwork	75, 116 70
Labor	1, 499 33
Material	138 00
Supplies	3 30
Outfit	8 75
Assistant engineers	1, 600 00
Clerk	175 00
Inspector	600 00
Stationery	8 25
Traveling expenses	267 95
Office rent and quarters	108 50
Telegrams	50 41
Subsistence	36 00
Advertising and printing	220 06
Total	79, 832 25

A. M. MILLER,
 Major, Corps of Engineers.

11 STATEMENT OF EXPENDITURES FOR SURVEY OF THE HELENA REACH.

For 1, 1882. Allotment.....	\$8, 000 00
-----------------------------	-------------

For 1, 1883. Amount expended for—	
Labor	\$3, 635 66
Material	41 08
Supplies	58 66
Repairs	6 00
Outfit	607 65
Assistant engineer	1, 205 00
Clerk	175 00
Draughtsman	750 00
Stationery	18 85
Freight	29 65
Office rent and quarters	193 00
Subsistence	562 74
Hire of plant	228 00
Total	7, 511 29

A. M. MILLER,
 Major, Corps of Engineers.

cully; so you directed the work should be done by laborers with pick and This is very expensive, as the earth has to be handled so often to get it into Fortunately, the river commenced rising and we just kept our work above did not require so much labor as if the water had been at a low stage. rading the bank we connected all the public and private drains and carried to low water by means of wooden culverts. We then laid wire upon the ank, 6 feet apart along the river bank, and 6 feet apart up the bank; upon we placed willow brush 6 inches thick, and then, on top of brush, we placed e as below, and secured same to the lower line of wire by connecting wires, the brush, so that along the upper bank it formed one large mattress. ork was done from the mouth of Wolf River to the elevator, with the excep- portion of the bank in navy-yard, 242 by 32 feet, and a portion, 200 by 30 ont of Brown & Jones' coal-yard. After the willows were secured to the y were well ballasted with stone, sand-bags and earthwork. This com- e work in a substantial manner, with the exception of the work noted and e amount estimated. ions were suspended February, 1883, and the plant and outfit turned over to field Bend works. the time we were at work we had very favorable weather and the river was l working stage; but we had considerable trouble to contend with, for want cient number of flat-boats, and considerable delay was experienced for want

ately after the suspension of operations the river rose and covered the whole rk, the gauge reading 34.75. Shortly afterwards the water fell to 18.20, when nation of the bank was made and the work was all found to be in good condi- the slightest sign of a break or crack in the bank appearing.

SUMMARY OF WORK DONE DURING SEASON.

mattresses sunk, 120 by 60 by 2 feet.
nare yards of willow brush shore protection.
ibic yards of excavation on bank.
et of wooden culverts, 2 by 2 feet, built.

AMOUNT OF MATERIAL EXPENDED.

ds of willow brush.
ds of cottonwood poles.
r pins, 4 feet long by 1 inch diameter.
r pins, 1 foot long by $\frac{1}{2}$ inch diameter.
ch carriage bolts.
nds wire.
nds rope.
ic yards stone.
d-bags.
ic yards cypress bark.
t of cypress lumber.
t of 6-inch stone pipe.
ave the honor to remain, very respectfully,

JOSEPH BURNEY,
Assistant Engineer.

J. M. MILLER,
Supr of Engineers, U. S. A.

K 2.

OF W. M. REES, ASSISTANT ENGINEER, UPON IMPROVEMENT OF MISSISSIPPI RIVER AT HOPEFIELD BEND.

UNITED STATES ENGINEER OFFICE,
Memphis, Tenn., November 1, 1883.

: In accordance with your verbal instructions, I have the honor to submit a operations for the improvement of the Mississippi River at Hopefield Bend, Reach, from December 1, 1882, to October 31, 1883. fect of this work is to prevent the caving of the bank, now rapidly taking d which threatens injury to the harbor of Memphis. arison of the survey of September, 1883, with that of December, 1877, shows ank in the middle of the bend has receded 1,500 feet. From August, 1882, iber, 1883, the caving was 300 feet in the middle of the bend, and near the above Hopefield, it was 450 feet. The distance across the neck of land to below is now about 13,000 feet. To arrest this caving the project is torevet with brush mattresses, these mattresses to cover the bank from the foot

DETAILED STATEMEN

August 2, 1892. All,

November 1, 1883. 5

REPORT OF JONET'S 11

MAJOR: I have the Memphis River I re to take local charge. work under water found in a fair case. Street, with the ex mill, and Messrs. B with this portion of private drains kept by the steamboat

In submitting the report by the elevator, he gave the property on the road cut to extent October 18, 1882, a quarter-boat fitted cottonwood poles constructed near the sink in front of the boat on: three in Jones' coal-yard to sink in front of C

Experience in the
mattress and great
river front this - at
tion of the river from
from using the boat
and great boat with
a small sailing
boat on the river
the water
he mattress
the mattress
reduced to
number of al-
of buildings

GRADING.

to level the bank above the low-water line it was necessary to grade it to slope for holding the brush and stone. During the first part of the work, from 21, 1882, to January 31, 1883, I used for this purpose hydraulic grader No. 2 of the Mississippi River Commission. This was loaned us by Capt. J. G. D. Mum Point, and was returned to him shortly after the high water closed. Before again resuming work, August 5, 1883, we obtained a small pump from Capt. W. L. Marshall, of Vicksburg, Miss., and with the latter, work is done. Both will be described.

Grader No. 2 consists of a duplex compound condensing plunger pump of the Dean Pump Company of Holyoke, Mass. The dimensions are as follows: low pressure cylinder, 36 inches; of high-pressure cylinders, 18 inches; plungers, 16 inches; length of stroke, 24 inches. The stroke is adjustable and was kept at about 23 inches. The piston speed averaged 61½ feet giving a theoretical discharge of 1,280 gallons of water per minute. This was with three steel boilers of 40 horse-power each, was placed on a barge 65 feet, which contains sleeping quarters for 30 men. Attached to the deck of the pump is a boom 65 feet long, made of lap-welded wrought-iron with cast-iron connections, and having openings at various points to which can be attached. This boom, with a double stage, overhangs one end of the barge and can be raised or lowered by a hoisting engine on deck. When in work the boat was held nearly at right angles to the bank, with the pump on the bank. The grader had not been run before we received it, and, as the machinery of large size, some time was lost in limbering it up so as to run. Delay was also caused by some imperfections in the machinery, and resulting in the breaking of a guide-arm to slide-valve rod, the piston rod, the tappet arm of condensing pump; in the settling of the foundation pumps, necessitating the building under them of two additional bulkheads; the small drift getting under the pump valves, thus destroying the latter was the principal cause of lost time, but the trouble was finally made up by putting up very fine screens over the ends of suction pipes.

Organization of the party for this grader was as follows: 1 assistant engineer, 2 steam engineers, 2 firemen, 1 foreman, 3 nozzle-men, 3 deck-hands, 1 cook, 14 fourteen men in all.

For the wet and dirty work, the foreman and nozzle-men were provided with suits complete, including caps, boots, and gloves.

The pump was supported upon a stand consisting of a piece of gas-pipe firmly fixed to the ground, and well braced. To it was attached a piece of round iron, 12 feet long, which passed into the pipe. This formed a universal swivel, the arrangement being light and quickly removable. A long lever, clamped to the end, rendered its direction easy, so that a large stream was manipulated with the same facility as a small one.

When in use, the nozzle was held as near to the bank as practicable, and the stream directed at angles varying from 45° to nearly 90°. The top part of the stream was cut off, so as to allow the water to always flow along the face of the cut. From experience the nozzle-men had no trouble in holding the face. The bank was hard blue clay and buckshot, interspersed with layers of sand and sand, causing the banks to cave in steps.

Of nozzles 2, 1½, and 1¼ inch diameters were used, and two sizes of hose, 1½ and 2 inches diameters.

From trials it was found to be best practice, in the hard material worked, to use nozzles, large hose, and but one stream. The water pressure at pump varied from 135 to 140 pounds per inch. I think better results could be obtained with larger nozzles, as 2½ to 3 inches diameter. Experience in softer material shows best results from smaller nozzles and two streams.

The now used consists of a Dayton cam piston pump of the following dimensions:

	Inches.
Steam cylinder	16½
Water cylinder	9
Stroke	18

The boiler of dimensions as follows: 30 feet long, 48 inches diameter of the two 14-inch flues. The whole is mounted on a barge 100 by 16 by 34 feet. The discharge is 6 inches in diameter, and the discharge is through from 100 six-ply test hose, with nozzle of 1½ to 1¼ inch diameters, the latter gave the best results. The theoretical discharge is at date, the speed being 80 single strokes.

This grader is as follows: One steam engineer, one foreman, one cook, and one deck-hand; seven in all.

2000 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

During the month of September, 1893, I was obliged to keep water pressure down on account of the inferior quality of the hose; since then, with new 6-ply test hose, have had at all times a pressure of 240 pounds to the inch.

With grader No. 2 the slope cut was 3 to 1 from the water edge to the top of the bank. As the working capacity of the small grader was so much less, I have been obliged to grade to a greater slope, viz, 2 to 1 and $2\frac{1}{2}$ to 1, being governed by nature of material, quantity to be removed, &c., and also to leave a vertical face, varying with the material, of from 6 to 12 feet. Under the head of "work done" will be found tables of results obtained with both graders.

WORK DONE TO NOVEMBER 1, 1893.

Preparations for commencing the work were made on December 6, 1892, by erecting quarters for the accommodation of 100 laborers, upon the bank near the upper end of the reach, and by employing a small force to clear the bank of timber and brush. The entire length of the bend, a distance of over two miles, was cleared to an average width of 75 feet. Many large trees had fallen over the bank into the water, thus forming obstructions to the placing of mattresses. Your attention being called to this, you obtained the United States snag-boat H. G. Wright to remove them. Between December 7 and 14, 1892, she cleared about $\frac{1}{2}$ mile of the bend.

On December 4, the steamer Emma Etheridge delivered the following plant: Hydraulic grader No. 2, two mattress boats, one machine-shop boat, one screen-boat, and one barge of coal.

Preparations were at once made to start the grading, which was begun on December 21, at which date, the quarters being finished, I commenced subsisting the men. Owing to the non-arrival of barges and quarter-boats for the brush party, the work of building mattresses was not begun until January 16, 1893, at which date Assistant Engineer Joseph Burney, who had charge of the work of protecting Memphis Harbor, commenced supplying me with brush. I obtained poles from bank clearing and others by sending a party several miles up the river, they returning to the work at night.

From December 29, 1892, to January 15, 1893, the United States snag-boat Jno. B. Meigs was employed to tow willows, &c., to the works. At the latter date the chartered tow-boat H. M. Graham arrived and took the place of the Meigs.

MATTRESS CONSTRUCTION.

The construction of "deep-water mattress" was begun at Mound City ferry-boat landing on January 16, 1893, and continued until February 10; during which time 1,127 lineal feet of mattress, 140 feet wide, was constructed and sunk; 194 by 25 feet of foot-mattress and 194 by 16 feet of shore-protection were also completed.

The mattresses sunk were four in number and from 256 to 298 feet long; it being considered advisable to make short mattresses on account of the rapidly rising water and the great amount of drift running, much of which lodged against the mooring barge and caused a very heavy strain on the lines and a led to a rending of the mattress. The intention was to lap the mattresses by about 15 feet, but when sunk, owing to the drift pressure, gaps of this distance were found in two places instead of laps. There was used in the construction of the above 845 cords of brush, 195 cords of poles, 2,554 pounds of wire, 80 pounds of rope, 1,950 pounds of wrought spikes, 200 pounds nails, 555 cubic yards of stone, and 4,500 gunny sacks. The latter were used to sink mattress No. 3, which was 298 by 140 feet in size; each sack was filled with about 120 pounds of buckshot clay, the total weight being equivalent to the weight of 214 cubic yards of stone. They cost when filled and loaded on barges about 9 cents each.

The depth of water in which mattresses were sunk was from 40 to 70 feet.

During the first ten days in February, 1893, the work was much retarded by bad weather. The water having risen from 7.50 feet on the Memphis gauge on January 16, to 23.30 feet on February 10, work was suspended on the latter date, the water being then on a level with the bank upon which quarters were located, and necessitating their removal.

The grading of the bank was begun December 21, 1892, and continued until January 31, 1893, when work was suspended on account of high water. During this time there was graded 1,703 lineal feet of bank; 42,087 cubic yards of earth removed, at a cost of 24 cents per lineal foot, or 4.03 cents per cubic yard. Table I, annexed to this report, will show in detail the work done.

On February 28, the tow-boat H. M. Graham was taken to Cairo.

From February 10 to August 6, 1893, no construction work was done, the water being so high. During this time a small force of mechanics were employed in getting barges, quarter-boats, &c., in readiness for this season's work.

On August 15, I received your verbal orders to prepare to resume work. The tow-boat H. M. Graham arrived on the 17th and was put in commission on the 20th.

A quarter-boat for brush party was at once fitted up and turned over to Joseph

United States Assistant Engineer. This party began work July 26, on Dean's, about 25 miles above. I received from them the first barge of brush on August 6, and began the construction of mattresses on August 6. After constructing 493 feet of mattress I deemed it expedient to sink it, as considerable drift had accumulated above the mooring barge, and much of it was getting under the mattress. Subsequently lengths of mattresses were increased to 900 and 1,000 feet. No trouble met in sinking mattresses of this length, it was decided (September 29) to construct continuous mattresses. The mattress now being built is 2,150 long, 1,580 feet wide has been sunk. No trouble whatever has been met in sinking part of the mattress and keeping part afloat, nor do I apprehend any except from drift, in which mattresses will have to be broken off and sunk when the drift causes excessive

willow party being insufficient to supply us, quarters for 70 men were erected on the river, and a second party sent out on September 17. The water being too low for a boat, both parties were withdrawn from Old River, west of Centennial, on September 24, and placed in the main river, where brush was scarce, and not far from the river.

October 15 the river rose sufficiently to permit entrance to Old River, and both parties were moved there.

Short of brush, I organized a third party, and placed them on "Old Hen" just opposite the work. They are supplying at date 60 cords per day, our requirements being about 200 cords per day.

Due to short supply of brush, no shore work was done until October 2, although considerable portion of the bank had been staked out and wired ready to have the mattresses placed in position.

August 17 the snag-boat John R. Meigs began work in clearing the bend of the river. She finished on October 11, having removed five hundred and forty-one hundred ten rack heaps. Two men were lost by falling overboard.

September 24 a small flat, loaded with 600 bushels of coal, was struck by a large log and sunk.

Following tables will show you the work done in detail:

TABLE No. 1.—HYDRAULIC GRADER No. 1.

Linear feet.	Cubic yards.	Average area of cross-section.	Time worked.	Yards cut per hour.	Average pressure.		Strokes per minute.	Coal.	Cost per cubic yard.	Cost per linear foot.	Composition of material.		
					Steam.	Water.					Buck-shot.	Clay.	Sand.
		Sq. ft.	Hrs.		Lbs. pr	sq. in.		Bush.	Cts.	Dols.	Pr. ct.	Pr. ct.	Pr. ct.
275	4,520	700	51	89.8	95	135	82	600	8.3	2.21	45	55
385	7,022	475	42	167.2	95	135	82	625	5.5	1.01	45	45	10
585	10,084	730	77	208.0	96	140	82	905	2.9	0.75	40	30	30
638	14,411	854	85 1/2	170.0	95	140	82	900	3.1	0.708	65	30	95
1,793	42,087	---	258 1/2	3,120
.....	165.0	137.5	0.403	0.94	49	40	11

TABLE No. 2.—DAYTON CAM PUMP.

2,385	4,150	80	52	80	95	64	150	3.5	0.120	40	25	35
300	5,245	90	58	80	95	64	175	2.9	0.170	18	30	54
655	4,105	80	51	80	120	64	208	3.5	0.322	50	30	20
1,475	4,590	82 1/2	52	80	125	72	175	3.5	0.105	72	13	15
1,675	4,195	82 1/2	51	80	130	72	144	3.5	0.140	30	45	25
3,700	3,170	80	53	80	135	62	108	4.0	0.244	No record.		
2,290	25,135	475	971
.....	53	3.5	0.150

RESUME OF GRADER WORK.

Brush graded	7,673
Brush removed	67,242
.....	\$0.334
.....	0.038

2802 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Mattress work done is as follows:

Mattress No. 1, sunk January 23, 1883	298' x 140'	
Mattress No. 2, sunk January 27, 1883	275' x 140'	
Mattress No. 3, sunk February 3, 1883	298' x 140'	
Mattress No. 4, sunk February 10, 1883	256' x 140'	1127' x 140'
Mattress No. 5, sunk August 11, 1883	493' x 140'	
Mattress No. 6, sunk August 23, 1883	850' x 140'	
Mattress No. 7, sunk September 4, 1883	952' x 140'	
Mattress No. 8, sunk September 15, 1883	925' x 140'	
Mattress No. 9, sunk September 28, 1883	1032' x 140'	
Mattress No. 10, sunk October 23, 1883	1580' x 140'	
Mattress No. 10, afloat	570' x 140'	6403' x 140'
Total amount of deep mattress made	7535' x 140'	
Total amount of deep mattresses sunk	6850' x 140'	

In addition to this there was made and sunk a mattress 100 by 300 feet to cover cave in bank between mattresses Nos. 3 and 4, due to their not lapping.

At date (November 1) 6,700 linear feet of bank is covered by "deep-water mattresses," and 4,100 linear feet by "upper-bank protection." The total revetment 120,918 square yards.

In preparing for work, the following (mostly heavy) timber was cleared from bank:

From December, 1882, to February, 1883	
From August, 1883, to November 1, 1883	
Total clearing	

Table showing material used in construction.

Material	Deep-water mattresses.		Upper bank protection.	Total
	January and February, 1883.	August to November, 1883.		
Brush	840.5	4,885.0	938.0	6,663.5
Poles	103.0	310.0		413.0
Wire	535.0	18,072.0	4,176.0	23,783.0
Spikes	13.0	44.0		57.0
Nails	2.0	11.0		13.0
Stone	565.0	2,703.0	434.0	4,702.0

I have on hand the following plant, viz:

- One quarter boat, 130 by 25 feet, capacity 180 men.
- One quarter-boat, 100 by 20 feet (double-decked), capacity 120 men.
- One quarter-boat, 90 by 20 feet, capacity 60 men.
- One quarter-boat, 82 by 18 feet, capacity 80 men.
- One quarter-boat, 80 by 18 feet, capacity 24 men.
- One quarter-boat, 60 by 16 feet, capacity 30 men.
- Five small flats used in construction.
- Four screen-barges, 100 by 25 feet.
- Two mattress-ways, 160 by 30 feet.
- One hydraulic grader-boat, 100 by 16 feet.
- One machine shop, 130 by 24 feet.
- One decked barge, 130 by 24 feet.
- Twenty-three decked barges, 100 by 25 feet.
- One decked barge, 100 by 18 feet.
- Thirty-nine skiffs.

Very respectfully, your obedient servant,

W. M. RICE,
United States Assistant Engineer.

Maj. A. M. MILLER,
Corps of Engineers, U. S. A.

1, for the time being, on account of high water, and, owing to the long continuation of the same, was not recommenced until by your orders, on August 1. The this portion was then pushed slowly forward; the party consisting of myself and men only, as on account of a lack of funds available at that time economy was necessary.

In the latter part of August, as you were informed that an allotment had been made for the completion of the survey, the party was increased by the addition of a transit and several skiffmen, and the work further facilitated by the use of the steam-launch.

At the time of the completion of the survey, as originally projected, I received orders to continue it up the river to the foot of Island No. 40, an additional distance of $7\frac{1}{2}$ miles, and soon afterwards received your further instructions to extend it up the river to Scanlan's Landing, a distance of $15\frac{1}{4}$ miles, making a total length of 30 miles along the main channel of 30 miles, and reaching from the foot of Island No. 40, above the foot of Jefferson street, Memphis, to Scanlan's Landing, $18\frac{1}{4}$ miles from the same point. This constitutes the survey as finally completed, and I will consider it as a whole.

There had been a very complete survey of almost the entire portion of this reach made in 1877-'78, under the direction of Lieut. Col. C. B. Comstock, Corps of Engineers, United States Army, the primary object of the present resurvey was to determine the changes in the bed and banks since that time; that is, the location and extent of the erosion of the banks, the accretion or formation of bars, and the scour of the bed of the stream.

METHOD OF MAKING SURVEY.

Complete triangulation of the reach having been made, both under the direction of Lieut. Col. Comstock and by the Coast and Geodetic Survey (the notes of which were in this office), and as most of their points were still intact it was not deemed necessary to make an entirely new trigonometrical survey. Both for economy of time and in order to make a more exact comparison with the previous survey, those old points which were found to be in good order were used in the new survey, and the points which had been destroyed and were necessary to insure the accuracy of the survey were replaced.

Bank and bar lines between the triangulation stations were determined by measurements, as were also the sounding stations. Soundings were located by sections from two transits on shore, usually placed on the bar or convex side of the river, so as to give the best angles of intersection.

Several methods of making soundings were tried and the one most generally used was

THE CHARTS.

The map of the river submitted herewith consists of four charts, made to a scale of 1:10,000, numbered from one to four, beginning at the foot of Island No. 40. As probably the best method of describing the reach surveyed, I will take up the charts in numerical order, and consider them separately.

Chart No. 1 extends from the foot of Island No. 40 to Mound City Landing, a distance along the channel line of $7\frac{1}{2}$ miles. Of this portion of the river, only that part had been previously plotted by the "Comstock survey" between the head of Old Hen Island and Mound City Landing. Heavy caving is shown to have taken place on the head of Old Hen Island, and the bar below has kept moving down the river, following the rapid caving in of Hopefield Bend. Above Mound City Landing, the caving on the right bank since the "Comstock survey" is inconsiderable. Above the head of Old Hen Island, the previous survey was made under the direction of the Mississippi River Commission, in 1879-'80. As their maps, plotted to a large scale, have not been furnished this office, I have not been able to place their shore-lines on the new maps. Throughout the reach of river on this chart, the width between bank lines is excessive, varying from 3,000 to 6,000 feet; but, at the stage to which the chart is plotted, the widths of the water-way are as follows: 3,000 feet at foot of Island Forty, thence contracting to 2,000 feet in next three miles, and again widening to 5,000 feet at head of Old Hen Island.

The soundings and shore-lines on this chart are reduced and plotted to a stage of water which corresponds to a reading of 11.4 feet on the Memphis gauge.

Chart No. 2 extends from Mound City Landing to the head of President's Island, a distance along the channel line of 7 miles, and includes the river-front and harbor of Memphis.

The most noticeable change shown to have taken place on this portion of the river, is the heavy caving above Hopefield, extending from Mound City Landing to Hopefield, and amounting to a maximum cutting of 1,200 feet, in the middle of the bend, since the survey of 1877-'78. Rapid caving is also taking place on the left bank above Wolf River. This caving, by comparison of more recent surveys, seems to be increasing in rapidity. Gradual caving is also shown to have taken place on the river-front of Memphis, above Jefferson street. This portion of the front has been partially re-vetted during the past four or five years, and the caving thereby stopped, or at least checked, as considerable caving of the top bank has taken place during the past year, which, although not showing largely on this map, is of considerable importance on account of the value of the property affected.

The water-way in front of Memphis and in a part of Hopefield Bend is contracted to a width of only 1,600 or 1,800 feet, at the stage of water to which the chart is plotted. This chart also shows the sweep of the bend opposite Memphis and the course of Four-mile Bayou, extending almost across it. The shortest distance through the bend is 13,000 feet.

The soundings and shore lines on this chart are reduced and plotted to a stage of water which corresponds to a reading of 11.4 feet on the Memphis gauge.

Chart No. 3 includes the whole of President's Island, and shows the main channel and chute on either side of it. The nearly equal division of the low-water discharge of the river at the head of the island has apparently been the cause of shoaling and contracting the low-water channel of the main river along its north and west sides.

Between the mouth of Four mile Bayou and Lake's Landing, the width of the water-way, at the stage to which the chart is plotted, is only 1,300 feet. Below Lake's Landing it widens out, but becomes shoal, and by the formation of a middle bar, one mile above Rowley's Landing, the actual available channel is contracted to 600 feet, and maintains this width for 2,000 feet. The clear high-water width of the main river averages from 4,000 feet to 5,000 feet, exclusive of the chute between President's and Vice-President's Islands.

The principal caving shown to have taken place in this portion of the main river extends from the head of the Apperson plantation to Jones's Landing, where there has been an average cutting of from 400 feet to 500 feet, for a distance of 10,000 feet. Caving has also taken place immediately above Lake's Landing, averaging 200 feet in width by one-half mile in length, and from the mouth of Four-mile Bayou, upstream, there has been an average caving of 150 feet for a distance of a mile.

The chute to the east and south of President's Island has a very uniform width between bank lines, varying only from 2,000 to 2,200 feet. At low stages its width in the bend is contracted by a bar to 1,200 feet, and a middle bar, or reef, also obstructs the upper end of the chute, for a distance of about a mile. From the lack of necessary tools and appliances for making the examination I was not able to judge of the nature of the material of which this reef is composed; but the bottom of the whole upper portion of the chute, as indicated merely by the feel and effect upon the sounding-lead, seems to be of a hard, gravelly nature. From the foot of

the bluff, at the head of the chute, a reef of ferruginous sand-rock juts into the stream, showing at a stage about 10 feet above low water; and this middle bar may possibly be of the same nature. In this connection, from the report of Assistant Engineer E. H. Wilson to the secretary of the Mississippi River Commission (June, 1881), I find the following information concerning the nature, depth, and probable location of this rock. At boring No. 1, located at the foot of the bluff, about three-fourths of a mile below the head of the chute, ferruginous sandstone stopped further progress at a depth of 107.4 feet below the top of the bluff, which, according to his diagram, would be about on a level with the low water of 1872.

In describing this boring Mr. Wilson says: "The sand rock which stopped the progress of the boring, it seems, is here of unusual extent, appearing above the water at low stages of the river some distance from the bank, which, washing away the overlying material, has been unable to remove the rock. * * * It seems possible that the submerged bar which extends from this point to the head of President's Island, may be an extension of this sandstone layer."

With the exception of the middle bar referred to, I did not find any shoal of a possible rocky formation in the stream, which would appear above the water at its lowest stage. At two points in the chute, where some disturbing elements on the bottom (claimed by some to be rock reefs) have caused large boils on the surface, there was found not less than 19 feet of water at the stage sounded—6.5 feet on the Memphis gauge.

The supposition as to the rocky nature of the middle bar may, very likely, be correct; but a thorough examination is necessary, in order to establish it as something more than a mere hypothesis.

The distance through the chute is $1\frac{1}{2}$ miles shorter than by way of the main river at low stages of water; the length of the main channel being $7\frac{1}{4}$ miles, and by way of the chute, $6\frac{1}{4}$ miles.

The principal caving shown to have taken place in the chute is at the head of President's Island, where there has been an average cutting of from 200 feet to 500 feet for a distance of a mile; and also on the foot of the island averaging 300 feet in width by one-half mile in length. Slighter caving, varying from 50 feet to 100 feet in width by two miles in length, has also taken place on the Tennessee shore below Nonconnah Creek.

The soundings and shore lines on this chart are reduced and plotted to a stage of water which corresponds to a reading of 6.5 feet on the Memphis gauge.

Chart No. 4 extends from the foot of President's Island to Scanlan's Landing, a distance along the channel of 8 miles.

The width of the river between banks throughout almost the whole of this reach is very excessive, being from 5,000 to 6,000 feet.

From Reeves' Landing to Harris' Landing, where the width from bank to bank is 6,000 feet, a middle bar has formed, which, at low water, divides the river into two channels, both of which are navigable for small boats of light draught, the one on the right, however, being the main channel and the only one through which large boats can pass with any degree of safety.

The bars at Hampton and Scanlan's Landing have been found to be greatly increased in size and are gradually moving down stream. The width of water-way of the main channel, as contracted by the bars at the stage of water at which the survey and map were made, is 2,600 feet at Ensley's plantation, 4,000 feet at Hampton Landing, 1,700 feet at Reeves' Landing, keeping about this width to Harris' Landing, then widening to 5,000 feet on the crossing below, but soon contracting again to 2,500 feet and keeping about this width to near Scanlan's Landing.

The principal caving found on this reach is at the following points: Between Reeves' and Harris' Landing where, for a distance of 4,000 feet, there has been an average cutting of 300 feet; below Fleece's plantation, where there has been a cutting of 200 feet to 400 feet, a distance of 3,600 feet; and on the head of the old Cow Islands, where the caving has been from 200 feet to 600 feet in width, by a mile in length.

Slight and inconsiderable caving has also taken place on the lower end of Ensley's plantation, between Horn Lake and Collins' Landings, and below Scanlan's Landing.

The soundings and shore lines on this chart are reduced and plotted to a stage of water which corresponds to a reading of 6.5 feet on the Memphis gauge.

SLOPE OF THE RIVER.

While the party was at Hampton Landing, a daily gauge record was kept at that point, the zero of the gauge being connected with that at Memphis, by means of the levels of the "Comstock" survey. In the following table are given the daily gauge readings at both points from November 30 to December 13, the zero of the Hampton gauge being reduced to the same level as that at Memphis. The daily differences in level and slope per mile are also given. Taking from this table 0.5308 foot, the average slope per mile, and multiplying by $7\frac{1}{4}$ miles (the distance around President's

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

of the main channel), we get 3.563 feet as the difference between the head and foot of the island; and, dividing this by 6½ miles, the distance, gives 0.5482 feet as the average slope per mile through the

Table of slopes.

Date.	Gauge readings.		Dist- ance.	Difference in level.	Slope.
	Memphis.	Hampton Landing.			
1882.					
November 29	Feet. 6.35	Feet. -4.34	Miles. 12½	Feet. 6.56	
December 1	6.36	-4.34	12½	6.54	
December 2	6.35	-4.28	12½	6.51	
December 3	6.36	-4.31	12½	6.41	
December 4	6.36	-4.31	12½	6.41	
December 5	6.40	-4.36	12½	6.66	
December 6	6.40	-4.36	12½	6.66	
December 7	6.45	-4.31	12½	6.76	
December 8	6.46	-4.36	12½	6.66	
December 9	6.46	-4.40	12½	6.71	
December 10	6.46	-4.40	12½	6.51	
December 11	6.50	-4.11	12½	6.61	
December 12	6.35	-4.31	12½	6.66	
December 13	6.40	-4.71	12½	6.71	

DISCHARGE OBSERVATIONS.

In order to ascertain the relative amounts of water passing on either side of Grant's Island, discharge observations were taken in both the chute and main channel at a short distance below the head of the island, on the following days, December 29, 1882, January 2 and February 20 and 21, 1883. The results of these observations are given in the following table:

Table of discharges.

Date.	Memphis gauge reading.	Main channel.				Chute.			
		Area of section.	Discharge per second.	Mean velocity.		Area of section.	Discharge per second.	Mean velocity.	
				Per second.	Per hour.			Per second.	Per hour.
1882.	Feet.	Sq. feet.	Cubic feet.	Feet.	Miles.	Sq. feet.	Cubic feet.	Feet.	Miles.
Dec. 29	6.35	29,445	18,100	3.44	2.6743	29,354	18,181	4.6634	3.1810
Dec. 31	6.36	32,817	18,965	3.77	2.5741	41,362	199,497	4.7693	3.2169
1883.									
Jan. 2	11.40	34,635	139,071	4.0671	2.7460	47,394	236,573	4.7694	3.2417
Feb. 20	21.26	14,447	61,808	4.22	2.8511	14,539	348,736	5.2703	3.5796
Feb. 21	22.2	14,864	64,346	4.3675	2.9913	15,733	561,715	5.3220	3.6286

From the above table it will be seen that on December 29 and 31, 1882, and Jan. 2, 1883, when the water was at a medium low stage, the discharge through the chute was about sixty per cent. greater than through the main river, but on February 20 and 21, when the river was bank full, the discharge through the main channel was about 10 per cent. greater than through the chute.

These observations were made with floats, running a distance of 200 feet.

The floats were of the same pattern as those used by this office in making discharge observations in 1879.

Very respectfully, your obedient servant,

F. S. BURROWS,
Assistant Engineer.

Capt. A. M. MILLER.

Corps of Engineers, U. S. A., Memphis, Tenn.

K 4.

OF F. A. FISHER, ASSISTANT ENGINEER, UPON A SURVEY OF THE HELENA REACH.

**UNITED STATES ENGINEER OFFICE,
Memphis, Tenn., May 31, 1883.**

S: I have the honor to present to you the following report of the survey of the Helena Reach, Mississippi River, you intrusted to my charge during the season 1882:

In accordance with your letter of instructions, dated October 16, 1882, I at once organized a party and procured the necessary outfit. The party consisted of one assistant in charge; two sub-assistants; four rodmen; one leadman; seven oarsmen, and a cook; the quarter-boat being just large enough to accommodate that number. I left Memphis October 22, 1882, allowing the boat to drift and piloting it with two well-manned skiffs to Commerce Landing, arriving October 24. Instruments furnished me were: Transit No. 4840 (Heller and Brightly); transit level (Heller); level No. 4918 (Heller and Brightly).

The survey comprised a tertiary triangulation, shore line of both banks, of bars, sand-bars, islands, and topography of same; soundings and necessary level connections between United States bench-marks and gauges; and, also, according to further instructions, dated November 25, 1882, location of levees along the river, when it did not exceed the survey too far, and the ascertaining the level of high water of 1882. The only triangulation station "Peters," being the only one near the beginning of the reach which could be found, observations for azimuth were made near Commerce Landing, and the triangulation carried from a carefully measured base-line, of known length, connecting this point with triangulation station "Peters," to a point at the head of Bordeaux Chute, where observations for azimuth were also made as a check on previous determination.

At K. Landing, Miss., the first complete connection with secondary triangulation line triangulation station O. K.—triangulation station Waddell, azimuth 7° 54', was made. My observed azimuth checked within one minute. The connection was made at Helena, Ark., with line triangulation station Battery—triangulation station Court-house, and again at Friar's Point, through line triangulation station Ship—triangulation station Westover.

To determine river slope, were placed at such points along the river as would indicate a change of inclination; and, elevation of their zeros was determined from known elevation of United States bench-marks. A number of United States bench-marks were connected by chain and transit with tertiary triangulation points.

Continuous readings of the gauges were taken at two points, usually for six hours each day, and days selected for slope determination at a nearly stationary stage of river. The result, with dates when observed and stage of river at Helena, are given in Table No. 1. The rate of caving of banks on the "reach," for the time of the surveys of 1878-79 and 1882-83, is given for the different sections in Table No. 2. Sand-bars have not been considered in this estimate.

The level of high water of 1882 is given in Table No. 3. The stage of water at Memphis, Tenn., and Helena, Ark., is given in Table No. 4. The amount of work done is given in Table No. 5.

TOPOGRAPHY.

In the "reach" many of the secondary stations have been washed away; in some cases plowed up, and in others buried under mud, and sand, some 2 or 3 feet. Tertiary points were substituted and placed in close proximity to each other, to avoid the cutting of heavy timber. Stadia lines were run between stations, and sights inland taken as far as stadia could be read. Elevations as given on the bench-marks, in feet, on a plane which is 225 feet below high water of June, 1858. The water corresponds to a reading on Memphis gauge of 34.16 feet.

SOUNDINGS.

In sounding, a lead weighing 17½ pounds was used. The original lead weighed 20 pounds but I found it too heavy for satisfactory use, so I reduced its weight as given. The lead-line measured 100 feet; the actual length of which was determined by standard measure at all times before its use, and correction noted in its proper sounding-books.

Usually, lines were sounded at an interval of about 1,000 feet, but at less distance where the river bed appeared changeable. Two transits occupied such triangulation.

...of position of sounding...
...feet and are reduced to four...
...on the Helena gauge; being the...
...The elevation of the stage...
...bench mark 22. High water...
...of water to which the charts are...
...days on which soundings were...
...gauges on these days are given...
...the day, at 9.30 a. m. and 1.30 p. m.

CAVING BANKS.

...and the rate of caving. The rate is...
...of the shore-line with its position...
...at east side of Bordeaux...
...in one year; and as the whole...
...only 1,117 feet, the river will...
...and resume its original bed...
...a reduced plot of this interesting section of river.

BAR AND TOW-HEADS.

...between old and new river, has...
...and is composed of a very fine sand...
...portion, where a small belt of gravel...
...silt and mud. The opening at...
...The bar immediately below, on...
...sand with some silt at extreme southern...
...this bar and has lost its identity.

...Ashley Point," is, at its highest...
...main shore, gravel exists and varies in...

...consists of a very fine sand; the...
...on the main shore, is composed of mud.

...down stream three-fourths of a mile, with...
...at a depth of one or two feet, it becomes...
...as 0.75 inch in size.

...doubt, an island, as the river above...
...W. of Bear Channel.

...Landing, as well as two...
...sand than usually found, probably...
...0.04 to 0.05 inch in size.

...At its eastern extremity, where it...
...a belt of mud which extends up a high...
...as well as shore bar opposite O. K...
...The island immediately surrounding them. The island immediately...
...consists of coarser sand mixed with large...

...are composed of fine sand. Sho...
...with some gravel at its northern...
...since 1878. From being egg...
...a long, narrow shape...
...to 1 1/2 miles below its former...

...The main channel of river...
...side and passes close to north...
...shore has a tendency to fill...
...includes at the present time...

...The tow head itself is composed of...
...former channel between tow-head...

...closing the former exist...
...entirely. The northern part of...
...At the eastern slope of...
...The southern part...
...water edge. Helena Tow-head is...
...also along eastern edge, where...
...with a heavy growth of willows and cottonwood.

K 2.

OF F. A. BURROWS, ASSISTANT ENGINEER, UPON A SURVEY OF THE MISSISSIPPI RIVER IN THE VICINITY OF MEMPHIS.

**UNITED STATES ENGINEER OFFICE,
Memphis, Tenn., March 12, 1883.**

SIR: I have the honor to submit the following report upon the survey of the Mississippi River, in the vicinity of Memphis, made under your instructions during the year.

The survey was begun May 5, 1882, under the direction of your predecessor, Maj. E. B. Bannard, Corps of Engineers, United States Army, and at that time was limited to include only that portion of the river from Mound City Landing to the President's Island, a distance of 7 miles. Ten days after field work was discontinued, for the time being, on account of high water, and, owing to the long continuance of the same, was not recommenced until by your orders, on August 1. The survey of this portion was then pushed slowly forward; the party consisting of myself and men only, as on account of a lack of funds available at that time economy was necessary.

In the latter part of August, as you were informed that an allotment had been made for the completion of the survey, the party was increased by the addition of a transit and several skiffmen, and the work further facilitated by the use of the steam-launch *Daphne*.

At the time of the completion of the survey, as originally projected, I received orders to continue it up the river to the foot of Island No. 40, an additional distance of $7\frac{1}{2}$ miles, and soon afterwards received your further instructions to extend it up the river to Scanlan's Landing, a distance of $15\frac{1}{2}$ miles, making a total length of 30 miles along the main channel, and reaching from the foot of Island No. 40, or above the foot of Jefferson street, Memphis, to Scanlan's Landing, $18\frac{1}{2}$ miles from the same point. This constitutes the survey as finally completed, and I will consider it as a whole.

There had been a very complete survey of almost the entire portion of this reach made in 1877-78, under the direction of Lieut. Col. C. B. Comstock, Corps of Engineers, United States Army, the primary object of the present resurvey was to determine the changes in the bed and banks since that time; that is, the location and extent of the erosion of the banks, the accretion or formation of bars, and the scour of the bed of the stream.

METHOD OF MAKING SURVEY.

Complete triangulation of the reach having been made, both under the direction of Lieut. Col. Comstock and by the Coast and Geodetic Survey (the notes of which were forwarded to this office), and as most of their points were still intact it was not deemed necessary to make an entirely new trigonometrical survey. Both for economy of time and in order to make a more exact comparison with the previous survey, those old points which were found to be in good order were used in the new survey, and the points which had been destroyed and were necessary to insure the accuracy of the survey were replaced.

Sunk and bar lines between the triangulation stations were determined by direct measurements, as were also the sounding stations. Soundings were located by sections from two transits on shore, usually placed on the bar or convex side of the river, so as to give the best angles of intersection.

Several methods of making soundings were tried and the one most generally used was that of giving the greatest number in a given time. A skiff, with three oarsmen, a man, and a recorder, was rowed rapidly back and forward across the stream with a lead cast every half-minute. Every second sounding being located by the man sighting on a flag raised and quickly lowered by the recorder at the instant of sounding. In order to keep a check on the numbers the flag was quickly raised and lowered twice at every fifth sounding, and such double flag noted by both man and recorder. On account of its too great draught the steam-launch was of very little utility in the actual taking of soundings at a low stage of water. It was, however, used to a considerable extent in the immediate vicinity of the bars, the soundings over this portion being taken in longitudinal lines. The lead was but once for each line and the launch and lead-line kept drifting together. Soundings were taken every fifteen seconds and every fourth sounding located. This method, without doubt, gives the most accurate results, but was abandoned on account of the great length of time consumed.

ET OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Note.—In a list of localities and the rate of caving. The rate is determined from a comparison of the present position of the shore-line with its position at first survey.

TABLE No. 2.—Caving banks.

Locality.	Rate of caving per year.	Total caving.	Material.	Remarks.
	<i>Feet.</i>	<i>Feet.</i>		<i>Feet.</i>
Ashley Point, Ark.	230	640	Sand	Dec.
Mbeon's Landing, Miss.	250	500	Sand and silt	Dec.
Bordeaux Point Landing, Miss.	400	800	Sand	Dec.
Bordeaux Island (east side)	1,100	1,200	Clay and sand	Dec.
Shore opposite Walnut Bend, Miss.	400	800	Sand	Dec.
Smith's Landing, Ark.	540	1,080	do	Jan.
One and a half miles above Harbert's Landing	132½	530	Clay and sand	Nov.
Opposite Shoo Fly Bar, Ark.	227½	1,310	Sand and silt	Dec.
Mouth of Saint Francis River	75	300	Clay and sand	Dec.
Below mouth of Saint Francis River	182½	720	do	Dec.
Trotter's Landing, Miss.	312½	1,250	do	Dec.
Glendale, Miss.	25	250	do	Dec.
One and a half to 3 miles below Helena, Ark.	250	1,000	Silt and sand	Dec.
Delta, Miss.	182½	650	do	Jan.
One and a half to 2½ miles below Friar's Point, Miss.	140	280	do	Feb.

TABLE No. 3.—Elevation of high-water marks of 1882.

Locality.	Elevation.	Distance.	High-water slope per mile.	High-water slope for the distance.	Description of marks.
	<i>Feet.</i>	<i>Miles.</i>	<i>Feet.</i>	<i>Feet.</i>	
At Dr. Peters' store, opposite Commerce Landing.	208.43				This mark is defined by a nail in the side of the counter inside store.
Mbeon's Landing, Miss.	208.13	5	0.260	1.30	Mark on tree close by B. M. 47.
Bordeaux Point Landing, Miss.	207.49	3	0.21	.64	Mark on house of Henry Wilson.
Walnut Bend Landing, Ark.	204.79	4	0.687	2.79	Two nails in door post of store.
Austin, Miss.	202.75				Height above bench mark on corner of house square, measured counts sixtexor.
O. K. Landing, Miss.	202.60	7	0.340	2.10	Mark on store and post office.
Mouth of Saint Francis River	200.63	8.5	0.255	1.97	Mark on large tree opposite post-office.
Helena, Ark.	195.88	9	0.528	4.75	Mark on window sill of brick house opposite elevator.
Westover, Ark. opposite Friar's Point	188.71	12.5	0.575	7.17	Well-defined mark on storehouse corner of levee.
Total		49.25		20.72	Entire high-water slope

NOTE.—Elevations as given in this table depend in feet on a plane which is 225 feet below high water of June 1858. This high water corresponds to a reading on Memphis gauge of 34.16 feet. High water of 1882 corresponds to a reading on Memphis gauge of 35.15 feet, and on Helena, Ark. gauge of 4.0 feet.

TABLE No. 4.—*Water gauges.*

[Showing stage of water at United States gauge at Memphis, Tenn., and Helena, Ark.]

Date.	Mean elevation of water in vicinity where soundings were taken.	Gauge reading at Memphis at 8 a. m.	Gauge readings at Helena at 9.30 a. m. and 1.30 p. m.	Mean of Helena gauge.
1882.	<i>Feet.</i>	<i>Feet.</i>	<i>Feet.</i>	<i>Feet.</i>
Nov. 3	177.13	5.23	10.55 10.76 10.60 10.70	10.68
4	177.13	5.23	11.56 11.76	10.68
13	177.45	6.13	12.00 12.11	11.62
20	174.50	7.30	12.75 12.80	12.50
24	174.00	6.75	12.10 12.10	12.77
Dec. 5	174.43	6.40	12.30 12.30	12.10
6	174.43	6.40	12.50 12.50	12.26
11	174.43	6.50	11.10 11.00	12.55
16	165.80	3.25	8.00 8.11	11.03
20	166.73	3.75	8.75 9.00	8.53
21	165.74	2.50	13.05 13.30	8.77
26	163.03	3.20	17.10 17.10	12.17
1883.				
Jan. 5	162.05	10.00	17.00 16.11	17.10
6	162.03	9.70	13.20 13.50	16.55
13	162.03	7.50	13.50 13.80	13.25
16	162.03	7.50	13.65 13.80	13.53
17	162.90	7.55	15.60 16.00	13.73
20	163.15	10.35	16.90 17.10	15.90
24	165.22	11.00		16.95
Mean for nineteen days.....				10.5

TABLE No. 5.—*Showing extent of work done from Commerce Cut-Off to Friar's Point.*

Survey triangulation stations built.....	185
paths observed.....	3
re chained.....	3
white pointings.....	4,996
cast, number of.....	6,184
gauges set.....	11
topography in miles along river channel, old and new.....	50
line in miles.....	135
bars surveyed, number of.....	41
alopes determined, number of.....	9
of levels run from United States bench-marks to connection with gauge.....	10.5

K 5.

ESTIMATE OF RICHARD KLEMM, ASSISTANT ENGINEER, FOR REBUILDING AND REPAIRING LEVEES, SAINT FRANCIS AND PART OF YAZOO FRONTS.

UNITED STATES ENGINEER OFFICE,
Memphis, Tenn., March 15, 1882

CAPTAIN: I have the honor to submit to you herewith estimates of amount cubic yards to be filled, and also the number of acres to be cleared for the repair and rebuilding of the old State levees along the "Saint Francis front" on the west bank of the Mississippi River and the "Yazoo front" on the east bank of the river.

The Saint Francis front in this district extends on the Arkansas side from No. 40 to the mouth of Saint Francis River, and the Yazoo front, as far as surveyed from the Chickasaw Bluffs, below Memphis, to Friar's Point, on the Mississippi.

In accordance with your orders, I have prepared two estimates—one to give the amount of cubic yards needed to fill the gaps and breaks in the old levees, and the other to give the amount of cubic yards needed to raise all levees 1½ feet above high water of 1882. The slope for new levees is calculated at 3 to 1 on the river side and 2 to 1 on the land side. The crown of the levees equals the fill up to a fill of 8 feet; if more than 8 feet fill the crown will not exceed 8 feet. The muck-ditch is 4 feet wide on top, 2 feet wide at the bottom, and 3 feet deep. At such places where previously no levee has been built, the calculations were made to a height of 1½ feet above high water of 1882 for both estimates.

The estimates are compiled partly from actual surveys made by Mr. Gartman and myself, and partly are taken from the charts made under the direction of Gen. Comstock in 1878. From a point below Commerce, in Tunica County, to the Coahoma County line, the amounts are taken from notes and profiles made by the county engineer of Tunica County, Mr. G. W. Owens, and from Coahoma County line to Friar's Point, in Coahoma County, from notes and profiles made by Levee Inspector William Hewson.

The high-water marks are partly from my own survey and partly from Assistant Engineer Hunter Stewart. In locating the new levees, I followed the line of the old levees as near as possible. At such places where the old levees had caved into the river, I laid the new levees far enough back to probably be safe for some time. I attach a sketch on tracing linen, showing the old levees, and also showing, in red ink, the proposed line of the new levees. The map shows that all the old levees were constructed to protect the farming interests only, and that the distances between levees on either side of the river vary from 1 to 6 miles.

I find that the highest ground is always along the river bank, and that most of the surface drainage goes towards the inland; on the Arkansas side, to the Saint Francis River basin, and on the Mississippi side towards the Coldwater and Yazoo basin.

Totals.

Location.	To height of old levees.	To 1½ feet above high water, 1882.	Clearing.
Arkansas side	Cubic yards. 1, 188, 126	Cubic yards. 1, 634, 153	Acres. 678
Mississippi side	663, 732	842, 082	243

Very respectfully, your obedient servant,

RICHARD KLEMM,
Assistant Engineer.

Capt. A. M. MILLER,
Corps of Engineers, U. S. A., Memphis, Tenn.

1.—Estimate for repairing and rebuilding the old State levees along the Mississippi River, on the Saint Francis front, in the State of Arkansas.

From—	To—	Distance.	To height of old levee.	To 14 feet above high water, 1882.	Muck-ditch.	Clearing.
		Miles.	Cu. yds.	Cu. yds.	Cu. yds.	Acres.
.....	Memph City.....	5	53, 083	174, 831	5, 800	48
.....	Four-Mile Bayou.....	8	76, 357	311, 728	5, 530	85
.....	Seaman's Landing.....	13	34, 773	178, 879	3, 733
.....	Cat Island Landing.....	7	39, 390	60, 921	5, 413	80
.....	Blair's Point.....	13	143, 758	253, 268	5, 909	84
.....	Head of Council Bend.....	5	302, 537	303, 537	6, 392	88
.....	Dr. Peters'.....	6	133, 853	133, 953	5, 405	74
.....	Head of Walnut Bend.....	5	100, 335	100, 335	3, 943	37
.....	Fall's Place.....	3	130, 616	130, 616	5, 731	86
.....	Mouth of Saint Francis.....	7	140, 539	140, 539	10, 955	163
.....	73	1, 123, 000	1, 569, 927	63, 135	873

2.—Estimate for repairing and rebuilding the old State levees along the Mississippi River, on the Yazoo front, in the States of Tennessee and Mississippi.

From—	To—	Distance.	To height of old levee.	To 14 feet above high water, 1882.	Muck-ditch.	Clearing.
		Miles.	Cu. yds.	Cu. yds.	Cu. yds.	Acres.
.....	Abbey's Field.....	28	82, 273	82, 273	7, 030	34
.....	Austin.....	20	395, 204	406, 633	5, 500	120
.....	Combs County Line.....	17	323, 688	274, 761	4, 120	81
.....	Friar's Point.....	14	44, 238	60, 046	1, 030	13
.....	79	845, 493	823, 783	18, 370	348

TABLE No. 3.—High-water marks, 1882.

ARKANSAS.

Location.	Station.	Elevation.	Remarks.
.....	Feet.	
.....	229. 63	Taken by J. Gartland.
.....	228. 68	Do.
.....	227. 65	Do.
.....	224. 31	Taken by H. Stewart.
.....	223. 238	Do.
.....	221. 060	Do.
.....	219. 771	Do.
.....	209. 49	Taken by R. Klemm.
.....	204. 67	Do.
.....	200. 63	Do.
.....	195. 28	Do.

1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific requirements of the task.

to of the last annual report, works had been inaugurated for the closure of Island 93, Balched, and Stack Island Chutes, and also the revetment at head of Island 93.

In past year work has been directed towards the completion of these works, has been greatly extended, and to the inauguration of the revetment work at Elton, and contraction works at Elton or Hopewell Bar.

1.—REVEINMENT AT PILCHER'S POINT.

is known as the Carolina, and Louisiana or Bunchs Bend, at the head of exhibit more rapid caving of the banks than any part of the reach, and the changes produced in the direction of currents below is plainly seen. The entire length of caving bank in the two concave bends approximates 1 mile. In the Louisiana Bend at Pilcher's Point, since December, 1881, the caving is such that the Mississippi low-water shore-line now occupies in places the position of the Louisiana shore-line then, or the river has caved its entire low-water reach two high-water seasons, or about 1,500 feet. The water is excessively deep to 100 feet in depth at low water. The effect of this caving has been to set up strong currents against the Mississippi shore above the contraction works at Elton, and partially undermine and destroy these works at the head of the chute, and endanger the works located in Skipwith Chute itself.

In 1882, a party was organized under Assistant Engineer Willard, who was assisted by Assistant Turtle; the wooded banks cleared, and preparations made for the matting of the banks there. After the decline in the river the matting-work was started, but during the sickly season no progress could be made. Labor was too scarce to supply the works already in progress and in consequence on October 1, the party has been increased, a snag-boat secured from Major M. H. Smith to remove the snags from the bank to be matted, and about one-half mile of work made, 1,228 linear feet of which has been sunk. This work, however, must be completed or made secure, on account of lack of funds, must now be abandoned.

2.—FROM DUNCANSBY TO STACK ISLAND.

Management of the work has been, during the year, under the local management of Engineer Arthur Hider, who submits a detailed report of operations, with sketches appended hereto.

3.—DUNCANSBY SYSTEM.

This system embraces the first work of contraction on the reach. The river is here divided into two tow-heads, or dry sand-bars, into two channels, the deeper of which is on the west shore. The object of the silting works built here is to close the Mississippi side of the tow-heads; and at the head of the tow-head and in the center of the tow-head, five cross-dikes, the upper three of which were provided with foot-mats, the two lower with screens only, have been built.

A longitudinal dike between the tow-heads was driven at high water and was built up to a high dike. The works in the chute and at head reached only to the head of water.

On a rise in February the water was thrown against the head of this system by the bend at Pilcher's Point, and parts of the upper dikes were washed out, but a decided and decided fill occurred behind the remnants of the cross-dikes and the longitudinal dike, between the tow-heads, the former of these, before being broken, offered sufficient resistance to determine the channel to the west of the longitudinal dike as desired. Along the longitudinal dike sand was piled up to the top of the dike in a very short while, and a rapid cutting away of the head of the upper dike resulting from the river crossing above it, set in.

At a threatened water-way at low water through the Skipwith Chute, and at the head of the tow-head, pile-driving was resumed at the head of the island at the chute April 4, 1883. Cross-dikes were driven on Ranges 37, 38, and 39, the stage of water would admit, and a screened dike 400 feet long driven at the head of the tow-head for the purpose of attempting to shield it against the high set directly against it. At this time the water stood so high that brush mat could not be had. A small quantity of brush remained on hand, and was used in constructing a mat 130 feet wide in rear of dike 37, to prevent a rapid cutting through the chute.

In the season the head and upper flanks of the tow-head were matted, but a rise went over the top of the island and washed it in two behind the matting, which remains as an obstruction in the channel. The dikes on Ranges 37, 38, and 39 have been completed, except narrow channels for communication through

Of the cross-dikes, six extend from the main dike across to the Mississippi shore, and six are still incomplete, not having been extended across the chute on account of deep water.

At the head of the system the main dike is built of three rows of braced piles, but on the highest part of the bar it is only of two rows. The cross-dikes at head are of three, four, and five rows, the better to withstand drift, and are protected at foot with thick foot-mats. The high dikes all reach to or above the 25-foot stage, and for 6 feet above the present bar surface are now being closely wattled to secure deposits of mud for the sustenance of willows, which have already begun to make their appearance.

On the decline in the river the deposits behind the long dikes were cut in channels by the water seeking the deep chute behind Baleshed Bar; in several places at head, and here also, the main dike is being closely wattled to prevent this action.

In front of the main dike a mattress, ranging in width from 100 feet at head to 60 feet at foot, has been laid to prevent longitudinal scour, and in places where the water falls through the dike into Baleshed Chute, grillage-mats have also been placed.

Along this system the local effects of main and cross-dikes can be well studied, as well as the influence of drift as an enemy or as an aid to these constructions, the cross-dikes driven at high water having caught much of it. This will be spoken of hereafter in this report.

The effect of the dikes of this Baleshed system has been all that could be expected. Although open, i. e., not wattled or curtained, they have caused a great fill behind them, have extended the bar both at head and foot, and thrown the current well over to the Louisiana shore, opposite the head of Stack Island, and have perhaps rendered the permanent closure of that chute, which is now 83 feet deep at low water, a possibility in the future, the main channel of the river having already been diverted or deflected from that chute by these works, aided by the dikes reaching from the foot of Baleshed Bar to the head of Stack Island, and the short dikes on the opposite side of the river at Elton.

The proposed channel at the head of Stack Island was projected through the crest of Hopewell Bar, and the change here has been a remarkable one. The Stack Island Chute next the Mississippi shore was 80 feet deep at low water. The Elton Chute, along the opposite or Louisiana shore, was also deep, exceeding 30 feet at low water, and the Hopewell Bar filled up the greater part of the main projected channel-way.

An open dike was built above the head of Stack Island on the crest of the crossing or weir, and a series of six short spur-dikes across the head of the Elton Chute. At high water these dikes induced a deposit, as shown on the map of the April survey herewith, and the main river cut its channel to the right of the island, as projected, removing immense deposits of sand. For some time this main channel was more shallow than either of the chutes next shore, or the river ran in a trough excavated through a mound in the middle of the river. The tendency is to cut across the narrow ridge at the head of Stack Island, and to fall back into the deep trough behind that island.

The dike work so far built here, at Stack Island and Elton, is insignificant in character and must be very materially extended and made both stronger and less permeable in order to permanently keep the river out of the chute.

Although the works have been nearly altogether open pile-dikes, the effects on the reach have been very marked in deepening the channel.

During the last low water there was a good channel not less than 15 feet in depth throughout the reach, and navigation was without a hindrance anywhere.

There are attached hereto tables giving all the work done on the reach, prepared by Assistant Engineer Hider, who has also given a detailed description of all constructions used.

The machines and appliances used on the work have been the same as heretofore, with the exception of an appliance for holding the head of a mattress in swift water during construction, and until it is safely sunk to the bottom of the river. This consists of a strong truss floating at the head of the mattress, to the lower chord of which the mattress is attached every 8 feet by rings and tripping-hooks, the latter of which can all be tripped simultaneously by a rod attached to a lever at the shore end of the truss and the truss released from the mat. A modification of the burdle-mattresses has also been found necessary in the deep and swift currents encountered. This modification consists in running alongside the poles on which the mattress is woven continuous lines of iron rods, 25 feet in length, connected by lap-rings and clevises, the rods ranging in diameter from $\frac{1}{4}$ to $\frac{1}{2}$ of an inch. Drawings and descriptions of this mattress and mattress-head are herewith. They have been used successfully at Pilber's Point, as may be seen from Assistant Engineer Turtle's report herewith.

The detachable mattress-head is a great assistance in sinking, without danger, the ends of continuous mats in swift currents.

Modifications have also been found necessary in the pile-dikes, which are now provided with thick foot-mats, and are built of three rows, sometimes of five rows, in all

exposed places. In three-row cross-dikes the wattling is placed on the middle row, or along the middle line of the foot-mat. In five-row dikes it is proposed to wattle the second and fourth rows. The latter construction is proposed for closing chutes, the two-wattled rows representing two cross-dikes with a short pool between them, gaining the advantage of wider foot-mats and stronger anchorage over two cross-dikes of less width farther apart.

The vertical close wattling has been adopted instead of inclined mats, or curtains, as first used, on account of the greater cheapness of the construction, as less material is required. An eddy will be produced under the lip or crest of the wattling when the water passes over the wattling. At the first stages of the fill below the dikes there will be a trough immediately below the wattling, due to this eddy, but after the fill above and below reaches the level of the top of the wattled portion of the dikes these troughs will evidently fill up even with the top of the general fill and the wattling be covered.

All the results accomplished on the Lake Providence Reach have been by open dikes, mostly without either screens or foot-mats. It is certain that the currents can be reduced in velocity by piles alone until they are too gentle to scour much at the foot of the dikes, and that piles alone offer sufficient obstruction to cause great fills behind them. When the dikes are matted at the foot there is danger that if the work is not a success the mats will remain a permanent obstruction to navigation.

It seems that it is better to secure the fill, if possible, by means which cannot by any possibility be damaging if they fail, and afterwards, with an expenditure of much less material than necessary to mattress and wattle or curtain all the dikes, to mattress only the proper parts of the new banks secured, or else in the first construction to restrict the brush work to important parts of the dikes only. The necessity for matted and wattling pile dikes causes great delay to the revetment of banks; causes the time, labor, material, and means to be expended to protect cottonwood piles that can last but two years at best, when our efforts would be more profitably directed to the bank work, which is more of a finality. It is my impression that no pile work is worth the extra expense of matted, except strong dikes placed in chutes to close them, and the main lines along the proposed new banks. Those for closing chutes should be built of cypress piles, well braced to stand any pressure that may be brought against them, heavily matted at foot against scour, and wattled or thickly curtained to form permeable or submergible dams.

DRIFT-WOOD.

During the early part of the rise last February, fields of drift were brought down by the flood and lodged against our piling. Most of this, on the further rise, was released and floated past, but on two of the cross-dikes on Baleshed Bar there were great accumulations. These dikes were only of two rows of piles, not provided with mats at bottom, and but insecurely braced. They were strengthened by additional rows of piles driven behind them, and the drift held by them. At first small parts of the dikes at the ends were broken away, but it has not been ascertained whether by natural scour around the outer ends of the spur dikes, or by impact of drift. The great mass of the drift accumulation was retained, and still remains above these dikes. Afterwards drift in smaller quantities lodged against the high cross-dikes in Baleshed Chute, and in one or two cases gaps were washed out in the dikes, due to its influence.

In all cases where *considerable* quantities of drift accumulated at high water there has not only not been any scour under the drift, but there has been a considerable fill, both under the drift and below it.

The action of the drift on the currents and dikes seems to be this: If in small quantities, extending a few feet only above the dike, and of moderate depth, it acts as a barrier with an aperture underneath; the head of water is increased by the barrier and the current under it directed against the bottom at the foot of the piles, which, under these circumstances, if not protected, are likely to scour out. When the accumulation gets larger the friction of the drift and bottom is more than sufficient to kill the current due to the hydrostatic head formed by the resistance of the drift to the current, flowing down upon it, and the water flowing under the drift heap runs with less velocity than before, and deposits sediment. The main body of the water then flows off along the sides of the drift obstruction, and endangers the piles on the flanks of the accumulations. A *small quantity* of drift, then, is dangerous; a *large quantity* is a help and an aid. If pile dikes are then built sufficiently strong to withstand the impact of the drift, and protected at foot sufficiently to stand the scour consequent upon the first small accumulations, this material may be made a very important part of our resources in filling up chutes and building bars.

I do not know of any case on the Providence Reach where piling yielded to pressure.

drift, but there were cases where dikes were broken by the force of impact, and by scour, caused by small drift accumulations. There are other cases where flotation of drift is supposed to have pulled piles out as the water rose.

FINANCIAL STATEMENT.

Lake Providence Reach.

Balance from previous appropriations.....	\$13,573 85	
Allotment under act of August, 1892.....	650,000 00	
New Madrid allotment (transferred).....	187,500 00	
Additional allotment from unallotted reserve	112,500 00	
		\$963,573 85
Expended by Captain Marshall, from July 1, 1892, to December 1, 1892:		
Plant and tools	\$23,068 48	
Piles, coal, &c.....	3,873 15	
Services	46,061 80	
Tow-boat service.....	5,492 08	
Subsistence.....	6,968 33	
Miscellaneous.....	1,611 44	
Total	87,075 23	
Expended by Captain Marshall, from December 1, 1892, to November 1, 1893:		
Plant and tools	\$63,766 26	
Brush, piles, &c.....	77,516 84	
Services: Construction.....	152,050 43	
Surveys	7,222 07	
Office and headquarters	10,433 64	
Tow-boats (including charter).....	17,454 11	
Snag-boat	625 32	
Medical attendance (including drugs).....	1,626 06	
Subsistence.....	22,774 61	
Miscellaneous (including transportation, traveling expenses, &c).....	7,170 02	
Total	360,639 36	
Expended by Captain Marshall:		
From July 1, 1892 to December 1, 1892.....	\$87,075 23	
From December 1, 1892, to November 1, 1893.....	360,639 36	
	447,714 59	
Expended by Captain Sears	359,531 33	
Total expenditures.....	807,245 92	
Balance available November 1, 1893	156,327 93	
Balance in Treasury	137,000 00	
Balance in hands of Captain Sears.....	4,700 78	
Balance in hands of Captain Marshall	14,627 15	
	156,327 93	

The following
Commission, 1

penditures were made by the executive officer, Mississippi River
ating property, &c., for use on Lake Providence Reach:

Description.	Number.	First cost, each.	Total cost.	Date of payment.	Marks and numbers.
Barges.....	11	\$2,000 00	\$22,000 00	Dec., 1882, to Mar., 1883	77, '8, '9, 80, '1, '2, '3, '4, '5, '6, '7.
	8	2,400 00	19,200 00	Jan. to Mar., 1883	88, 91, 154, '3, '4, '7, '8
	2	1,000 00	8,920 00	June, 1883	59, 60.
	1	1,800 00	1,800 00	Mar., 1883	194.
	4	2,000 00	8,000 00	Not known	135, 'd, '7, '8.
Total	26		54,420 00		
Mattress-boats	2	6,600 00	13,200 00	June to Aug., 1883	30, 31.
Steam tow-boat	1	17,404 00	17,404 00	Jan., 1883	De Pauw, new Vicksburg
Quarter-boats	4	4,000 00	16,000 00	Apr., 1883	21, '2, '3, '4.
Skiffs with oars	5	20 00	100 00	Jan., 1883	
	10	20 25	202 50	July, 1883	
	8	25 50	204 00	Aug., 1883	
Total	23		506 50		
Electric light and outfit	1	938 50	938 50	June, 1883	
Anchor			365 58	Mar. to Apr., 1883	
Outfit of quarters, boats and other plant			8,920 10	Jan. to June, 1883	
Total			107,854 68		

Barges Nos. 135, 136, 137, 138, in use on Lake Providence Reach, were paid for out of
Memphis allotment; four, at \$2,000=\$8,000.

This list does not include plant bought for general service out of Lake Providence
allotment.

REVEYMENT AT DELTA POINT.

This work during the last year was carried on under the immediate direction of
Assistant Engineer H. St. L. Coppée, and was a continuation of the work begun in
1878, under the supervision of Maj. W. H. H. Benyaurd, Corps of Engineers, in accordance
with the recommendation of the Board of Engineers upon the Restoration of the
Harbor of Vicksburg, published in the report of the Chief of Engineers for 1878.

The report of Mr. Coppée herewith is full and details at length the work done.

A description of the methods employed was given by Mr. Coppée in the last annual
report of the Commission, at which time about 1,100 feet of the work was completed.
From the date of that report (December 1, 1882) work progressed continuously until
February 10, 1883, when the allotment had been expended. The plant was then trans-
ferred to Wilson's Point, La.

The work during the past year was carried on in the same manner as described in
the former report, with the exception that the piles through the shore edges of the
mats were omitted, in order that if high water should find the work incomplete, con-
tinuous mats might be sunk without interruption, overlapping the low-water mat-
tress, and with the further exception that a mud flat some 250 feet wide, below the
old bank, was not revetted above the 12-foot stage; also the upper bank revetment
of the last 625 feet consisted of a woven hurdle-mat sunk at high water, reaching to
the 32-foot stage, instead of the usual upper bank revetment which could not then be
placed.

The work was carried several hundreds of feet below the head of the sand-bar at the
point at low water.

The low water just passed revealed that the work done under the Commission
stood intact, but that the mud flat mentioned above should be covered with brush
and stone to prevent a possible eddy-cut around the revetted old bank.

A small portion of the dike built in 1879 at the projecting point itself has fallen in,
due, probably, to the rotting away of the thick brush mats of which the dike was
principally built. In all, about 500 linear feet of brush and stone patch-work should
be done to secure the work against another flood. In all, about 4,000 feet of revet-
ment measured along the bank was laid, costing, including additional quarters on
shore, one quarter-boat, and the redecking of one barge, towing, superintendence,
tools transferred to Wilson's Point, La., &c., \$75,762.49, or \$18.75 per linear foot.
Mr. Coppée estimates the actual cost of labor, subsistence, towing, and material at
\$13.37 per linear foot, as the actual cost of the work done.

FINANCIAL STATEMENT.

oved June 18, 1878	\$84,000 00
oved March 3, 1879	50,000 00
oved June 14, 1880	20,000 00
oved March 3, 1881	75,000 00
its from appropriation for improving Mississippi River, Au- 82.....	50,000 00
.....	279,000 00
rior to December 1, 1882	231,242 17
.....	
ailable December 1, 1882.....	47,757 83
ince December 1, 1882:	
nt and tools	\$1,335 39
vices	22,781 45
sistence	6,318 46
ne and coal	12,260 92
urter of tow-boats, &c.....	3,408 37
ice supplies.....	257 57
aneous (including traveling expenses, transporta- quarters, mule hire, &c).....	1,388 03
.....	
.....	47,750 19
.....	
ailable November 1, 1883.....	7 64

DREDGING IN VICKSBURG HARBOR.

allotment of \$100,000 made by the Commission from the general approp-
improving Mississippi River, and the project adopted by them September,
ere solicited for dredging, and received and opened just before the date
annual report. An abstract of the bids received was published in the last
e Commission.

et for this work was to excavate a basin 300 feet wide, 1,700 feet long in
elevator; a canal 150 feet wide from this basin to deep water in the lake,
open the west entrance to the lake. The dredging to be done to the
Vicksburg gauge.

t responsible bidder for this work was Mr. Rittenhouse Moore, of Mobile,
nta. The next lowest, S. N. Kimball, of Mobile, Ala., at 18 $\frac{1}{2}$ ¢. The third,
n., of Baltimore, Md., at 19 cents per cubic yard. Of the three, Moore
he could not begin work until February 10; Kimball was not provided
and Fobes & Co. expressed their ability to complete the work by June 30.
sible success of the entire project for the year's work depended upon the
th which the work could be done, and it was especially necessary that it
ompleted before the decline of the water that could be expected in July,
amended that the work should be divided; one-half to Moore at his bid,
er half to Kimball or Fobes & Co., at their prices. The entire contract
d to Rittenhouse Moore, of Mobile, Ala., the lowest responsible bidder,
able to begin at the time required, prosecute the work with the vigor re-
r the specifications, or complete it within the time specified. The work
ractor was not begun until April 5, 1883, and was prosecuted, with many
il September 18, 1883, when, on account of the rapid decline of the river,
g was necessarily suspended, less than one-half the required work having
med.

ne to be given hereafter in this report, the contract was then allowed to
135 cubic yards having been removed.

he period covered by the dredging operations, the basin was excavated
ore of the gauge for a width of 160 feet, and four additional cuts; or 160
down to the +5' plane, 80 feet in width of the canal was excavated to
no, and an attempt was made to excavate the West Pass, which since the
water had filled until the depth of cut required was about 17 feet. The
ed for want of proper facilities for removing the material excavated, which
sand, and the work there was ordered abandoned by the construction com-
issippi River Commission, August 22, 1883.

ence of the failure of the dredging operations at West Pass, and the in-
adition of the basin, the wharf-boat was removed from the upper landing
t, August 7, 1883, when the river stood at 23.7 feet on the Vicksburg gauge,
er boats were excluded from the harbor a few days later, or after the
d the 20-foot stage at Vicksburg.

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

of the water below the edges of the excavated area extensive sloughing inwards of the mud deposit composing its side took place, and, in fluidity, or plasticity, the weight of the banks themselves caused the bottom until the slopes reached the inclination of $1\frac{1}{2}$ to 1, and in places it was greatest in the deepest part of the excavation, on account of the high deposit along the Vicksburg front, which sank down vertically. The upheaval here amounted to as much as 8 feet. This material was raised to the zero plane for a width of 80 feet by the dredge party.

The excavated areas are now quite regular, with nearly uniform slopes of about eight horizontal.

The West Pass of water through the narrow and shallow cut made by the dredge at the West Pass was sufficient to keep the sand-bar cut down as the river fell, and boats began to make their appearance in the harbor on the first rise of the water. At the 12-foot stage steamers drawing 5 feet of water now land in the wharves, and in front of the city, turn in the basin, and go out through the canal and cut to the West Pass. Larger boats, it is expected, will make their appearance at a lower stage of water than for several years. To this extent the dredging has been successful, and the benefits so far secured will probably more than repay the expenditure.

The rapid fall of the present temporary advance from dredging was receded to the date of the expiration of the contract, and the benefits so far secured will probably more than repay the expenditure.

Early in September a contract was made in accordance with the water survey of the area, and the survey was made in the month of September.

The main channel of the river is now within the limits of the contract, and the amount to be removed has been estimated.

The river has been thrown over against the bar at the West Entrance, and has cut a deep tongue-shaped trough through the center of last year's bar, cut down to the level of the Mississippi shore, and piled up a barrier with a nearly horizontal top at the southwest end of the lake. The tendency of the river is to cut away the sand-bar above Delta, and make its bend further in towards Vicksburg, lengthening its radius of curvature. This change will necessitate more extensive revetment of banks above Delta to protect the work already done. The change will not probably materially shorten the distance from Vicksburg to deep water for many years.

The increased eddy current around De Soto Island, and the consequent increased current in the harbor of Vicksburg, results directly from the changes at Young's Point. The current will evidently increase as the water is thrown further in towards Vicksburg, and the access of water to the lake is entirely cut off by the deposit. The river is now rapidly developing its new high water shore, and across the ends of the lake.

The survey made in May revealed at that time an average fill of only about one foot, but the great fill shown by Cooper's recent survey, took place after the decline of the water after June 1. This, if it always happens, in connection with further dredging operations in the harbor, the annual fill must be removed each year after June 1, or on the first rise of the river, which is always rapid, or during low water, the project to maintain navigation by annual dredging would seem impracticable, for the case does not take place before its removal is necessary, nor can it be removed before the rise of the river in the late fall restores navigation. The only practicable way by dredging alone under these conditions is to prolong navigation, and to hasten the return each year of the steamers to the harbor.

It is necessary to introduce some scouring force, as the Yazoo River, and the Mississippi and other rivers proposed by the Board of Engineers of 1877 to be cut through the lowlands may be had to prevent ingress of mud, and to keep the river open.

It is also necessary to provide some scouring force, as the Yazoo River, and the Mississippi and other rivers proposed by the Board of Engineers of 1877 to be cut through the lowlands may be had to prevent ingress of mud, and to keep the river open.

and this recurring expense, to make rapid progress on the main work itself, the excavation of the channel for the Yazoo from Old River to Centennial Lake, and from Centennial Lake to deep water in the river.

In the estimates prepared by the Board of Engineers in 1877 the cost of the diversion of the Yazoo via the dead end of Old River is placed at \$1,800,000. The removal of the deposit from the line of the canal is estimated (now) to cost \$766,000, with a probable annual expenditure to maintain an open canal of about \$200,000, or say, if the work be done simultaneously and at once, \$2,800,000. The assessed valuation of the city of Vicksburg, real estate only, was for last year (1882) \$1,459,000. The nearest steamboat landing is about 4,500 feet below the elevator. Annual value of the commerce of the city, about \$10,500,000.

There is still another scheme which finds favor in Vicksburg—as does, indeed, any plan for restoring its water front—and it is this, that since the river has now determined that Vicksburg is on the dead end of the cut off, and the expense of damming the Mississippi mud at that end is small compared with the expense of dredging the deposit, let the Yazoo be diverted and allowed to go out at the West Pass and that passage be dredged from the city front to the deep water in the then live end of the lake. This would reduce the probable expense about one-third and allow the diversion of the Yazoo to be made with advantage to the city prior to excavating the narrow basin and canal from deep water in the lake along the city front to deep water in the river, or it would make the two works independent of each other. The advantages of placing the town at the dead end of the cut-off are evident, but the scheme is advantageous from the above considerations and from the further fact that it is not opposed to the canal for the Yazoo ultimately along the city front, the work requiring only to be stopped for one low-water season, and the canal in front of the city to be prosecuted to completion, to effect this end as proposed.

If this scheme were executed it would be advantageous to put all dredged material along the crest of the mud bar and across the line of the proposed canal in front of town, near Ryan's mill, to shut off ingress of muddy water, where it now requires dams from 16 to 24 feet in height to entirely close that line at ordinary high water. The west arm of the lake, formed by the cut off, is gradually shoaling behind the bar, and here also there might be considerable dredging required before the deposit is of sufficient depth to allow a defined channel for the diverted river, or rather before the banks of the Yazoo are formed by the contraction due to the slow deposit.

Every scheme, however, having in view the diversion of the Yazoo or the execution of a canal, involves annual dredging to maintain the proposed works. At the present mouth of the Yazoo this past low water there was only four feet of water. Boats using three feet struck and encountered difficulty, and it is not to be presumed that it will be deeper at the proposed mouth.

The tending of the Mississippi by deflecting or tilting dikes and revetments above the Point and at Young's Point is also proposed for the purpose of bringing the river further in towards the town, but the cost and result of such works are still more estimational and less adapted to close estimates; the works would be tentative and slip. It is practicable, however, to maintain the river where it is, at least for many years, and it is to this work that it seems advisable to direct our efforts until doubt to the sufficiency of the works for that end is removed.

With reference to the further prosecution of work here, then, the following propositions have been made, and are given in the order of cost:

1. Abandon the "restoration" of Vicksburg Harbor and maintain the low-water wharf at Klinton, 4,500 feet below. This requires constant watching and care of the Point, and an extension of the revetment, after the bar above has cut away as rap stream as the head of the saving in this bond. All other projects also require

2. Scrape or dredge the bar at West Entrance sufficiently to determine the line of flow down due to the efflux of water during the falling stages, to allow an earlier run of vessels to the Vicksburg front. This will require also dredging in the basin & canal dredged this year to a greater or less extent, as it fills up. No estimate can be made, but it will probably not be less than \$30,000 per annum after the first year.

3. Divert the Yazoo into Centennial Lake, and allow its current to flow out at West Pass, and keep present canal and basin dredged. Approximate cost, \$1,850,000, first cost, and annual dredging in canal, basin, and West Pass to maintain it. If the low-water discharge of the Yazoo must be controlled, this estimate will be increased.

4. Condition would make the scheme impracticable.

5. Divert the Yazoo, close the West Pass, and dredge canal and basin in front of town. Estimated at \$2,800,000, with annual dredging at mouth of canal. Same condition concerning high-water control of the Yazoo.

6. Condition that the navigation of the Yazoo shall not be interfered with by the work introduced additional difficulties in the execution of any scheme involving a change of the Yazoo.

preserve the heavy buckshot levee, closing the "Alsatia" crevasse; but the sing the Edgwood and Illawara crevasses, was carried away in a wind and rain ing the night, and there resulted to the contractor a loss of about 32,600 cubic irthwork. The river having determined a new channel through the chute of , the wings, proposed last winter as protection works, are now made parts of line, the old levee in front being enlarged and used also as part of the main

a to Milliken's bend" levee, Louisiana, another large and important work, was incomplete condition, and the saving it was rendered still more difficult by at water collected behind the levee, which, with the river pressing in front of a supply of material with which to raise it. Barges were sent down from the Wilson's Point, and by strenuous efforts the top of the levee was kept above material transported from a distance, and the entire work saved.

"Delta to Bedford's" levee, six miles in length, a gap of 1,100 feet was un- Backwater from the Diamond Island crevasses shut off access to it, and the an running through low places in the banks in front. Here a line of protec-, nearly three miles long, along the edge of the river bank was built, which, the situation allowed, was reduced in length to about one-half by a cross-levee in work, built by hired labor. This long line several times gave way in t the gaps were in each case promptly closed, and the work saved.

Yasoo front, in Mississippi, the flood found the levees in such condition that entirely safe, except the Longwood, Skipwith, and Elleslie levees, at each of ation levees were built.

Elleslie gave way from a storm dashing waves against it, and the water broke e incomplete main line, flooding several plantations and washing out 2,600 cubic irth from the main levee. This break was more advantageous than otherwise to d lands. The banks are high, and the water on the first decline of the river was ed by a second protection levee along the site of the first.

ed hereto are reports of Assistant Engineer H. D. Garden, in charge of the the Tensas front in Louisiana, and of Assistant Engineer George M. Helm, in the Yasoo levees in Mississippi, which give in condensed form information g the levees built in the district.

latter gentleman has been chief engineer of the Mississippi Levee Board for the years, and has had much experience in levee construction, he was requested to s report, for the information of the Commission, a statement of the work done ee district authorities during the past eighteen months, and also to submit the lice, as shown by his experience, in stopping crevasses, building heavy levees ble foundations, and revetting the ends of breaks to prevent enlargement. llen submit estimates for raising the levees in their charge to 3 feet above r mark of 1882.

re also submitted with this report tables showing earthwork built in the dis- arch 1, 1883, or in four months prior to the flood, and the condition of the levee ler the various contracts November 1, 1883, the date of this report. From this le it appears that there has been built in all, including the small amounts re- last annual report:

	Cubic yards.
unt, Arkansas	243, 428. 0
unt, Louisiana	1, 001, 734. 0
unt, Mississippi	1, 193, 281. 1
tal	2, 438, 443. 1
there remains to be done—	
	Cubic yards.
ness front in Louisiana	99, 381. 6
asoo front	14, 627. 0
	114, 008. 6

pected that work will be completed and contracts closed by December 1, 1883. ness the grades of the levees have been restricted to the grades of the old levees, : Wilton to Raleigh where the bank was exceptionally low, and the levee of very onstruction, from the nature of the material.

r break here would make it still more difficult and costly to rebuild the levee, d allow enormous quantities of water to escape from the channel, the ill effects on navigation are now seen just below the present crevasse, at Foster's.

no reason, the grade as established for this levee was placed at about 18 inches n that of the levees immediately above and below, which were on high ground, vee across the sandy part of the line built of increased dimensions.

FINANCIAL STATEMENT.

Tensas front.

To amount allotted \$322
 To amount transferred from Yazoo front 25
 To amount redeposited on account of error in voucher 45

Total 348

Expended prior to December 1, 1882:

Contractor's estimates	\$28,888 06	
Services	2,616 05	
Instruments	1,319 35	
Subsistence	177 93	
Miscellaneous	637 20	
		\$33,638 59

Expended from December 1, 1882, to November 1, 1883:

Contractor's estimates	\$239,531 20	
Services	10,372 11	
Services on protection levees	4,662 79	
Instruments	282 75	
Subsistence	135 69	
Office supplies	357 42	
Miscellaneous (including bags used on protection levees)	2,176 94	
		257,518 90

Total expenditures 291,

Balance available November 1, 1883 57,

Yazoo front.

To amount allotted \$35
 By amount transferred to Tensas front

Balance

Expended prior to December 1, 1882:

Contractor's estimates	\$28,435 49	
Services	1,511 00	
Miscellaneous	112 61	
		\$30,059 10

Expended from December 1, 1882, to November 1, 1883:

Contractor's estimates	\$266,749 89	
Services	12,504 33	
Services on protection levees	1,082 73	
Office supplies	304 50	
Instruments	170 60	
Miscellaneous (including bags used on protection levees)	2,965 17	
		283,

Total expenditures 22

Balance available November 1, 1883

ount of earthwork constructed on levees, third district, before the
d amount constructed since then to November 1, 1883.

	Total amount in levee. Approx.	Amount constructed March 1, 1883, date of expiration of contracts.	Amount constructed since March 1, 1883.	Amount yet to be constructed.
	Cubic yards.	Cubic yards.	Cubic yards.	Cubic yards.
.....	243,903.3	182,739.0	61,164.8
.....	39,156.9	39,156.9
ele.	90,002.2	90,002.2
.....	199,059.2	156,032.6	43,026.6
.....	41,287.7	41,287.7
.....	* 387,941.8	223,495.0	63,065.2	99,381.6
.....	61,162.9	16,572.0
.....	61,162.9
.....	80,246.0	2,029.6
.....	163,182.0	80,246.0
.....	163,182.0
NT	1,305,942.0	1,077,906.9	167,356.1	99,381.6
.....	49,357.0	49,357.0
.....	67,299.1	67,299.1
.....	133,500.0	104,627.9	28,872.1
.....	2,796.0
.....	71,660.0	63,067.0	8,593.0
.....	3,500.0
.....	75,891.0	60,041.0	15,850.0
.....	15,978.0
.....	68,631.0	31,017.0	30,270.0	7,344.0
.....	156,213.0	155,149.0	1,064.0
nda.	103,298.0	95,148.0	887.0	7,282.0
.....	50,714.0	50,112.0	602.0
.....	22,882.0	22,882.0
.....	150,538.0	139,797.0	10,741.0
.....	66,836.0	66,836.0
.....	27,152.0	27,152.0
.....	151,663.0	151,663.0
.....	1,185,634.1	1,106,422.0	88,859.1	14,627.0

31,552 cubic yards, which was washed away during flood of 1883. It has
Second Comptroller of the Treasury whether this quantity will have to
tractors, at their expense, or paid for by the Government.
of the levee, the amount of 13,302.1 cubic yards already paid for was
of levee
levee when completed will be 343,067.7 cubic yards.

LEVEE SURVEYS THIRD DISTRICT.

1,000 made by the Mississippi River Commission at their meet-
arty was organized September 20, 1883, by Assistant Engineer
y and location of levees in Arkansas from the high land on
2, 7 miles back from the river and about 18 miles above
ana State line.

ey was completed November 1, 1883. Assistant Star-
ulation of volumes and in plotting and neces-
where broken.

rest of the president of the com- notes of the
Arkansas City have been reduced from Amos
these other show as follows

Cubic yards.
351,325.0
483,763.0
846,919.0

2828 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

These estimates considerably exceed that made for the Board of Engineers which
vened at Memphis, September 4, 1882, but have been deduced from careful su
More than one-half the water that escapes into the Tensas Basin flows through the
above Arkansas City, and there is now an effort being made by the State of Louis
corporations, and private individuals in Arkansas to the effect closure of this line
a contract for the work has been made by them. If the reduction of the note
be made in time the results of the survey will be incorporated in this report before it
submitted to Congress.

FINANCIAL STATEMENT.

Amount allotted	\$1, 01
Expended:	
Instruments and outfit.....	\$51 75
Services.....	386 06
Subsistence.....	35 50
Miscellaneous	23 05
	<hr/>
	4
Balance available November 1, 1883.....	5

SURVEY OF CHOCTAW BEND REACH.

At the date of the last annual report of the commission the survey party unde
sistant Engineer William T. Blunt was in the field. The survey was begun Nove
17, 1882, and completed and the party returned to Wilson's Point December 30, 18

The survey was restricted to the hydrography proper, the shore line as determin
Assistant Engineer Ockerson the preceding year being accepted, except where a
banks rendered new locations of shore lines necessary.

The survey extended from Cook's Point to Arkansas City, a distance of 28 miles.
survey shows that there was not less than 13 feet of water at a stage correspondi
a gauge reading of zero on the Arkansas City gauge, or that there existed no obsta
to navigation in 1882, low-water season.

A complete project for the improvement of the reach will be submitted with the
at the earliest practicable moment. For the present there is no especial demand f
improvement, except the revetment of the upper and lower banks of Cook's Point
where it is caving and a cut-off imminent. This requires 7 miles of revetment,
probable cost of \$515,000, if carried to the top of the bank, or \$210,000 if restricted
subaqueous mat. The caving is now back to the cypress swamps, and the material
usual in slowly-deposited banks, heavy buckshot, very tough and difficult to cave.
banks, however, are wearing quite rapidly, and the configuration of the river point
cut-off. The neck now is nearly a mile wide, but low, the water flowing across at
eral feet below the ordinary high water. At the up-stream side of the neck is Persim
hollow, leading into Long Lake, which occupies the middle of the neck, and drain
through Cypress Bayou, on the lower side of neck. The danger lies in this low de
sion, already sufficiently lowered to cause quite a deep channel-way across at high w
obstructed, however, by a thick undergrowth of cypress, willow, and cottonwood
accumulated drift-wood.

The report of Assistant Engineer Blunt is herewith.

FINANCIAL STATEMENT.

To amount allotted.....	\$4, 01
Expended:	
For services.....	\$1, 587 92
For subsistence.....	495 06
For tools and supplies.....	531 36
Miscellaneous	65 52
	<hr/>
	2, 6
Balance available November 1, 1883.....	1, 2

L 1.

REPORT OF ARTHUR HIDER, ASSISTANT ENGINEER, UPON OPERATIONS OF THE
PROVIDENCE CONSTRUCTION PARTY.

WILSON'S POINT, LA., November 15, 18

SIR: The following report of operations of the Lake Providence construction
from December 1, 1882, to November 1, 1883, is respectfully submitted.

The work undertaken in accordance with your instructions, and that which
far been executed, has had in view the following objects:

reducing of the width of the river in places where it was excessive, to bring the channel within the boundaries fixed in accordance with the original project, following methods, viz:

The closing of the Duncansby and Skipwith chutes by the construction of a pile dike at and near the head of the Duncansby chute. The filling up of boat channel, which was between the upper and the lower towheads, by the construction of a pile dike joining the two bars and the concentration by this means of the current on the right of the towheads, so as to permanently fix the channel next the shore and prevent the further caving of the banks in the Skipwith chute.

The closing of the Mayersville chute by a pile dike across the head, and others further down, and the protection of the channel side of Mayersville Island by construction of willow mattresses and revetting the front face of the island to prevent further caving, so as to retain the channel of the river in its present location.

The closing and silting up of the chute between the Baleshed Bar and the Misere, and the prolongation of the Baleshed Bar at its upper and lower extremities by a system of dikes placed longitudinally and normal to the direction of the current, to prevent restricting the width of the river along the Vista and Longwood fronts to such limits as would afford a good channel at all stages and prevent the river from being driven to the Mississippi side into the Baleshed Chute.

The closing of the main channel of the river, which passed between the foot of Elton Bar and the head of Stack Island, and bringing it back to the right of Stack Island by a system of deflecting dikes located on the Louisiana side at Elton Bar, and a main dike, driven across the channel between the lower end of Baleshed Bar and the head of Stack Island, so as to prevent further caving on the Mississippi shore behind, which had already done a great deal of damage and was increasing at an alarming rate.

The objects sought to be obtained at all these points have, to a great extent, already been accomplished, as shown by comparative soundings and surveys furnished by the Commission, which accompany this report.

The lack of stone to properly secure the revetment work done in November and December last year along the face of Mayersville Island, was the cause of the caving of the island in rear of the mattress work. This would, no doubt, have been prevented had stone been available to properly secure the work.

DESCRIPTION AND EFFECTS OF WORK DONE.

Duncansby chute.—During last season a system of low-water dikes was constructed at the head of this chute, the two upper dikes and the main dike at the head consisting of piles of piling, securely braced. These dikes were provided with light brush footed with stone, laid between the piling, and had screens or open hurdle work in front of them.

The lower dikes across the chute consisted of single rows of piles with screens or hurdle work in front.

These dikes did good service and caused a heavy deposit in the chute during the season; in many places the fill extended to the top of the piles.

The dikes A and B built last season, connecting the upper and lower towheads, produced the result desired, viz, the filling up of the steamboat channel, before existing between the upper and lower towheads; the fill here also extended nearly to the top of the piles. The two bars are now one, and even at high water there is no channel between them.

There has been a general enlargement of the bars in front of Duncansby, and a shoaling of the chute along its whole length. At low water this season a skiff would not float in Duncansby and Skipwith Landing, and at the head of the chute the bar was above water, no water at all entering the chute at the upper end. Skipwith was moved down nearly a mile nearer the mouth of the chute on account of the water, to enable steamboats to deliver freight.

On account of the rapid caving which took place during the high water in the bend below Lecher's Point, deflecting the main current across the river immediately above the dikes at the head of the chute, seriously threatening the work heretofore done, and together with the rapid caving back of the upper Duncansby towhead, which had been left unprotected; in accordance with your direction, four additional dikes, Nos. 5, 6, 7, and 8, were driven during the high-water stages across the chute, as close to the shore as the depth of the water would permit; dike No. 6 consisted of three rows of piles, with a woven mattress 130 feet in width, made in sections 50 to 200 feet, overlapping each other, sunk in rear of the dike.

The lower dikes, Nos. 7 and 8, were provided with thick grillage mats between the piles. These dikes, where the water was shallow, consisted of two rows of piling

The following table shows the results of the survey conducted in the year 2000. The data is presented in a tabular format, with columns representing different categories and rows representing different sub-categories. The table is organized into two main sections: 'General Information' and 'Detailed Data'. The 'General Information' section includes the title of the survey, the date, and the location. The 'Detailed Data' section includes the results of the survey, presented in a tabular format. The table is organized into two main sections: 'General Information' and 'Detailed Data'. The 'General Information' section includes the title of the survey, the date, and the location. The 'Detailed Data' section includes the results of the survey, presented in a tabular format.

of the main dike from No. 4 cross-dike to No. 11, to prevent scour. The dike is provided with a woven mattress in front will have a thick grillage foot-mat placed between the rows of piling, which is now being done. This will complete the work as laid out at this locality in accordance with your instructions. The general character of the work here has been—

The enlargement of the Baleshed Bar, both in size and height, and the lengthening of the bar by accretions, both at its head and at the foot.

The filling up of the Baleshed Chute at its upper end, and the enlargement and straightening of the channel along the Vista and Longwood fronts.

The prevention of the threatened crossing of the river between the foot of Mayers Island and the head of the Baleshed Bar, behind the bar, and down the Mississippi

The filling up of the old crossing between the foot of the bar and the head of Mayers Island. For location, &c., of this work see accompanying map.

Stack Island.—In order to force the main channel of the river, which flowed down the Island chute, on the outside and along the face of the island between it and the Baleshed Bar, a main dike consisting of two rows of piles was driven from a point below the foot of Baleshed Bar to the head of Stack Island, leaving the low-water channel from the foot of Baleshed Bar to the head of Stack Island open for the passage of boats. This dike was made as a low-water dike; a grillage foot-mat was constructed between the piles, beginning at the head, as far down as could be put in before the high water covered the

During high water this work showed good results, forcing the main channel of the river to the right of the island and building a bar to the head of Stack Island, as shown by the high-water survey of April, 1883. As the river fell to low-water stage the face of slope on the chute side and the main river was so great, caused by the system of dikes at the upper end of Baleshed preventing the water from freely entering the head of the chute, as to render the current extremely rapid through this dike, resulting in cutting off the top of the bar in front of the dike, and finally carrying away the dike near the head of Stack Island. This was replaced and again broken by a large log lodging against it. The break has again been repaired and a grillage foot-mat sunk between the rows of piling. The current passing across the head of Stack Island will be materially lessened as the river rises, and the slope on both sides of the island is more nearly equalized. A channel across the head of Stack Island is not expected, as at high water the works on Baleshed Bar above, will be sufficient to force the bar to again form at a greater height than before, and it is believed entirely dry water passing into the chute at this point at next low water. For location of work see map herewith.

Elton Bar.—The work here consisted in the construction of a main dike and six short cross-dikes at the head of Elton Bar and in the chute, to act in deflecting the channel across the chute toward the head of Stack Island, auxiliary to the Stack Island main dike, and to straighten the chute, which was rapidly enlarging, along the Louisiana shore and caving the bar at a very rapid rate, and thus concentrate the water in one channel; as when the dikes were put in it was difficult to determine which of these channels the river would follow behind Stack Island, along the Louisiana shore, or whether it could be concentrated between Stack Island and the then large Elton Bar. Parts of these dikes were carried away by drift during the high water, but not before they had accomplished the desired result. For location of these dikes see map herewith.

METHODS OF CONSTRUCTION.

General work.—No material change has been made in the methods employed in the construction of pile dikes from those of last season. The principal change has been in making the dikes of a greater number of rows of piles. The distance between the rows has been increased from 10 to 15 feet in deep water to allow of more secure bracing as well as the thickness and width of the brush work laid at the foot of the dikes to protect them from the action of the current and prevent scour. The experience of last season's work has conclusively shown that the strongest form of construction is required in order to withstand the force of the current at high water, and has led to putting in work of greater strength where exposed to the action of drift.

Driving and bracing.—The plan pursued in building pile dikes has been to drive the piles in several rows of piles simultaneously when it could be done, fasten the longitudinal and cross-braces, in addition to being fastened to the piles, have been well wired with No. 8 wire passed around the pile and on the upper to the lower edge, and made taut by twisting the wire on account of the material used for both piles and

drivers are provided with large boiler capacity and pumps capable of forcing water under a greater pressure. Piles can be sunk deeper with the jetters, but the difficulty of handling them in cross-currents reduces the depth.

Between 15 and 20 feet has been the average depth of penetration, reaching that depth, if further sinking is not stopped by gravel, buckshot, or other material, the frictional resistance exerted by the sand along the side of the pile prevents further penetration. This resistance could not be overcome by the water-jet or the hammer, or both combined, as the wood of the pile, if composed of soft wood, will not withstand, without splitting, the shock of the hammer from a great height. The usual method has been to sink the piles with the jetter down; the butts are cut off square, and are about 18 inches in diameter, and not less than 10 inches diameter, and the length of the piles from 35 to 45 feet. Piles is counted as an average day's work for one driver with a crew consisting of a foreman, engineer, and five laborers. No special improvements have followed in pile sinking or in the construction of drivers has suggested. The drivers are well adapted for the purposes for which they were designed. For the purpose of hoisting engines are in use, each of which has an advantage in some of the others; on the whole the small horizontal engines have given the best results, quicker in operation, and, next to the ordinary crab in use on four of the dikes, less for repairs on account of breakage.

Brush mats, hurdles, &c.—The principal dikes have been protected against scouring out, by constructing mats formed of two, three, or four layers of brush, depending upon the importance of the dike, rapidity of current, depth of water, and the amount of cutting out. These layers of brush are placed alternately crosswise and lengthwise of the dike. Stringers, or waling-pieces, as binders, are first hung from the dikes, and work for the brush to be laid upon. When the mat is of sufficient thickness, the stringers are laid on top of the mat connected with those underneath by wires at intervals of 10 feet, leading up from the under stringer pieces, twisted together so as to make the mat as close as practicable. The brush is laid so as to extend through the water, and quaring on some of the dikes three lengths of brush, the brush ends over the dikes. When finished, the mat extends both in front and rear of the dike from side to side. The grillage mats thus constructed are then sunk in place by the jetter, with rock taken to the dike on barges. When woven mats are placed on the dikes to prevent longitudinal scour they have been built similar in construction to the grillage mats used for the protection of caving banks, and sunk in place by the jetter with rock. For the purpose of preventing the threatened deepening of the channel during high water, a brush foot-mat 130 feet in width, made in sections 100 to 200 feet in length, was woven on a mattress barge in rear of dike No. 1, and was towed up the head. Alternate sections were built and sunk on the dikes.

by fastening sacks of rock to the curtain, to counteract the force of the current & in position.

tiling or hurdling has been made close by forcing the pieces of brush down so in contact with each other, and has been done on either the middle or front the brush mats are built between the rows of piling so as to provide against the overfall cutting out the sand in rear of the dikes. Sketches giving different forms of construction employed in the dikes built and their location on map herewith.

owing statements furnished by Assistant Engineer C. P. Ruple, gives in detail, and form, the work done in dike construction; also an estimated cost for labor for each class of work, and amount of material required. All the pile-driving been under his charge, and since June 1, 1882, at which time the foot-mat or Assistant Engineer E. D. Thompson was consolidated with the pile-driving class of work also.

Statement showing dike work from December 1, 1882, to November 1, 1883.

Location.	Dike.	Feet driven since December 1, 1882, standing November 1, 1883.	Washed out and replaced during construction.
	Duncanby Bar protection.		340
	Main dike A		230
	No. 1	100	
	No. 3	150	
	No. 5	545	
	No. 6	2,105	275
	No. 7	3,061	
	No. 8	2,310	
	Main dike.	2,300*	
	No. 1	505	
	Main dike above 1	1,991	
	Main dike from 3 to 7	2,837	1,021
	Main dike from 7 to 11	5,005	
	No. 1	933	
	No. 2	1,192	
	No. 3	1,172	
	No. 4 of 1883	661	450
	No. 5 of 1883	983	153
	No. 6	1,452	150
	No. 7	1,204	500
	No. 8	1,011	150
	No. 9	1,097	
	No. 10	524	
	No. 11	804	
	No. 12	543	
	Main dike.	5,350	1,429
	Main dike	948	857
	No. 1	746	54
	No. 2	887	63
	No. 3	985	
	No. 4	300	356
	No. 5	484	40
	No. 6	435	
		44,335	6,432

*Three hundred feet of this dike is incomplete.

are like there is in—

	2,836
	25,187
	14,150
	565
	1,997
	44,230

ANNUAL REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Statement showing cost of different kinds of work, and material required in the construction of pay-roll.

Less: Amount other parties, with substance.

Estimated as follows:

For clearing, grading, hauling, and stringing.
 Less: work done by waiting, shore-work, etc., making and
 setting.

Water, from the river—oil, kerosene \$50.00—cost \$1.55 per barrel.

Oil, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

Water, from the river—oil, kerosene—cost \$1.24 per barrel.

are in unit; the ends of these rods are connected with lap-rings or clevises. They are to give the necessary longitudinal strength to the mat, and prevent it from coming apart while being sunk, and allow it to adjust itself to any irregularities on the bottom. The mat is then further strengthened by binders made of poles placed on the mat and fastened to the mat with wire to the weaving poles.

In mats, and where the current is swift and the water deep, additional longitudinal strength has been obtained by the use of No. 8 wire twisted in the form of a cable, run on top of the mattress, securely fastened at intervals by wire to the weaving poles. The upper end of the mat while being constructed is held in place by lines leading to a mooring barge leading to fastenings on the shore above. The mooring barge is placed with one end next the bank, the outer end being kept in place by lines leading to suitable fastenings on shore. The head of the mat is held up by small lines run over the side of the mooring barge, to which they are fastened, which are slackened as the mat is sunk; additional lines leading from the mat to the bank are placed along the mat at intervals, so connected with it by iron clevises as easily to be freed after the mat has been sunk in position.

One of the mooring barges is to prevent drift from lodging on the head of the mat, and keep it from being submerged until it is ready to be sunk. The mats have been first loaded the edge next shore along the slope, with rock, and afterwards by loading rock on it, beginning at a suitable distance below the head to allow the mat to sink to the bottom without breaking. The head is then sunk last.

A deal of trouble and some loss has been experienced in sinking large mattresses. It has been shown that in deep water and where the current is swift the mat can be made too strong, and should not be of a greater length than from 600 to 800 feet. The frictional resistance offered by a mattress of, say, 150 feet in width of this enormous, and renders the greatest amount of care and precaution necessary at all times. The methods employed heretofore in sinking large mattresses are not satisfactory, as there is always danger of their loss when the current is swift and the water is deep. The irregular supply of stone has led to the construction of barges larger than otherwise would have been built, in order to keep the men employed.

After sinking the mattresses in place the bank has been graded by the hydraulic dredgers to a uniform slope of from $2\frac{1}{2}$ to 3 to 1, ready for the brush revetment; a great deal of hand-work is required to trim up the bank, except where it is of sand. The following is a description of the plant and how operated, furnished by Assistant Engineer Stuebing, who has had charge of the grading:

Description of Plant.—The plant consists of two large pumps placed on barges 110 by 50 feet hold, on the deck of which are the machinery and boilers. A cabin is built above the boilers and machinery, which contains sleeping room for 30 men. The

boilers are of steel, and on No. 3 of iron, both of 60,000 T. S. They were tested for a steam pressure of 125 pounds. They are supplemented by an upright auxiliary boiler for cleaning and pumping up main boilers. In front of the furnace is the coal-box, with storage room for 500 bushels of coal. The water to supply each of the main pumps is taken from a well in the bottom of the boat 3 by 3 feet, one on each side, through a 12-inch pipe. The bottom of the well is covered by a strainer made of three-eighths-inch flange iron. This strainer has 2,500 holes of three-eighths-inch diameter, which gives nearly $2\frac{1}{2}$ times the area of the suction pipe. The water is discharged through two 12-inch pipes, one from each pump, into the main pipe, to which the boom-pipe is connected, the joints so arranged where the pipes come together as to allow the boom-pipe to have motion, both perpendicular and horizontal. The length of the boom-pipe is 65 feet, tapering from 12 inches to 8 inches, and consists of 4 flanged pieces, which are bolted together. These pieces of the boom-pipe are lapwelded tubes screwed in to cast-iron flanges and bolted through flange and screw end of tube. The whole is stiffened by two hog-chains, one below extending along the whole length, the upper one on top of the two smallest pieces to which is attached the hoisting rope. The hoisting rope is 1 inch steel wire leading over a pulley on top of the shears, thence to the drum of the hoisting engine. The shears are pine timber, 54 feet long, 12 by 12 inches, the heels butting in iron shoes on deck in a line with the hoisting engine. They are slightly inclined forward and are held by two $1\frac{1}{2}$ -inch wire rope guys, which are fastened to the gunwales. The pumps have a capacity to discharge 2,000 gallons a minute, under a pump pressure of 160 pounds.

Method of operating.—The grader is placed in position with one end next the bank, and the stage and boom-pipe lowered so as to almost rest on the ground. When the bank is perpendicular a trench is first cut at the proper slope so as to give a face to begin grading. When a steam pressure of 80 pounds, giving an efficient water pressure in the pumps of 140 pounds, is obtained, the work of grading is begun. A piece of 2-inch gas-pipe, about 4 feet long and pointed at one end, is driven into the ground about 10 or 15 feet from the face, and a little above the middle of the slope. The upper end of this gas-pipe is allowed to remain from 10 to 12 inches above the ground; a piece of iron is fitted into the top of this pipe, to support the nozzle, with holes on each side, into which trunnions on the nozzle fit, so as to admit of motion in any direction. After the nozzle has been fastened in this swivel and the hose connected with the boom-pipe at one of the valves, which are placed at intervals along the pipe for this purpose, two men take hold of the nozzle by means of a lever, which is fastened to it by clamps, and the signal is given to turn on the water; 3 or 4 men are kept ready to lighten up the hose, so as to enable the nozzle-men to point the nozzle in any required direction. The stream issuing from the nozzle is directed against the bottom of the face to undermine it to a depth of from 6 to 12 inches, and in doing this is moved along the whole length of the slope. The earth that has caved through this undermining is then washed into the river. The quickest way to do this is to soak the whole of the loose material first and then direct the stream so as to carry this saturated material into the river, pushing it down by the force of the stream. In undermining, it is always best to commence at the bottom and move upward. If the bank is more than 14 feet high 2 nozzles can be worked with advantage. Where one nozzle is used 11 men are required, while for two, 3 additional men are needed. The force to run one grader requires 1 foreman, 2 engineers, 1 fireman, 1 greaser, 2 nozzle-men, and 4 laborers—total, 11 men. With 2 nozzles working, 15 men are required. A $1\frac{1}{2}$ or 1-inch nozzle is then put very near the top of the slope, and undermines the upper one-third of the face, while the 2-inch nozzle does the same with the lower two-thirds, and washes all of the caved material into the river. After the bank has been caved and washed down as far as from 30 to 35 feet from the nozzle this is moved 10–15 feet again. In doing this the water is shut off from the hose, and is wasted through one of the other valves. The difference in the quality of the material that has to be undermined or cut into, the various positions in which the different strata are found underlying each other, height of bank, &c., requires, besides this general method employed, various modifications in special cases of managing the nozzle that can hardly be described, and only learned by experience. This is well demonstrated by the cost of grading.

While grader No. 1 was at Delta Point, opposite Vicksburg, in November and December of 1882, the cost for grading for the first two weeks was 9 cents, from November 20 to 30, 6 cents. In December No. 1 excavated 39,000 cubic yards, at an actual cost of $3\frac{1}{2}$ cents. Grader No. 3 had in the mean time excavated at Mayersville Island 15,000 cubic yards, at a cost of $2\frac{1}{2}$ cents, the bank consisting entirely of sand, while at Delta it was to a great extent intermixed with strata of hard clay, the different strata lying in unfavorable position for rapid work. In January, 1883 Nos. 1 and 3 together excavated on Mayersville Island 75,000 cubic yards, at a cost of $3\frac{1}{2}$ cents, or, deducting all time lost through inclemency of the weather, &c., of 2.5 cents. The cost of grading in February

accurately calculated, as the grading did not amount to much, and was in-
l delayed through stormy weather and the rising river. Work was stopped
February.

rain began September 26. Serious delays have been caused by the bursting
Nearly one-half of the time in the first two weeks was lost on this account,
cessary to constantly stop grading and change hose. The hose had been in
ous season. Besides, all outside laborers and foremen were inexperienced,
st of this trouble had been overcome, the rubber valves in the main pumps
o give out, and, as there were only few extra ones on hand, it was thought
t to work the pumps up to their full capacity. The work consequently pro-
eratively slowly. In September, only 3,260 cubic yards were excavated, the
h cannot be properly calculated. In October, in the first ten days, of ten
rs each, 11,395 cubic yards were excavated by No. 1. Since October 11
has been worked both day and night; at night the electric light has been
had been put up in January last. A double crew was put on, changing every
d working twenty out of twenty-four hours. Twenty-five thousand eight
ic yards were thus excavated from October 11 to October 20. On the 20th
received to work three crews and to make no stoppage for meals. In the one
fifty-two working hours from October 20 to 29, when work had to be tem-
ped, 25,111 cubic yards were excavated, making a total of 62,306 cubic
ted in the month of October, at a cost of 3 cents per cubic yard. The slope
the last month is smoother and more uniform than any ever made before,
very little or, in some places, no grading even by shovels to make it ready
t. This, I think, is of more importance than to do more excavating with a
r worked slope. I have already mentioned that the usually required water
10 pounds for one nozzle, while for two nozzles the pressure is run up to 160
greater pressure cannot be used very well, as it makes it difficult and dan-
e nozzle-men, besides the liability of bursting hose. By daily observations
the last month it is found that to excavate one cubic yard of earth it takes a
n less than one cubic yard of water under a pressure of 140 pounds, this water
g attained by a steam pressure of 80 pounds and a vacuum of 26½ inches.
ure of 80 pounds of steam it takes 3 pounds of coal per cubic yard of water
rth excavated. In comparing this hydraulic grading of earth with hand
of shovels, I think I may safely assume that the moving by shovel would
per cubic yard. This makes a difference in favor of the hydraulic moving
Grader No. 1 has so far moved about 165,000 cubic yards, and caused a sav-
e, of nearly \$44,550, or over one and one-half times the original cost. I am
it another month's constant running, with the past experience, new hose,
&c., the cost per cubic yard can be greatly reduced.

ment.—Where revetment has been laid, a grillage of poles is first placed
pe; on this grillage the brush is laid perpendicular to the direction of the
ther set of poles is laid on top of the brush over those underneath, to which
ened with wire to hold the brush in place. The poles are also fastened
stakes driven in the slope, and the revetment covered with stone. On ac-
scarcity of stone last season bags of sand were tried for the purpose of keep-
ment in place, but they failed in accomplishing the desired result; they
orn, and the action of the current washed out the sand, rendering them
e object intended. The following tabulated statement, showing the amount
mplished by the bank-protection party, and its condition November 1, 1883,
ate of the labor, cost, and material required for the different kinds of work,
ished by Assistant Engineer W. M. Childs, who has had charge of this class
the beginning:

Description of work.	Location.	Remaining in good condition November 1, 1888.			Washed away or bank caved back of mattress.			Remarks.
		Length.	Width.	Area.	Length.	Width.	Area.	
		Feet.	Feet.	Squares.	Feet.	Feet.	Squares.	
Woven mattress.....	Protection dike at head of Duncansby tow-head.....	377	135	574	All the work shown here has been washed away by the caving bank of the tow-head. The mattresses are on the bottom and show up at places, but are useless for the purposes for which they were intended. This work is in many places intact on the bottom, but the bank has caved back so as to render the building of a new mat necessary between old mattresses and the present bank.
Do.....	Duncansby tow-head inside.....	240	135	324	
Do.....	do.....	257	135	300	
Do.....	do.....	430	100	430	
Do.....	Duncansby tow-head outside.....	283	100	283	
Do.....	Duncansby tow-head across head.....	282	96	271	
Do.....	do.....	331	50	160	
Do.....	Mayersville Island between Ranges 53 and 54.....	4,000	100	4,000	
Do.....	Mayersville Island between Ranges 54 and 55.....	1,200	120	1,440	
Do.....	Mayersville Island 225 feet below Range 54.....	600	75	450	
Do.....	Mayersville Island between Range 54 and foot of island.....	5,210	186.8	9,784	
Totals.....	5,210	9,784	8,505	8,697	
Revetment.....	Duncansby tow-head inside.....	425	42	179	
Do.....	Mayersville Island at head.....	1,700	58.6	996	
Totals.....	1,700	996	425	179	

SUMMARY OF ABOVE STATEMENT.

	Feet.	Squares.
Linear feet of mattress in good condition, November 1, 1888.....	5,210	9,784
Linear feet of revetment in good condition, November 1, 1888.....	1,700	996
Totals.....	6,910	10,780
Mattress washed away by caving of tow-head, and from which the bank has caved back on Mayersville Island.....	8,505	8,697
Linear feet of revetment washed away on Duncansby tow-head.....	425	179
Total.....	8,930	8,876

2346 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

From the above statements an estimate is made of the cost of protecting caving by with a woven mattress 150 feet wide, the slope graded and covered with a brush or stone laid in place with stone, as follows:

In this estimate a square = 100 square feet.

Labour cost for 100 linear feet:

130 squares mattress at \$1.21	\$157 30
44 squares grillage at \$1.61	70 84
Graded at 50 cents	50 00
44 squares mattresses at \$1.74	76 56
Staking 130 squares mat at 15 cents	19 50
Covering with rock 44 squares revetment at 50 cents	22 00
	<hr/> 444 20

Add cost of—

Material 153.75 cords brush at \$1.75	\$269 06
Staking mat 72.2 yards stone at \$2	144 40
Covering revetment 36 yards stone at \$2	60 00
12.5 cords poles at \$2	25 00
127.2 pounds spikes at 5 cents	6 36
222 pounds wire at 7 cents	15 54
1,600 pounds iron rod at 5 cents	50 00
Towing, estimated one-sixth of cost of tow-boat service	83 32
	<hr/> 644 68

Total cost of 100 linear feet 1,111 88

Or. per linear foot, \$11.21.

SUMMARY.

Work completed from December 1, 1882, to November 1, 1883, and in good condition.

Number linear feet pile dikes, 44,235.

Number linear feet woven foot mats, 11,945; squares of 100 square feet, 9,386.1

Number linear feet grillage, 24,341; squares of 100 square feet, 9,586.2.

Number linear feet woven mattresses, 5,210; squares of 100 square feet, 9,734.

Number linear feet bank revetment, 2,645; squares of 100 square feet, 2,416.22.

SURVEYS, ETC.

After completing the survey and maps of the low-water survey of October, 1882, party under Assistant Engineer Blunt made a hydrographic survey of the Choctaw from A. Caulk's Point to A. Arkansas City, occupying them from November 16 to December 31, 1882, the party returning to Wilson's Point on the latter date.

During January, 1883, maps were made of the Choctaw Reach survey, of compass soundings at Pilcher's Point, and soundings taken from foot of Island 93 to foot of 194; pile dikes were located, and the lines of regularized river marked by flags on lines on Baleshed Bar. In February and March, soundings for comparison were taken at various parts of the reach near Duncansby and Baleshed Bars and Mayersville. Maps of which were made and are on record. Caving banks were resurveyed, showing changes; new levees located from Duncansby to Homochitto, at Elleslie, and at St. Louis and a general preparation made in office and field for a high-water survey. A variety of map work was done. In April and May a high-water survey was made from Pilcher's Point to Range 100; contour and section maps made. Sections for comparison were sounded in the Duncansby and Baleshed chutes, and similar work done in June, and August.

Assistant W. T. Blunt resigned May 15, and was succeeded by Assistant Hart V. who took charge May 17. In September a complete low-water survey was made from Range 14 to Range 107, shore lines and bars resurveyed, and water surfaces determined for slope in various parts of the reach.

The survey was concluded in October, and maps made of same, and also in reduced scale for annual reports. This survey shows Duncansby, Mayersville, Baleshed, Stack Island chutes closed at low water, and a channel of not less than 10 feet on the Lake Providence gauge through the reach from Ashton to Point Lookout.

The lowest gauge reading for the year was 4.45 (L. P. gauge), October 5, so that during the period of lowest water during this year there was a channel of not less than 10 feet in that part of the river covered by the survey. The maps accompanying this report show all dike and mat work constructed since the beginning of the work.

October 31; also the sand-bars appearing at the time of the September survey, same bars as they would have appeared in December, 1881, before the construction commenced, had the river been at the same stage the September, 1883, sur-nade. The Louisiana shore line at Pilcher's Point has caved back 200 yards -water survey of 1882. The maps of comparative sections were taken from f February, 1882, and September, 1883, and show nearly the total change in el since the beginning of dike construction, as but little was done previous to , 1882. Regular ten-day-progress sketches of construction work were furnished y 1, except while the party was engaged on the Choctaw Reach. Since that have been made once a month. All soundings were located either by transit : in regular surveys; shore lines and bars, by stadia lines checking upon trian-stations. In September gauges reading the same as the Lake Providence gauge at Lake Providence and Baleshed dikes, Wilson's Point, and Sarah's Island, to slope. Of these, the ones at Baleshed, Lake Providence, and Wilson's Point read twice daily; a gauge has been maintained at the quarter-boat the entire ings being taken at 7 a. m. and 6 p. m.

	Feet.
auge reading October 5, 1883.....	4. 45
auge reading July 6, 1883.....	35. 30
a of river	30. 85

Summary of work done by the survey party.

	Choctaw Reach.	Lake Provi-dence Reach.	Totals.
urveys	1	2	3
'soundings	2, 088	13, 235	15, 273
ated.....	73		73
located.....miles...	25	25	50
rations.....	10	16	26
stations built.....	86	17	53
stations located.....	30	12	42
veys.....		13	13
al soundings.....		148	148
.....miles...		25	25
.....			57
.....			47

arty was under the charge of Assistant Engineer W. T. Blunt until May 13, from that time until November 1, under that of Assistant Engineer Hart The above report of the work done, and the tracings accompanying this report, furnished by Assistant Engineer E. D. Thompson, who is at present in charge rty.

Plant, &c.

lowing is a list of boats and barges, &c., on reach November 1, 1883: 19 quar-; 1 boat used as machine and repair shop; 1 tow-boat (Vidalia); 3 tow-boats d); 1 steam-launch (Nellie); 1 snag-boat (O. G. Wagner); 2 hydraulic graders; -boat; 9 large mattress-boats; 4 small mattress-boats; 21 pile-drivers; 5 coal-ecked); 46 decked barges (brush and stone); 1 catamaran; 9 coal-barges (open); at; 10 small flats for pile-driving; 60 skiffs; 195 pieces in all. these quarter-boats were built here on the hulls of coal-barges, one coal-barge nd one cut down to serve as a mooring-barge. The rakes and sides of 35 barges e-drivers have been caulked, changes and repairs made to pile-drivers, and the pairs incident to so large amount of floating property, kept up. The plant is in good condition except some of the coal-boats, which are worthless. The f some of the barges will need caulking next season. erage cost of subsisting the employés for each days' labor secured, has been a, including cost of ice during the warm months. The number of days' service each month has been as follows:

r, 1882	14, 077	April, 1883.....	8, 565	August, 1883.....	14, 547
1883.....	19, 008	May, 1883.....	9, 721	September, 1883 ...	12, 234
, 1883.....	10, 826	June, 1883.....	13, 017	October, 1883.....	14, 841
883.....	6, 785	July, 1883.....	13, 296		

The first of these is the fact that the... the second is the fact that the... the third is the fact that the... the fourth is the fact that the... the fifth is the fact that the... the sixth is the fact that the... the seventh is the fact that the... the eighth is the fact that the... the ninth is the fact that the... the tenth is the fact that the...

JOHN SMITH
Department of Anthropology

Dr. J. Smith
123 Main Street

THE JOURNAL OF THE ROYAL ANTHROPOLOGICAL INSTITUTE

The first of these is the fact that the... the second is the fact that the... the third is the fact that the... the fourth is the fact that the... the fifth is the fact that the... the sixth is the fact that the... the seventh is the fact that the... the eighth is the fact that the... the ninth is the fact that the... the tenth is the fact that the... the eleventh is the fact that the... the twelfth is the fact that the... the thirteenth is the fact that the... the fourteenth is the fact that the... the fifteenth is the fact that the... the sixteenth is the fact that the... the seventeenth is the fact that the... the eighteenth is the fact that the... the nineteenth is the fact that the... the twentieth is the fact that the... the twenty-first is the fact that the... the twenty-second is the fact that the... the twenty-third is the fact that the... the twenty-fourth is the fact that the... the twenty-fifth is the fact that the... the twenty-sixth is the fact that the... the twenty-seventh is the fact that the... the twenty-eighth is the fact that the... the twenty-ninth is the fact that the... the thirtieth is the fact that the... the thirty-first is the fact that the... the thirty-second is the fact that the... the thirty-third is the fact that the... the thirty-fourth is the fact that the... the thirty-fifth is the fact that the... the thirty-sixth is the fact that the... the thirty-seventh is the fact that the... the thirty-eighth is the fact that the... the thirty-ninth is the fact that the... the fortieth is the fact that the... the forty-first is the fact that the... the forty-second is the fact that the... the forty-third is the fact that the... the forty-fourth is the fact that the... the forty-fifth is the fact that the... the forty-sixth is the fact that the... the forty-seventh is the fact that the... the forty-eighth is the fact that the... the forty-ninth is the fact that the... the fiftieth is the fact that the... the fifty-first is the fact that the... the fifty-second is the fact that the... the fifty-third is the fact that the... the fifty-fourth is the fact that the... the fifty-fifth is the fact that the... the fifty-sixth is the fact that the... the fifty-seventh is the fact that the... the fifty-eighth is the fact that the... the fifty-ninth is the fact that the... the sixtieth is the fact that the... the sixty-first is the fact that the... the sixty-second is the fact that the... the sixty-third is the fact that the... the sixty-fourth is the fact that the... the sixty-fifth is the fact that the... the sixty-sixth is the fact that the... the sixty-seventh is the fact that the... the sixty-eighth is the fact that the... the sixty-ninth is the fact that the... the seventieth is the fact that the... the seventy-first is the fact that the... the seventy-second is the fact that the... the seventy-third is the fact that the... the seventy-fourth is the fact that the... the seventy-fifth is the fact that the... the seventy-sixth is the fact that the... the seventy-seventh is the fact that the... the seventy-eighth is the fact that the... the seventy-ninth is the fact that the... the eightieth is the fact that the... the eighty-first is the fact that the... the eighty-second is the fact that the... the eighty-third is the fact that the... the eighty-fourth is the fact that the... the eighty-fifth is the fact that the... the eighty-sixth is the fact that the... the eighty-seventh is the fact that the... the eighty-eighth is the fact that the... the eighty-ninth is the fact that the... the ninetieth is the fact that the... the ninety-first is the fact that the... the ninety-second is the fact that the... the ninety-third is the fact that the... the ninety-fourth is the fact that the... the ninety-fifth is the fact that the... the ninety-sixth is the fact that the... the ninety-seventh is the fact that the... the ninety-eighth is the fact that the... the ninety-ninth is the fact that the... the hundredth is the fact that the...

force of thirty-one laborers; which force was increased as much as could be done to any detriment to the construction of mattress.

Brush party is at present making good progress, and, with the addition of the team ordered, will supply the three mattress-boats at this place. The shortest haul brush is one mile, and I think there can be secured from Sarah's Island 8,000 choice brush.

DESCRIPTION OF WORK.

Mattresses are constructed in the usual way, upon ways built on mattress-barges, as being made when the ways are full, by means of lines and captains; the materials being poles, longitudinal and transverse, willow brush, spikes, wire, and which run longitudinally through the mattress. These rods are fastened to by means of lap links, and fastened to the weaving-poles by means of staples; at hundred feet they are fastened to the mat by wire, the connection of the rods being as follows:

Brush is hauled by mules, on cars properly adapted for the purpose. These cars are foot gangs, and run on a track made of wooden rails, iron rails being employed where necessary.

October 16, the first mat at this place was successfully sunk, and two others completed; one at the head of caving bank, the other overlapping the one sunk. The location of these mats is shown on tracings accompanying this report. At this date there are under construction two mattresses, one 150 feet in width, the other 182 feet in width. The first is making good progress, and is being pushed as rapidly as possible. The second of mat made now per day is nearly double that made ten days ago, without any increase in the force employed. This is due to the fact that when laborers come here they are entirely new to them.

There is in readiness a third mattress barge, which will be put in use as soon as the quantity of brush can be increased. One of the mattress boats is supplied with poles by labor; the other is furnished by a contractor.

Mattress head employed and intended to be used instead of a mooring-barge. As a perfect success, a drawing of this mattress head is submitted with this report. The mattress head consists of two chords, 20 feet apart, with a series of cross and diagonal bracing, and a hog chain, as shown in drawing.

Up-stream chord is 12 inches in width by 30 inches in depth; the lower one 12 inches in width by 19 inches in depth. These chords are one hundred and sixty-three feet long, and have a camber of 6 inches; they are constructed of pine plank. During construction of the mattress it is by lines anchored to the mattress head. During sinking the mattress head is sunk with the mat, and by means of a lever and trips the mattress head is released from the mat and again used. The method employed in sinking and releasing the mattress head is as follows: The mat to which it was attached is 122 feet in length by 152 feet in width. The sinking of the mat was commenced at the center and the mat loaded with stone both ways; in this way the entire mat was turned over and sunk to a depth varying from 10 feet to 35 feet.

The barges were then lashed together side by side, and about 8 feet apart, and placed 150 feet from mattress head, and this portion of the mat loaded for the second time.

These barges were by means of lines pulled up stream and toward the mattress head, the stone being thrown from each barge on the up and down stream sides. This caused the mattress head to sink rapidly. Previous to this second loading of the mattress, the depth of water at outer end of mattress head was carefully taken, and a line was made fast to lower chord of mattress head and held by a man on the bank, the object of this was to know how rapidly the mattress head was sinking. When it had sunk to $\frac{3}{4}$ of the entire depth, ten men who were ready to haul on a line attached to ring at upper end of lever were ordered to pull. The mattress head was released, and the head of the mat being relieved of its buoyancy sank rapidly to bottom.

Wreck-boat Wagner reported for duty on September 21, and has been employed in clearing wreckage from this bend, she was employed 7 days pulling piles from dike at head of Lewisby chute, and has lost 54 days in making repairs.

Boat Pearl reported for duty September 23, and has, with the exception of a few days, been constantly employed.

SUMMARY OF WORK DONE.

One and sleeping-room, 36 by 23 feet; 1 kitchen and dining-room, 30 by 24 feet; 1 laundry, 36 by 30 feet; 1 warehouse, 32 by 30 feet; 1 stable, 20 by 15 feet; 1 pump, 14 by 16 feet; 1 mattress head.
and on 3 quarter-boats.

2844 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Roofs of 4 quarter-boats painted.

Mattress constructed: 928 by 152 feet, 300 by 235 feet, 610 by 150 feet, 585 by 150 feet.

Mattress sunk: 928 by 152 feet, 300 by 235 feet.

Scows pulled: 154; piles pulled, 122; cords of brush cut, 2,059; cords of brush laid and landed on barges, 1,109; cords of poles cut, 94.

Feet of track laid, 3,324; feet of track corduroyed, 1,872.

Timber has been cleared from the bank below Pilcher's Point for a distance of 500 feet and 400 feet in width, and above Pilcher's Point for a distance of 1,480 by 100 feet in width.

Respectfully submitted.

J. E. TUTTLE,
U. S. Asst. Engineer.

Capt. L. W. S. MARSHALL,
Corps of Engineers, U. S. A.

L 3.

REPORT OF H. ST. L. COPPÉE, ASSISTANT ENGINEER, UPON IMPROVEMENT OF VICKSBURG HARBOR.

OCTOBER 21, 1883.

CAPTAIN: I have the honor to submit herewith a report on the improvement of Vicksburg Harbor, dating from December 1, 1882, to October 10, 1883, accompanied by maps, profiles, tables &c.

Very respectfully, yours,

H. ST. L. COPPÉE,
Assistant Engineer.

Capt. W. L. MARSHALL,
Corps of Engineers, U. S. A.

REPORT ON IMPROVEMENT OF VICKSBURG HARBOR, FROM DECEMBER 1, 1882, TO OCTOBER 10, 1883.

I have divided the following report, in accordance with the progress of the work, into five parts, viz: The protection of Delta Point, La.; dredging in Vicksburg Harbor; profile survey of harbor and Mississippi River in the vicinity; results obtained by comparison of surveys from 1877 to 1883; and tables.

The protection of Delta Point, with a view to stopping the caving of its banks and keeping the channel of the river as near its old bed as possible, was commenced in 1877 and carried on in succeeding years up to the season of 1882, under the direction of Major W. H. H. BENYARD. During this time a spur-dike was constructed with brush and stone, two screen-dikes built and anchored in the current, and 144 mattresses sunk as shown on maps. The last mattress sunk in 1881, occupying a position just below the spur-dike. In October, 1882, I commenced the further revetment of the point, under your directions. In compliance with an order received from you November 24, 1882, I forwarded to your office a report, accompanied by maps, giving the positions and extent of the work accomplished at Delta, up to December 1 of that year; also a description of the methods adopted and under way, for protecting the banks against the action of the current. These methods were not changed, but the work carried on in the same manner to its completion, with the one exception, that the plan of driving piles through the upper edge of the mattress was abandoned, so that no obstructions would be offered to the sinking of mats on the upper graded bank during high water, in place of revetment, which would be impossible to build.

December 1, 1882, the condition of the work was as follows:

Grade of upper bank, finished to a slope of about 2½ to 1.....	linear feet..	1,400
Grade partly finished.....	do.....	200
Poles or frame-work on upper bank.....	do.....	200
Upper bank revetted with brush.....	do.....	200
Upper bank revetted with brush and covered with stone.....	square yards..	2,000
Foot-mats built, 35 feet wide.....	linear feet..	400
Foot-mats built and sunk, 35 feet wide.....	do.....	1,000
Mattresses constructed, 144 feet wide.....	do.....	1,200
Mattresses constructed and sunk, 144 feet wide.....	do.....	800
Piles driven through edge of mattresses.....	do.....	0

e the water was standing at 13.7 feet on the gauge, and all other conditions pushing the work. About 440 men were employed; 90 at the brush camps, : camp, 322 constructing mattresses, revetting the upper bank, grading with and 18 on the hydraulic grader. This force was as great as we could pose-work, with the plant in use. The work was carried on, the force employed approximating the above number, until February 10, 1883, when, owing to the water and lack of funds, it was abandoned. January 5, 1883, the hydraulic having cut the banks to the required slope as far down the river as it would , mattress during the season, returned to Wilson's Point, having during its from November 7 to January 5, graded 3,500 linear feet of bank. During the ember it moved 38,790 cubic yards of earth. Operations during the month of e carried on with much difficulty, owing to the high stage of water, swift onstant annoyance occasioned by the drift in the river; at one time the pres- latter on our mattress barge, was so great as to break the lines connecting oating mattress, and carry it down the river nearly a mile. The mattresses k with trouble, the drift having accumulated under them to such an extent onstruction. During the progress of the work, i. e., from October 10, 1882— 10, 1883—no portion of the mattresses, foot-mats, or bank revetment was lost. omplished during this time was as follows:

constructed and sunk:			
No. 1.....	feet..	130	184
No. 2.....	do...	140	365
No. 3.....	do...	144	358
No. 4.....	do...	144	280
No. 5.....	do...	144	87
No. 6.....	do...	144	300
No. 7.....	do...	144	285
No. 8.....	do...	144	400
No. 9.....	do...	144	460
No. 10.....	do...	144	408
No. 11.....	do...	136	475
No. 12.....	do...	144	80
No. 13.....	do...	80	745
No. 14.....	do...	140	45
No. 15.....	do...	140	40
No. 16.....	do...	150	40

constructed and sunk, about 35 feet wide.....		linear feet..	830
d and covered with stone.....		do.....	3, 500
-----			96
, grader No. 1, 3,500 feet }-----		linear feet..	4,500
, shovels, 1,000 feet }			
work:			
l, but not stoned		feet..	400×25
same work finished.....		do.....	112 18

m and extent of the work is shown in plan, as on accompanying plate. The ting the bank at Delta—i. e., the cost for labor and materials, not including es, purchasing tools, rope, general outfit, towing, superintendence, assist- &c.—was as follows:

Cost of constructing and sinking 100 feet of mattress 144 feet wide.

da, at \$2.53.....	\$151	80
t 32 cents.....	53	12
170 pounds, at 5 cents.....	8	50
h, 50 pounds, at 5 cents.....	2	50
0 pounds, at 4 cents.....	1	20
ic yards, at \$1.90.....	114	00
y, at \$1.65 (including subsistence).....	82	50
i \$2.15 (including subsistence).....	2	15
rer, \$1.90 (including subsistence).....	1	90
		417 60
or foot of mats.....	4 17	

abandonment on account of low water the dredge worked twenty-four hours each day, with the exception of Sundays, which were used for repairs to machinery. Two sectors were employed by the Government to measure the amount of material excavated and placed in scows, each inspector remaining on the dredge twelve hours, thus dividing the day into two watches, as was also done by the crew employed by the contractor. Two scows were used to convey the material excavated to the point designated by the inspector. The capacity of the scows were respectively 116 and 366 cubic yards. The material was dumped in the low ground in the willow ridge opposite the compressor (shown on map), the haul or tow being about one mile, round trip, from the center of the basin. At first it was impossible to dredge to the desired plane (zero), as the pole or bucket-poles were not of a sufficient length to allow of the bucket reaching that depth, thus making it necessary to go over a portion of the proposed basin twice. It will be noticed by a glance at the gauge table that during the early stages of the work, for two months, the water was above the forty-foot mark; the dredging was necessarily slower and performed with greater difficulty than afterwards, when the river fell to a lower level. During the progress of the work there were numerous break-downs and delays, in many instances caused by bad management on the part of those representing the contractor. At times the force employed on the dredge was not sufficient to do the work properly. There were also some delays caused by the careless handling of boats that frequented the harbor, running over the guide stakes, lights, &c. This, however, was soon remedied by cautioning the pilots, it being to their interest to help rather than retard the work. The dredging was at first confined to the basin, the material being taken out in cuts 40 feet wide, but not to the zero, as stated above, because of the shortness of the bucket-poles. Six parallel cuts were taken out the entire length of the basin, commencing at the western edge and working eastward to a plane about 5 feet above zero, thence, May 26, the dredge was moved to its eastern edge, and the water being recently low commenced excavating to the zero. Four cuts were made working westward with the exception of a small ridge in front of and close to the elevator, which it was impossible to dig with the bucket in use. As the contractor claimed that this material was rock, I had borings made and found it to be as I anticipated, simply a hard, compact deposit.

The contractor was requested to send me a bucket capable of removing this, but did not comply with the request. July 18 the condition of the work was as follows (all the operations having been confined to the basin):

Four cuts or 160 feet from western edge excavated to + 5 feet. Four cuts or 160 feet from eastern edge excavated to zero, leaving 160 feet to be re-dredged in order to finish the basin to the required depth. There was practically no more work done in the basin. The water at this time (July 18) had fallen to 38 feet on the gauge and was going down rapidly, you thought it expedient before finishing the basin to make a couple of cuts (a 40 feet wide to zero) to deep water in the lake, in order, if possible to prevent the necessity of moving the wharf boat and general river business to the lower landing. The dredge was therefore placed in the temporary canal, and worked there until August 2, when you ordered her moved to the southwest entrance to the lake. The lower entrance to the landing was at that time closed, and the upper or southwestern shoaling rapidly. The temporary canal was then in the following condition: One cut 40 feet by 100 feet excavated to zero, and a portion of a second 1,000 feet to the same plane. August 3, dredging commenced at a point on King's Bar, marked on the map West Pass, a twelve feet of water (the gauge reading 31.5 feet) and carried on up to the 24th. The material to be moved was of such a consistency (compact sand) that the soft-bottom bucket had to be abandoned, and one shipped by the contractor from Mobile used in its place. This worked to much better advantage, but was not a success. Numerous experiments were resorted to, but the plan of making a passage through the bar had finally to be abandoned and the dredge towed back to the second cut in the temporary canal. The accompanying map and profiles show the position and dimensions of the excavation at West Pass, its present condition is not all due to the dredging, but in great part to the scouring force of the current running from the lake into the river at that point. The probability is that a rising river will fill this up again in a short time. From August 24 until September 18 the dredger worked in the temporary canal. At the latter date the gauge-reading was 7.4 feet, the dredge drawing 7.5 feet. As your orders were not to excavate below the zero plane, it was impossible to continue until the water should rise. The dredge was therefore removed to deep water in the lake, and as it continued to fall steadily, has remained there to date. Should the contractor remove his outfit, the time for finishing the contract (Sept. 30) having been impossible, all access to the main river being closed. During the work, a record of the material dredged was kept, giving the excavation watch, day, &c., the causes of delay, and general log.

I give the amount of material excavated each month, that taken from

basin, temporary canal, and West Pass, and totals. The total amount, 350,035 cubic yards at 12.1 cents, \$42,354.23, minus 10 per cent., \$38,118.81, has been paid the contractor in monthly estimates. The condition of that portion of the lake where the excavation was made at the present time, to which I will refer in the results obtained by comparison of surveys, will show a decided filling or sliding in from the sides, giving a very poor idea of the amount of material originally dredged. There was also a deposit taking place during the entire time of dredging, as shown on the profiles, Plates XII and XIII.

SURVEY.

Early in September, in accordance with instructions to make a thorough survey of the harbor and Mississippi River in the vicinity, for the purpose of comparing the data then obtained with the surveys of previous years, with a view to ascertaining the probable additional cost of dredging, should it be deemed expedient, and noting the changes that had taken place in the main river. I put a party into the field and obtained all the desired information by the 10th instant. The work in the inner harbor was pursued with some difficulty, being not only expensive but dangerous, the mud-bar in front of the city being in such a condition as to necessitate the laying of plank in order to obtain the elevation of the ground sounded the year before. The laborers employed in placing the plank ways were numerous times immersed up to their armpits, and but for the boards to which they clung would have disappeared entirely. This extremely soft deposit extended the entire length of the proposed permanent canal and basin, with the exception of a small strip of bar at section No. 1; the ground there, being much higher, was hardened by the sun, but one foot below the surface was very soft, as I ascertained by attempting to drive my horse over it.

The survey consisted in remeasuring and either leveling over or sounding the sections sounded in 1881 and 1882 in the inner harbor, twenty-three in number, running a line of levels from Ryan's lower saw-mill to a point on King's Bar opposite the Delta wharf-boat, obtaining the low-water line of King's Bar, the middle-ground bar, the bar above Delta, and the bar just below the revetted portion of the Delta Point bank, sounding twelve sections in the upper lake and fifteen sections in the main river. A meander line was run up to King's Point. Levels were also carried from the gauge at Kleinston to the gauge in the lake, the difference in elevation of the water in the river and lake obtained, cross-sections made of West Pass, and cross-sections of the excavated basin obtained every 100 feet, giving the slopes the sides had assumed. Posts were planted at the end of each section in the inner harbor for future use. The soundings were made in every instance as nearly as possible on sections used in previous years, in order to better compare results. The levels and soundings are referred to the zero of the gauge at Kleinston, no deduction being made in the case of soundings in the main river for slope, but simply referring them to the datum by subtracting the reading of the gauge at the time of sounding from the depth obtained.

RESULTS.

The results of this survey, and those made in the past, I have collected and arranged in the form of tables, which will explain themselves, leaving but little to be added. The data from which the changes during 1877, 1878, 1879, and 1880 were obtained were very meager, and in most instances but approximate; but will serve to show the general conditions which existed during those years, and the change which has taken place in the inner harbor since the time of the cut-off in 1876; a gradual filling has taken place which will continue until the lake is free from all access to the muddy water of the river unless some means are adopted to cut off the current that flows around De Soto Island during high water. This current has existed since 1877 to a greater or less extent, having a velocity in that year of nearly one-fourth mile per hour. In 1882 it was hardly perceptible, float observations made in July of that year showing practically no velocity, but during the last high water it traveled from Ryan's mill to the compress at the mouth of one-half mile per hour, gradually becoming slower as it reached the northern end of the island. This has caused a more rapid filling of the area than has taken place in years.

Glass Bayou, which enters the lake at the northern boundary of the city, has also been the cause of considerable filling, bringing during every heavy rain a great quantity of mud from the adjacent hills. The changes that have taken place in the main river during the last high water, as shown on the accompanying map, are to a great extent a repetition of what occurred the year before. The bar above Delta has moved down stream 600 feet; some caving has taken place at King's Point. The King's Point Bar has been split, the sand taken from its former crest being deposited in the form of a middle ground, outside of its old position and extending

...the upper entrance to the lake, and ...landing. The bank has caved to some ...a strong eddy current there, the water ...ston front. The bar below the revetted ...upper end 100 feet, and 1,000 feet below, ...of the revetment at Delta Point and found ...in 1879, has been swept away, carrying ...also at a point (marked on drawing of Delta ...placed, there has been some caving. To ...lake, and at this mud flat, to insure the perma- ...it be necessary to put down 500 linear feet of ...harbor are shown on the profiles, and in tables

ESTIMATES FOR DREDGING.

15 foot plane, canal, 250 by 4,800; basin,	\$80,000 00
boards, at 15 cents	335,333 25
to 1, canal and basin same as in second	
boards, at 15 c	347,279 25
canal and basin in map, including tempo-	
slopes 5 to	390,980 36
in SCOWS	
slopes 8 to	
permanent	
632.7 cubic yd	795,822 65
basin during the	244,456 cubic yards, at 12 $\frac{1}{2}$
spent in order to the	29,579 07
all during the progress	
the harbor be as great	766,243 68
increased over \$300,000	
slopes assumed by the	
using the next high water, this estimate	
making the total cost, approximately,	
ed portion of the lake are shown on the	

TABLE No. 1.

Date.	Gauge.	Date.	Gauge.	Date.	Gauge.	Date.	Gauge.
1882.		1882.		1882.		1882.	
Jan. 1	11.90	Feb. 1	24.70	Mar. 4	42.70	Apr. 4	43.90
Jan. 2	12.80	Feb. 2	26.80	Mar. 5	42.80	Apr. 5	43.80
Jan. 3	13.75	Feb. 3	28.80	Mar. 6	42.90	Apr. 6	43.70
Jan. 4	14.70	Feb. 4	29.80	Mar. 7	43.05	Apr. 7	43.95
Jan. 5	15.60	Feb. 5	30.70	Mar. 8	43.10	Apr. 8	43.85
Jan. 6	16.40	Feb. 6	31.40	Mar. 9	43.10	Apr. 9	43.80
Jan. 7	17.00	Feb. 7	31.90	Mar. 10	43.15	Apr. 10	43.75
Jan. 8	17.30	Feb. 8	32.10	Mar. 11	43.20	Apr. 11	43.70
Jan. 9	17.30	Feb. 9	32.40	Mar. 12	43.20	Apr. 12	43.60
Jan. 10	17.50	Feb. 10	32.70	Mar. 13	43.25	Apr. 13	43.60
Jan. 11	17.55	Feb. 11	32.90	Mar. 14	43.25	Apr. 14	43.60
Jan. 12	17.40	Feb. 12	33.45	Mar. 15	43.30	Apr. 15	43.55
Jan. 13	17.30	Feb. 13	34.10	Mar. 16	43.35	Apr. 16	43.55
Jan. 14	17.50	Feb. 14	34.90	Mar. 17	43.20	Apr. 17	43.50
Jan. 15	17.30	Feb. 15	35.80	Mar. 18	43.20	Apr. 18	43.30
Jan. 16	16.80	Feb. 16	36.70	Mar. 19	43.20	Apr. 19	43.20
Jan. 17	16.40	Feb. 17	37.70	Mar. 20	43.15	Apr. 20	43.10
Jan. 18	16.10	Feb. 18	38.40	Mar. 21	43.05	Apr. 21	43.00
Jan. 19	16.00	Feb. 19	38.95	Mar. 22	43.00	Apr. 22	43.00
Jan. 20	15.90	Feb. 20	39.60	Mar. 23	42.95	Apr. 23	42.11
Jan. 21	15.90	Feb. 21	40.35	Mar. 24	42.80	Apr. 24	42.10
Jan. 22	15.90	Feb. 22	40.60	Mar. 25	42.85	Apr. 25	42.80
Jan. 23	15.80	Feb. 23	41.05	Mar. 26	42.80	Apr. 26	42.80
Jan. 24	15.00	Feb. 24	41.55	Mar. 27	42.70	Apr. 27	42.70
Jan. 25	14.80	Feb. 25	41.85	Mar. 28	42.80	Apr. 28	42.60
			42.05	Mar. 29	43.00	Apr. 29	42.50
			42.20	Mar. 30	43.30	Apr. 30	42.40
			42.25	Mar. 31	43.60	May 1	42.30
			42.35	Apr. 1	43.80	May 2	42.20
			42.55	Apr. 2	43.90	May 3	42.10
			42.65	Apr. 3	43.90	May 4	42.00

TABLE No. 1—Continued.

Date.	Gauge.	Date.	Gauge.	Date.	Gauge.	Date.	Gauge.	Date.	Gauge.
1882.		1882.		1882.		1882.		1882.	
May 5.	41.11	June 6.	38.50	July 3.	38.70	Aug. 9.	22.10	Sept. 10.	22.10
May 6.	41.11	June 7.	38.10	July 9.	38.70	Aug. 10.	22.00	Sept. 11.	22.00
May 7.	41.10	June 8.	38.00	July 10.	38.70	Aug. 11.	22.10	Sept. 12.	22.10
May 8.	41.00	June 9.	38.00	July 11.	38.70	Aug. 12.	22.30	Sept. 13.	22.30
May 9.	41.00	June 10.	38.10	July 12.	38.70	Aug. 13.	22.10	Sept. 14.	22.10
May 10.	41.00	June 11.	38.10	July 13.	38.00	Aug. 14.	22.00	Sept. 15.	22.00
May 11.	41.00	June 12.	38.10	July 14.	38.00	Aug. 15.	22.10	Sept. 16.	22.10
May 12.	41.00	June 13.	38.10	July 15.	38.20	Aug. 16.	22.10	Sept. 17.	22.10
May 13.	41.70	June 14.	38.10	July 16.	38.10	Aug. 17.	22.40	Sept. 18.	22.40
May 14.	41.00	June 15.	38.00	July 17.	38.00	Aug. 18.	21.11	Sept. 19.	21.11
May 15.	41.50	June 16.	38.00	July 18.	37.10	Aug. 19.	21.40	Sept. 20.	21.40
May 16.	41.30	June 17.	38.10	July 19.	37.10	Aug. 20.	20.10	Sept. 21.	20.10
May 17.	41.10	June 18.	38.10	July 20.	37.40	Aug. 21.	20.20	Sept. 22.	20.20
May 18.	40.10	June 19.	38.20	July 21.	37.40	Aug. 22.	19.40	Sept. 23.	19.40
May 19.	40.10	June 20.	38.00	July 22.	36.70	Aug. 23.	19.20	Sept. 24.	19.20
May 20.	40.10	June 21.	38.50	July 23.	34.10	Aug. 24.	18.00	Sept. 25.	18.00
May 21.	39.70	June 22.	38.50	July 24.	34.40	Aug. 25.	18.00	Sept. 26.	18.00
May 22.	39.00	June 23.	38.00	July 25.	34.30	Aug. 26.	17.40	Sept. 27.	17.40
May 23.	39.50	June 24.	38.00	July 26.	34.10	Aug. 27.	16.10	Sept. 28.	16.10
May 24.	37.11	June 25.	38.00	July 27.	34.00	Aug. 28.	16.00	Sept. 29.	16.00
May 25.	37.70	June 26.	38.00	July 28.	33.11	Aug. 29.	15.50	Sept. 30.	15.50
May 26.	37.70	June 27.	38.00	July 29.	33.00	Aug. 30.	14.30	Oct. 1.	14.30
May 27.	37.00	June 28.	38.70	July 30.	32.00	Aug. 31.	14.20	Oct. 2.	14.20
May 28.	37.11	June 29.	38.70	July 31.	31.50	Sept. 1.	12.80	Oct. 3.	12.80
May 29.	36.00	June 30.	38.70	Aug. 1.	30.20	Sept. 2.	13.20	Oct. 4.	13.20
May 30.	36.20	July 1.	38.00	Aug. 2.	29.00	Sept. 3.	12.10	Oct. 5.	12.10
May 31.	36.40	July 2.	38.00	Aug. 3.	27.00	Sept. 4.	12.40	Oct. 6.	12.40
June 1.	36.00	July 3.	38.00	Aug. 4.	26.30	Sept. 5.	11.11	Oct. 7.	11.11
June 2.	36.00	July 4.	38.00	Aug. 5.	25.00	Sept. 6.	Oct. 8.
June 3.	36.70	July 5.	38.00	Aug. 6.	24.00	Sept. 7.	Oct. 9.
June 4.	36.70	July 6.	38.70	Aug. 7.	22.70	Sept. 8.	14.20	Oct. 10.	14.20
June 5.	36.00	July 7.	38.70	Aug. 8.	22.00	Sept. 9.	9.70		

TABLE No. 2.—Showing fill every 100 feet on King's Bar (or section 1 continued) / 1882 to 1883.

Distance.	Fill.	Distance.	Fill.	Distance.	Fill.
Feet.	Feet.	Feet.	Feet.	Feet.	Feet.
100	12.0	1,000	9.4	1,900	12.5
200	12.0	1,100	9.4	2,000	14.0
300	14.0	1,200	9.5	2,100	12.8
400	17.0	1,300	9.2	2,200	12.8
500	18.8	1,400	9.1	2,300	9.6
600	18.6	1,500	9.5	2,400	10.2
700	16.6	1,600	11.6	2,500	8.4
800	14.0	1,700	14.2	2,600	6.4
900	12.0	1,800	17.6	2,700	6.4

* Middle of canal.

† Middle of west pass.

TABLE No. 3.—The maximum fill, in inner harbor, within the limits of canal, from 18 1883, omitting sections sounded in 1880, which are not accurate enough for comparison

Sections.	Fill, in feet.				
	1877 to 1878.	1878 to 1879.	1879 to 1881.	1881 to 1882.	1882 to 1883.
No. 4.....	20	12	12	6	6
No. 13.....	13	12	Approx. 0	4	0
No. 14.....	17	7	Approx. 0	2	0
No. 15.....	13	10	Approx. 0	1	10
No. 16.....	16	6	Approx. 0	Approx. 1	10
No. 17.....	6	5	Approx. 0	Approx. 1	0
No. 24.....	23	13	1879 to 1883. 16	Approx. 0	Approx. 5

No. 4.—Fill in inner harbor within the limits of the slopes of canal and basin from 1881 to 1892 (see profiles). In the fractions, the numerator denotes the distance measured from the shore edge of the slope, the denominator, the fill at that distance.

Section.	Fill in feet.															
	0	45	75	95	100	105	175	195	245	295	300					
	0	8.3	8.8	8.7	11.0	10.6	10.4	8.2	8.8	08	0.0					
	0	50	100	150	200	250	300	350	370	400	410	430	450	500	550	580
	0	8.8	8.4	8.0	10.0	8.6	8.0	5.2	7.2	10.4	11.0	11.2	11.8	7.9	8.0	0.6
	0	25	75	125	175	225	275	325	375	425	4.75	535				
	0	1.4	2.6	4.5	8.9	6.8	8.6	9.1	10.0	7.0	6.0	8				
	0	10	60	110	160	210	260	310	360	410	460	510	560	580	587	
	0	1.2	2.5	3.4	8.2	6.0	6.0	5.9	5.0	5.2	6.0	5.8	6.0	8.0	8	
	0	30	50	80	100	150	200	300	350	400	450	500	550	580		
	0	2.4	1.4	1.1	3.8	6.4	5.0	4.0	6.6	4.4	5.2	5.8	5.0	0		
	0	50	100	150	200	250	300	350	400	450	500	550	570	600	605	
	0	0.8	1.0	1.1	1.8	2.0	2.6	2.8	2.8	3.8	3.8	3.8	3.8	0.4	0	
	0	15	30	50	100	1.50	2.30	260	330	360	430	480	530	550	580	
	0	4.5	2.5	1.2	0.4	1.0	1.4	2.0	3.4	2.4	2.4	2.6	2.2	2.0	0	
	0	8	50	50	80	85	120	180	230	280	300	330	360	430	455	475
	0	2.8	2.4	2.0	2.4	2.6	2.4	1.8	2.8	2.8	2.6	2.2	2.6	2.4	2.6	8
	0	10	50	80	120	180	230	280	330	380	430	480	495	530		
	0	4.8	2.2	3.6	4.2	4.0	4.0	4.0	4.2	4.4	3.6	3.8	4.0	8		
	0	10	60	110	160	185	210	260	310	360	410	460	510			
	0	1.0	1.0	1.0	1.0	0.8	1.8	2.4	4.0	4.1	4.4	5.0	0			
	0	10	60	110	160	210	260	310	360	410	450	480	475			
	0	1.0	2.2	2.0	4.6	3.2	2.6	2.0	2.4	3.0	3.2	1.6	0			
	0	10	60	110	160	210	260	310	360	410	445					
	0	0.8	0.6	0.8	1.2	2.8	4.0	2.4	3.4	3.6	0					
	0	15	65	85	115	105	215	265	315	415	442	465				
	0	3.2	5.0	4.0	3.4	3.0	3.2	2.8	2.6	2.8	2.8	0				
	0	10	50	75	100	150	200	250	300	350	400	450	550	600	650	700
	0	3.6	2.0	1.8	2.6	1.6	1.4	0.8	0.2	0.8	0.9	1.0	0.8	1.4	1.3	1.2
	0	50	100	150	200	250	300	350	400	450	475	480				
	0	0.4	0.6	0.4	0.0	0.1	0.6	0.1	0.4	0.6	1.0	0				

No. 5 showing mean fill and areas, calculated from above co-ordinates.

No. 5.—Mean fill and areas of fill in inner harbor within the limits of the slopes of the canal and basin from 1881 to 1892.

Section.	Mean fill.	Area.
	<i>Feet.</i>	<i>Sq. feet</i>
No. 1	2.2	1967.5
No. 2	2.0	3125.5
No. 3	5.6	3052.5
No. 4	4.0	2749.5
No. 5	2.6	2561.5
No. 6	2.0	1800.0
No. 7	1.8	1008.5
No. 8	2.1	1127.5
No. 9	3.4	3007.5
No. 10	2.1	1315.0
No. 11	2.2	1265.0
No. 12	1.8	967.0
No. 13	2.9	1494.2
No. 14	1.2	361.5
No. 15	6.2	177.5

See Table No. 4 for co-ordinates.

一、
二、
三、
四、
五、
六、
七、
八、
九、
十、
十一、
十二、
十三、
十四、
十五、
十六、
十七、
十八、
十九、
二十、
二十一、
二十二、
二十三、
二十四、
二十五、
二十六、
二十七、
二十八、
二十九、
三十、
三十一、
三十二、
三十三、
三十四、
三十五、
三十六、
三十七、
三十八、
三十九、
四十、
四十一、
四十二、
四十三、
四十四、
四十五、
四十六、
四十七、
四十八、
四十九、
五十、
五十一、
五十二、
五十三、
五十四、
五十五、
五十六、
五十七、
五十八、
五十九、
六十、
六十一、
六十二、
六十三、
六十四、
六十五、
六十六、
六十七、
六十八、
六十九、
七十、
七十一、
七十二、
七十三、
七十四、
七十五、
七十六、
七十七、
七十八、
七十九、
八十、
八十一、
八十二、
八十三、
八十四、
八十五、
八十六、
八十七、
八十八、
八十九、
九十、
九十一、
九十二、
九十三、
九十四、
九十五、
九十六、
九十七、
九十八、
九十九、
一百、

No. 7.—Estimates of canal and basin, 1883; table showing mean ordinates, areas, volumes within the limits of the slopes of canal and basin, and the lines of bottoms of canal and lake in 1883, including dredged volume.

Section.	Mean ordi- nate.	Area.	Distance between sections.	Quantities.
				<i>Cubic yards.</i>
No. 1.....	16.1	10,082.0	320	74,997.6
No. 2.....	16.0	12,056.8	361	102,815.4
No. 3.....	16.1	11,044.3	482	219,303.0
No. 4.....	17.3	12,805.0	475	205,823.8
No. 5.....	20.3	12,908.2	365	137,056.0
No. 6.....	19.7	12,465.7	372	182,090.7
No. 7.....	20.4	12,905.5	423	206,078.3
No. 8.....	17.1	11,352.0	390	148,145.6
No. 9.....	17.5	12,220.0	222	101,225.8
No. 10.....	18.0	11,503.2	540	287,152.1
No. 11.....	17.0	11,939.0	390	125,236.5
No. 12.....	16.7	10,282.0	304	119,758.6
No. 13.....	16.0	10,486.5	406	156,482.6
No. 14.....	21.2	17,100.9	430	100,357.6
No. 15.....	19.3	16,354.6	430	276,671.6
No. 16.....	18.5	16,910.6	430	262,686.8
No. 17.....	18.1	16,738.2	340	102,800.8
No. 18.....	12.1	7,610.5	650	812,294.2
No. 19.....	12.6	6,675.9	418	110,508.2
No. 20.....	11.1	5,355.4	574	127,500.2
No. 21.....	11.0	5,353.5	706	151,622.6
		0	1,316	107,907.9
Total				3,789,632.7

See Table No. 6 for co-ordinates.

2554 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

TABLE No. 5.—Showing fill in inner harbor within the limits of the slopes of canal and basin from 1332 to 1353 (see profile). In the fractions, the numerator, denotes the distance measured from the shore edge of the slope, the denominator, the fill at that distance on the limits of proposed excavation.

Section.	Ordinates and distances.																			
No. 1	1	21	33	130	135	135	200	225	230	200	200	230	250	400	450	435	500	550	600	650
	1	2	22	4	5	5	12	12	12	12	12	12	12	12	12	12	12	12	12	12
No. 2	1	30	30	130	130	130	200	250	270	200	200	230	250	475	500	505	600	650	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 3	1	25	25	125	125	125	200	225	200	200	200	230	250	415	405	515	505	605	605	605
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 4	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 5	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 6	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 7	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 8	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 9	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 10	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 11	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 12	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 13	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 14	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 15	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 16	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 17	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 18	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 19	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
No. 20	1	30	30	130	130	130	200	250	230	200	200	230	250	400	400	500	500	600	600	600
	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2

See Table No. 3 for mean ordinates, maximum ordinates, areas, distances between sections, volume.

Calbarne group of tertiary strata: Clayey green sand marl.....	Feet. 229.5 to 231.3	Clear and round; 3/16 of an inch in diameter and less.	A little in crystals.	Same species as at 1713.	
					<i>Planulina n. ampla</i> Ehr. two species. Do. <i>n. octenaria</i> Ehr. Do. <i>n. cornu</i> Ehr. <i>Cristallaria</i> , sp. undet. 2. Do. <i>n. arcuata</i> Williamson. <i>Lenticulina</i> , <i>n. discus</i> , Ehr. <i>Discorbina</i> , ten species undet. <i>Rotula</i> , two species undet. <i>Rotulina</i> , <i>n. Ehrenbergii</i> Bailey. <i>Globigerina</i> , sp. undet. Do. <i>n. helicina</i> , Carp. <i>Sphaeroidina</i> , sp. <i>Polystomella n. craticulata</i> , Carp. <i>Glandulina n. lacvigata</i> , D. orb. <i>Strophocornus</i> , sp. undet. <i>Polymorphina</i> , sp. undet. No. 1. <i>Vaginulina n. tenuis</i> , Ehr. <i>Textilaria</i> , 3 species undet. <i>Rhizopoda</i> , <i>Planophrys</i> , sp. undet. <i>Halimma</i> , <i>n. octatum</i> , Ehr. <i>Foraminifera</i> , as follows: <i>Miliola</i> , <i>n. orum</i> , Ehr. <i>Gromia</i> , sp. undet. <i>Lagena (entosolenia)</i> , <i>n. globosa</i> , W. Do. <i>n. squamosa</i> , W. Do. <i>n. marginata</i> , W. <i>Rotalina</i> , <i>n. Ehrenbergii</i> Bailey. <i>Cristallaria</i> , <i>n. arcuata</i> , W. sp. 2. Do. sp. No. 3, undet. Do. sp. No. 4, undet. <i>Globigerina</i> , sp. No. 3, undet. <i>Discorbina</i> , sp. No. 11, undet. <i>Bulimina</i> , sp. undet. None.
Do.....	231 to 231.3do.....	Crystals.....do.....	
Clay-colored calcareous rock.	231.3do.....	None.....	Fragments.....	
Dark sandy clay, with pebbles.	234 to 236.8do.....do.....	None.....	
Clay-colored sand *	236.8	Clear, sharp, and rounded, some grains spotted with carnelian.	Rare.....	Fragments very abundant.	<i>Lagena (entosolenia)</i> , <i>n. marginata</i> , W. sp. No. 2. <i>Coriispira</i> , sp. undet. <i>Trochammma gordialis</i> , Carp. <i>Spiroloculina</i> , sp. undet.

* By some mistake Mr. Wilson reports the last specimen as "limestone."

L 4.

REPORT OF H. D. GARDEN, ASSISTANT ENGINEER, UPON LEVEE WORK ON THE FRONT, THIRD DISTRICT.

UNITED STATES ENGINEER OFFICE
Vicksburg, Miss., October 8,

SIR: In compliance with your instructions of the 3d instant, to "prepare a report of levee work on the Tensas Front, for embodiment in the annual report to the Commission," I have the honor to submit the following tabulated statement with remarks on the levees under my direction in Louisiana:

TABULATED STATEMENT.

Levees, Tensas front, in Louisiana, Third District.

Names of levees.	Average height.	Length of levee.	Contents (completed).	Amount embodied yet not to cost.
		Feet.	Cubic yards.	Cubic yards.
Upper Providence	6	7,283	46,857.7
Hagaman Point	7	1,963	14,305.2
Wilton to Raleigh	12.5	23,588	343,087.7
Raleigh to Willow Point		9,648	41,287.7
Omega	9	16,310	199,059.7
Cabin Teele	6.5	13,621	90,002.2
Sparta	6	6,771	39,156.9
Delta to Bedford	9	28,287	243,903.3
Panther Forest		26,380	163,182.0
Duffin Break	6.7	10,960	80,246.0

Names of levees.	Width of crown.	Front slopes.	Back slopes.	Height of net grades above high-water mark of 1882.	Height or above grade at water level.
	Feet.			Feet.	
Upper Providence	8	3 to 1	3 to 1	1.5	
Hagaman Point	8	3 to 1	3 to 1	1.5	
Wilton to Raleigh	8 and 6	3, 4, and 5 to 1	3 to 1	1.5	
Raleigh to Willow Point	8	3 to 1	3 and 2½ to 1	1.5
Omega	8 and 7	3 to 1	3 and 2½ to 1	0.5	
Cabin Teele	8 and 6	3 to 1	3 and 2½ to 1	0.5	
Sparta	8 and 7	3 to 1	3 to 1	1.1	
Delta to Bedford	6	3 to 1	2½ to 1	0.5	
Panther Forest	8, 6, and 3	3, 3½, and 2 to 1	2½, 2 and 1½ to 1	.53
Duffin Break	8	3½ to 1	2½ and 2 to 1	.3	

NAME OF LEVEES AND REMARKS.

Upper Providence levee, East Carroll Parish, Louisiana.—About 3 miles above town of Providence. Work began November, 1882. Completed February, 1883.

Hagaman Point levee, East Carroll Parish, Louisiana.—About 2½ miles below town of Providence. Work began February, 1883. Completed March, 1883. During the construction of this work, a temporary protection levee was ordered built containing 2,029½ cubic yards.

Wilton to Raleigh levee, East Carroll Parish, Louisiana.—Work began on this in October, 1882, and with as large a force as the contractors could collect, proceeded from each end towards the center, until the suspension on account of the March, 1883, at which time there was a gap of 1½ miles on which very little work had been done. The river bank along this front is very low, and the water rising in February it was deemed impossible with the force on hand (between four or five hundred men) to fill up the gap before the overflow; protection levees were therefore ordered to connect the new work with the "Old Front levee." The upper protection levee sustained the pressure of the water and saved all the work above it, but the lower levee succumbed to the fast rising flood, and the strong current rushing rapidly through the main line swept away 31,552 cubic yards before its destructive effects could be averted. It has since been found inexpedient, on account of insufficient funds, to continue the work on this front.

L 5.

REPORT OF GEORGE M. HELM, ASSISTANT ENGINEER, UPON LEVEE WORK ON THE
YAZOO FRONT, THIRD DISTRICT.GREENVILLE, MISS., *November 15, 1882.*

SIR: In accordance with your request, the following report of operations under my charge on levee construction on the Yazoo front, third district, in connection with maps and profiles of each project of work done by the river commission, together with a plan and folio profile of survey of levees sent on heretofore, is respectfully submitted.

This survey was commenced by the "Mississippi Levee Board" in March, 1882, and was under your instructions finished from Leota to the Warren County line, December 25, 1882. It covers the entire district of the "Mississippi Levee Board" from Totter Ridge, north of Hushpukna, in Coahoma County, through Bolivar, Washington, and Issaquena Counties, to the Warren County line, a distance of 1,056,200 feet, or 201 miles.

Levees were run with reference to Memphis datum plane, and U. S. P. B. M., and average fall of the river from Hushpukna to Greenville found to be 0.377 foot per mile and from Greenville to the Warren County line 0.306 foot per mile. Average fall from upper to lower end of district 0.304 foot. Average height of levees above Greenville, not including Hushpukna and Lake Bolivar crossings, 8.05 feet; average height above Greenville, 6.06 feet; height of Hushpukna levee, 36 feet; height of Lake Bolivar levee, 24 feet.

The following statement will exhibit the length of levee constructed, amount of work embraced in estimates returned to date, and amount of cubic yards to complete same, with specifications of all work done in your district from October 1, 1882, to November 1, 1883:

Name of levee.	Length of levee.	Contents completed.	Amount November 1, 1908, paid.	Width of crown.	Front slopes.	Back slopes.	Height of new grade above high-water mark of 1908.	Height of ground or obstructions above high-water of 1908.
	Feet.	Cubic yards.	Cubic yards.	Feet.			Feet.	Feet.
Riverton levee.....	9,372	152,058		8	3 and 4 to 1	3 to 1	1.1	2.6
Benlah break—1 to 9 inclusive.....	4,000	27,122		8	3 and 4 to 1	3 to 1	0.4	1.08
Benlah to Riverton enlargement.....	18,700	66,886		8	3 to 1	3 to 1	1.8	3.15
Benlah to Hughes enlargement.....	26,410	150,538		3, 1, and 4	3, 4, and 5 to 1	2 and 3 to 1	1.28	1.60
Hughes break.....	1,766	22,892		8	3 to 1	3 to 1	1.4	3.3
Wade break.....	2,207	50,714		8	4 to 1	3 to 1	1.1	3.4
Clay and Hagot to Rowlands.....	41,140	96,015	7,253	8	3 and 4 to 1	2 and 3 to 1	1.43	1.73
Rowlands to Jenkins.....	42,919	156,218		8	3 and 4 to 1	2 and 3 to 1	1.76	2.33
Jenkins to Easton, including Bolivar bayou and Easton break.....	14,010							1.9
Longwood.....	21,287	51,287	7,844	8	3 and 3 to 1	2 and 3 to 1	1.53	3.7
Longwood protection.....	4,980	75,891		8	4 to 1	3 to 1	8.87	5.93
Skipwith.....	2,228	18,978		4 and 5	3 to 1	3 to 1		1.45
Elleslie.....	68,012	77,600		8	3 and 4 to 1	3 to 1	2.9	3.87
Elleslie protection.....	9,975	133,500		3 and 4	4 and 3 to 1	3 to 1	4.08	5.49
Drainage ditch.....	2,000	2,936		3	3 to 1	3 to 1	.05	1.0
Shiloh and new line at Arcadia.....	21,155	57,209		3, 4, 6, and 8 to 1				
Magna Vista to Chotard.....	4,044				3 to 1	2 and 3 to 1	3	3.8
Higgins break.....	32,935							2.2
	3,205	49,367		4 and 6	3 to 1	2 and 3 to 1	2	2.48
Total.....	301,305	1,194,199						3.0

Description of specimens.	Depth.	Quartz.	Mica.	Tourmaline.	Microscopic fossils.
non-calcareous silt, crested vegetable matter in the proportions of clay every few feet.	Feet.	Rounded and clear, with some grains of jasper and chert.	A little	None	None
sand, slightly coherent.	0. to 2.5	Clear, small, and sharp	do.	do.	Do.
ash blue clay.	15.5 to 29	Mostly clear, with some grains of milky quartz and chert.	A good deal	do.	Do.
yellow sand, slightly coherent.	29 to 37	Small, clear, and sharp	None	do.	Do.
Hudson: Loose sand with grains of lignite.	37 to 42.9	Well rounded, clear, and variegated.	A little	do.	Do.
Fine brownish silt, darker below, with lignite in grains.	54.5	Clear, rounded, and sharp; some grains spotted with carnelian.	Abundant	A little	None
Bluish gray clay	55 to 59	Rounded, clear, and red spotted	A good deal	In brown and green crystals.	Do.
Clayey silt of a terra-cotta color; abundant lignite grains.	59 to 64	Rounded and sharp, clear and reddish.	do.	None	Do.
Grayish yellow sand, vegetable matter abundant.	100.5 to 101	do	Abundant	None	Do.
Brownish clay	101 to 103.2	Rounded, clear, and reddish	do	A good deal	Do.
Coarse sand with chert pebbles.	103.2 to 104	Small, clear, and sharp	None	None	Do.
Black lignite	109 to 127.5	Variegated, round, and sharp.	do	do.	Do.
Whitish, blue sandy clay	127 to 131.5	None	do.	do.	Do.
Fine yellowish clayey sand	131.5 to 170	Clear and sharp.	A good deal.	A little.	Do.
Gray sand with clayey streaks	170 to 191	Clear and variegated, rounded.	None	None.	Do.
Blackish brown clay	191 to 247	Clear and smoky, well rounded	do.	do.	Do.
	247 to 249	Small and sharp, clear and yellow	do.	A little.	Nasirula, n. sigma, Ehr. Nasirula, sp. undet.

For comparison with the above, an examination was made of a typical specimen of "buckshot" clay collected in Issaquena County, Mississippi; an undoubted Port Hudson locality.

Description of specimens.	Depth.	Quartz.	Mica.	Tourmaline.	Microscopic fossils.
Stiff blue clay with ferruginous concretions, or "buckshot;" lignite grains abundant.	10 inches from the surface.	Mostly clear; some grains red; from the to size of an inch in diameter; the larger grains round, the smaller sharp.	None	None	None.



A. Method of checking Sloughing.



B. Method of stopping Crayfish Borings.



C. Revetment of Ends of Broken Levees.
Scale 1 inch = 15 feet.









BY THE CHIEF OF ENGINEERS, U. S. ARMY.

from the known sides at lower portion of work to check on lower
 year. These points were then plotted on protractor sheets and transferred
 on already made of old points, and fitted at upper end by bench marks

The map work was done by Messrs. Amelang and Ritchie in conjunction. The plan and location of triangulation points and ranges was done by Mr. Amelang, the soundings by Mr. Ritchie, and the levels by Mr. Paterson, who also acted as recorder for the gentlemen. To their exertions is principally due the completion of the survey by the rise of river, which began the day after the work closed.

The quarter-boat, in tow of the launch Nellie, returned to Wilson's Point and reported to Mr. Hader for duty on the 30th.

Remotely submitted.

Wm. T. Bliss,
United States Assistant Engineer

Capt. W. L. MARSHALL,
 Corps of Engineers, U. S. A.

APPENDIX M.

REPORT OF MAJOR AMOS STICKNEY, CORPS OF ENGINEERS, UPON OPERATIONS IN NORTH DISTRICT.

UNITED STATES ENGINEER OFFICE,
No. 3 SOUTH RAMPART STREET,
New Orleans, La., November 20, 1900

SEN: I have the honor to report as follows on the several works in my charge as the supervisor of the commission, from December 1, 1892, to October 31, 1893.

Since December 1, 1933, work on levees has continued with some interruption by water in the Mississippi, which in some cases caused a total suspension of work and extended the extension of the time for completion of all unfinished levees. Progress has been much slower than was anticipated when contracts were made. This was due to scarcity of labor last season, and unusual amount of malarial fevers this season, and the management of contractors. Repeated notices have been sent to the different contractors to increase the number of laborers, but it seems to have had no effect. Up to date six levees have been completed and six are unfinished. Two of these will probably be completed this year and the others, it is hoped, before the floods. The weather of the contractors largely increasing the

6 MAY 1965

It has been found that the best method of connecting the line of levees in the Mississippi River is by the use of the "levee" or "levee" method. Portions of the levee system have been found to be too close together, and others have proved to be too close together. The following table shows the line of levees to make them continuous, and the following table shows the method of connecting the levees. The following report is a summary of the work done in general charge of levees, gives the details:

NEW ORLEANS LA November 5 1963

2. Have the contractor submit the following report on the construction and repair work performed from December 1, 1982 to October 31, 1983, giving each lot

354-355

Total length of embankment
Slopes 2 and 3 to 1. Crow
with a small force be
yards, but on Dec
he was directed to emp
sufficient to re
before the rising river
the water and the levee was





DEPT OF MISSISSIPPI RIVER COMMISSION APPENDIX B , PLATE II.

67

OF THE CHIEF OF ENGINEERS, U. S. ARMY.

UNLEVERED FRONTS

	Estimated length	Estimated cubic yards
Castlemann's to New Carthage Boughton Black Hawk to Red River	Feet. 50,000 23,400 88,500	60,000 67,000

Timber felled on all levee lines, 260 acres.
Total length of levees under contract, 51 miles, 2,065 feet.
Length constructed to October 31, 45 miles, 3,936 feet.
Remaining to build, 5 miles, 3,409 feet.

	Feet.
Total contents of levees as computed.....	1,784,291.00
In embankment October 31.....	1,257,366.00
Remaining to place in embankment.....	506,925.00

Very respectfully, your obedient servant,

H. S. DOUGLAS,
Assistant Engineer.

Mr. AMOS STICKNEY,
Office of Engineers, U. S. A.

IMPROVING MISSISSIPPI RIVER AT NATCHEZ AND VIDALIA

No work has been done since the transfer of this work to me by Capt. A. M. Miller, Corps of Engineers, U. S. A. It had been my expectation to have an examination made of this locality during low water, for the purpose of preparing a project for work, but the unusual sickness of the season has so crippled my force of assistants that nothing has been done. The old survey shows the principal features of the locality, and I expect to have a project upon that survey. A recent general view of the banks obtained in passing on a steamer shows that the caving of the banks continues as before, but only to small extent in Giles Bend, the worst caving being in Marengo Bend and down toward Waverly Point. The danger to Natchez Harbor is not immediate, but works for bank protection will be required to prevent the working down of the bend above Natchez.

IMPROVING MOUTH OF RED RIVER.

On the 10th of July last annual report to the Commission work in old river and at the new one. The river was suspended as high water made it no longer necessary for navigation.

On June 1, 1887, to the president of the Commission, I recommended to keep open navigation during low water, the same as in 1886, by moving a stern-wheel steamboat attached to the tugboat, over the shoal places to stir up the mud so that the current would carry the mud away. A boat for cutting a channel through the bar was also recommended. The following day, approved by the Commission, steps were taken to carry out the plan.

September 3, 1883, but on account of
the water starting from New Orleans, and the sink-
ing of the operations were not commenced
until the water on the outer bar and 5
feet deep. It was thought that a channel
would be made with great rapidity, and the banks
would be raised as the water was
drawn down. The drawing of Lower
water was the first of Turnbull's
operations, and it was not until the water was
drawn down to any water around

... width of about 3 feet with
... This ending in or the

banks has occurred at each low-water season for a number of years, but never before to the extent of this year.

Some harsh comments have been made, as in previous years, with regard to the failure of the plant to keep a navigable channel, but such comments must certainly have emanated from persons much interested in keeping navigation open, but ignorant of the cause, or extent of the cause, which operated to close the channel. It has never been claimed that the plant used could do anything more than help the current in deepening shoal places, when the water was low enough for the action of the tug wheels to be felt on the bottom and the volume of water and current strong enough to carry off the material stirred up. The dams formed by the sliding in of hundreds of feet of the river banks not only cut off the necessary water to float the boats, but stopped the current necessary to carry away any material that might have been stirred up. This peculiar sliding in of the banks in this locality has, I believe, never been satisfactorily explained. Upon my recent visit I made a special investigation of the matter, and I believe I have discovered the cause of the instability of the banks to be the presence of water back of the banks, whose surface is at a considerable elevation above the river. When the river falls rapidly this back water, acting under a considerable head, forces its way under the banks, converting the lower strata into a semi-liquid material which will not stand under a slope of 1 in 20, or even flatter. I believe there was not a single instance of sliding bank behind which I did not find either standing water or pools where water had recently been. The natural drains for this back water are each year more and more obstructed by the deposit of sediment from overflows, the obstruction increasing more rapidly near the river banks. As a result of this the pond water is held at a higher level, and when the river is low forces its way through the soil under greater head.

The steamboat and tugs commenced work September 7, and were compelled to stop September 25. They resumed work on October 17, and on November 10 were ordered to return to New Orleans, there being a navigable channel 8 feet deep through Old River. The dredge commenced work on the outer bar September 8, and worked continuously until October 22, when she was moved up to the gut. On the 10th of November she was laid off. I am at present engaged upon a plan for the permanent improvement of this locality, which I hope to present to the Commission in a short time. In November, 1882, an assistant engineer was sent to make some surveys of Old River in order to obtain data for estimates and project for placing a sill across old river, with a dam across the valley to check the enlargement of the passage into the Atchafalaya River. This was completed early in February, and estimates were submitted to the Commission March 20, 1883. The Commission decided to postpone action on this. At my recommendation for a resurvey of the old river, which was approved by the Commission, a party was started from New Orleans, June 5, and work commenced a few days afterwards, but sickness and unfavorable weather at times almost suspended operations. The survey is still in progress, and it is hoped that the present cool weather will enable the party to complete it soon. The following report of the assistant engineer in charge gives the details:

RED RIVER LANDING, *October 31, 1883.*

MAJOR: I have the honor to report to you the amount of work accomplished on the survey of the mouth of Red River and vicinity since the 7th of June, when I arrived with a portion of my party, which was not complete until the arrival of the steamboat on the 23d of June. The survey of the Mississippi, including both banks, is finished from below Red River Landing to Carr's Point, by means of a shore line on the left bank and distances carefully measured to the top of the bank, so as to show the elevation accurately, and a note of the stage of water and its line at the edge. The opposite bank is located by a series of angles taken on flag stations placed on all points and so as to define the line of the top of the bank correctly. The sides of triangulation on the right bank forming the bases are never less than half a mile in length, and every base has been carefully measured and checked with a steel-tape measure. Observations of the true meridian have been taken on this base line. A traverse line of the immediate topography has been run on the levee from half a mile below Red River Landing to section No. 12, on Atchafalaya River. Cross-sections Nos. 2, 4, 6, and 13 of the Atchafalaya have been relocated, sounded, plotted, and sent into the office. Likewise in the lower old river, cross-sections F, G, I, Z, X, also D, V, and W, at the mouth, near the Mississippi. These sections require to be extended back on the ground on the right of the Atchafalaya, and on the Turnbull Island side of the River, now that the water is low enough to make it practicable to do so. Eight sections have been taken on the upper old river at right angles to the bed of the river and extending across all the chutes to the high ground on either side, and the approximate location on the map of 1879 have been sent to the office. A second set of the low-water discharge of Red River have been taken 1,000 feet above the




BOER
33° 43'

40 METRES

40 METRES

40 METRES

40 METRES



2876 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

Tabulated results of discharge measurements.

Date.	Gauge.	Water width.	Water area.	Datum area.	Mean velocity per second.	
1883.			Sq. feet.	Sq. feet.*	Feet.	C
January 27	4.008	2,288	147,506	137,236	2.830	
January 30	4.970	2,280	148,642	137,448	2.904	
January 31	5.310	2,280	149,784	137,708	3.008	
February 1	5.630	2,291	152,046	139,061	3.088	
February 2	6.170	2,292	153,062	139,181	3.249	
February 5	7.634	2,300	157,366	140,836	3.620	
February 7	8.494	2,329	159,190	139,338	4.133	
February 8	8.733	2,340	159,068	139,614	4.070	
February 9	8.989	2,342	160,362	139,637	4.198	
February 10	9.330	2,348	161,014	140,051	4.219	
February 12	9.495	2,355	162,122	140,517	4.190	
February 15	9.915	2,365	161,230	139,612	4.309	
February 17	10.398	2,360	162,212	138,566	4.705	
February 19	10.980	2,362	162,736	137,501	4.833	
February 20	11.078	2,364	163,014	137,424	4.832	
February 21	11.105	2,366	162,862	137,107	4.908	
February 22	11.440	2,420	164,376	139,275	4.922	
February 23	11.680	2,518	165,012	137,506	5.173	
February 28	12.151	2,530	165,492	136,892	5.143	
March 1	12.530	2,546	164,848	135,783	5.159	
March 2	12.577	2,546	164,936	136,151	5.288	
March 3	12.298	2,580	165,496	136,627	5.388	
March 5	12.490	2,585	165,976	137,301	5.467	
March 7	12.685	2,580	163,498	135,140	5.551	
March 9	12.902	2,567	164,686	133,881	5.688	
March 12	12.786	2,567	158,542	128,171	5.681	
March 13	12.875	2,567	158,633	128,240	5.671	
March 14	12.940	2,567	160,700	130,022	5.670	
March 15	12.045	2,567	161,146	130,152	5.743	
March 16	13.102	2,567	163,386	131,267	5.670	
March 17	13.175	2,567	162,664	131,384	5.644	
March 19	13.317	2,567	163,436	131,570	5.702	
March 20	13.462	2,567	162,638	131,560	5.815	
March 21	13.412	2,567	164,040	132,640	5.834	
March 22	13.300	2,567	163,658	132,694	5.857	
March 23	13.468	2,567	163,280	132,000	5.840	
March 24	13.910	2,567	164,422	132,170	5.854	
March 26	13.991	2,567	159,410	128,802	6.218	
March 28	14.120	2,567	159,726	126,832	6.199	
March 29	14.364	2,567	160,132	126,879	6.154	
March 30	14.580	2,567	164,784	131,055	6.107	1,
March 31	14.675	2,567	165,070	131,087	6.123	1,
April 2	14.830	2,567	167,010	132,141	6.220	1,
April 3	14.945	2,568	167,244	132,143	6.175	1,
April 4	15.007	2,568	170,620	135,452	6.066	1,
April 5	15.089	2,568	171,610	136,871	6.078	1,
April 6	15.133	2,568	173,062	137,922	6.070	1,
April 7	15.398	2,568	173,487	137,772	6.219	1,
April 9	15.465	2,568	174,694	138,428	6.082	1,
April 10	15.260	2,568	174,195	138,475	6.005	1,
April 11	15.123	2,568	175,870	141,080	6.323	1,
April 12	15.108	2,568	178,980	142,814	6.800	1,
April 14	15.061	2,568	183,372	147,936	6.621	1,
April 16	14.808	2,568	179,526	144,980	6.683	1,
April 17	14.699	2,567	184,212	149,936	6.584	1,
April 18	14.610	2,567	184,123	149,972	5.538	1,
April 19	14.564	2,567	181,130	146,998	5.507	
April 20	14.580	2,567	182,189	148,021	5.489	
April 21	14.600	2,567	180,716	146,007	5.315	
April 23	14.487	2,567	180,689	146,609	5.397	
April 24	14.420	2,567	179,468	145,724	5.286	
April 25	14.335	2,567	179,467	145,715	5.346	
April 26	14.223	2,567	180,091	147,023	5.313	
April 27	14.300	2,567	180,123	146,946	5.330	
April 28	14.201	2,567	179,579	146,619	5.414	
April 30	14.213	2,567	178,714	145,655	5.361	
May 1	14.233	2,567	178,608	145,378	5.280	
May 2	14.234	2,567	178,608	145,378	5.256	
May 3	14.245	2,567	179,716	146,838	5.263	
May 4	14.190	2,567	179,569	146,833	5.356	
May 5	14.268	2,567	179,774	146,337	5.365	
May 7	14.130	2,567	178,888	145,251	5.287	
May 8	14.014	2,567	178,192	145,338	5.209	

* Below zero of Carrollton gauge.



APPENDIX F , PLATE 1.



reaching to within 50 feet of the deep-water end of the mattress. The dike will consist of willow brush and stone. The brush will be woven in thicknesses of 4 or 5 feet and sunk one on another till a thickness of 20 feet is reached. In this bend a dike 20 feet high will carry the bank out horizontally about 60 feet. The current, passing a dike and moving in a line tangent to the curve above, will strike the bank again in about 75 feet, where another dike would have to be constructed. As the bend is somewhat irregular the dikes would have to be nearer together at some places and farther apart at others.

The mattress under the dike would cost, at 4.42 cents per square foot..... \$1.54
The dike, at 4.97 cents per cubic foot, would cost..... 8.94

Making a total cost of mattress and dike..... 10.48

I have estimated stone to cost \$3 per cubic yard, loose measurement, and the dikes to contain 5.1 pounds of stone, weighed in water, per cubic foot, over the amount necessary to overcome the buoyancy of the brush. This weight would be increased by the mud and silt which would collect.

COST OF THE IMPROVEMENT.

FIRST SECTION.

Length of section..... feet..... 20,300
Cost to protect with mattress..... \$314,000
Cost to protect with dikes, 750 feet apart..... 294,000

SECOND SECTION.

Length of section..... feet..... 6,500
Cost to protect with mattress..... \$101,000
Cost to protect with dikes, 1,635 feet apart..... 42,000

THIRD SECTION.

Length of section..... feet..... 13,000
Cost to protect with mattress..... \$210,000
Cost to protect with dikes, 750 feet apart..... 189,000

The entire third section is a raving bank, and if not protected it will in time cut away at Algiers, and change the whole front on the opposite side of the river.

Respectfully submitted

W. G. PRICE,
United States Assistant Engineer

MAJOR GENERAL
U. S. ARMY

Enclosed will find a full statement of the different works in my charge.

CONSTRUCTION AND REPAIR OF LEVEES, FOURTH DISTRICT

	Amount paid out since first of January 1882	Amount received since first of January 1882
Amount paid out since first of January 1882	\$1,200.00	\$1,200.00
Received since first of January 1882	17,100.00	17,100.00
Balance on hand October 31, 1882	521,500.00	521,500.00
Expended to October 31, 1883	311,500.00	311,500.00
Balance on hand October 31, 1883	171,500.00	171,500.00
Disbursements since December 1, 1882		
Transportation		1,919.57
Miscellaneous		9,000.00
Inspection of contract work, salaries		\$11,700.00
Contract work on levees and protection during high water		126,800.00
Total since December 1, 1882		349,519.57

IT OF

PLATE III
APPENDIX G.



2884 REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

IMPROVING MISSISSIPPI RIVER—OBSERVATIONS AT CARROLLTON, LOUISIANA

Allotment		\$3,0
Drawn		3,0
Expended		3,0
Balance December 1, 1882		3,0
Expended to October 31, 1883		3,0
Disbursements since December 1, 1882:		
Telegram	\$0 72	
Storage	6 00	
Stationery	10 93	
Lumber	12 39	
Coal	134 15	
Material	187 63	
Transportation	220 60	
Hire of launch	300 00	
Services	2,127 58	
		3,0

MISSISSIPPI RIVER COMMISSION—OBSERVATIONS AT CARROLLTON, LOUISIANA

Allotted		\$1,5
Expended		1,4
Balance on hand October 31, 1883		
Disbursements since December 1, 1882:		
Telegrams	\$0 75	
Transportation	15 00	
Material	41 98	
Fuel	72 55	
Service	1,314 33	
		1,4

CLOSING BONNET CABRÉ CREVASSE.

Allotted		\$15,0
Drawn		15,0
Expended since December 1, 1882, contract work		15,0

HARBOR AT NEW ORLEANS, LOUISIANA.

In Treasury Department, Washington, July 1, 1882	\$144,525 90	
On hand, Assistant Treasurer, New Orleans, July 1, 1882	3,267 91	
In hands of Assistant Engineer, October 31, 1883	100 00	
		\$147,8
Expended since July 1, 1882		8,8
Balance on hand December 1, 1882	2,055 79	
Expended since	7,632 89	
Balance due from appropriation	5,577 10	
Disbursements since December 1, 1882:		
Miscellaneous	506 97	
Material	453 88	
Surveys	145 14	
Service at the works	1,966 06	
Office expenses, &c	570 93	
Plant	3,989 91	
		7,
First cost of plant now employed		30,

Very respectfully, your obedient servant,

AMOS STICKNEY,
Major of Engineers, U. S. A.

Lieut. Col. C. B. COMSTOCK,
Corps of Engineers, U. S. A.,
President Mississippi River Commission.

APPENDIX 8 , PLATE V.



ings, which he inclines to consider as the result of imperfect development in consequence of the influx of fresh water. At the early time at which these, the equivalents of Claiborne beds of Alabama, were formed, the continental drainage had its mouth at Cairo, and the Mississippi of to-day had not yet become the one great outlet, the Missouri having no existence. A gradual upheaval, prevalently from the eastward, shallowing a part of the great Mississippi embayment, so as to convert its margin into swamps, intersected by occasional estuaries. Such continued to be the state of things in middle tertiary times over much of the States of Mississippi and Louisiana. Yet we find in the intercalated marl the largest and finest fossils; moreover, as a matter of fact, there are fragments of large fossils in several instances—e. g., *Venericardia planicosta*, *Atletha Tuomeyi*, *Monoceros vetustus*, and others. As a rule such large fossils would be driven out of the way by the pipe in its descent, or ground to fragments. The small and especially those combining hardness with smallness, would be the ones that would be left, and would leave comparatively uninjured, such as *pleurotomas*, *naticas*, &c.

Such as they are, however, these fossils overwhelmingly demonstrate the close correspondence of the beds penetrated at Helena and Choctaw Bar (whose facies is altogether identical) with the lower portion of the Claiborne beds of Alabama; perhaps most nearly with those older ones, which Dr. Eugene A. Smith, State geologist of Alabama, has examined at and near Wood's Bluff, Alabama, and which rest directly upon the oldest Cretaceous and flatwoods clays. This is obviously the position of the Helena marl bed, and the clays found in the bottom boring, No. 1, at 162.3 feet and lower, are absolutely distinguishable from those of the Memphis boring. These facts agree again with the fact that, since the strike of the Claiborne strata observed in Mississippi is about north-northwest (not due west, as inferred by Mr. Wilson from the older geological maps of Mississippi), their dip must be correspondingly a south-southwesterly one, from Memphis toward Helena.

The difference of nearly 150 feet between the levels at which the tertiary strata have been reached in the bluff and in the bottom boring at Helena, not quite two miles apart, affords a measure of the energy of the erosion effected by the gravel-charged flood of the quaternary epoch.

BOTTOM BORINGS.

In all the deeper bottom borings, save one (viz: No. 2, Lake Providence), three distinct formations have been penetrated, viz, the river alluvium or its equivalents in the equivalents of the Port Hudson beds, and the eocene tertiary strata.

Much speculation has been indulged in heretofore as to the average depth of the alluvial deposits of the Mississippi, and the results of my observations in the Delta, which seemed to indicate that the deposits of the modern river are comparatively shallow, have been repeatedly called in question. The present investigation throws new light on this subject, and likewise rectifies the interpretation of the age of the "bottom gravel," which has long been known to underlie the great bottom, but was by me conjectured to be, in the main, the representative of the "orange sand" of the upper Mississippi. Mr. Wilson correctly concludes, from the constant occurrence through these gravelly layers of lignite grains or "wash," that they are not an equivalent of the orange sand, which is always singularly free from any oxidizable matter. The microscopic examination corroborates the importance of the lignite grains, and associates them with grains of opal, and clear quartz spotted with carnelian as characteristics of the Port Hudson strata to which group the great beds of gravelly sand with the overlying finer sands accordingly referred. On the other hand the same examination shows the vegetable remains in the alluvium to be merely macerated, or slightly carbonized, detecting no other fossils at all.

It is not altogether easy to see why this should be so, and why a few remains of shells or wood fibers, and rarely even these, should be all that remain of the multitude of objects that the great river has an opportunity of carrying off in its long course, especially at high stages of water. The only reasonable explanation seems to be that the trititious effect of the sharp sand, with the rapid eddying motion of the river, tends to destroy by mechanical attrition, all but the toughest material and such large fossils as logs, which cannot but be presumed that in the back or slack-water deposits of to-day some of the many organisms of the cypress swamps must be preserved; but no such material has been found under our examination. On the whole, a person habitually familiar with the deposits of the river will rarely fail to recognize them. Moreover, they are all, even to the sand, characterized by a very frequent alternation of materials, due to the alternate influx of deposits from different sources at different seasons of the same year, so that a close observer may in many cases identify the materials deposited by floods derived from different sources, such as the Arkansas on the one hand, and the Red River on the other. On the other hand, as great a thickness as 20, or even 15 feet, of uniform and unquestionably alluvial

of to-day will rarely be seen, even 10 feet being unusual, and from a few inches to 3 feet the most common range.

At this point of view, the great sand bed of boring No. 1, at Helena, as well as those beneath the unquestioned alluvium in the Choctaw Bar borings, and in No. 1 of Providence reaches (Mayersville), presented a doubtful point, these sands being really uniform in their nature and appearance, not only at different depths in the same, but even on comparison of those from different borings. The fact that in all cases the massive sand-beds show both the lignite grains and those of quartz spotted with carnelian, which they have in common, not only with each other, but with the "buckshot clay" of known Port Hudson age, of which an authentic sample was lately in my possession,* is sufficient, in the absence of fossils, to cause them all to be referred to the Port Hudson epoch. It is a curious fact that this buckshot clay, is so abundant in the back lands of the bottom, happened not to form the surface point where borings were made, unless it be at Greenville. Stiff clay soils were in several cases found at the surface, but these were underlain by the undoubted river alluvium.

Greenville boring is unique, in that it was made at a point in the bottom apparently above high-water mark, and that coincident with this the red and spotted quartz with lignite were found in the sand within a few feet of the surface. No micro-organisms were found in the surface soil, but even that is unlike the river alluvium.

In other words, it seems as if at Greenville the older (Port Hudson) materials were at the surface near the river bank, as some distance back they are on the "buckshot lands," uncovered by any alluvium. The local elevation of Greenville would be due to the "Dogwood Ridge" shown on the map of the Mississippi alluvial region by Sphreys and Abbot's report, as the only land above overflow in the Yazoo bot-

tom. The deepest boring of the whole series, No. 2 of Lake Providence, is unique despite of its great depth (248 feet), it has failed to reach the tertiary beds. Mr. Smith was misled by the close resemblance of the clays at 131.5 feet and below, and the overlying lignite, into the belief that the rest of the boring was in tertiary materials, which conclusion was made more plausible by the occurrence of calcareous sand and materials resembling greatly the tertiary marls. The microscopic examination, however, leaves no doubt of the fresh water and "Port Hudson" character of the boring from at most 42.9 feet down. In this latitude, moreover, the outcrops of materials in the Yazoo bottom render the identification, even to the naked eye, very complete. How much deeper the trough was excavated into the tertiary at this point is open to conjecture; but the occurrence of the tertiary marl at 110 feet in No. 3 (at Hay's Landing), 6 miles southeast from Lake Providence, shows that the trough was not continued in that direction, but more probably in a southwestward direction. In this connection it should not be forgotten that, as I have shown,* the old current bore, not in the direction of the present mouths of the Mississippi, but toward Vermilion Bay. This, therefore, is the direction in which we would expect the deepest excavations in the tertiary materials.

As regards the comparative age of the marine tertiary beds at Lake Providence (or Hay's Landing) and Choctaw Bar or Helena, the larger as well as the microscopic examination tend to show that while the beds reached at the first-named locality have a somewhat different *facies* from those above, yet the horizon of the next higher group, the "Ogishian," had not been reached. Now it is known that southeast of Hay's Landing on the Yazoo River, near Haines's Bluff, the Jackson strata begin to disappear beneath the level, being there overlaid by a lignitic bed of variable thickness, which in its turn is capped by the "Vicksburg" series. The dip of the tertiary here very little west of south, it follows that at Hay's Landing the strata at 110.7 feet must belong to a group considerably below the Jackson beds; which fact what the fossils found also indicate. In other words, the bed belongs to the lower portion of the Claiborne group, and, according to the rate of dip observed at Vicksburg, the Jackson beds would not be reached in a boring of that depth until about the level of Warrenton, south of Vicksburg.

General conclusions reached as regards the geological history and structure of the bottom within the limits of the borings in question are therefore these: A trough of depth exceeds at one point 248 feet below high-water mark has been excavated in the tertiary beds originally filling it probably to a height considerably above that of the present surface.

This trough has subsequently been filled up to above present high-water mark in its present position, from the period of gradual depression following the deposition of the orange sand, and during which the orange-sand materials were eroded and redeposited in the trough, or similar materials were brought *de novo* to the surface.

*For geological details regarding this clay, refer to Dr. E. A. Smith's paper on the Geology of the Yazoo Bottom, Proceedings A. A. A. S., 1871, p. 252.

from northern regions. The gravel and coarser sand were of course left in the northerly portion of the trough, while in the southerly one the comparatively water produced deposits of sandy loams, fine silt, and "back-shot" clay. As the flood increased and the slack-water advanced up the valley, finer materials, loams, overlying the gravels, were deposited, and finally the loess and yellow loam covering the uplands. Upon re-elevation the loam and loess in the middle of the trough were washed away; but when the resistant back-shot clays were reached, concentrated upon the lines of least resistance, and the river of to-day was left in the great alluvial ridge in the axis of the valley, flows that while the river was being channelled by the formation and cutting off of bends, its general line of position remained the same. Where the river has advanced very recently, it is possible that the alluvium overlying such as remained; but while of many points it is difficult to say, it must, of course, be of corresponding thickness, and in some cases, as in the Mississippi more alluvium of such thickness has been shown only a few feet above the Bar, viz. 68.2 feet; the maximum thickness found elsewhere being on the eastern bluffs bordering Lake Providence, No. 3 boring, 76.8 feet, and No. 5, 75 feet or 70 feet. This is in accord with the similarly shallow depths at which the alluvium found to terminate in the lower delta.

It would be extremely desirable to verify these conclusions by the comparative location of samples carefully taken, both of various kinds of modern alluvium and various materials of the noted cut-crops of the Fort Hudson group. This is especially interesting in connection with borings made at points further south in the great valley itself.

PREFATORY LETTER BY DR. F. V. HOPKINS.

SAN FRANCISCO, CAL., May 1, 1895

Prof. E. W. HILGARD, *Ph. D.*:

DEAR SIR: The microscopic examination of the specimens submitted to me by you has now been carried as far as the objects had to view by the Mississippi River Commission will warrant. In fact, it has been carried much farther, far under the impression that what was desired was a full account of their fossil contents, such as I had the pleasure of preparing for you in the case of the Lake Borgne borings in 1874. I figured carefully every organism observed. The tertiary marls proved to be very rich in foraminifera, almost all of undescribed species, and one or two new genera may have to be given in order to describe them fully. This work, after having occupied my time for not unfortunatly proving to be of little avail, the Commission having decided at their meeting in January last to publish no plates with this report.

Under these circumstances I have done what I could to compare my specimens with those already described, and have prepared lists of names, indicating those species of others that most strongly resemble the fossils observed. These names are in the following tables, and will be of aid in the determination of the geological position of the strata through which the borings have passed. It is to be hoped that they will attract the attention of naturalists to a rich and as yet unworked field for research.

The specimens were prepared for examination by shaking, or in the case of clay boiling, with about 4 inches of water in a 6-inch test-tube until the grains were separated. After settling, first for 25 seconds, the water containing the finer portion decanted into another tube, and a fresh supply poured in. This process was repeated four times, the settling being 5 seconds shorter each time. The remaining portion of the separate deposits in the tubes were then examined carefully under a microscope with powers varying from 70 to 1,400 diameters. The results are set forth in the following tables.

Yours, very truly,

F. V. HOPKINS

* Smithsonian Contributions to Science, No. 218; also, Proceedings A. A. A. S., 1871, p. 230, 1.

† The height at which we find the tertiary beds at this time on the bordering bluffs is probably not a fair measure of the amount of erosion, since the axis of the Mississippi embayment was doubtless a trough lower than its border.

Record of examination of specimens of borings.

scopic character by Dr. F. V. Hopkins; larger organisms and final determination of the strata by Prof. E. W. Hilgard.]

BORING NO. 2, MEMPHIS, TENN. (ON BLUFF).

Location of specimens.	Depth.	Quartz.	Tourmaline.	Vegetable matter.	Mica.	Large fossils.	Small fossils.
LOESS.							
Light, non-calcareous.	1 to 47	Small rounded and clear.	None.	A little.	None.	None.	None.
LARGE SAND.							
Yellow, coarse.	47 to 53.9	Variegated with pebbles.	None.	None.	None.	(+)	None.
Clay, with yellow streaks.	53.9 to 60.6	Small, clear, and rounded.	do.	do.	do.	None.	Do.
Reddish sand.	60.6 to 63	Clear, mixed with chert and jasper.	do.	do.	do.	do.	Do.
Red sand with chert.	63 to 93.9	Sharp and rounded, clear, white, yellow, red, and black.	do.	do.	A little.	(+)	Do.
Red-colored sand.	93.9 to 99.8	Variegated.	do.	do.	do.	None.	Do.
Red-colored sand, silty.	99.8 to 117	do.	do.	do.	do.	(+)	Do.
Red-colored sand, or part cemented by iron into a conglomerate.	117.5 to 132.2	do.	do.	do.	do.	(+)	Do.
Shale clay.	132.2 to 132.5	Fine and clear.	do.	do.	do.	None.	Do.
Yellowish sand.	132.5 to 133.4	Variegated.	do.	do.	do.	do.	Do.
Shale clay.	133.4 to 134.1	Fine and clear.	do.	do.	do.	do.	Do.
Yellowish sand.	134.1 to 139.3	Variegated.	do.	do.	(+)	do.	Do.
MEMPHIS LIGITIC TERTIARY.							
Orange Group.							
Clay, yellow, passing into gray.	139.3 to 150	Clear, small, and rounded.	None.	(2)	None.	None.	None.
Sand.	150 to 154.5	Rounded and sharp, clear, some white and yellow.	do.	do.	do.	do.	Do.
WOODS Group.							
Blue clay.	154 to 167	Very small, clear, and round.	None.	None.	None.	None.	None.
Blue sand.	167 to 168.5	Clear and round.	do.	do.	do.	do.	Do.
Blue clay.	168.5 to 273.1	Fine and clear.	do.	(+)	do.	do.	Do.

Red paleosol in pebbles. † Casts in pebbles. ‡ A good deal. § Lignite grains and larger pieces. ¶ Lignite grains.

NOTES ON MEMPHIS SECTION, BORINGS NOS. 1 AND 2.

(E. W. HILGARD.)

The loess specimens within the first 47.2 feet agree entirely with the usual character of the deposit in the northerly region. It is much less calcareous than farther south, and, as well as concretions of calcic carbonate, occur only in streaks, sporadically. The upper 10 feet are properly a subsoil layer belonging to the "yellow-loam" division, which in the interior is directly superimposed upon the orange sand or stratified loess. The latter presents here a most characteristic section, embracing a series of all its characteristic materials, even to the ferruginous conglomerate of coarse sandstone, which, as elsewhere, marks the approach to an impervious or clayey layer. The lowest part of the loess also shows for a few feet a change toward a sandy hardpan, which finally forms a transition to the orange sand proper; and at the base of the latter the appearance of sharp sand-grains, as against the rounded and rust-incrusted ones, heralds the approach of the tertiary sands that commonly form the upper portion of the "La-

REPORT OF THE CHIEF OF ENGINEERS, U. S. ARMY.

grange groups - in Tennessee. The great clay bed with occasional streaks of gray sand is the exact counterpart of sections obtained in bored wells in the "Flatwood belt" in Mississippi, indicating the variation in sandiness that is so apparent between 230 and 245 feet of the section. As these clays immediately overlie the highest cretaceous of the southwestern States, it is probable that between 100 and 200 feet lower down the cretaceous limestone would have been reached after passing through a zone of estuarine deposits with shelved marine fossils. The dark-colored concretions found at 184.7 and 304 feet are mostly of bird-shot size, and consist of sand-grains cemented by brown iron ore, evidently a pseudomorph after iron pyrites. They are therefore not calcareous, as stated in the record of borings; nor does the material inclosing them show any signs of effervescence. Had it been otherwise, the fact would have been of especial interest, indicating the approach of oldest marine tertiary strata found at some points in Mississippi and Alabama.

Boring No. 3 manifestly agrees in all prominent points with the sections obtained in the bottom borings at Helena, Choctaw Bar, and Lake Providence; viz: the tertiary strata are overlaid first by a heavy deposit of gravel and gravelly sand, this by fine sand, and this finally by the obviously alluvial layers.

[Specimens from below the depth of 51 feet. No microscope organisms detected.]

Description of specimens.	Depth.	Quartz.	Mica.	Lignite.
Port Hudson.				
Fine sand.....	Feet. 31 to 45.0	Grains clear, rounded, and sharp, some red; largest .065 inch in diameter.	But little; some red and green, mostly colorless; no tourmaline.	None.
Fine sand	45 to 57.4	As above, from .017 inches down.	Plentiful in broad plates	Abundant. Too ripe for an alluvial deposit.
Coarser sand with gravel.....	57.4 to 116.4	Rounded, mostly colorless, but varied with milky quartz, carnelian, yellowish chert, &c.	None	Do.
Clean sand with gravel.....	116.4 to 142.7	Perfectly rounded, mostly clear; some spotted with carnelian, chert, jasper, quartz, &c., and fragments of composite rocks, gray and brown.do	Not very abundant.
Coarse sand.....	142.7 to 156.8dodo	Do.
Finer sand.....	156.8 to 161.5dodo	Do.
Coarse sand.....	161.5 to 162.8dodo	Do.
Northern lignite (tertiary):				
Smooth blue clay.....	162.8 to 189.5	Very fine, clear, and roundeddo	Abundant and ripe.
Lignite in mass.....	189.5 to 189.7	None.....do	Well ripened.
Smooth blue clay.....	189.7 to 206.4	Very fine, clear, and round.....do	In grains, ripe as last.



Calaborno group of tertiary strata. Clayey green sand and marl.....	230.5 to 231.3 Fwt.	Clear and round; 1/16 of an inch in diameter and less.	A little in crystals.	Same species as at 1713.	Planulina n. ampla Ehr. two species. Do. n. octocarinata Ehr. Do. n. cornuta Ehr. Cyclonema, sp. undet. 2. Do. n. arenaria Williamson. Lenticula, n. n. distincta, Ehr. Discosporina ten species undet. Retolima, n. Ehrenbergii Halley. Globularina, sp. undet. Do. n. bicarinata, Carp. Sphaerocyclonema, sp. Polystomella n. craticulata, Carp. Globularina n. laevissima, D. orb. Strophomena, sp. undet. Pachymenidium, sp. undet. No. 1. Venus, n. n. 1 to 4, Ehr. Tectonites, 3 species undet. Reticularia Planorbis, sp. undet. Halysites, n. n. 1 to 4, Ehr. Reticularia, n. n. 1 to 4, Ehr. Murchisonia, sp. undet. Graptolites, sp. undet. Lagerstomia, n. n. 1 to 4, Ehr. Do. n. squamulosa, W. Do. n. n. 1 to 4, Ehr. Retolima, n. n. 1 to 4, Ehr. Cyclonema, n. n. 1 to 4, Ehr. Do. sp. No. 3, undet. Do. sp. No. 4, undet. Globularina, sp. No. 3, undet. Discosporina, sp. No. 11, undet. Bulimina, sp. undet. None.
Clay-colored calcareous rock.	231.3do.....	Crystalsdo.....	Planulina (entolentia), n. marginata, W. sp. No. 2. Cyclonema, sp. undet. Trachymenia gordini, Carp. Spiroloculina, sp. undet.
Dark sandy clay, with pebbles	234 to 236.8do.....do.....do.....	None.
Clay-colored sand *	236.8	Clear, sharp, and rounded, some grains spotted with carmelum.	Rare	Fragmenta very abundant	None.

*By some mistake Mr. Wilson reports the last specimen as "limestone."

NOTES ON THE HELENA SECTION.

(R. W. HILGARD.)

BORING NO. 2 (ON BLUFF).

The first 139.7 feet of this section is highly typical loess, with land snails (*Helix labris*) and loess puppets or calcareous concretions of the silty mass. It differs quite variously from the yellowish and much more clayey material of the Memphis bluff and marginal region of the loess in Tennessee and north Mississippi generally, which may properly be distinguished as "marginal loess."

The materials found from 139.7 to 158 feet, though non-effervescent, seem most closely related to the loess, and, with the underlying siliceous clays, seem to correspond to the transition strata between the loess and orange sand observed at Vicksburg and Grand Gulf, Miss.


The pebble bed at 167.8 to 171.3 doubtless represents the orange sand pebble bed, which has been found of such very variable thickness by Mr. Wilson in this very locality, and shows the same variability almost everywhere else.


The fossiliferous clay and marl bed, 171.3 to 231.3, with its intercalated layer of blue impure limestone, is very distinctly characterized as tertiary, of the (marine) Claiborne Group by the well-preserved specimens of the following shells: *Monoceros vetustus* Lea, *Actæon lineatus* Lea, *Nucula magna* Lea, *Dentalium turritum* Lea, or *microstriatum* Helms, *Natica minima* Lea, *N. magno-umbilicata* Lea, *Pleurotoma Lonsdalei* Lea; there is also an undescribed *Pleurotoma*, *Flabellum*, and *Retepora*. The abundance of microscopic organisms shown by Dr. Hopkins's record is very remarkable.

BORING NO. 1 (IN BOTTOM).

This boring begins at a level about 138 feet lower than No. 2, and reaches to a depth greater by 116 feet. After penetrating 27 feet of unquestionable alluvium, it penetrates first 56.4 feet of very fine and uniform sand, which then becomes coarser and slightly gravelly through the succeeding 29 feet, making 85.4 feet of sand. The materials then become gravelly and pebbly, and so continue with variations to 162.3 feet, making in all 131.3 feet of sandy and gravelly materials, the physical composition of which shows them to belong to one and the same epoch. Then follow strata of solid clays, void of marine fossils, but agreeing in every character with the "northern lignitic" clays penetrated in the Memphis boring at the lower depths. Helena boring No. 1 has therefore passed beyond the limits of the marine Claiborne strata found in boring No. 2, reaching the older underlying tertiary at the lowest level at which it has been found in the borings under consideration, viz, 162.3 feet below the high-water reference level. The ready disintegration of the calcareous marls has allowed the ancient floods, charged with gravel, to wear them away down to their tough floor clays; the latter, contrary to the statements in the boring record, show no signs of calcareous matter.



PLATE N^o VIII.




APPENDIX L . PLATE XII.

BASIN.





APPENDIX M , PLATE II.



BORING No. 2, HELENA, ARK.

Description of specimens.	Depth.	Quartz.	Tourmaline.	Large fossils.	Small fossils.
Loess: Brownish-yellow loam, non-calcareous.	Feet. 0 to 0.5	Brown yellow and clear; grains from .03 of an inch down, smaller, grains sharp, larger rounded.	None	None	None.
Yellow silt, calcareous, and full of snail shells and concretions of lime called "loess puppets."	0.5 to 189.7	Clear rounded and sharp, from .002 of an inch down.	Green crystals of tourmaline.	<i>Helix albolabris</i> (Say)	Do.
Transition stratum: Yellowish clay	189.7 to 167.8	Clear rounded .002 of an inch and less in diameter.	None	None	Do.
Orange sand (drift): Chert pebbles	167.8 to 171.3	Yellowish chert, well rounded, often several inches in diameter; full of casts.do	Casts of paleozoic fossils	Do.
Olaiborne group of Tertiary strata (Marine): Stiff blue clay, with green sand and lignitized sea-weed.	171.3 to 199	Clear and round; some carnelian.	A little crystallized ..	<i>Corbula</i> , <i>Turbinolia</i> , <i>Natica magno-umbilicata</i> , <i>Volula petrosa</i> .	Do.
Stiff blue clay, calcareous; a clayey green-sand marl.	199 to 211.2dodo	<i>Corbula</i> , <i>Turbinolia</i> , <i>Natica magno-umbilicata</i> , <i>Volula petrosa</i> , fragments.	Do.
Ferruginous concretion of stony hardness.	211.2 to 211.4do	None	Fragments	Do.
Clayey green-sand marl	211.4 to 212.8	Clear and round, $\frac{1}{16}$ of an inch in diameter, and less.	A little in crystals...	Same species as at 171.3	Do.
Do.	212.8 to 222dododo	Spot of <i>Dentalium</i> .
Do.	222 to 229.5dododo	Spot of <i>Dentalium</i> , with spot of <i>Ostrac.</i>
Do.	229.5 to 231.8dododo	Abounding in foraminifera, viz: <i>Planulina</i> , sp.; <i>Planulina</i> , near <i>P. leptostigma</i> Ehr.

Clalborne group of tertiary strata:	Feet. 229.5 to 231.3	Clear and round; 1/16 of an inch in diameter and less.	A little in crystals.	Same species as at 171 3.	Planulina n. ampla Ehr. two species. Do. n. octenaria Ehr. Do. n. cornu Ehr. Cristellaria, sp. undet. 2. Do. n. arcuata Williamson. Lenticulina, n. discus, Ehr. Discorbina, ten species undet. Rotula, two species undet. Rotalina, n. Ehrenbergii Bailey. Globigerina, sp. undet. Do. n. helicina, Carp. Sphaeroidina, sp. Polystomella n. craticulata, Carp. Glandulina n. laetigata, D. orb. Strophoconus, sp. undet. Polymorphina, sp. undet. No. 1. Vaginulina n. tenuis, Ehr. Textilaria, 3 species undet. Rhizopoda, Plagiophrys, sp. undet. Haliommu, n. ovatum, Ehr. Foraminifera, as follows: Miliola, n. ovum, Ehr. Gronia, sp. undet. Lagena (entosolenia), n. globosa, W. Do. n. squamosa, W. Do. n. marginata, W. Rotalina, n. Ehrenbergii Bailey. Cristellaria, n. arcuata, W. sp. 2. Do. sp. No. 3, undet. Do. sp. No. 4, undet. Globigerina, sp. No. 3, undet. Discorbina, sp. No. 11, undet. Bulimina, sp. undet. None.
Do.....	231 to 231.3	do.....	Crystals.....	do.....	
Clay-colored calcareous rock.	231.3	do.....	None.....	Fragments.....	None.
Dark sandy clay, with pebbles.	234 to 236.8	do.....	do.....	None.....	None.
Clay-colored sand *	236.8	Clear, sharp, and rounded, some grains spotted with carnelian.	Rare.....	Fragments very abundant.	Lagena (entosolenia), n. marginata, W. sp. No. 2. Cornuspira, sp. undet. Trochammina gordialis, Carp. Spiroloculina, sp. undet.

* By some mistake Mr. Wilson reports the last specimen as "limestone."



INDEX.

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
A.			
flume for river improvement, test of	244		
e Harbor, Wis., improvement of	280		1847
a River, improvement of	203	1200	
a Creek, Cal., examination of	334		2207
ny River, Pa., improvement of	262		1702
r River, N. C., examination of	177	1059	
Harbor, Mich., improvement	303		2036
na River, Ga., improvement of	187	1114	
tiver, La., improvement of	210	1263	
age capacity of harbors	579		
oggin River below Brunswick, Me., examina- f	73 473		
e River, Ark., improvement of	231	1403	
lis Harbor, Md., improvement of	143	900	
icola Bay, Fla., improvement of	197	1175	
icola River, Fla., improvement of	197	1174	
ttox River, Va., improvement of	147	913	
Pass and Bay, Tex., improvement of	219	1312	
s Hope River, Va., improvement of	165	1031	
s River from Fort Gibson to Wichita, survey of	232	1405	
s River at Little Rock, bridge across	270		1778
s River at Pine Bluff, Ark., improvement of	229	1393	
s River at Van Buren, Ark., bridge across	270		1792
s River, improvement of, between Fort Smith, and Wichita	229	1399	
s River, operations of snag-boats on	227	1390	
lates and turrets, &c., information in relation o	421		
River, S. C., improvement of	182	1097	
la Harbor, Ohio, improvement of	318		2113
laya River, between Berwick's Bay and the of Mexico, examination of	216	1285	
e Harbor, Mich., improvement of	304		2040
B.			
re, defenses of	35		
re Harbor, improvement of entrance to	142	894	
Harbor, Me., examination and survey of	73 475		
n of Engineers	65 425		
er, N. C., examination of	177	1064	
uperior, Wis., improvement of	272		1818
artholomew, Ark., improvement of	222	1330	
lack, La., improvement of	213	1276	
œuf, La., improvement of	222	1331	
ourtableau, La., improvement of	213	1277	
orcheat, La., examination of	227	1363	
a Fourche, La., examination of	216	1291	
a Fourche, La., improvement of	214	1280	
etit Anse, La., examination of	227	1369	
ierre, La., survey of	221 227		
oundaway, La., examination of	227	1347	
eche, La., connecting with Grand Lake	212	1275	
5908			

SUBJECT.	Page.		
	Part I.	Part II.	P.
Bayou Teche, La., improvement of	212		1272
Bayou Terrebonne, La., improvement of	214		1279
Bayou Vidal, La., examination of	227		1347
Beattyville, Ky., report on lock and dam in Kentucky River at			
Beaufort to New Berne, N. C., inland navigation between, survey of and improvement of	171	177	1040, 1065
Beaufort, N. C., defenses of	40		
Beaufort Harbor, N. C., improvement of	169		1039
Beaufort and New River, N. C., examination of sound between	177		1065
Beaver, Pa., bridge across Ohio River near	270		
Belfast Harbor, Me., improvement of	69	463	
Belle Plaine, examination and survey of Minnesota River near	250		
Belle River, Mich., ice harbor at	306		
Benton Harbor, Saint Joseph's River, Mich., improvement of	300		
Big Bayou Meto, Ark., examination of	232		1409
Big Hatchie River, Tenn., improvement of	225		1337
Big Sandy River, examination of Lou	267		
Big Sandy River, W. Va. and Ky., improvement of	265		
Big Stone Lake, examination of Minnesota River near	250		
Big Sunflower River, Miss., improvement of	224		1334
Biloxi, Miss., improvement of harbor at	206		1217
Bissell's Cove, R. I., examination of	99	663	
Bisteneau Lake, La., examination of	227		
Black Bayou, La., improvement of	213		1276
Black Lake Harbor, Mich., improvement of	298		
Black Rock Harbor, Conn., examination and survey of	99	665	
Black River, Ark. and Mo., improvement of	231		1403
Black River, from its mouth to Trinity, La., examination of	227		1363
Black River, N. C., examination of	177		1061
Black River Harbor, Ohio, improvement of	314		
Black Warrior River, Ala., improvement of	203		1204
Blackwater River, Va., improvement of	165		1031
Black Island, R. I., construction of harbor at	84	626	
Blue Back Bay, Tex., improvement of	207		1249
Board of Engineers for Fortifications and for River and Harbor Improvements	55		
Board of Engineers for the Pacific coast	64		
Boat River, La., improvement of	222		1331
Bogue Fata River, La., examination of	216		1283
Boquet River, N. Y., examination of	330		
Boston, Mass., defenses of	17		
Boston Harbor, Mass., examination and survey of Fort Point Channel	79	588	
Boston Harbor, Mass., improvement of	75	503	
Brandywine River, Del., examination and survey of	139	879	
Brantford Harbor, Conn., examination and survey of	99	678	
Brazos River, Tex., improvement of mouth of	218		1309
Brazos Santiago, Tex., improvement of harbor at	220		1316
Brockwater at New Haven, Conn., construction of	95	647	
Bacter Bay, Md., improvement of	155		981
Bridge across Arkansas River at Little Rock, Ark.	270		
Bridge across Arkansas River at Van Buren, Ark.	270		
Bridge across the Kanawha River, W. Va.	271		
Bridge across the Mississippi River at Dubuque, Iowa ..	271		
Bridge across Ohio River near Beaver, Pa.	269		
Bridge across the Ohio River at Wheeling, W. Va.	269		
Bridge across Saint Croix River	270		

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
across Thames River at New London, Conn.	269		1769
ing navigable waters of the United States.	269		1769
port Harbor, Conn., improvement of.	97 651		
Creek, Del., improvement of.	145	903	
River, N. C., examination of.	177	1058	
kiln River, Del., improvement of.	130 828		
, Fort, Tex., protection of river bank at.	220	1320	
wick Harbor, Ga., improvement of.	188	1118	
annon River, W. Va., examination of.	263		1718
o Bayou, Tex., improvement of.	218	1305	
o Harbor, N. Y., improvement of.	321		2126
gton Harbor, Vt., improvement of.	328		2157
milk Channel, New York Harbor, improvement	102 701		
C.			
a River, Ala., improvement of.	199	1186	
ieu Pass, La., improvement of.	215	1282	
ieu River and Sabine Pass, examination for wa-			
oute to connect.	216	1285	
ieu River, La., improvement of.	215	1281	
ahatchee River, Fla., improvement of.	201	1195	
et Harbor, Ill., improvement of.	290		1946
et River, Ill. and Ind., examination of.	291		1950
et River, Ill., improvement of.	290		1947
idge Harbor, Md., improvement of.	144	902	
at Des Moines Rapids, Mississippi River.	242		1580
at the Cascades, Columbia River, Oreg., construc-			
of.	337		2246
Hennepin, surveys for.	291		1950
Louisville and Portland, operating and main-			
ing.	261		1692
Muscle Shoals, Tennessee River, construction of.	251		1641
Saint Clair Flats, Mich., operating and care of. .	306		2072
Saint Mary's Falls, Mich., construction of.	302		2011
ie Bay, N. Y., improvement of.	108 731		
River, La., examination of.	227	1366	
Fork River, Tenn., improvement of.	256		1653
n River, Minn., examination and survey of lakes			
headwaters of.	250		1634
ear River above Fayetteville, N. C., examination			
.	177	1064	
ear River, N. C., improvement of entrance to. .	150	937	
ear River, N. C., improvement of, from Wilming-			
to Fayetteville.	172	1042	
irardeau, improvement of Mississippi River at. .	235	1529	
lle Harbor, Mich., examination of.	308		2077
ce River, Me., improvement of.	70 465		
Keys Harbor, Fla., examination of northwest			
anel.	206	1218	
Keys Harbor, Fla., examination and survey of. .	206	1223	
Keys to Clearwater Harbor, examination for			
anel from.	206	1220	
Point and Dauphin Island, Ala., examination and			
ey of shoal between.	206	1227	
River, Mich., improvement at mouth of.	276		1833
plain River, N. Y., examination of.	330		2165
el between Staten Island and New Jersey, im-			
ovement of.	113 742		
nton Canal, Saint Mary's Parish, La., improve-			
t of.	212	1275	
ston, S. C., defenses of.	41		

SUBJECT.	Page.		
	Part I.	Part II.	Part
Charleston Harbor, S. C., improvement of	178	1078	
Charlevoix Harbor, Mich., improvement of	293		
Charlevoix Harbor, Mich., removal of wreck in	300		
Charlotte Harbor, N. Y., improvement of	323		
Chattahooche River, Ala. and Ga., improvement of	196	1167	
Cheboygan Harbor, Mich., improvement of	303		
Cheesquakes Creek, N. J., improvement of	110	735	
Chahalis River, Wash., improvement of	340		
Cherrystone Creek, Va., examination of	151	953	
Chesapeake Bay, removal of wrecks in	151	949	
Chester, Pa., ice-harbor at	128	816	
Chester River, Md., at Kent Island Narrows, improve- ment of	141	893	
Chester River, Md., improvement of	141	893	
Chicago Harbor, Ill., improvement of	289		
Chicamuxen Creek, Md., examination of	163	1005	
Chickahominy River, Va., improvement of	159	996	
Chippewa River, Wis., improvement	246		
Chippewa River, at Yellow Banks, W. improvement of	246		
Choctawhatchee River, Fla. and Ala., improvement of	198	1180	
Choptank River, Md., improvement of	144	901	
Cincinnati, Ohio, construction of ice-harbor near	263		
Clear Lake, Cal., examination of	334		
Clearwater Harbor, Fla., examination of			
Cedar Keys to	206	1220	
Clearwater River, Idaho, improvement of	341		
Cleveland, Ohio, examination of channel			
Bed at	318		
Cleveland Harbor, Ohio, improvement of	315		
Clinch River, Tenn., improvement of	255		
Clinton Harbor, Conn., improvement of	94	643	
Clinton River, Mich., improvement of entrance to	307		
Clubfoot River, N. C., examination and survey of	177	1085	
Clubfoot River, N. C., improvement of	171	1046	
Columbia River, N. C., improvement of	167	1034	
Columbia River, N. J., improvement of	72	471	
Columbia River, N. E., improvement of	112	831	
Columbia River, Miss., improvement of	225	1336	
Columbia River, Oreg., construction of canal at the Cascades	137		
Columbia River, Oreg., defenses of	54		
Columbia River, Lower Oreg., improvement of	334		
Columbia River, Oreg., mouth of	335		
Columbia River, Upper and Snake River, Oreg., im- provement of	317		
Columbia River, Oreg., water-gauges on Lower	341		
Connetquot Creek, N. J., examination and survey of	122	770	
Connetquot River, Ala., improvement of	202	1192	
Connetquot Harbor, Ohio, improvement of	319		
Connetquot River, above Hartford, Conn., improve- ment of	93	639	
Connetquot River, below Hartford, Conn., improve- ment of	93	640	
Connetquot River, from Bellows Falls, Vt. to Pitts- burg, N. H., examination of	99	659	
Centerville Creek, N. C., improvement of	172	1042	
Coosa River, Ala. and Ga., improvement of	236		
Coosawattee River, Ga., improvement of	257		
Coos Bay, Oreg., improvement of entrance to	338		
Coquille River, Oreg., improvement of mouth of	339		
Corsier Creek, Md., improvement of	141	891	
Courtaulieu Bayou, La., improvement of	213	1277	
Cowlitz River, Wash., &c., improvement of	339		

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
Village Harbor, Mich, examination and survey of	301		1995
land River above Pineville, Ky., examination	260		1661
land River from Nashville to the Cincinnati			
ern Railroad in Kentucky, examination and	260		1662
y of			
land River, Ky., South Fork of, improvement	259		1660
land River, Tenn. and Ky., improvement of	252		1644
land Sound, Fla. and Ga., defenses of	44		
land Sound, Fla. and Ga., improvement of en-			
e to	189	1121	
ck Sound, improvement of	167	1034	
ga River, examination of channel of Old River			
leading from	318		2110
Bayou, Tex. and La., improvement of	223	1332	
D.			
ver, Va. and N. C., improvement of	161	1000	
ne River, La., examination and survey of	227	1372	
n Island and Cedar Point, Ala., examination			
survey of shoal between	206	1227	
land, Ohio River, movable dam at	260		1678
land, Md., water-passage at, improvement of	145	903	
Seabright, examination for breakwater at har-			
f Long Branch, N. J.	122	763	
s of the northern frontier	10		
sea-coast and lake frontier, general remarks			
on and estimates for	4	55	
torpedo	59		
re Breakwater Harbor, improvement of	137	845	
re Bay and River, removal of wrecks from	137	847	
	138	850	
re River:			
Schooner Ledge, improvement of	126	808	
ow Bridesburg, Pa., improvement of	123	794	
ween Trenton and Bridesburg, Pa., improve-			
ment of	122	792	
ween Trenton and Port Jervis, examination of	138	855	
front of Philadelphia, examination and survey			
of, for removal of Windmill or Smith's Island	138	858	
or Cherry Island Flats, improvement of	126	809	
ines Rapids Canal, Mississippi River, operating			
are of	242		1580
ines Rapids Canal, Mississippi River, dry-dock			
	243		1586
ines Rapids, Mississippi River, improvement at	242		1576
ines River, examination and survey	291		1957
River, Mich., improvement of	307		2074
g Creek, Md., examination of	151	962	
at Bayou, La., examination of	227	1363	
rtugas Harbor, Fla., defenses of	46		
ie, Iowa, bridge across Mississippi River at	271		
ie, Iowa, improvement of harbor at	240		1571
reek, Del., improvement of	131	830	
land Harbor, Conn., examination of	99	684	
iver, Tenn., improvement of	255		1651
Harbor, Minn., improvement of	271		1890
k Harbor, N. Y., improvement of	320		2124
and rank of officers of the Corps of Engineers	351		
sh River, Wash., examination of	342		2296

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
G.			
ston, Tex., defenses of	52		
ston Bay, ship-channel in, improvement of	217	1303	
ston Harbor, Tex., improvement of entrance to	216	1295	
nade River, Mo., improvement of	237		1540
aphical explorations and surveys west of 100th idian	346		2375
etown and Washington harbors, D. C., improve- nt of	151	965	
etown Harbor, S. C., improvement of	177	1052	
ester Harbor, Mass., removal of wrecks in	78 552		
Rapids, Red River of the North, Minn. and Dak.	248		1612
nus Creek, N. Y., examination of	105 713		
nus Bay, N. Y., improvement of	103 706		
l Haven Harbor, Mich., improvement of	297		1984
l Marais, Minn., improvement of harbor at	273		1822
l Marais, Mich., harbor of refuge at	275		1831
l River, Mich., improvement of	298		1986
l River, N. Y., improvement of, at Massena	327		2154
l Bay, N. H., examination and survey of	73 485		
l Kanawha River, W. Va., bridging	271		1796
l Kanawha River, W. Va., improvement of	149	928	
l Peconic Bay, N. Y., examination and survey of nel-way from Riverhead to	99 681		
l Pee Dee River, S. C., improvement of	174	1047	
l Sodus Harbor, N. Y., improvement of	324		2140
l Wicomico River, examination and survey of, from ar Point to Indian Point, Va.	163	1016	
l Bay, Wis., improvement of harbor at	278		1844
l port Harbor, N. Y., improvement of	99 658		
l idotte River, W. Va., improvement of	266		1753
H.			
ton Roads, Va., defenses of	37		
r of refuge, Belle River, Mich., construction of	306		2070
r of refuge near Cincinnati, Ohio, construction	263		1703
r of refuge, Grand Marais, Mich.	275		1831
r of refuge, Lake Huron, construction of	305		2046
r of refuge in Lake Pepin, Mississippi River, con- ction of	240		1570
r of refuge, Milwaukee Bay, construction of	284		1863
r of refuge, Portage Lake, Lake Michigan, con- ction of	294		1974
r of refuge, Sturgeon Bay Canal, Wis., construc- of	279		1846
rs, anchorage capacity of	579		
n River, N. Y., improvement of	103 704		
ve River, N. C., examination and survey of	177	1065	
ve River, N. C., improvement of	171	1040	
ate, N. Y., improvement of navigation at	100 689		
stead Bay, N. Y., examination of channel in	122 764		
pin Canal, surveys for	291		1950
ee River, Tenn., improvement of	254		1649
tonic River, Conn., improvement of	96 650		
n River in front of Jersey City and Hoboken, ination and survey of	122 774		
n River, N. Y., improvement of	101 695		
Mass., examination and survey of headland at ..	78 552		

SUBJECT.	Page	
	Part I.	Part
Hull's Creek, Va., examination of.....	163	10
Humboldt Bay and Harbor, Cal., improvement of.....	333	
Humptulep River, Wash., examination of.....	342	
Hunting Creek, Va., examination of.....	151	
Huron Harbor, Ohio, improvement of.....	313	
Hyannis Harbor, Mass., improvement of.....	79	591

I.

Ice-breakers at Rochester and Freedom, Ohio River, examinations and surveys for.....	263	
Ice-harbor at Belle River, Mich., construction of.....	306	
Ice-harbor at Chester, Pa., condition of.....	128	816
Ice-harbor near Cincinnati, Ohio, construction of.....	263	
Ice-harbor head of Delaware Bay.....	129	817
Ice-harbor at Dubuque, Iowa.....	240	
Ice-harbor at Marcus Hook, Pa., construction of.....	128	814
Ice-harbor at Middleport, Ohio, examination and survey for.....	263	
Ice-harbor at mouth of Muskingum River.....	263	
Ice-harbor at New Castle, Del.....	128	816
Illinois River, examination and survey of.....	291	
Illinois River, improvement of.....	290	
Indian River, Del., examination of.....	151	
Indian River, Del., improvement of.....	135	842
Indian River and Mosquito Lagoon, Fla., examination and survey of passage between.....	194	
Inside passage between Fernandina and Saint John's River, Fla., improvement of.....	190	
Iowa River, examination of.....	244	
Ipswich River, Mass., examination and survey of.....	79	557
Isle of Wight, Md., examination of.....	151	

J.

James River, Va., improvement of.....	146	
Jeffersonville, Ind., estimate for a levee.....		
Jetties at South Pass of the Mississippi River, inspection of.....	206	
Jonesport, Me., improvement of Moose-a-bee Bar at.....	68	462

K.

Kanawha River, Great, improvement of.....	149	
Kanawha River, Little, improvement of.....	266	
Kankakee River, examination of stone formation at Momence, Ill.....	269	
Kennebec River, Me., defenses of.....	14	
Kennebunk River, Me., improvement of.....	71	468
Kenosha Harbor, Wis., improvement of.....	286	
Kent Island Narrows, Md., improvement of.....	141	
Kentucky River, Ky., improvement of.....	264	
Kentucky River, Ky., lock and dam at Beattyville, report on.....		
Kewaunee, Mich., improvement of harbor at.....	280	
Keyport Harbor, N. J., improvement of.....	120	758
Key West, Fla., defenses of.....	45	
Key West, Fla., improvement of harbor at.....	195	11

L.

La Fourche Bayou, La., examination of.....	216	12
La Fourche Bayou, La., improvement of.....	214	12
La Grange Bayou, Fla., improvement of.....	201	11

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
ean, La., examination of	227	1363	
inn., construction of harbor of refuge at ..	240		1570
, harbor of refuge on, at Sand Beach, Mich.	305		2046
ern and Northwestern, issue of charts of ..	345		2373
ra, La. and Miss., examination of mouth of ..	227	1370	
bigoshish, experimental dam at	249		1614
ver, N. H., improvement of	72	472	
River, Ark., improvement of	231	1403	
ty-eighth Congress, first session, affecting ..			
Engineers	371		
r, Del., examination of	138	854	
n Harbor, Md., improvement of	155	981	
, Wash., examination of	342		2293
construction of piers at	137	843	
iver, N. C., improvement of	173	1044	
l Harbor, N. J., removal of wreck off	138	850	
wha River, W. Va., improvement of	266		1754
gansett Bay, R. I. and Conn., improvement ..	89	629	
, Ark., examination of	232	1406	
Ark., bridge across Arkansas River at ..	270		1788
Harbor, N. Y., improvement of	325		2142
see River, improvement of	259		1659
a, La., examination of	227	1363	
Harbor, N. J., examination of coast from ..			
abright for breakwater at	122	763	
River, Miss., examination of	226	1344	
. Big Sandy River, examination of	267		1755
nd Portland Canal, operating and main- ..	261		1692
water River, Idaho, improvement of	341		2279
amette and Columbia rivers, Oreg., im- ..			
t of	334		2215
nel, Me., improvement of	67	460	
l Harbor, Mich., plan and estimate for harbor ..	301		1899
l Harbor, Mich., improvement of	295		1977
r, Mass., improvement of	77	520	
M.			
rbor, Conn., examination of	100	685	
er, Mass., improvement of	78	551	
r Harbor, N. Y., improvement of	98	655	
River, N. J., improvement of	116	751	
er, Fla., improvement of	205	1215	
l Harbor, Mich., improvement of	295		1976
Harbor, Mich., improvement of	276		1832
Harbor, Wis., improvement of	282		1853
ver, Md., examination of	151	951	
ek, N. J., improvement of	134	837	
ary and geographical, preparation of	345		
Harbor, Mass., defenses of	17		
k, Pa., improvement of ice-harbor at	128	814	
l Harbor, Mich., improvement of	274		1829
Y., improvement of Grass River at	327		2154
lay, Tex., improvement of entrance to	219	1310	
iver, Va., improvement of	158	991	
reek, N. J., improvement of	119	756	
er, N. J., improvement of	134	836	
and, Minn., lock and dam at	245		1599
ver, N. C., improvement of	166	1034	

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
Abec Bar, Jonesport, Me., improvement of	68 462		
Ad City, N. C., examination of sound near	177	1062	
Alto Lagoon and Indian River, Fla., examination			
survey for passage between	194	1143	
Vernon, Va., improvement of channel at	154	980	
Alle dam at Davis Island, Ohio River	280		1678
Alton, Iowa, improvement of harbor at	241		1675
Alton Harbor, Mich., improvement of	297		1983
Alton River, construction of ice-harbor at	263		1703
Alton Shoals Canal, Tennessee River, construction of	251		1641
N.			
Alton Harbor, Mass., improvement of	79 593		
Alton Bay, defenses of	20		
Alton Bay, R. I., improvement of	85 617		
Alton River, La., examination and survey of	216	1289	
Alton Creek, Va., improvement of	155	980	
Alton River, Tex., improvement of	208	1256	
Alton River, N. C., improvement of	169	1037	
Altonford, Mass., defenses of	19		
Alton to Beaufort, N. C., inland navigation be-			
gin, survey of and improvement of	171 177	1040, 1067	
Alton Harbor, Mich., improvement of	293		1900
Alton Harbor, Mass., improvement of	73 493		
Alton, Del., ice harbor at	128 816		
Alton Harbor, Conn., construction of breakwater			
	95 647		
Alton Harbor, Conn., defenses of	22		
Alton Harbor, Conn., improvement of	94 645		
Alton, Conn., bridge across the Thames River			
	269		1769
Alton Harbor, Conn., defenses of	21		
Alton Harbor, Conn., improvement of	92 638		
Alton, La., defenses of	49		
Alton Harbor, R. I., improvement of	87 623		
Alton River, N. C., examination and survey of	177	1065	
Alton River, N. C., improvement of	171	1040	
Alton River, N. C., improvement of	174	1046	
Alton and Beaufort, N. C., examination of sound			
between	177	1055	
Alton, Va. and W. Va., improvement of	149	928	
Alton Harbor, N. Y., improvement at	105 709		
Alton Creek, N. J., examination of	139		
Alton Creek, N. Y., examination and survey of	122 765		
Alton Creek, N. Y., improvement of	107 726		
Alton Harbor defenses of	22		
Alton Harbor, removal of wrecks in	121 762		
Alton River, N. Y., improvement of	321		2131
Alton Creek, Va., improvement of	155	982	
Alton River, Wash., improvement of	340		2274
Alton Harbor, Va., and its approaches, improve-			
ment of	163	1028	
Alton and Northwestern Lakes, issue of charts of	345		2373
Alton Landing River, Va. and N. C., improvement			
	168	1040	
Alton River Bar, Currituck Sound, N. C., improvement			
	167	1034	
Alton River, in front of Jersey City and Hoboken, ex-			
amination and survey of	122 774		
Alton Harbor, Conn., improvement of	97 654		
Alton River, Va., improvement of	165	1031	
Alton River, Miss., improvement of	111	1211	

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
Harbor, Fla., defenses of.....	46		
Harbor, Fla., improvement of.....	195	1161	
Harbor, Mich., improvement of.....	278		1842
Creek, N. J., examination of.....	138	852	
Harbor, Mich., improvement of.....	296		1978
Creek, Cal., improvement of.....	332		2198
Bayou, La., examination of.....	227	1369	
ia, Pa., defenses of.....	31		
c River, Va., examination and survey of....	163	1013	
ves, Del., construction of.....	137	843	
ou, La., survey of.....	221	227	
River, N. H. and Me., examination and sur-	73	485	
r Creek, Md., examination of.....	163	1005	
r Creek, Va., examination of.....	163	1006	
Harbor, N. Y., improvement of.....	327		2155
Harbor, Mass., improvement of.....	76	514	
Harbor, Mass., defenses of.....	19		
River, Md., examination of.....	151	949	
ke, Mich., construction of harbor of refuge at.....	294		1974
er Harbor, N. Y., improvement of.....	105	712	
on Harbor, Ohio, improvement of.....	310		2086
y Harbor, N. Y., examination of.....	330		2168
son Harbor, L. I., N. Y., improvement of....	98	656	
larbor, Me., defenses of.....	14		
larbor, Me., improvement of.....	70	467	
all Harbor, N. Y., examination of.....	330		2161
h Harbor, N. H., defenses of.....	16		
h Harbor, N. H., examination of.....	73	474	
h Harbor, N. H., improvement of.....	71	469	
xo Creek, Md., examination of.....	163	1008	
en's Line at Philadelphia.....	138	851	
ington Harbor, Wis., improvement of.....	283		1858
river, D. C., improvement of, in vicinity of	152	970	
river, fish-ways at Great Falls of.....	344		2311
river at Mount Vernon, improvement of.....	154	980	
epot at Willets Point.....	65	455	
e River, R. I., improvement of.....	85	617	
wn Harbor, Mass., improvement of.....	77	518	
ldings and grounds, District of Columbia....	344		2339
le Harbor, N. Y., improvement of.....	324		2138
ne Creek, Va., examination of.....	151	952	
Q.			
reek, Va., examination and survey of.....	163	1010	
l., improvement of Mississippi River at.....	243	1588	
y, Ill., improvement of.....	243	1590	
R.			
iver, N. J., improvement of.....	135	839	
rbor, Wis., improvement of.....	285	1867	
iver, N. J., improvement of.....	115	747	
river, N. J., improvement of.....	133	833	
duties, officers of engineers.....	351		
ock River, Va., improvement of.....	156	985	
y, N. J., improvement of.....	117	752	
ver, N. J., improvement of.....	118	754	
ances and explorations.....	347		
from its mouth to Fulton, survey of.....	221		


SUBJECT.	Page.	
	Part I.	Part II.
Red River, La., improvement of.....	221	1322
survey of	221 227	
Red River of the North, improvement of	248	
Red River of the North, construction of lock and dam at Goose Rapids	248	
Red River, Tenn., improvement of	259	
Redwood Slough, Cal., examination and survey of	334	
Reedy Island, Delaware River, ice-harbor at	129 817	
Reservoirs at sources of the Mississippi and its tributa- ries, construction of	249	
Reservoirs at sources of the Mississippi and its tributa- ries, surveys for	250	
River and harbor improvements	66	
Roanoke River, N. C., examination and survey of	163	102
Roanoke River, N. C., improvement of	161	100
Rochester, Pa., examination and survey of Ohio River at for ice-breaker	263	
Rock Island Harbor, Mississippi River, improvement at	241	
Rock Island Rapids, Mississippi River, improvement at	241	
Rockland Harbor, Me., improvement of	69 464	
Rockport, Mass., examination for harbor of refuge at Sandy Bay	79 565	
Rocky River Harbor, Ohio, improvement of	315	
Roebuck Lake, Miss., examination of	227	135
Romerly Marsh, Ga., improvement of water-route through	186	111
Rondout Harbor, N. Y., improvement of	102 700	
Roundaway Bayou, La., examination of	227	134
Rouse's Point, N. Y., examination and survey for break- water at	330	
Royal River, Me., improvement of	70 466	
S.		
Sabine Pass and Calcasieu River, examination for water- route to connect	216	126
Sabine Pass, Tex., improvement of	207	124
Sabine River, Tex., improvement of	208	125
Sackett's Harbor, N. Y., improvement of	326	
Saco River, Me., resurvey of	73 482	
Sacramento River, Cal., improvement of	331	
Saginaw River, Mich., improvement of	304	
Saint Anthony, preservation of Falls of	244	
Saint Augustine Creek, Ga., improvement of	186	111
Saint Augustine, Fla., defenses of	45	
Saint Clair Flats Ship-canal, Mich.	306	
Saint Croix River, Wis. and Minn., improvement of	247	
Saint Croix River, bridging	270	
Saint Francis and White rivers, Ark., improvement of	228	139
Saint Jerome's Creek, Md., improvement of harbor at	156	98
Saint John's River and Fernandina, Fla., deepening in- side passage between	190	112
Saint John's River, Fla., examination and survey be- tween Lake George and Lake Monroe	194	113
Saint John's River, Fla., improvement of bar at mouth of	190	112
Saint John's River, Fla., Upper, improvement of	193	113
Saint Jones River, Del., improvement of	133 835	
Saint Joseph Harbor, Mich., improvement of	300	
Saint Mark's River, Fla., examination of	206	122
Saint Mary's Falls Canal and Saint Mary's River, Mich., improvement of	302	

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
Mary's Falls Canal, Mich., dry-dock at	302		2030
Mary's Falls Canal, Mich., operating canal	302		2016
Mary's River, Mich., improvement of Hay Lake Inlet	301		2004
River, N. J., improvement of	132	832	
River, Ark., examination of	232	1406	
River, Ark., improvement of	231	1404	
Matchie River, S. C., improvement of	181	1094	
Beach, Mich., Lake Huron, harbor of refuge at	305		2046
Mexico, Cal., defenses of	52		
Mexico Harbor, Cal., improvement of	334		2213
Wesley City Harbor, Ohio, improvement of	311		2088
Wesley River, Ohio, improvement of	312		2091
Bay, Rockport, Mass., examination and survey harbor of refuge at	79	565	
San Francisco, Cal., defenses of	52		
San Francisco Bay, Cal., deposit of dredged material in			2183
San Francisco Harbor, Cal., removal of wreck from	333		2201
Union River, Ill., examination and survey of	291		1952
San Joaquin River, Cal., improvement of	332		2195
Monica Bay, Cal., examination of	334		2209
River, S. C., improvement of	175	1049	
Waukegan Harbor, Mich., improvement of	299		1989
Waukegan Harbor, N. Y., examination and survey of	106	715	
Waukegan, Ga., defenses of	43		
Waukegan River and Harbor, Ga., improvement of	183	1098	
Waukegan River, Ga., above Augusta, improvement of	185	1110	
Waukegan River, Ga., below Augusta, improvement of	184	1107	
of Application, Battalion of Engineers	65	425	
Waukegan River, Pa., improvement of	127	811	
Waukegan Harbor, Mass., improvement of	75	502	
Waukegan River., N. C., improvement of	167	1035	
Waukegan and lake frontier defenses, general remarks on estimates for	4	55	
Waukegan Harbor, Mich., re-survey of	308		2079
Waukegan Harbor, Wis., improvement of	282		1855
Waukegan Harbor, Wis., removal of wreck in	284		1860
Waukegan Head Bay, N. Y., improvement of	109	732	
Waukegan River, Va. and W. Va., improvement of	148	927	
Waukegan Harbor, N. J., examination and survey of	122	770	
Waukegan River, N. J., improvement of	114	745	
Waukegan River, Wash., improvement of	340		2274
Waukegan Mills and White Oak River, N. C., examina- tion of sound between	177	1055	
Waukegan boats on the Arkansas, operations of	227	1390	
Waukegan boats on the Lower Mississippi and Missouri, oper- ations of	236		1531
Waukegan boats on the Upper Mississippi, operations of	238	1545	
Waukegan River, Wash., improvement of	337		2229
Waukegan River, Wash., improvement of	340		2274
Waukegan River, Wash., improvement of	340		2274
Waukegan Harbor, N. Y., Great, improvement of	324		2140
Waukegan Harbor, N. Y., Little, improvement of	325		2142
Waukegan Forked Deer River, Tenn., improvement of	226	1338	
Waukegan Haven Harbor, Mich., improvement of	299		1991
Waukegan Harbor, N. Y., examination of	100	686	
Waukegan Pass, Mississippi River, inspection of improve- ment at	206	1235	
Waukegan Port Harbor, Conn., improvement of	97	653	
Waukegan River, N. J., improvement of	120	760	
Waukegan Harbor, Conn., examination and survey of	99	670	

SUBJECT.	Page.	
	Part I	Part II
Staten Island, N. Y., improvement of New Jersey Chan- nel	113	742
Staunton River, Va., improvement of	161	88
Steel's Bayou, Miss., examination of	227	139
Stedakamish River, Wash., improvement of	340	
Stockholm, Wis., construction of harbor of refuge at ..	240	
Stonington Harbor, Conn., improvement of	80	630
Stony Brook Harbor, N. Y., examination of	99	664
Sturgeon Bay Canal, Wis., harbor of refuge at	273	
Sulphur River, Tex., examination of	227	1345
Sumpawamus Inlet, L. I., N. Y., improvement of	110	734
Sundowner River, Miss., improvement of	224	134
Superior Bay, Wis., improvement of	272	
Survey of Northern and Northwestern lakes, issue of charts of	345	
Surveys and examinations for improvement of rivers and harbors, estimates for	342	
Surveys and explorations west of 100th meridian	346	
Surveys for Menepin Canal	291	
Susquehanna River, examination and survey of North Branch of	138	569
Susquehanna River, Pa., improvement of North Branch of	136	842
Susquehanna River, near Havre de Grace, Md., improve- ment of	139	88
Suwannee River, Fla., improvement of	198	1179
Swanton Harbor, Vt., improvement of	328	
Synepuxent Bay, Md., examination of	151	957
T.		
Tallahatchie River, Miss., improvement of	224	1335
Tallapoosa River, Ala., improvement of	200	1189
Tampa Bay, Fla., improvement of	198	1178
Tangipahoa River, La., improvement of	210	1266
Tar River, N. C., improvement of	168	1036
Taunton River, Mass., improvement of	83	604
Tchefunete River, La., improvement of	211	1268
Tchula Lake, Miss., improvement of	224	1335
Teche, Bayou, La., connection with Grand Lake at Charenton	212	1275
Teche, Bayou, La., improvement of	212	1272
Tennessee River, above Chattanooga, improvement of ..	250	
Tennessee River, below Chattanooga, improvement of ..	251	
Texas River, La., improvement of	223	1331
Terrebonne, Bayou, La., improvement of	214	1279
Ticklaw River, La., improvement of	211	1271
Thames River, Conn., at New London, bridge across	269	
Thames River, Conn., improvement of	92	636
Thunder Bay Harbor, Mich., improvement of	303	
Thunderbolt River, Ga., improvement of	186	1111
Ticonderoga River, N. Y., improvement of	329	
Tionesta Creek, Pa., examination of	263	
Toledo Harbor, Ohio, improvement of	309	
Tombigbee River, Ala., above Columbus, Miss., im- provement of	204	1210
Tombigbee River, Ala., improvement of	203	1206
Torpedo defense	59	
Totusky River, Va., improvement of	157	988
Town Creek, N. C., examination of	177	1063
Tradewater River, Ky., improvement of	264	
Trenton Harbor, La., examination of	227	1381

SUBJECT.	Page.		
	Part I.	Part II.	Part III.
River, N. C., improvement of.....	171	1041	
y River, Tex., improvement of.....	217	1304	
ts and armor-plates, &c., information in relation eto	421		
ivers Harbor, Wis., improvement of.....	281	1851	
t's Valley River, W. Va., examination and survey	263		1718
U.			
Columbia and Snake rivers, Oreg. and Wash., rovements of.....	337		2229
Mississippi River, operations of snag-boats on....	238		1545
Saint John's River, Fla., improvement of.....	193	1137	
Thoroughfare, Deal's Island and mainland, Md., rovement of.....	145	903	
Willamette River, Oreg., improvement of.....	336		2226
a Creek, Va., improvement of.....	158	990	
V.			
uren, Ark., bridge across Arkansas River at.....	270		1792
illion Harbor, Ohio, improvement of.....	313		2093
Bayou, La., examination of	227	1347	
ia Bar, Lake George, Fla., improvement of.....	192	1134	
W.			
sh River, Ind., improvement of	267		1757
amaw River, N. C. and S. C., examination of....	177	1056	
amaw River, N. C. improvement of	175	1048	
ita River, Ark. and La., improvement of	221	1329	
oo Cut, S. C., improvement of.....	180	1089	
nam Harbor, Mass., improvement of.....	82	600	
or River, Ala., improvement of.....	203	1204	
ngton Aqueduct, D. C.....	342		2299
ngton, D. C., defenses of.....	36		
ngton and Georgetown harbors, D. C., improve- it of.....	151	965	
ngton, D. C., improvement of Potomac River at....	152	970	
ngton, D. C., increasing water-supply of.....	343		2301
ee River, S. C., improvement of.....	176	1051	
-ganges on Mississippi River and tributaries.....	226	1341	
passage, Deal's Island, Md., improvement of....	145	903	
egan Harbor, Ill., improvement of.....	286		1871
ort Harbor, Conn., examination and survey of..	99	673	
guin Creek, Md., examination of.....	151	956	
ling, W. Va., bridge across Ohio River at.....	269		1772
and Saint Francis rivers, Ark., improvement of..	228	1392	
Oak River to Smith's Mills, N. C., examination	177	1055	
River, Ark., above Buffalo Shoals, improvement	230	1402	
River, Ark., near Duvall's Bluff, examination survey of	232	1409	
River, between Jacksonport and Buffalo Shoals, ., improvement of.....	230	1401	
River Harbor, Mich., improvement of.....	296		1981
River, Ind., improvement of.....	268		1765
nico River, Great, Md., examination and survey from Cedar Point to Indian Point.....	163	1016	
nico River, Md., examination of.....	151	959	
nico River, Md., improvement of	145	903	

SUBJECT.	Page.	
	Part I.	Part II.
Willamette River, Lower, Oreg., improvement of	324	
Willamette River, Upper, Oreg., improvement of	325	
Wileys Point, N. Y., engineer post and depot at	45	455
Willapa River Harbor, Cal., improvement of	331	
Willapa River Harbor, Del., improvement of	130	226
Washington, N. C., defenses of	41	
Wilson Harbor, N. Y., improvement of	322	
Winnebago Lake, experimental dam at	249	
Wisconsin and Fox rivers, improvement of	257	
Wisconsin River, from Portage to Merrill, examination of	283	
Withlacooche River, Fla., improvement of	201	1134
Wichitanga Creek, N. J., improvement of	116	742
Wichitanga Creek, N. J., improvement of	135	838
Woods Hole Harbor, Mass., improvement of	81	597
Wreck in Charlevoix Harbor, Mich., removal of	300	
Wreck in Cape Sable Bay, removal of	151	948
Wreck on coast of New Jersey, removal of	138	550
Wreck in Gloucester Harbor, Mass., removal of	78	552
Wreck off Little Egg Harbor, N. J., removal of	138	550
Wreck in Mobile River, removal of	206	1217
Wreck in New York Harbor endangering navigation, removal of	121	702
Wreck in San Francisco Harbor, Cal., removal of	333	
Wreck in Sheboygan Harbor, Wis., removal of	284	
Y.		
Yadkin River, N. C., improvement of	173	1043
Yalabusha River, Miss., examination of	226	1348
Yalabusha River, Miss., improvement of	225	1337
Yaquina Bay, Oreg., improvement of entrance to	338	
Yazoo Pass, Miss., examination of	227	1351
Yazoo River, Miss., improvement of	223	1333
Yellowstone River, improvement of	238	
York River, Va., improvement of	159	98
Youghiogheny River, examination and survey of	263	







1961 10 10

